


# Rust IN ACTION

Systems programming concepts  
and techniques

Tim McNamara



MANNING

<b>Raw Pointer</b>	<b>Box&lt;T&gt;</b>	<b>Rc&lt;T&gt;</b>	<b>Arc&lt;T&gt;</b>																										
																													
<p>The cousins *mut T and *const T are the free radicals of the pointer world. Lightning fast, but wildly unsafe.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Speed</td><td>• Unsafe</td></tr> <tr> <td>• Can interact with the outside world</td><td></td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Speed	• Unsafe	• Can interact with the outside world		<p>Store anything in a box. Accepts almost any type for long-term storage. The workhorse of a new, safe programming era.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Store a value in central storage in a location called "the heap"</td><td>• Size increase</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Store a value in central storage in a location called "the heap"	• Size increase	<p>The reference counted pointer, Rc&lt;T&gt; is Rust's competent, yet miserly bookkeeper. It knows who has borrowed what and when.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Shared access to values</td><td>• Size increase</td></tr> <tr> <td></td><td>• Runtime cost</td></tr> <tr> <td></td><td>• Not threadsafe</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Shared access to values	• Size increase		• Runtime cost		• Not threadsafe	<p>Arc&lt;T&gt; is Rust's ambassador. It can share values across threads, guaranteeing that these will not interfere with each other.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Shared access to values</td><td>• Size increase</td></tr> <tr> <td></td><td>• Runtime cost</td></tr> <tr> <td></td><td>• Threadsafe</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Shared access to values	• Size increase		• Runtime cost		• Threadsafe
<b>Powers</b>	<b>Weaknesses</b>																												
• Speed	• Unsafe																												
• Can interact with the outside world																													
<b>Powers</b>	<b>Weaknesses</b>																												
• Store a value in central storage in a location called "the heap"	• Size increase																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Shared access to values	• Size increase																												
	• Runtime cost																												
	• Not threadsafe																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Shared access to values	• Size increase																												
	• Runtime cost																												
	• Threadsafe																												
<b>Cell&lt;T&gt;</b>	<b>RefCell&lt;T&gt;</b>	<b>Cow&lt;T&gt;</b>	<b>String</b>																										
																													
<p>An expert in metamorphosis, Cell&lt;T&gt; confers the ability to mutate immutable values.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Interior mutability</td><td>• Size increase</td></tr> <tr> <td></td><td>• Performance</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Interior mutability	• Size increase		• Performance	<p>Performs mutation on immutable references with RefCell&lt;T&gt;. Its mind-bending powers come with some costs.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Interior mutability</td><td>• Size increase</td></tr> <tr> <td>• Can be nested within Rc and Arc, which only accept immutable refs</td><td>• Runtime cost</td></tr> <tr> <td></td><td>• Lack of compile-time guarantees</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Interior mutability	• Size increase	• Can be nested within Rc and Arc, which only accept immutable refs	• Runtime cost		• Lack of compile-time guarantees	<p>Why write something down when you only need to read it? Perhaps you only want to make modifications. This is the role of Cow (copy on write).</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Avoids writes when only read access is used</td><td>• Possible size increase</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Avoids writes when only read access is used	• Possible size increase	<p>Acting as a guide on how to deal with the uncertainties of user input, String shows us how to build safe abstractions.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Grows dynamically as required</td><td>• Can over allocate size</td></tr> <tr> <td></td><td>• Guarantees correct encoding at runtime</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Grows dynamically as required	• Can over allocate size		• Guarantees correct encoding at runtime		
<b>Powers</b>	<b>Weaknesses</b>																												
• Interior mutability	• Size increase																												
	• Performance																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Interior mutability	• Size increase																												
• Can be nested within Rc and Arc, which only accept immutable refs	• Runtime cost																												
	• Lack of compile-time guarantees																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Avoids writes when only read access is used	• Possible size increase																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Grows dynamically as required	• Can over allocate size																												
	• Guarantees correct encoding at runtime																												
<b>Arc&lt;T&gt;</b>	<b>RawVec&lt;T&gt;</b>	<b>Unique&lt;T&gt;</b>	<b>Shared&lt;T&gt;</b>																										
																													
<p>Your program's main storage system. Vec&lt;T&gt; keeps your data orderly as values are created and destroyed.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Grows dynamically as required</td><td>• Can over allocate size</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Grows dynamically as required	• Can over allocate size	<p>The bedrock of Vec&lt;T&gt; and other dynamically sized types. Understands how to provide a home for your data as needed.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Grows dynamically as required</td><td>• Not directly applicable from your code</td></tr> <tr> <td>• Works with the memory allocator to find space</td><td></td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Grows dynamically as required	• Not directly applicable from your code	• Works with the memory allocator to find space		<p>Sole owner of a value, a unique pointer is guaranteed to possess full control.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Base for types such as Strings, requiring exclusive possession of values.</td><td>• Not appropriate for application code directly</td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Base for types such as Strings, requiring exclusive possession of values.	• Not appropriate for application code directly	<p>Sharing ownership is hard. Shared&lt;T&gt; makes life a little bit easier.</p> <table> <tr> <td><b>Powers</b></td><td><b>Weaknesses</b></td></tr> <tr> <td>• Shared ownership</td><td>• Not appropriate for application code directly</td></tr> <tr> <td>• Can align memory to T's width, even when empty</td><td></td></tr> </table>	<b>Powers</b>	<b>Weaknesses</b>	• Shared ownership	• Not appropriate for application code directly	• Can align memory to T's width, even when empty							
<b>Powers</b>	<b>Weaknesses</b>																												
• Grows dynamically as required	• Can over allocate size																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Grows dynamically as required	• Not directly applicable from your code																												
• Works with the memory allocator to find space																													
<b>Powers</b>	<b>Weaknesses</b>																												
• Base for types such as Strings, requiring exclusive possession of values.	• Not appropriate for application code directly																												
<b>Powers</b>	<b>Weaknesses</b>																												
• Shared ownership	• Not appropriate for application code directly																												
• Can align memory to T's width, even when empty																													

*Rust in Action*

Licensed to UNKNOWN UNKNOWN <auxo86@gmail.com>

# *Rust in Action*

SYSTEMS PROGRAMMING  
CONCEPTS AND TECHNIQUES

TIM McNAMARA



MANNING  
SHELTER ISLAND

For online information and ordering of this and other Manning books, please visit [www.manning.com](http://www.manning.com). The publisher offers discounts on this book when ordered in quantity. For more information, please contact

Special Sales Department  
Manning Publications Co.  
20 Baldwin Road  
PO Box 761  
Shelter Island, NY 11964  
Email: [orders@manning.com](mailto:orders@manning.com)

©2021 by Manning Publications Co. All rights reserved.

No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by means electronic, mechanical, photocopying, or otherwise, without prior written permission of the publisher.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in the book, and Manning Publications was aware of a trademark claim, the designations have been printed in initial caps or all caps.

⊗ Recognizing the importance of preserving what has been written, it is Manning's policy to have the books we publish printed on acid-free paper, and we exert our best efforts to that end. Recognizing also our responsibility to conserve the resources of our planet, Manning books are printed on paper that is at least 15 percent recycled and processed without the use of elemental chlorine.

 Manning Publications Co.  
20 Baldwin Road  
PO Box 761  
Shelter Island, NY 11964

Development editor: Elesha Hyde  
Technical development editor: René van den Berg  
Review editor: Mihaela Batinic  
Production editor: Deirdre S. Hiam  
Copy editor: Frances Buran  
Proofreader: Melody Dolab  
Technical proofreader: Jerry Kuch  
Typesetter: Dennis Dalinnik  
Cover designer: Marija Tudor

ISBN: 9781617294556  
Printed in the United States of America

*To everyone aspiring to write safer software.*

Licensed to UNKNOWN UNKNOWN <auxo86@gmail.com>

# *contents*

---

*preface* xv  
*acknowledgments* xvii  
*about this book* xix  
*about the author* xxii  
*about the cover illustration* xxiii

## **I** *Introducing Rust 1*

- 1.1 Where is Rust used? 2
- 1.2 Advocating for Rust at work 3
- 1.3 A taste of the language 4
  - Cheating your way to “Hello, world!”* 5 ▀ *Your first Rust program* 7
- 1.4 Downloading the book’s source code 8
- 1.5 What does Rust look and feel like? 8
- 1.6 What is Rust? 11
  - Goal of Rust: Safety* 12 ▀ *Goal of Rust: Productivity* 16
  - Goal of Rust: Control* 18
- 1.7 Rust’s big features 19
  - Performance* 19 ▀ *Concurrency* 20 ▀ *Memory efficiency* 20

1.8	Downsides of Rust	20		
	<i>Cyclic data structures</i>	20 ▪ <i>Compile times</i>	20 ▪ <i>Strictness</i>	21
	<i>Size of the language</i>	21 ▪ <i>Hype</i>	21	
1.9	TLS security case studies	21		
	<i>Heartbleed</i>	21 ▪ <i>Goto fail;</i>	22	
1.10	Where does Rust fit best?	23		
	<i>Command-line utilities</i>	23 ▪ <i>Data processing</i>	24 ▪ <i>Extending applications</i>	24
	<i>Resource-constrained environments</i>	24		
	<i>Server-side applications</i>	25 ▪ <i>Desktop applications</i>	25	
	<i>Desktop</i>	25 ▪ <i>Mobile</i>	25 ▪ <i>Web</i>	26 ▪ <i>Systems programming</i>
		26		
1.11	Rust's hidden feature: Its community	26		
1.12	Rust phrase book	26		

## PART 1 RUST LANGUAGE DISTINCTIVES ..... 29

## 2 *Language foundations* 31

2.1	Creating a running program	33	
	<i>Compiling single files with rustc</i>	33 ▪ <i>Compiling Rust projects with cargo</i>	33
2.2	A glance at Rust's syntax	34	
	<i>Defining variables and calling functions</i>	35	
2.3	Numbers	36	
	<i>Integers and decimal (floating-point) numbers</i>	36 ▪ <i>Integers with base 2, base 8, and base 16 notation</i>	37
	<i>Comparing numbers</i>	37 ▪ <i>Rational, complex numbers, and other numeric types</i>	38
2.4	Flow control	45	
	<i>For: The central pillar of iteration</i>	45 ▪ <i>Continue: Skipping the rest of the current iteration</i>	47
	<i>While: Looping until a condition changes its state</i>	47 ▪ <i>Loop: The basis for Rust's looping constructs</i>	48
	<i>Break: Aborting a loop</i>	48 ▪ <i>If, if else, and else: Conditional branching</i>	49
	<i>Match: Type-aware pattern matching</i>	51	
2.5	Defining functions	52	
2.6	Using references	53	
2.7	Project: Rendering the Mandelbrot set	54	

- 2.8 Advanced function definitions 56
  - Explicit lifetime annotations* 56 ▪ *Generic functions* 58
- 2.9 Creating grep-lite 60
- 2.10 Making lists of things with arrays, slices, and vectors 63
  - Arrays* 64 ▪ *Slices* 65 ▪ *Vectors* 66
- 2.11 Including third-party code 67
  - Adding support for regular expressions* 68 ▪ *Generating the third-party crate documentation locally* 69 ▪ *Managing Rust toolchains with rustup* 70
- 2.12 Supporting command-line arguments 70
- 2.13 Reading from files 72
- 2.14 Reading from stdin 74

## 3 Compound data types 77

- 3.1 Using plain functions to experiment with an API 78
- 3.2 Modeling files with struct 80
- 3.3 Adding methods to a struct with impl 84
  - Simplifying object creation by implementing new()* 84
- 3.4 Returning errors 87
  - Modifying a known global variable* 87 ▪ *Making use of the Result return type* 92
- 3.5 Defining and making use of an enum 95
  - Using an enum to manage internal state* 96
- 3.6 Defining common behavior with traits 98
  - Creating a Read trait* 98 ▪ *Implementing std::fmt::Display for your own types* 99
- 3.7 Exposing your types to the world 102
  - Protecting private data* 102
- 3.8 Creating inline documentation for your projects 103
  - Using rustdoc to render docs for a single source file* 104
  - Using cargo to render docs for a crate and its dependencies* 104

## 4 Lifetimes, ownership, and borrowing 107

- 4.1 Implementing a mock CubeSat ground station 108
  - Encountering our first lifetime issue* 110 ▪ *Special behavior of primitive types* 112

4.2	Guide to the figures in this chapter	114
4.3	What is an owner? Does it have any responsibilities?	115
4.4	How ownership moves	115
4.5	Resolving ownership issues	118
	<i>Use references where full ownership is not required</i>	119
	<i>Use fewer long-lived values</i>	123
	<i>Duplicate the value</i>	128
	<i>Wrap data within specialty types</i>	131

## PART 2 DEMYSTIFYING SYSTEMS PROGRAMMING ..... 135

### 5 Data in depth 137

5.1	Bit patterns and types	137
5.2	Life of an integer	139
	<i>Understanding endianness</i>	142
5.3	Representing decimal numbers	143
5.4	Floating-point numbers	144
	<i>Looking inside an f32</i>	144
	<i>Isolating the sign bit</i>	146
	<i>Isolating the exponent</i>	146
	<i>Isolate the mantissa</i>	148
	<i>Dissecting a floating-point number</i>	150
5.5	Fixed-point number formats	152
5.6	Generating random probabilities from random bytes	157
5.7	Implementing a CPU to establish that functions are also data	158
	<i>CPU RIA/1: The Adder</i>	159
	<i>Full code listing for CPU RIA/1: The Adder</i>	163
	<i>CPU RIA/2: The Multiplier</i>	164
	<i>CPU RIA/3: The Caller</i>	167
	<i>CPU 4: Adding the rest</i>	173

### 6 Memory 175

6.1	Pointers	176
6.2	Exploring Rust's reference and pointer types	178
	<i>Raw pointers in Rust</i>	183
	<i>Rust's pointer ecosystem</i>	185
	<i>Smart pointer building blocks</i>	186
6.3	Providing programs with memory for their data	187
	<i>The stack</i>	188
	<i>The heap</i>	190
	<i>What is dynamic memory allocation?</i>	194
	<i>Analyzing the impact of dynamic memory allocation</i>	199

## 6.4 Virtual memory 202

*Background 202 ▪ Step 1: Having a process scan its own memory 203 ▪ Translating virtual addresses to physical addresses 205 ▪ Step 2: Working with the OS to scan an address space 208 ▪ Step 3: Reading from and writing to process memory 211*

# 7 Files and storage 212

## 7.1 What is a file format? 213

## 7.2 Creating your own file formats for data storage 214

*Writing data to disk with serde and the bincode format 214*

## 7.3 Implementing a hexdump clone 217

## 7.4 File operations in Rust 219

*Opening a file in Rust and controlling its file mode 219*

*Interacting with the filesystem in a type-safe manner with std::fs::Path 220*

## 7.5 Implementing a key-value store with a log-structured, append-only storage architecture 222

*The key-value model 222 ▪ Introducing actionkv v1: An in-memory key-value store with a command-line interface 222*

## 7.6 Actionkv v1: The front-end code 224

*Tailoring what is compiled with conditional compilation 226*

## 7.7 Understanding the core of actionkv: The libactionkv crate 228

*Initializing the ActionKV struct 228 ▪ Processing an individual record 230 ▪ Writing multi-byte binary data to disk in a guaranteed byte order 232 ▪ Validating I/O errors with checksums 234 ▪ Inserting a new key-value pair into an existing database 236 ▪ The full code listing for actionkv 237*

*Working with keys and values with HashMap and BTreeMap 241*

*Creating a HashMap and populating it with values 243*

*Retrieving values from HashMap and BTreeMap 244 ▪ How to decide between HashMap and BTreeMap 245 ▪ Adding a*

*database index to actionkv v2.0 246*

# 8 Networking 251

## 8.1 All of networking in seven paragraphs 252

## 8.2 Generating an HTTP GET request with reqwest 254

8.3	Trait objects	256
	<i>What do trait objects enable?</i>	256
	<i>What is a trait object?</i>	256
	<i>Creating a tiny role-playing game: The rpg project</i>	257
8.4	TCP	260
	<i>What is a port number?</i>	261
	<i>Converting a hostname to an IP address</i>	261
8.5	Ergonomic error handling for libraries	268
	<i>Issue: Unable to return multiple error types</i>	269
	<i>Wrapping downstream errors by defining our own error type</i>	272
	<i>Cheating with unwrap() and expect()</i>	277
8.6	MAC addresses	277
	<i>Generating MAC addresses</i>	279
8.7	Implementing state machines with Rust's enums	281
8.8	Raw TCP	282
8.9	Creating a virtual networking device	282
8.10	"Raw" HTTP	283

## 9 Time and timekeeping 293

9.1	Background	294
9.2	Sources of time	296
9.3	Definitions	296
9.4	Encoding time	297
	<i>Representing time zones</i>	298
9.5	clock v0.1.0: Teaching an application how to tell the time	298
9.6	clock v0.1.1: Formatting timestamps to comply with ISO 8601 and email standards	299
	<i>Refactoring the clock v0.1.0 code to support a wider architecture</i>	300
	<i>Formatting the time</i>	301
	<i>Providing a full command-line interface</i>	301
	<i>clock v0.1.1: Full project</i>	303
9.7	clock v0.1.2: Setting the time	305
	<i>Common behavior</i>	306
	<i>Setting the time for operating systems that use libc</i>	306
	<i>Setting the time on MS Windows</i>	308
	<i>clock v0.1.2: The full code listing</i>	310
9.8	Improving error handling	313

- 9.9 clock v0.1.3: Resolving differences between clocks with the Network Time Protocol (NTP) 314  
*Sending NTP requests and interpreting responses* 314 ▪ *Adjusting the local time as a result of the server's response* 316 ▪ *Converting between time representations that use different precisions and epochs* 318 ▪ *clock v0.1.3: The full code listing* 319

## 10 Processes, threads, and containers 328

- 10.1 Anonymous functions 329
- 10.2 Spawning threads 330  
*Introduction to closures* 330 ▪ *Spawning a thread* 331  
*Effect of spawning a few threads* 331 ▪ *Effect of spawning many threads* 333 ▪ *Reproducing the results* 335 ▪ *Shared variables* 338
- 10.3 Differences between closures and functions 340
- 10.4 Procedurally generated avatars from a multithreaded parser and code generator 341  
*How to run render-hex and its intended output* 342 ▪ *Single-threaded render-hex overview* 342 ▪ *Spawning a thread per logical task* 351 ▪ *Using a thread pool and task queue* 353
- 10.5 Concurrency and task virtualization 360  
*Threads* 362 ▪ *What is a context switch?* 362 ▪ *Processes* 363  
*WebAssembly* 363 ▪ *Containers* 363 ▪ *Why use an operating system (OS) at all?* 363

## 11 Kernel 365

- 11.1 A fledgling operating system (FledgeOS) 365  
*Setting up a development environment for developing an OS kernel* 366 ▪ *Verifying the development environment* 367
- 11.2 Fledgeos-0: Getting something working 368  
*First boot* 368 ▪ *Compilation instructions* 370 ▪ *Source code listings* 370 ▪ *Panic handling* 374 ▪ *Writing to the screen with VGA-compatible text mode* 375 ▪ *\_start(): The main() function for FledgeOS* 377
- 11.3 fledgeos-1: Avoiding a busy loop 377  
*Being power conscious by interacting with the CPU directly* 377  
*fledgeos-1 source code* 378
- 11.4 fledgeos-2: Custom exception handling 379  
*Handling exceptions properly, almost* 379 ▪ *fledgeos-2 source code* 380

11.5	fledgeos-3: Text output	381
	<i>Writing colored text to the screen</i>	381
	<i>Controlling the in-memory representation of enums</i>	382
	<i>Why use enums?</i>	382
	<i>Creating a type that can print to the VGA frame buffer</i>	382
	<i>Printing to the screen</i>	383
	<i>fledgeos-3 source code</i>	383
11.6	fledgeos-4: Custom panic handling	385
	<i>Implementing a panic handler that reports the error to the user</i>	385
	<i>Reimplementing panic() by making use of core::fmt::Write</i>	385
	<i>Implementing core::fmt::Write</i>	386
	<i>fledge-4 source code</i>	387

## 12 Signals, interrupts, and exceptions 390

12.1	Glossary	391
	<i>Signals vs. interrupts</i>	391
12.2	How interrupts affect applications	393
12.3	Software interrupts	395
12.4	Hardware interrupts	395
12.5	Signal handling	395
	<i>Default behavior</i>	395
	<i>Suspend and resume a program's operation</i>	397
	<i>Listing all signals supported by the OS</i>	399
12.6	Handling signals with custom actions	400
	<i>Global variables in Rust</i>	401
	<i>Using a global variable to indicate that shutdown has been initiated</i>	402
12.7	Sending application-defined signals	405
	<i>Understanding function pointers and their syntax</i>	405
12.8	Ignoring signals	407
12.9	Shutting down from deeply nested call stacks	408
	<i>Introducing the sjlj project</i>	409
	<i>Setting up intrinsics in a program</i>	409
	<i>Casting a pointer to another type</i>	412
	<i>Compiling the sjlj project</i>	413
	<i>sjlj project source code</i>	414
12.10	A note on applying these techniques to platforms without signals	417
12.11	Revising exceptions	417

*index* 419

# ***preface***

---

No one knows whether reading a technical book is going to be worth the effort. These books can be expensive, dull, and poorly written. Even worse, there's a good chance that you won't learn anything. Luckily, this book is written by someone who understands that.

This book's first aim is to teach you Rust. *Rust in Action* presents large, working projects to promote your learning. Over the course of the book, you'll write a database, a CPU emulator, an operating system kernel, and several other interesting projects. You'll even dabble with generative art. Each project is designed to enable you to explore the Rust programming language at your own pace. For those readers who know little Rust, there are many opportunities to expand the projects in whatever direction you choose.

There is more to learning a programming language than studying its syntax and semantics, however. You are also joining a community. Unfortunately, established communities can create invisible barriers for new entrants because of their shared knowledge, jargon, and practices.

One such barrier for many new Rust programmers is the concept of systems programming. Lots of programmers come to Rust without a background in that area. To compensate for this, *Rust in Action* has a second aim—to teach you systems programming. And, among other topics, you'll learn about how memory, digital time-keeping, and device drivers work in the book's 12 chapters. I hope this enables you to feel more comfortable when becoming a member of the Rust community. And we need you!

Our societies depend on software, yet critical security holes are accepted as normal and, perhaps, inevitable. Rust demonstrates that these are neither. Moreover, our computers are filled with bloated, energy-intensive applications. Rust provides a viable alternative for developing software that is less demanding on these finite resources.

*Rust in Action* is about empowerment. This book's ultimate objective is to convince you of that. Rust is not reserved for a select group of experts. It is a tool that's available for everyone. Well done for making it this far through your learning journey; it's my pleasure to take you a few more steps.

## *acknowledgments*

---

Thank you to Katie for preventing me from collapsing and for picking me up when I fell down anyway. Thanks also to Florence and Octavia for your hugs and smiles, even when Dad was unable to play because he was writing.

I'm indebted to so many that it feels unfair to list only a select few. There are many members of the Rust community who have supported the book's development. Thousands of readers submitted corrections, questions, and suggestions via the liveBook during the book's development. Every contribution has helped me refine the text. Thank you.

I'm especially grateful to a small number of readers, many of whom have become friends. To Ai Maiga, Ana Hobden, Andrew Meredith, Andréy Lesníkóv, Andy Grove, Arturo J. Pérez, Bruce Mitchener, Cecile Tonglet, Daniel Carosone, Eric Ridge, Esteban Kuber, Florian Gilcher, Ian Battersby, Jane Lusby, Javier Viola, Jonathan Turner, Lachezar Lechev, Luciano Mammino, Luke Jones, Natalie Bloomfield, Oleksandr Kalenik, Olivia Ifrim, Paul Faria, Paul J. Symonds, Philipp Gniewosz, Rod Elias, Stephen Oates, Steve Klabnik, Tannr Allard, Thomas Lockney, and William Brown; interacting with you over the last four years has been a special privilege.

To the book's reviewers, I extend my warm thanks to Afshin Mehrabani, Alastair Smith, Bryce Darling, Christoffer Fink, Christopher Haupt, Damian Esteban, Federico Hernandez, Geert Van Laethem, Jeff Lim, Johan Liseborn, Josh Cohen, Konark Modi, Marc Cooper, Morgan Nelson, Ramnivas Laddad, Riccardo Moschetti, Sanket Naik, Sumant Tambe, Tim van Deurzen, Tom Barber, Wade Johnson, William Brown, William Wheeler, and Yves Dorfsman. All of your comments were read. Many of the

improvements in the latter stages of the book's development are owed to your thoughtful feedback.

Two team members at Manning deserve special credit for their patience, professionalism, and positivity: Elesha Hyde and Frances Buran have skillfully guided the book through many, many drafts.

Thank you also to the rest of the development editors, including Bert Bates, Jerry Kuch, Mihaela Batinić, Rebecca Rinehart, René van den Berg, and Tim van Deurzen. My thanks also extends to the production editors, including Benjamin Berg, Deirdre Hiam, Jennifer Houle, and Paul Wells.

*Rust in Action* had 16 releases during its MEAP process, and these would have been impossible without the support of many. Thank you to Aleksandar Dragosavljević, Ana Romac, Eleonor Gardner, Ivan Martinović, Lori Weidert, Marko Rajkovic, Matko Hrvatin, Mehmed Pasic, Melissa Ice, Mihaela Batinic, Owen Roberts, Radmila Ercegovac, and Rejhana Markanovic.

Thanks also to the members of the marketing team, including Branko Latincic, Candace Gillhoolley, Cody Tankersley, Lucas Weber, and Stjepan Jureković. You've been a tremendous source of encouragement for me.

The wider Manning team has also been very responsive and helpful. To Aira Dučić, Andrew Waldron, Barbara Mirecki, Branko Latincic, Breckyn Ely, Christopher Kaufmann, Dennis Dalinnik, Erin Twohey, Ian Hough, Josip Maras, Julia Quinn, Lana Klasic, Linda Kotlyarsky, Lori Kehrwald, and Melody Dolab, thank you for your assistance during the book's development. And to Mike Stephens, thanks for kicking this whole life-changing process off. You warned me that it would be hard. You were right.

# *about this book*

---

*Rust in Action* is primarily intended for people who may have explored Rust's free material online, but who then have asked themselves, "What's next?" This book contains dozens of examples that are interesting and can be extended as creativity and time allow. Those examples allow the book's 12 chapters to cover a productive subset of Rust and many of the ecosystem's most important third-party libraries.

The code examples emphasize accessibility to beginners over elegant, idiomatic Rust. If you are already a knowledgeable Rust programmer, you may find yourself disagreeing with some style decisions in the examples. I hope that you will tolerate this for the sake of learners.

*Rust in Action* is not intended as a comprehensive reference text book. There are parts of the language and standard library that have been omitted. Typically, these are highly specialized and deserve specific treatment. Instead, this book aims to provide readers with enough basic knowledge and confidence to learn specialized topics when necessary. *Rust in Action* is also unique from the point of view of systems programming books as almost every example works on Microsoft Windows.

## ***Who should read this book***

Anyone who is interested in Rust, who learns by applying practical examples, or who is intimidated by the fact that Rust is a systems programming language will enjoy *Rust in Action*. Readers with prior programming experience will benefit most as some computer programming concepts are assumed.

## How this book is organized: A roadmap

*Rust in Action* has two parts. The first introduces Rust’s syntax and some of its distinctive characteristics. The second part applies the knowledge gained in part one to several projects. In each chapter, one or two new Rust concepts are introduced. That said, part 1 provides a quick-fire introduction to Rust:

- Chapter 1, “Introducing Rust,” explains why Rust exists and how to get started programming with it.
- Chapter 2, “Language foundations,” provides a solid base of Rust syntax. Examples include a Mandelbrot set renderer and a grep clone.
- Chapter 3, “Compound data types,” explains how to compose Rust data types and its error-handling facilities.
- Chapter 4, “Lifetimes, ownership, and borrowing,” discusses the mechanisms for ensuring that accessing data is always valid.

Part 2 applies Rust to introductory systems programming areas:

- Chapter 5, “Data in Depth,” covers how information is represented in digital computers with a special emphasis on how numbers are approximated. Examples include a bespoke number format and a CPU emulator.
- Chapter 6, “Memory,” explains the terms references, pointers, virtual memory, stack, and heap. Examples include a memory scanner and a generative art project.
- Chapter 7, “Files and storage,” explains the process for storing data structures into storage devices. Examples include a hex dump clone and a working database.
- Chapter 8, “Networking,” provides an explanation of how computers communicate by reimplementing HTTP multiple times, stripping away a layer of abstraction each time.
- Chapter 9, “Time and timekeeping,” explores the process for keeping track of time within a digital computer. Examples include a working NTP client.
- Chapter 10, “Processes, threads, and containers,” explains processes, threads, and related abstractions. Examples include a turtle graphics application and a parallel parser.
- Chapter 11, “Kernel,” describes the role of the operating system and how computers boot up. Examples include compiling your own bootloader and an operating system kernel.
- Chapter 12, “Signals, interrupts, and exceptions,” explains how the external world communicates with the CPU and operating systems.

The book is intended to be read linearly. Latter chapters assume knowledge taught in earlier ones. However, projects from each chapter are standalone. Therefore, you are welcome to jump backward and forward if there are topics that you would like to cover.

## About the code

The code examples in *Rust in Action* are written with the 2018 edition of Rust and have been tested with Windows and Ubuntu Linux. No special software is required outside of a working Rust installation. Installation instructions are provided in chapter 2.

This book contains many examples of source code both in numbered listings and inline with normal text. In both cases, source code is formatted in a fixed-width font, like this, to separate it from ordinary text. Sometimes code is also in **bold** to highlight code that has changed from the previous steps in the chapter, such as when a new feature is added to an existing line of code.

In many cases, the original source code has been reformatted; we've added line breaks and reworked indentation to accommodate the available page space in the book. In rare cases, even this was not enough, and listings include line-continuation markers (→). Additionally, comments in the source code have often been removed from the listings when the code is described in the text. Code annotations accompany many of the listings, highlighting important concepts.

## liveBook discussion forum

Purchase of *Rust in Action* includes free access to a private web forum run by Manning Publications where you can make comments about the book, ask technical questions, and receive help from the author and from other users:

- To access the forum, go to <https://livebook.manning.com/book/rust-in-action/welcome/v-16/>.
- You can also learn more about Manning's forums and the rules of conduct at this location: <https://livebook.manning.com/#!/discussion>.

Manning's commitment to our readers is to provide a venue where a meaningful dialogue between individual readers and between readers and the author can take place. It is not a commitment to any specific amount of participation on the part of the author, whose contribution to the forum remains voluntary (and unpaid). We suggest you try asking the author some challenging questions lest his interest stray! The forum and the archives of previous discussions will be accessible from the publisher's website as long as the book is in print.

## Other online resources

Tim can be found on social media as @timClicks. His primary channels are Twitter (<https://twitter.com/timclicks>), YouTube (<https://youtube.com/c/timclicks>), and Twitch (<https://twitch.tv/timclicks>). You are also welcome to join his Discord server at <https://discord.gg/vZBX2bDa7W>.

## *about the author*

---

**TIM McNAMARA** learned programming to assist with humanitarian relief projects around the world from his home in New Zealand. Over the last 15 years, Tim has become an expert in text mining, natural language processing, and data engineering. He is the organizer of Rust Wellington and hosts regular Rust programming tutorials in person and online via Twitch and YouTube.

## *about the cover illustration*

---

The figure on the cover of *Rust in Action* is captioned “Le maitre de chausson” or “The boxer.” The illustration is taken from a collection of works by many artists, edited by Louis Curmer and published in Paris in 1841. The title of the collection is *LesFrançais peints par eux-mêmes*, which translates as *The French People Painted by Themselves*. Each illustration is finely drawn and colored by hand, and the rich variety of drawing in the collection reminds us vividly of how culturally apart the world’s regions, towns, villages, and neighborhoods were just 200 years ago. Isolated from each other, people spoke different dialects and languages. In the streets or in the countryside, it was easy to identify where they lived and what their trade or station in life was just by their dress.

Dress codes have changed since then and the diversity by region, so rich at the time, has faded away. It is now hard to tell apart the inhabitants of different continents, let alone different towns or regions. Perhaps we have traded cultural diversity for a more varied personal life—certainly for a more varied and fast-paced technological life.

At a time when it is hard to tell one computer book from another, Manning celebrates the inventiveness and initiative of the computer business with book covers based on the rich diversity of regional life of two centuries ago, brought back to life by pictures from collections such as this one.



# Introducing Rust



## This chapter covers

- Introducing Rust's features and goals
- Exposing Rust's syntax
- Discussing where to use Rust and when to avoid it
- Building your first Rust program
- Explaining how Rust compares to object-oriented and wider languages

Welcome to Rust—the empowering programming language. Once you scratch its surface, you will not only find a programming language with unparalleled speed and safety, but one that is enjoyable enough to use every day.

When you begin to program in Rust, it's likely that you will want to continue to do so. And this book, *Rust in Action*, will build your confidence as a Rust programmer. But it will not teach you how to program from the beginning. This book is intended to be read by people who are considering Rust as their next language and for those who enjoy implementing practical working examples. Here is a list of some of the larger examples this book includes:

- Mandelbrot set renderer
- A grep clone

- CPU emulator
- Generative art
- A database
- HTTP, NTP, and hexdump clients
- LOGO language interpreter
- Operating system kernel

As you may gather from scanning through that list, reading this book will teach you more than just Rust. It also introduces you to *systems programming* and *low-level programming*. As you work through *Rust in Action*, you'll learn about the role of an operating system (OS), how a CPU works, how computers keep time, what pointers are, and what a data type is. You will gain an understanding of how the computer's internal systems interoperate. Learning more than syntax, you will also see why Rust was created and the challenges that it addresses.

## 1.1 **Where is Rust used?**

Rust has won the “most loved programming language” award in Stack Overflow’s annual developer survey every year in 2016-2020. Perhaps that’s why large technology leaders such as the following have adopted Rust:

- Amazon Web Services (AWS) has used Rust since 2017 for its serverless computing offerings, AWS Lambda and AWS Fargate. With that, Rust has gained further inroads. The company has written the Bottlerocket OS and the AWS Nitro System to deliver its Elastic Compute Cloud (EC2) service.<sup>1</sup>
- Cloudflare develops many of its services, including its public DNS, serverless computing, and packet inspection offerings with Rust.<sup>2</sup>
- Dropbox rebuilt its backend warehouse, which manages exabytes of storage, with Rust.<sup>3</sup>
- Google develops parts of Android, such as its Bluetooth module, with Rust. Rust is also used for the crosvm component of Chrome OS and plays an important role in Google’s new operating system, Fuchsia.<sup>4</sup>
- Facebook uses Rust to power Facebook’s web, mobile, and API services, as well as parts of HHVM, the HipHop virtual machine used by the Hack programming language.<sup>5</sup>
- Microsoft writes components of its Azure platform including a security daemon for its Internet of Things (IoT) service in Rust.<sup>6</sup>

<sup>1</sup> See “How our AWS Rust team will contribute to Rust’s future successes,” <http://mng.bz/BR4J>.

<sup>2</sup> See “Rust at Cloudflare,” <https://news.ycombinator.com/item?id=17077358>.

<sup>3</sup> See “The Epic Story of Dropbox’s Exodus From the Amazon Cloud Empire,” <http://mng.bz/d45Q>.

<sup>4</sup> See “Google joins the Rust Foundation,” <http://mng.bz/ryOX>.

<sup>5</sup> See “HHVM 4.20.0 and 4.20.1,” <https://hhvm.com/blog/2019/08/27/hhvm-4.20.0.html>.

<sup>6</sup> See <https://github.com/Azure/iotedge/tree/master/edgelet>.

- Mozilla uses Rust to enhance the Firefox web browser, which contains 15 million lines of code. Mozilla's first two Rust-in-Firefox projects, its MP4 metadata parser and text encoder/decoder, led to overall performance and stability improvements.
- GitHub's npm, Inc., uses Rust to deliver "upwards of 1.3 billion package downloads per day."<sup>7</sup>
- Oracle developed a container runtime with Rust to overcome problems with the Go reference implementation.<sup>8</sup>
- Samsung, via its subsidiary SmartThings, uses Rust in its *Hub*, which is the firmware backend for its Internet of Things (IoT) service.

Rust is also productive enough for fast-moving startups to deploy it. Here are a few examples:

- Sourcegraph uses Rust to serve syntax highlighting across all of its languages.<sup>9</sup>
- Figma employs Rust in the performance-critical components of its multi-player server.<sup>10</sup>
- Parity develops its client to the Ethereum blockchain with Rust.<sup>11</sup>

## 1.2 Advocating for Rust at work

What is it like to advocate for Rust at work? After overcoming the initial hurdle, it tends to go well. A 2017 discussion, reprinted below, provides a nice anecdote. One member of Google's Chrome OS team discusses what it was like to introduce the language to the project:<sup>12</sup>

indy on Sept 27, 2017  
Is Rust an officially sanctioned language at Google?

zaxcellent on Sept 27, 2017  
Author here: Rust is not officially sanctioned at Google, but there are pockets of folks using it here. The trick with using Rust in this component was convincing my coworkers that no other language was right for job, which I believe to be the case in this instance.

That being said, there was a ton of work getting Rust to play nice within the Chrome OS build environment. The Rust folks have been super helpful in answering my questions though.

ekidd on Sept 27, 2017  
> The trick with using Rust in this component was convincing my

<sup>7</sup> See "Rust Case Study: Community makes Rust an easy choice for npm," <http://mng.bz/xm9B>.

<sup>8</sup> See "Building a Container Runtime in Rust," <http://mng.bz/d40Q>.

<sup>9</sup> See "HTTP code syntax highlighting server written in Rust," [https://github.com/sourcegraph/syntect\\_server](https://github.com/sourcegraph/syntect_server).

<sup>10</sup> See "Rust in Production at Figma," <https://www.figma.com/blog/rust-in-production-at-figma/>.

<sup>11</sup> See "The fast, light, and robust EVM and WASM client," <https://github.com/paritytech/parity-ethereum>.

<sup>12</sup> See "Chrome OS KVM—A component written in Rust," <https://news.ycombinator.com/item?id=15346557>.

> coworkers that no other language was right for job, which I believe  
 > to be the case in this instance.

I ran into a similar use case in one of my own projects—a vobsub subtitle decoder, which parses complicated binary data, and which I someday want to run as web service. So obviously, I want to ensure that there are no vulnerabilities in my code.

I wrote the code in Rust, and then I used 'cargo fuzz' to try and find vulnerabilities. After running a billion(!) fuzz iterations, I found 5 bugs (see the 'vobsub' section of the trophy case for a list <https://github.com/rust-fuzz/trophy-case>).

Happily, not \_one\_ of those bugs could actually be escalated into an actual exploit. In each case, Rust's various runtime checks successfully caught the problem and turned it into a controlled panic. (In practice, this would restart the web server cleanly.)

So my takeaway from this was that whenever I want a language (1) with no GC, but (2) which I can trust in a security-critical context, Rust is an excellent choice. The fact that I can statically link Linux binaries (like with Go) is a nice plus.

Manishearth on Sept 27, 2017

> Happily, not one of those bugs could actually be escalated into  
 > an actual exploit. In each case, Rust's various runtime checks  
 > successfully caught the problem and turned it into a controlled  
 > panic.

This has been more or less our experience with fuzzing rust code in firefox too, fwiw. Fuzzing found a lot of panics (and debug assertions / "safe" overflow assertions). In one case it actually found a bug that had been under the radar in the analogous Gecko code for around a decade.

From this excerpt, we can see that language adoption has been “bottom up” by engineers looking to overcome technical challenges in relatively small projects. Experience gained from these successes is then used as evidence to justify undertaking more ambitious work.

In the time since late 2017, Rust has continued to mature and strengthen. It has become an accepted part of Google’s technology landscape, and is now an officially sanctioned language within the Android and Fuchsia operating systems.

### 1.3 *A taste of the language*

This section gives you a chance to experience Rust firsthand. It demonstrates how to use the compiler and then moves on to writing a quick program. We tackle full projects in later chapters.

**NOTE** To install Rust, use the official installers provided at <https://rustup.rs/>.

### 1.3.1 Cheating your way to “Hello, world!”

The first thing that most programmers do when they reach for a new programming language is to learn how to print “Hello, world!” to the console. You’ll do that too, but with flair. You’ll verify that everything is in working order *before* you encounter annoying syntax errors.

If you use Windows, open the Rust command prompt that is available in the Start menu after installing Rust. Then execute this command:

```
C:\> cd %TMP%
```

If you are running Linux or macOS, open a Terminal window. Once open, enter the following:

```
$ cd $TMP
```

From this point forward, the commands for all operating systems should be the same. If you installed Rust correctly, the following three commands will display “Hello, world!” on the screen (as well as a bunch of other output):

```
$ cargo new hello
$ cd hello
$ cargo run
```

Here is an example of what the entire session looks like when running cmd.exe on MS Windows:

```
C:\> cd %TMP%
C:\Users\Tim\AppData\Local\Temp\> cargo new hello
    Created binary (application) `hello` project
C:\Users\Tim\AppData\Local\Temp\> cd hello
C:\Users\Tim\AppData\Local\Temp\hello\> cargo run
    Compiling hello v0.1.0 (file:///C:/Users/Tim/AppData/Local/Temp/hello)
    Finished dev [unoptimized + debuginfo] target(s) in 0.32s
        Running `target\debug\hello.exe`
Hello, world!
```

And on Linux or macOS, your console would look like this:

```
$ cd $TMP
$ cargo new hello
    Created binary (application) `hello` package
$ cd hello
$ cargo run
    Compiling hello v0.1.0 (/tmp/hello)
```

```
Finished dev [unoptimized + debuginfo] target(s) in 0.26s
  Running `target/debug/hello`
Hello, world!
```

If you have made it this far, fantastic! You have run your first Rust code without needing to write any Rust. Let's take a look at what just happened.

Rust's cargo tool provides both a build system and a package manager. That means cargo knows how to convert your Rust code into executable binaries and also can manage the process of downloading and compiling the project's dependencies.

`cargo new` creates a project for you that follows a standard template. The `tree` command can reveal the default project structure and the files that are created after issuing `cargo new`:

```
$ tree hello
hello
├── Cargo.toml
└── src
    └── main.rs

1 directory, 2 files
```


All Rust projects created with cargo have the same structure. In the base directory, a file called `Cargo.toml` describes the project's metadata, such as the project's name, its version, and its dependencies. Source code appears in the `src` directory. Rust source code files use the `.rs` filename extension. To view the files that `cargo new` creates, use the `tree` command.

The next command that you executed was `cargo run`. This line is much simpler to grasp, but cargo actually did much more work than you realized. You asked cargo to run the project. As there was nothing to actually run when you invoked the command, it decided to compile the code in debug mode on your behalf to provide maximal error information. As it happens, the `src/main.rs` file always includes a “Hello, world!” stub. The result of that compilation was a file called `hello` (or `hello.exe`). The `hello` file was executed, and the result printed to your screen.

Executing `cargo run` has also added new files to the project. We now have a `Cargo.lock` file in the base of our project and a `target/` directory. Both that file and the directory are managed by cargo. Because these are artifacts of the compilation process, we won't need to touch these. `Cargo.lock` is a file that specifies the exact version numbers of all the dependencies so that future builds are reliably built the same way until `Cargo.toml` is modified.

Running `tree` again reveals the new structure created by invoking `cargo run` to compile the `hello` project:

```
$ tree --dirsfirst hello
hello
├── src
│   └── main.rs
```



For getting things up and running, well done! Now that we've cheated our way to "Hello, World!", let's get there via the long way.

### 1.3.2 Your first Rust program

For our first program, we want to write something that outputs the following text in multiple languages:

```
Hello, world!
Grüß Gott!
ハロー・ワールド
```

You have probably seen the first line in your travels. The other two are there to highlight a few of Rust's features: easy iteration and built-in support for Unicode. For this program, we'll use cargo to create it as before. Here are the steps to follow:

- 1 Open a console prompt.
- 2 Run `cd %TMP%` on MS Windows; otherwise `cd $TMP`.
- 3 Run `cargo new hello2` to create a new project.
- 4 Run `cd hello2` to move into the project's root directory.
- 5 Open the file `src/main.rs` in a text editor.
- 6 Replace the text in that file with the text in listing 1.1.

The code for the following listing is in the source code repository. Open `ch1/ch1-hello2/src/hello2.rs`.

**Listing 1.1 "Hello World!" in three languages**

```

The exclamation mark indicates the use of
a macro, which we'll discuss shortly.
1 fn greet_world() {
2     println!("Hello, world!");           ←
3     let southern_germany = "Grüß Gott!"; ←
4     let japan = "ハロー・ワールド";
5     let regions = [southern_germany, japan];
6     for region in regions.iter() {
7         println!("{}", &region);          ←
8     }
9 }
```

**Assignment in Rust, more properly called variable binding, uses the `let` keyword.**

**Unicode support is provided out of the box.**

**Many types can have an `iter()` method to return an iterator.**

**The ampersand “borrows” region for read-only access.**

**Array literals use square brackets.**

```

10
11 fn main() {
12     greet_world();      ← Calls a function. Note
13 }
```

that parentheses follow  
the function name.

Now that `src/main.rs` is updated, execute `cargo run` from the `hello2/` directory. You should see three greetings appear after some output generated from `cargo` itself:

```

$ cargo run
Compiling hello2 v0.1.0 (/path/to/ch1/ch1-hello2)
  Finished dev [unoptimized + debuginfo] target(s) in 0.95s
    Running `target/debug/hello2`  

Hello, world!
Grüß Gott!
ハロー・ワールド
```

Let's take a few moments to touch on some of the interesting elements of Rust from listing 1.2.

One of the first things that you are likely to notice is that strings in Rust are able to include a wide range of characters. Strings are guaranteed to be encoded as UTF-8. This means that you can use non-English languages with relative ease.

The one character that might look out of place is the exclamation mark after `println!`. If you have programmed in Ruby, you may be used to thinking that it is used to signal a destructive operation. In Rust, it signals the use of a *macro*. Macros can be thought of as fancy functions for now. These offer the ability to avoid boilerplate code. In the case of `println!`, there is a lot of type detection going on under the hood so that arbitrary data types can be printed to the screen.

## 1.4 **Downloading the book's source code**

In order to follow along with the examples in this book, you might want to access the source code for the listings. For your convenience, source code for every example is available from two sources:

- <https://manning.com/books/rust-in-action>
- <https://github.com/rust-in-action/code>

## 1.5 **What does Rust look and feel like?**

Rust is the programming language that allows Haskell and Java programmers to get along. Rust comes close to the high-level, expressive feel of dynamic languages like Haskell and Java while achieving low-level, bare-metal performance.

We looked at a few “Hello, world!” examples in section 1.3, so let's try something slightly more complex to get a better feel for Rust's features. Listing 1.2 provides a quick look at what Rust can do for basic text processing. The source code for this listing is in the `ch1/ch1-penguins/src/main.rs` file. Some features to notice include

- *Common control flow mechanisms*—This includes for loops and the continue keyword.
- *Method syntax*—Although Rust is not object-oriented as it does not support inheritance, it carries over this feature of object-oriented languages.
- *Higher-order programming*—Functions can both accept and return functions. For example, line 19 (.map(|field| field.trim())) includes a *closure*, also known as an *anonymous function* or *lambda function*.
- *Type annotations*—Although relatively rare, these are occasionally required as a hint to the compiler (for example, see line 27 beginning with if let Ok(length)).
- *Conditional compilation*—In the listing, lines 21–24 (if cfg!(...);) are not included in release builds of the program.
- *Implicit return*—Rust provides a return keyword, but it's usually omitted. Rust is an *expression-based language*.

**Listing 1.2 Example of Rust code showing some basic processing of CSV data**

```

1 fn main() {
2     let penguin_data = "\n
3         common_name,length (cm)
4         Little penguin,33
5         Yellow-eyed penguin,65
6         Fiordland penguin,60
7         Invalid,data
8     ";
9
10    let records = penguin_data.lines();
11
12    for (i, record) in records.enumerate() {
13        if i == 0 || record.trim().len() == 0 {
14            continue;
15        }
16
17        let fields: Vec<_> = record
18            .split(',')
19            .map(|field| field.trim())
20            .collect();
21        if cfg!(debug_assertions) {
22            eprintln!("debug: {:?} -> {:?}", record, fields);
23        }
24
25        let name = fields[0];
26        if let Ok(length) = fields[1].parse::<f32>() {
27            println!("{} , {}cm", name, length);
28        }
29    }
30 }
31 }
```

The diagram illustrates various features of the Rust code in Listing 1.2 with callout boxes:

- Splits record into fields**: Points to the line `let fields: Vec<\_> = record .split(',') .map(|field| field.trim()) .collect();` which splits each CSV record into individual fields.
- Builds a collection of fields**: Points to the line `if cfg!(debug\_assertions) {` which uses the `cfg!` macro to check configuration at compile time.
- Executable projects require a main() function**: Points to the line `fn main()`.
- Escapes the trailing newline character**: Points to the backslash before the final closing brace on line 9.
- Starts with a line of text**: Points to the first two lines of the CSV data.
- Trims whitespace of each field**: Points to the line `.map(|field| field.trim())`.
- cfg! checks configuration at compile time.**: Points to the line `if cfg!(debug_assertions) {`.
- eprintln! prints to standard error (stderr).**: Points to the line `eprintln!("debug: {:?} -> {:?}", record, fields);`.
- Attempts to parse field as a floating-point number**: Points to the line `if let Ok(length) = fields[1].parse::<f32>()`.
- eprintln! prints to standard out (stdout).**: Points to the line `println!("{} , {}cm", name, length);`.

Listing 1.2 might be confusing to some readers, especially those who have never seen Rust before. Here are some brief notes before moving on:

- On line 17, the `fields` variable is annotated with the type `Vec<_>`. `Vec` is shorthand for `_vector_`, a collection type that can expand dynamically. The underscore (`_`) instructs Rust to infer the type of the elements.
- On lines 22 and 28, we instruct Rust to print information to the console. The `println!` macro prints its arguments to standard out (`stdout`), whereas `eprintln!` prints to standard error (`stderr`).

Macros are similar to functions except that instead of returning data, these return code. Macros are often used to simplify common patterns.

`eprintln!` and `println!` both use a string literal with an embedded mini-language in their first argument to control their output. The `{}` placeholder tells Rust to use a programmer-defined method to represent the value as a string rather than the default representation available with `{:?}`.

- Line 27 contains some novel features. `if let Ok(length) = fields[1].parse::()` reads as “attempt to parse `fields[1]` as a 32-bit floating-point number and, if that is successful, then assign the number to the `length` variable.”

The `if let` construct is a concise method of conditionally processing data that also provides a local variable assigned to that data. The `parse()` method returns `Ok(T)` (where `T` stands for any type) when it can successfully parse the string; otherwise, it returns `Err(E)` (where `E` stands for an error type). The effect of `if let Ok(T)` is to skip any error cases like the one that’s encountered while processing the line `Invalid, data`.

When Rust is unable to infer the types from the surrounding context, it will ask for you to specify those. The call to `parse()` includes an inline type annotation as `parse::<f32>()`.

Converting source code into an executable file is called *compiling*. To compile Rust code, we need to install the Rust compiler and run it against the source code. To compile listing 1.2, follow these steps:

- 1 Open a console prompt (such as cmd.exe, PowerShell, Terminal, or Alacritty).
- 2 Move to the `ch1/ch1-penguins` directory (not `ch1/ch1-penguins/src`) of the source code you downloaded in section 1.4.
- 3 Execute `cargo run`. Its output is shown in the following code snippet:

```
$ cargo run
Compiling ch1-penguins v0.1.0 (..../code/ch1/ch1-penguins)
Finished dev [unoptimized + debuginfo] target(s) in 0.40s
    Running `target/debug/ch1-penguins`
dbg: " Little penguin,33" -> ["Little penguin", "33"]
Little penguin, 33cm
dbg: " Yellow-eyed penguin,65" -> ["Yellow-eyed penguin", "65"]
Yellow-eyed penguin, 65cm
dbg: " Fiordland penguin,60" -> ["Fiordland penguin", "60"]
Fiordland penguin, 60cm
dbg: " Invalid,data" -> ["Invalid", "data"]
```

You probably noticed the distracting lines starting with `dbg!`. We can eliminate these by compiling a *release build* using cargo’s `--release` flag. This conditional compilation functionality is provided by the `cfg!(debug_assertions) { ... }` block within lines 22–24 of listing 1.2. Release builds are much faster at runtime, but incur longer compilation times:

```
$ cargo run --release
Compiling ch1-penguins v0.1.0 (....code/ch1/ch1-penguins)
Finished release [optimized] target(s) in 0.34s
    Running `target/release/ch1-penguins`
Little penguin, 33cm
Yellow-eyed penguin, 65cm
Fiordland penguin, 60cm
```

It’s possible to further reduce the output by adding the `-q` flag to cargo commands. `-q` is shorthand for *quiet*. The following snippet shows what that looks like:

```
$ cargo run -q --release
Little penguin, 33cm
Yellow-eyed penguin, 65cm
Fiordland penguin, 60cm
```

Listing 1.1 and listing 1.2 were chosen to pack as many representative features of Rust into examples that are easy to understand. Hopefully these demonstrated that Rust programs have a high-level feel, paired with low-level performance. Let’s take a step back from specific language features now and consider some of the thinking behind the language and where it fits within the programming language ecosystem.

## 1.6 What is Rust?

Rust’s distinguishing feature as a programming language is its ability to prevent invalid data access at compile time. Research projects by Microsoft’s Security Response Center and the Chromium browser project both suggest that issues relating to invalid data access account for approximately 70% of serious security bugs.<sup>13</sup> Rust eliminates that class of bugs. It guarantees that your program is *memory-safe* without imposing any runtime costs.

Other languages can provide this level of safety, but these require adding checks that execute while your program is running, thus slowing it down. Rust manages to break out of this continuum, creating its own space as illustrated by figure 1.1.

Rust’s distinguishing feature as a professional community is its willingness to explicitly include values into its decision-making process. This ethos of inclusion is pervasive. Public messaging is welcoming. All interactions within the Rust community are governed by its code of conduct. Even the Rust compiler’s error messages are ridiculously helpful.

---

<sup>13</sup> See the articles “We need a safer systems programming language,” <http://mng.bz/VdN5> and “Memory safety,” <http://mng.bz/xm7B> for more information.




Figure 1.1 Rust provides both safety and control. Other languages have tended to trade one against the other.

Until late 2018, visitors to the Rust home page were greeted with the (technically heavy) message, “Rust is a systems programming language that runs blazingly fast, prevents segfaults, and guarantees thread safety.” At that point, the community implemented a change to its wording to put its users (and its potential users) at the center (table 1.1).

**Table 1.1 Rust slogans over time. As Rust has developed its confidence, it has increasingly embraced the idea of acting as a facilitator and supporter of everyone wanting to achieve their programming aspirations.**

Until late 2018	From that point onward
“Rust is a systems programming language that runs blazingly fast, prevents segfaults, and guarantees thread safety.”	“Empowering everyone to build reliable and efficient software.”

Rust is labelled as a *systems programming language*, which tends to be seen as quite a specialized, almost esoteric branch of programming. However, many Rust programmers have discovered that the language is applicable to many other domains. Safety, productivity, and control are useful in all software engineering projects. Moreover, the Rust community’s inclusiveness means that the language benefits from a steady stream of new voices with diverse interests.

Let’s flesh out those three goals: safety, productivity, and control. What are these and why do these matter?

## 16.1 Goal of Rust: Safety

Rust programs are free from

- *Dangling pointers*—Live references to data that has become invalid over the course of the program (see listing 1.3)

- *Data races*—The inability to determine how a program will behave from run to run because external factors change (see listing 1.4)
- *Buffer overflow*—An attempt to access the 12th element of an array with only 6 elements (see listing 1.5)
- *Iterator invalidation*—An issue caused by something that is iterated over after being altered midway through (see listing 1.6)

When programs are compiled in debug mode, Rust also protects against *integer overflow*. What is integer overflow? Well, integers can only represent a finite set of numbers; these have a fixed-width in memory. Integer overflow is what happens when the integers hit their limit and flow over to the beginning again.

The following listing shows a dangling pointer. Note that you'll find this source code in the ch1/ch1-cereals/src/main.rs file.

### Listing 1.3 Attempting to create a dangling pointer

```

1 #[derive(Debug)]
2 enum Cereal {
3     Barley, Millet, Rice,
4     Rye, Spelt, Wheat,
5 }
6
7 fn main() {
8     let mut grains: Vec<Cereal> = vec![];
9     grains.push(Cereal::Rye);
10    drop(grains);
11    println!("{:?}", grains);
12 }
```

Annotations for Listing 1.3:

- An arrow points to the `#[derive(Debug)]` attribute with the text: "Allows the `println!` macro to print the Cereal enum".
- An arrow points to the `enum` keyword with the text: "An enum (enumeration) is a type with a fixed number of legal variants."
- An arrow points to the `vec![]` constructor with the text: "Initializes an empty vector of Cereal".
- An arrow points to the `push` method with the text: "Adds one item to the grains vector".
- An arrow points to the `drop` statement with the text: "Deletes grains and its contents".
- An arrow points to the `println` statement with the text: "Attempts to access the deleted value".

Listing 1.3 contains a pointer within `grains`, which is created on line 8. `Vec<Cereal>` is implemented with an internal pointer to an underlying array. But the listing does not compile. An attempt to do so triggers an error message that complains about attempting to “borrow” a “moved” value. Learning how to interpret that error message and to fix the underlying error are topics for the pages to come. Here's the output from attempting to compile the code for listing 1.4:

```

$ cargo run
Compiling ch1-cereals v0.1.0 (/rust-in-action/code/ch1/ch1-cereals)
error[E0382]: borrow of moved value: `grains`
--> src/main.rs:12:22
 |
8 |     let mut grains: Vec<Cereal> = vec![];
|     ----- move occurs because `grains` has type
|             `std::vec::Vec<Cereal>`, which does not implement
|                 the `Copy` trait
9 |     grains.push(Cereal::Rye);
10 |     drop(grains);
|     ----- value moved here
11 | 
```

```

12 |     println!("{}: {}", grains);
|          ^^^^^^ value borrowed here after move
|
error: aborting due to previous error

For more information about this error, try `rustc --explain E0382`.
error: could not compile `ch1-cereals`.
```

Listing 1.4 shows an example of a data race condition. If you remember, this condition results from the inability to determine how a program behaves from run to run due to changing external factors. You'll find this code in the ch1/ch1-race/src/main.rs file.

#### Listing 1.4 Example of Rust preventing a race condition

```

1 use std::thread;           ← Brings multi-threading
2 fn main() {               into local scope
3     let mut data = 100;
4
5     thread::spawn(|| { data = 500; });
6     thread::spawn(|| { data = 1000; }); | thread::spawn() takes a
7     println!("{}: {}", data);           | closure as an argument.
8 }
```

If you are unfamiliar with the term *thread*, the upshot is that this code is not deterministic. It's impossible to know what value data will hold when main() exits. On lines 6 and 7 of the listing, two threads are created by calls to `thread::spawn()`. Each call takes a closure as an argument, denoted by vertical bars and curly braces (e.g., `|| {...}`). The thread spawned on line 5 is attempting to set the data variable to 500, whereas the thread spawned on line 6 is attempting to set it to 1,000. Because the scheduling of threads is determined by the OS rather than the program, it's impossible to know if the thread defined first will be the one that runs first.

Attempting to compile listing 1.5 results in a stampede of error messages. Rust does not allow multiple places in an application to have write access to data. The code attempts to allow this in three places: once within the main thread running `main()` and once in each child thread created by `thread::spawn()`. Here's the compiler message:

```

$ cargo run
Compiling ch1-race v0.1.0 (rust-in-action/code/ch1/ch1-race)
error[E0373]: closure may outlive the current function, but it
    borrows `data`, which is owned by the current function
--> src/main.rs:6:19
|
6 |     thread::spawn(|| { data = 500; });
|          ^^^ ----- `data` is borrowed here
|          |
|          may outlive borrowed value `data`
|
note: function requires argument type to outlive ``static``
--> src/main.rs:6:5
```

```

6 |     thread::spawn(|| { data = 500; });
|     ^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^^
help: to force the closure to take ownership of `data`  

      (and any other referenced variables), use the `move` keyword
6 |     thread::spawn(move || { data = 500; });
|     ^^^^
...           ↙ Three other errors omitted.
error: aborting due to 4 previous errors

Some errors have detailed explanations: E0373, E0499, E0502.  

For more information about an error, try `rustc --explain E0373`.  

error: could not compile `ch1-race`.

```

Listing 1.5 provides an example of a buffer overflow. A buffer overflow describes situations where an attempt is made to access items in memory that do not exist or that are illegal. In our case, an attempt to access fruit[4] results in the program crashing, as the fruit variable only contains three fruit. The source code for this listing is in the file ch1/ch1-fruit/src/main.rs.

#### Listing 1.5 Example of invoking a panic via a buffer overflow

```

1 fn main() {
2     let fruit = vec!['apple', 'banana', 'orange'];
3
4     let buffer_overflow = fruit[4];    ← Rust will cause a crash rather
5     assert_eq!(buffer_overflow, 'apple') ← than assign an invalid memory
6 }                                     ← location to a variable.
                                         ← assert_eq!() tests that
                                         ← arguments are equal.

```

When listing 1.5 is compiled and executed, you'll encounter this error message:

```

$ cargo run
Compiling ch1-fruit v0.1.0 (/rust-in-action/code/ch1/ch1-fruit)
Finished dev [unoptimized + debuginfo] target(s) in 0.31s
Running `target/debug/ch1-fruit`
thread 'main' panicked at 'index out of bounds:
the len is 3 but the index is 4', src/main.rs:3:25
note: run with `RUST_BACKTRACE=1` environment variable
      to display a backtrace

```

The next listing shows an example of iterator invalidation, where an issue is caused by something that's iterated over after being altered midway through. The source code for this listing is in ch1/ch1-letters/src/main.rs.

#### Listing 1.6 Attempting to modify an iterator while iterating over it

```

1 fn main() {
2     let mut letters = vec![          ← Creates a mutable
3         "a", "b", "c"             ← vector letters
4     ];

```

```

5
6     for letter in letters {
7         println!("{}", letter);
8         letters.push(letter.clone());
9     }
10 }

```

Copies each letter  
and appends it to the  
end of letters

Listing 1.6 fails to compile because Rust does not allow the `letters` variable to be modified within the iteration block. Here's the error message:

```

$ cargo run
Compiling ch1-letters v0.1.0 (/rust-in-action/code/ch1/ch1-letters)
error[E0382]: borrow of moved value: `letters`
--> src/main.rs:8:7
|
2 |     let mut letters = vec![
|         ----- move occurs because `letters` has type
|         `std::vec::Vec<&str>`, which does not
|         implement the `Copy` trait
...
6 |     for letter in letters {
|         -----
|         |
|             `letters` moved due to this implicit call
|             to `~.into_iter()`
|             help: consider borrowing to avoid moving
|             into the for loop: `&letters`
7 |     println!("{}", letter);
8 |     letters.push(letter.clone());
|     ^^^^^^^ value borrowed here after move
|
error: aborting due to previous error

```

For more information about this error, try `rustc --explain E0382`.  
error: could not compile `ch1-letters`.

To learn more, run the command again with `--verbose`.

While the language of the error message is filled with jargon (*borrow*, *move*, *trait*, and so on), Rust has protected the programmer from stepping into a trap that many others fall into. And fear not—that jargon will become easier to understand as you work through the first few chapters of this book.

Knowing that a language is safe provides programmers with a degree of liberty. Because they know their program won't implode, they become much more willing to experiment. Within the Rust community, this liberty has spawned the expression *fearless concurrency*.

## 16.2 Goal of Rust: Productivity

When given a choice, Rust prefers the option that is easiest for the developer. Many of its more subtle features are productivity boosts. But programmer productivity is a difficult concept to demonstrate through an example in a book. Let's start with something

that can snag beginners—using assignment (=) within an expression that should use an equality (==) test:

```
1 fn main() {
2     let a = 10;
3
4     if a = 10 {
5         println!("a equals ten");
6     }
7 }
```

In Rust, the preceding code fails to compile. The Rust compiler generates the following message:

```
error[E0308]: mismatched types
--> src/main.rs:4:8
|
4 |     if a = 10 {
|     ^^^^^^
|     |
|     expected `bool`, found `()`  

|     help: try comparing for equality: `a == 10`  

|
|     error: aborting due to previous error
```

For more information about this error, try `rustc --explain E0308`.  
 error: could not compile `playground`.

To learn more, run the command again with --verbose.

At first, “mismatched types” might feel like a strange error message to encounter. Surely we can test variables for equality against integers.

After some thought, it becomes apparent why the if test receives the wrong type. The if is not receiving an integer. It’s receiving the result of an assignment. In Rust, this is the blank type: (). () is pronounced *unit*.<sup>14</sup>

When there is no other meaningful return value, expressions return (). As the following shows, adding a second equals sign on line 4 results in a working program that prints a equals ten:

```
1 fn main() {
2     let a = 10;
3
4     if a == 10 {           ←
5         println!("a equals ten");
6     }
7 }
```

**Using a valid assignment operator (==) allows the program to compile.**

<sup>14</sup> The name *unit* reveals some of Rust’s heritage as a descendant of the ML family of programming languages that includes OCaml and F#. The term stems from mathematics. Theoretically, a unit type only has a single value. Compare this with Boolean types that have two values, true or false, or strings that have an infinite number of valid values.

Rust has many ergonomic features. It offers generics, sophisticated data types, pattern matching, and closures.<sup>15</sup> Those who have worked with other ahead-of-time compilation languages are likely to appreciate Rust’s build system and its comprehensive package manager: cargo.

At first glance, we see that cargo is a front end for rustc, the Rust compiler, but cargo provides several additional utilities including the following:

- cargo new creates a skeleton Rust project in a new directory (cargo init uses the current directory).
- cargo build downloads dependencies and compiles the code.
- cargo run executes cargo build and then also runs the resulting executable file.
- cargo doc builds HTML documentation for every dependency in the current project.

### 1.6.3 **Goal of Rust: Control**

Rust offers programmers fine-grained control over how data structures are laid out in memory and their access patterns. While Rust uses sensible defaults that align with its “zero cost abstractions” philosophy, those defaults do not suit all situations.

At times, it is imperative to manage your application’s performance. It might matter to you that data is stored in the *stack* rather than on the *heap*. Perhaps, it might make sense to add *reference counting* to create a shared reference to a value. Occasionally, it might be useful to create one’s own type of *pointer* for a particular access pattern. The design space is large and Rust provides the tools to allow you to implement your preferred solution.

**NOTE** If terms such as *stack*, *heap*, and *reference counting* are new, don’t put the book down! We’ll spend lots of time explaining these and how they work together throughout the rest of the book.

Listing 1.7 prints the line `a: 10, b: 20, c: 30, d: Mutex { data: 40 }`. Each representation is another way to store an integer. As we progress through the next few chapters, the trade-offs related to each level become apparent. For the moment, the important thing to remember is that the menu of types is comprehensive. You are welcome to choose exactly what’s right for your specific use case.

Listing 1.7 also demonstrates multiple ways to create integers. Each form provides differing semantics and runtime characteristics. But programmers retain full control of the trade-offs that they want to make.

---

<sup>15</sup> If these terms are unfamiliar, do keep reading. These are explained throughout the book. They are language features that you will miss in other languages.

### Listing 1.7 Multiple ways to create integer values

```

1 use std::rc::Rc;
2 use std::sync::{Arc, Mutex};
3
4 fn main() {
5     let a = 10;
6     let b = Box::new(20);
7     let c = Rc::new(Box::new(30));
8     let d = Arc::new(Mutex::new(40));
9     println!("a: {:?}", a, b: {:?}", b, c: {:?}", c, d: {:?}", d);
10 }

```

To understand why Rust is doing something the way it is, it can be helpful to refer back to these three principles:

- The language's first priority is safety.
- Data within Rust is immutable by default.
- Compile-time checks are strongly preferred. Safety should be a "zero-cost abstraction."

## 1.7 Rust's big features

Our tools shape what we believe we can create. Rust enables you to build the software that you want to make, but were too scared to try. What kind of tool is Rust? Flowing from the three principles discussed in the last section are three overarching features of the language:

- Performance
- Concurrency
- Memory efficiency

### 17.1 Performance

Rust offers all of your computer's available performance. Famously, Rust does not rely on a garbage collector to provide its memory safety.

There is, unfortunately, a problem with promising you faster programs: the speed of your CPU is fixed. Thus, for software to run faster, it needs to do less. Yet, the language is large. To resolve this conflict, Rust pushes the burden onto the compiler.

The Rust community prefers a bigger language with a compiler that does more, rather than a simpler language where the compiler does less. The Rust compiler aggressively optimizes both the size and speed of your program. Rust also has some less obvious tricks:

- *Cache-friendly data structures are provided by default.* Arrays usually hold data within Rust programs rather than deeply nested tree structures that are created by pointers. This is referred to as *data-oriented programming*.

- *The availability of a modern package manager (cargo) makes it trivial to benefit from tens of thousands of open source packages.* C and C++ have much less consistency here, and building large projects with many dependencies is typically difficult.
- *Methods are always dispatched statically unless you explicitly request dynamic dispatch.* This enables the compiler to heavily optimize code, sometimes to the point of eliminating the cost of a function call entirely.

## 17.2 **Concurrency**

Asking a computer to do more than one thing at the same time has proven difficult for software engineers. As far as an OS is concerned, two independent threads of execution are at liberty to destroy each other if a programmer makes a serious mistake. Yet Rust has spawned the expression *fearless concurrency*. Its emphasis on safety crosses the bounds of independent threads. There is no global interpreter lock (GIL) to constrain a thread's speed. We explore some of the implications of this in part 2.

## 17.3 **Memory efficiency**

Rust enables you to create programs that require minimal memory. When needed, you can use fixed-size structures and know exactly how every byte is managed. High-level constructs, such as iteration and generic types, incur minimal runtime overhead.

## 1.8 **Downsides of Rust**

It's easy to talk about this language as if it is the panacea for all software engineering. For example

- “A high-level syntax with low-level performance!”
- “Concurrency without crashes!”
- “C with perfect safety!”

These slogans (sometimes overstated) are great. But for all of its merits, Rust does have some disadvantages.

### 18.1 **Cyclic data structures**

In Rust, it is difficult to model cyclic data like an arbitrary graph structure. Implementing a doubly-linked list is an undergraduate-level computer science problem. Yet Rust's safety checks do hamper progress here. If you're new to the language, avoid implementing these sorts of data structures until you're more familiar with Rust.

### 18.2 **Compile times**

Rust is slower at compiling code than its peer languages. It has a complex compiler toolchain that receives multiple intermediate representations and sends lots of code to the LLVM compiler. The unit of compilation for a Rust program is not an individual file but a whole package (known affectionately as a *crate*). As crates can include

multiple modules, these can be exceedingly large units to compile. Although this enables whole-of-crate optimization, it requires whole-of-crate compilation as well.

### 18.3 Strictness

It's impossible—well, difficult—to be lazy when programming with Rust. Programs won't compile until everything is just right. The compiler is strict, but helpful.

Over time, it's likely that you'll come to appreciate this feature. If you've ever programmed in a dynamic language, then you may have encountered the frustration of your program crashing because of a misnamed variable. Rust brings that frustration forward so that your users don't have to experience the frustration of things crashing.

### 18.4 Size of the language

Rust is large! It has a rich type system, several dozen keywords, and includes some features that are unavailable in other languages. These factors all combine to create a steep learning curve. To make this manageable, I encourage learning Rust gradually. Start with a minimal subset of the language and give yourself time to learn the details when you need these. That is the approach taken in this book. Advanced concepts are deferred until much later.

### 18.5 Hype

The Rust community is wary of growing too quickly and being consumed by hype. Yet, a number of software projects have encountered this question in their Inbox: "Have you considered rewriting this in Rust?" Unfortunately, software written in Rust is still software. It is not immune to security problems and does not offer a panacea to all of software engineering's ills.

## 1.9 TLS security case studies

To demonstrate that Rust will not alleviate all errors, let's examine two serious exploits that threatened almost all internet-facing devices and consider whether Rust would have prevented those.

By 2015, as Rust gained prominence, implementations of SSL/TLS (namely, OpenSSL and Apple's own fork) were found to have serious security holes. Known informally as *Heartbleed* and *goto fail*, both exploits provide opportunities to test Rust's claims of memory safety. Rust is likely to have helped in both cases, but it is still possible to write Rust code that suffers from similar issues.

### 1.9.1 Heartbleed

Heartbleed, officially designated as CVE-2014-0160,<sup>16</sup> was caused by re-using a buffer incorrectly. A *buffer* is a space set aside in memory for receiving input. Data can leak from one read to the next if the buffer's contents are not cleared between writes.

---

<sup>16</sup> See "CVE-2014-0160 Detail," <https://nvd.nist.gov/vuln/detail/CVE-2014-0160>.

Why does this situation occur? Programmers hunt for performance. Buffers are reused to minimize how often memory applications ask for memory from the OS.

Imagine that we want to process some secret information from multiple users. We decide, for whatever reason, to reuse a single buffer through the course of the program. If we don't reset this buffer once we use it, information from earlier calls will leak to the latter ones. Here is a précis of a program that would encounter this error:

```

Binds a reference (&) to a mutable (mut) array
([...]) that contains 1,024 unsigned 8-bit integers
(u8) initialized to 0 to the variable buffer
let buffer = &mut [0u8; 1024];
read_secrets(&user1, buffer);
store_secrets(buffer);

Fills buffer with
bytes from the data
from user1

The buffer still contains data
from user1 that may or may
not be overwritten by user2.

read_secrets(&user2, buffer);
store_secrets(buffer);

```

Rust does not protect you from logical errors. It ensures that your data is never able to be written in two places at the same time. It does not ensure that your program is free from all security issues.

## 19.2 Goto fail;

The `goto fail;` bug, officially designated as CVE-2014-1266,<sup>17</sup> was caused by programmer error coupled with C design issues (and potentially by its compiler not pointing out the flaw). A function that was designed to verify a cryptographic key pair ended up skipping all checks. Here is a selected extract from the original `SSLVerifySignedServerKeyExchange` function with a fair amount of obfuscatory syntax retained:<sup>18</sup>

```

1 static OSStatus
2 SSLVerifySignedServerKeyExchange(SSLContext *ctx,
3                                     bool isRsa,
4                                     SSLBuffer signedParams,
5                                     uint8_t *signature,
6                                     UInt16 signatureLen)
7{
8     OSStatus         err;           ← Initialize OSStatus with
9     ...             ← a pass value (e.g., 0)
10
11    if ((err = SSLHashSHA1.update(
12        &hashCtx, &serverRandom)) != 0)   ← A series of defensive
13        goto fail;
14
15    if ((err = SSLHashSHA1.update(&hashCtx, &signedParams)) != 0)

```

<sup>17</sup> See “CVE-2014-1266 Detail,” <https://nvd.nist.gov/vuln/detail/CVE-2014-1266>.

<sup>18</sup> Original available at <http://mng.bz/RKGj>.

```

16      goto fail;           | Unconditional goto skips SSLHashSHA1.final()
17      goto fail;           | and the (significant) call to sslRawVerify().
18  if ((err = SSLHashSHA1.final(&hashCtx, &hashOut)) != 0)
19      goto fail;
20
21  err = sslRawVerify(ctx,
22                      ctx->peerPubKey,
23                      dataToSign,             /* plaintext */
24                      dataToSignLen,          /* plaintext length */
25                      signature,
26                      signatureLen);
27  if(err) {
28      sslErrorLog("SSLDecodeSignedServerKeyExchange: sslRawVerify "
29                  "returned %d\n", (int)err);
30      goto fail;
31  }
32
33 fail:
34  SSLFreeBuffer(&signedHashes);
35  SSLFreeBuffer(&hashCtx);    | Returns the pass value of 0, even for inputs
36  return err;                | that should have failed the verification test
37 }
```

In the example code, the issue lies between lines 15 and 17. In C, logical tests do not require curly braces. C compilers interpret those three lines like this:

```

if ((err = SSLHashSHA1.update(&hashCtx, &signedParams)) != 0) {
    goto fail;
}
goto fail;
```

Would Rust have helped? Probably. In this specific case, Rust's grammar would have caught the bug. It does not allow logical tests without curly braces. Rust also issues a warning when code is unreachable. But that doesn't mean the error is made impossible in Rust. Stressed programmers under tight deadlines make mistakes. In general, similar code would compile and run.

**TIP** Code with caution.

## 1.10 Where does Rust fit best?

Although it was designed as a systems programming language, Rust is a general-purpose language. It has been successfully deployed in many areas, which we discuss next.

### 1.10.1 Command-line utilities

Rust offers three main advantages for programmers creating command-line utilities: minimal startup time, low memory use, and easy deployment. Programs start their work quickly because Rust does not need to initialize an interpreter (Python, Ruby, etc.) or virtual machine (Java, C#, etc.).

As a bare metal language, Rust produces memory-efficient programs.<sup>19</sup> As you'll see throughout the book, many types are zero-sized. That is, these only exist as hints to the compiler and take up no memory at all in the running program.

Utilities written in Rust are compiled as *static binaries* by default. This compilation method avoids depending on shared libraries that you must install before the program can run. Creating programs that can run without installation steps makes these easy to distribute.

### **1.10.2 Data processing**

Rust excels at text processing and other forms of data wrangling. Programmers benefit from control over memory use and fast startup times. As of mid-2017, Rust touts the world's fastest regular expression engine. In 2019, the Apache Arrow data-processing project—foundational to the Python and R data science ecosystems—accepted the Rust-based DataFusion project.

Rust also underlies the implementation of multiple search engines, data-processing engines, and log-parsing systems. Its type system and memory control provide you with the ability to create high throughput data pipelines with a low and stable memory footprint. Small filter programs can be easily embedded into the larger framework via Apache Storm, Apache Kafka, or Apache Hadoop streaming.

### **1.10.3 Extending applications**

Rust is well suited for extending programs written in a dynamic language. This enables JNI (Java Native Interface) extensions, C extensions, or Erlang/Elixir NIFs (native implemented functions) in Rust. C extensions are typically a scary proposition. These tend to be quite tightly integrated with the runtime. Make a mistake and you could be looking at runaway memory consumption due to a memory leak or a complete crash. Rust takes away a lot of this anxiety.

- Sentry, a company that processes application errors, finds that Rust is an excellent candidate for rewriting CPU-intensive components of their Python system.<sup>20</sup>
- Dropbox used Rust to rewrite the file synchronization engine of its client-side application: “More than performance, [Rust’s] ergonomics and focus on correctness have helped us tame sync’s complexity.”<sup>21</sup>

### **1.10.4 Resource-constrained environments**

C has occupied the domain of microcontrollers for decades. Yet, the Internet of Things (IoT) is coming. That could mean many billions of insecure devices exposed to the network. Any input parsing code will be routinely probed for weaknesses. Given how infrequently firmware updates for these devices occur, it’s critical that these are as

---

<sup>19</sup> The joke goes that Rust is as close to bare metal as possible.

<sup>20</sup> See “Fixing Python Performance with Rust,” <http://mng.bz/ryxX>.

<sup>21</sup> See “Rewriting the heart of our sync engine,” <http://mng.bz/Vdv5>.

secure as possible from the outset. Rust can play an important role here by adding a layer of safety without imposing runtime costs.

### 1.10.5 Server-side applications

Most applications written in Rust live on the server. These could be serving web traffic or supporting businesses running their operations. There is also a tier of services that sit between the OS and your application. Rust is used to write databases, monitoring systems, search appliances, and messaging systems. For example

- The npm package registry for the JavaScript and node.js communities is written in Rust.<sup>22</sup>
- sled (<https://github.com/spacejam/sled>), an embedded database, can process a workload of 1 billion operations that includes 5% writes in less than a minute on a 16-core machine.
- Tantivy, a full text search engine, can index 8 GB of English Wikipedia in approximately 100 s on a 4-core desktop machine.<sup>23</sup>

### 1.10.6 Desktop applications

There is nothing inherent in Rust's design that prevents it from being deployed to develop user-facing software. Servo, the web browser engine that acted as an incubator for Rust's early development, is a user-facing application. Naturally, so are games.

### 1.10.7 Desktop

There is still a significant need to write applications that live on people's computers. Desktop applications are often complex, difficult to engineer, and hard to support. With Rust's ergonomic approach to deployment and its rigor, it is likely to become the secret sauce for many applications. To start, these will be built by small, independent developers. As Rust matures, so will the ecosystem.

### 1.10.8 Mobile

Android, iOS, and other smartphone operating systems generally provide a blessed path for developers. In the case of Android, that path is Java. In the case of macOS, developers generally program in Swift. There is, however, another way.

Both platforms provide the ability for native applications to run on them. This is generally intended for applications written in C++, such as games, to be able to be deployed to people's phones. Rust is able to talk to the phone via the same interface with no additional runtime cost.

---

<sup>22</sup> See "Community makes Rust an easy choice for npm: The npm Registry uses Rust for its CPU-bound bottlenecks," <http://mng.bz/xm9B>.

<sup>23</sup> See "Of tantivy's indexing," <https://fulmicoton.com/posts/behold-tantivy-part2/>.

### 1.10.9 Web

As you are probably aware, JavaScript is the language of the web. Over time though, this will change. Browser vendors are developing a standard called WebAssembly (Wasm) that promises to be a compiler target for many languages. Rust is one of the first. Porting a Rust project to the browser requires only two additional command-line commands. Several companies are exploring the use of Rust in the browser via Wasm, notably CloudFlare and Fastly.

### 1.10.10 Systems programming

In some sense, systems programming is Rust’s raison d’être. Many large programs have been implemented in Rust, including compilers (Rust itself), video game engines, and operating systems. The Rust community includes writers of parser generators, databases, and file formats.

Rust has proven to be a productive environment for programmers who share Rust’s goals. Three standout projects in this area include the following:

- Google is sponsoring the development of Fuchsia OS, an operating system for devices.<sup>24</sup>
- Microsoft is actively exploring writing low-level components in Rust for Windows.<sup>25</sup>
- Amazon Web Services (AWS) is building Bottlerocket, a bespoke OS for hosting containers in the cloud.<sup>26</sup>

## 1.11 Rust’s hidden feature: Its community

It takes more than software to grow a programming language. One of the things that the Rust team has done extraordinarily well is to foster a positive and welcoming community around the language. Everywhere you go within the Rust world, you’ll find that you’ll be treated with courtesy and respect.

## 1.12 Rust phrase book

When you interact with members of the Rust community, you’ll soon encounter a few terms that have special meaning. Understanding the following terms makes it easier to understand why Rust has evolved the way that it has and the problems that it attempts to solve:

- *Empowering everyone*—All programmers regardless of ability or background are welcome to participate. Programming, and particularly systems programming, should not be restricted to a blessed few.

---

<sup>24</sup> See “Welcome to Fuchsia!,” <https://fuchsia.dev/>.

<sup>25</sup> See “Using Rust in Windows,” <http://mng.bz/A0vW>.

<sup>26</sup> See “Bottlerocket: Linux-based operating system purpose-built to run containers,” <https://aws.amazon.com/bottlerocket/>.

- *Blazingly fast*—Rust is a fast programming language. You'll be able to write programs that match or exceed the performance of its peer languages, but you will have more safety guarantees.
- *Fearless concurrency*—Concurrent and parallel programming have always been seen as difficult. Rust frees you from whole classes of errors that have plagued its peer languages.
- *No Rust 2.0*—Rust code written today will always compile with a future Rust compiler. Rust is intended to be a reliable programming language that can be depended upon for decades to come. In accordance with *semantic versioning*, Rust is never backward-incompatible, so it will never release a new major version.
- *Zero-cost abstractions*—The features you gain from Rust impose no runtime cost. When you program in Rust, safety does not sacrifice speed.

## Summary

- Many companies have successfully built large software projects in Rust.
- Software written in Rust can be compiled for the PC, the browser, and the server, as well as mobile and IoT devices.
- The Rust language is well loved by software developers. It has repeatedly won Stack Overflow's "most loved programming language" title.
- Rust allows you to experiment without fear. It provides correctness guarantees that other tools are unable to provide without imposing runtime costs.
- With Rust, there are three main command\_line tools to learn:
  - cargo, which manages a whole crate
  - rustup, which manages Rust installations
  - rustc, which manages compilation of Rust source code
- Rust projects are not immune from all bugs.
- Rust code is stable, fast, and light on resources.



## *Part 1*

# *Rust language distinctives*

**P**

art 1 of the book is a quick-fire introduction to the Rust programming language. By the end of the chapters in this part, you will have a good understanding of Rust syntax and know what motivates people to choose Rust. You will also understand some fundamental differences between Rust and its peer languages.



# Language foundations

## This chapter covers

- Coming to grips with the Rust syntax
- Learning fundamental types and data structures
- Building command-line utilities
- Compiling programs

This chapter introduces you to the fundamentals of Rust programming. By the end of the chapter, you will be able to create command-line utilities and should be able to get the gist of most Rust programs. We'll work through most of the language's syntax, but defer much of the detail about *why* things are *how* they are for later in the book.


**NOTE** Programmers who have experience with another programming language will benefit the most from this chapter. If you are an experienced Rust programmer, feel free to skim through it.

Beginners are welcomed. Rust's community strives to be responsive to newcomers. At times, you may strike a mental pothole when you encounter terms such as *lifetime elision*, *hygienic macros*, *move semantics*, and *algebraic data types* without context. Don't

be afraid to ask for help. The community is much more welcoming than these helpful, yet opaque, terms might suggest.

In this chapter, we will build grep-lite, a greatly stripped-down version of the ubiquitous grep utility. Our grep-lite program looks for patterns within text and prints lines that match. This simple program allows us to focus on the unique features of Rust.

The chapter takes a spiral approach to learning. A few concepts will be discussed multiple times. With each iteration, you will find yourself learning more. Figure 2.1 shows a completely unscientific map of the chapter.



**Figure 2.1** Chapter topic outline. Starting with primitive types, the chapter progresses through several concepts with increasing levels of depth.

It's highly recommended that you follow along with the examples in this book. As a reminder, to access or download the source code for the listings, use either of these two sources:

- <https://manning.com/books/rust-in-action>
- <https://github.com/rust-in-action/code>

## 2.1 Creating a running program

Every plain text file has a hidden superpower: when it includes the right symbols, it can be converted into something that can be interpreted by a CPU. That is the magic of a programming language. This chapter's aim is to allow you to become familiar with the process of converting Rust source code into a running program.

Understanding this process is more fun than it sounds! And it sets you up for an exciting learning journey. By the end of chapter 4, you will have implemented a virtual CPU that can also interpret programs that you create.

### 2.1.1 Compiling single files with rustc

Listing 2.1 is a short, yet complete Rust program. To translate it into a working program, we use software called a *compiler*. The compiler's role is to translate the source code into machine code, as well as take care of lots of bookkeeping to satisfy the operating system (OS) and CPU that it is a runnable program. The Rust compiler is called *rustc*. You'll find the source code for listing 2.1 in the file ch2/ok.rs.

#### Listing 2.1 Almost the shortest valid Rust program

```
1 fn main() {  
2     println!("OK")  
3 }
```

To compile a single file written in Rust into a working program

- 1 Save your source code to a file. In our case, we'll use the filename ok.rs.
- 2 Make sure that the source code includes a `main()` function.
- 3 Open a shell window such as Terminal, cmd.exe, Powershell, bash, zsh, or any other.
- 4 Execute the command `rustc <file>`, where `<file>` is the file you want to compile.

When compilation succeeds, rustc sends no output to the console. Behind the scenes, rustc has dutifully created an executable, using the input filename to choose the output filename.

Assuming that you've saved listing 2.1 to a file called ok.rs, let's see what that looks like. The following snippet provides a short demonstration of the process:

```
$ rustc ok.rs  
$ ./ok ← For Windows, include the .exe filename  
OK
```

### 2.1.2 Compiling Rust projects with cargo

Most Rust projects are larger than a single file. These typically include dependencies. To prepare ourselves for that, we'll use a higher-level tool than rustc, called cargo. cargo understands how to drive rustc (and much more).

Migrating from a single file workflow managed by rustc to one managed by cargo is a two-stage process. The first is to move that original file into an empty directory. Then execute the cargo init command.

Here is a detailed overview of that process, assuming that you are starting from a file called ok.rs generated by following the steps in the previous section:

- 1 Run `mkdir <project>` to create an empty directory (e.g., `mkdir ok`).
- 2 Move your source code into the `<project>` directory (e.g., `mv ok.rs ok`).
- 3 Change to the `<project>` directory (e.g., `cd ok`).
- 4 Run `cargo init`.

From this point on, you can issue `cargo run` to execute your project's source code. One difference from rustc is that compiled executables are found in a `<project>/target` subdirectory. Another is that cargo provides much more output by default:

```
$ cargo run
    Finished dev [unoptimized + debuginfo] target(s) in 0.03s
      Running `target/debug/ok`
OK
```

If you're ever curious about what cargo is doing under the hood to drive rustc, add the verbose flag (`-v`) to your command:

```
$ rm -rf target/          ←
$ cargo run -v           ←
  Compiling ok v0.1.0 (/tmp/ok)
    Running `rustc
      --crate-name ok
      --edition=2018
      ok.rs
      --error-format=json
      --json=diagnostic-rendered-ansi
      --crate-type bin
      --emit=dep-info,link
      -C embed-bitcode=no
      -C debuginfo=2
      -C metadata=55485250d3e77978
      -C extra-filename=-55485250d3e77978
      --out-dir /tmp/ok/target/debug/deps
      -C incremental=/tmp/ok/target/debug/incremental
      -L dependency=/tmp/ok/target/debug/deps
      -C link-arg=-fuse-ld=lld`           Added here to provoke
                                         cargo into compiling
                                         the project from
                                         scratch
  Finished dev [unoptimized + debuginfo] target(s) in 0.31s
    Running `target/debug/ok`
OK
```

## 2.2 A glance at Rust's syntax

Rust is boring and predictable where possible. It has variables, numbers, functions, and other familiar things that you have seen in other languages. For example, it delimits blocks with curly brackets (`{` and `}`), it uses a single equals sign as its assignment operator (`=`), and it is whitespace-agnostic.

## 2.2.1 Defining variables and calling functions

Let's look at another short listing to introduce some fundamentals: defining variables with type annotations and calling functions. Listing 2.2 prints  $a + b = 30$  to the console. As you can see from lines 2–5 in the listing, there are multiple syntactic choices for annotating data types to integers. Use whichever feels most natural for the situation at hand. The source code for this listing is in ch2/ch2-first-steps.rs.

### Listing 2.2 Adding integers using variables and declaring types

```

Rust is flexible with
the location of the
main() function.
1 fn main() {           ←
2   let a = 10;          ←
3   let b: i32 = 20;    ←
4   let c = 30i32;      ←
5   let d = 30_i32;     ←
6   let e = add(add(a, b), add(c, d)); ←
7
8   println!("( a + b ) + ( c + d ) = {} ", e); ←
9 }                      ←
10
11 fn add(i: i32, j: i32) -> i32 {           ←
12   i + j              ←
13 }                      ←

```

Types can be inferred  
by the compiler...

...or declared by the programmer  
when creating variables.

Numeric types can include a type  
annotation in their literal form.

Numbers can include underscores,  
which are intended to increase  
readability and have no functional  
impact.

Type declarations are required  
when defining functions.

Functions return the last  
expression's result so that  
return is not required.

**NOTE** In the listing, be careful about adding a semicolon to the `add()` function declaration. This changes the semantics, returning `()` (unit) rather than `i32`.

Although there are only 13 lines of code, there is quite a lot packed into listing 2.2. Here's a brief description that should provide the gist of what's going on. We will cover the details in the rest of the chapter.

In line 1 (`fn main() {}`), the `fn` keyword begins a function definition. The entry point to all Rust programs is `main()`. It takes no arguments and returns no value.<sup>1</sup> Code blocks, also known as *lexical scopes*, are defined with curly braces: `{` and `}`.

In line 2 (`let a = 10;`), we use `let` to declare *variable bindings*. Variables are *immutable* by default, meaning that they are read-only rather than read-write. And finally, statements are delimited with semicolons (`;`).

In line 3 (`let b: i32 = 20;`), you can designate a specific data type for the compiler. At times, this will be required as the compiler will be unable to deduce a unique type on your behalf.

In line 4 (`let c = 30i32;`), you'll note that Rust's numeric literals can include types annotations. This can be helpful when navigating complex numerical expressions. And

<sup>1</sup> This isn't technically correct, but is accurate enough for now. If you're an experienced Rust programmer skimming through this chapter, you'll know that `main()` returns `()` (unit) by default and can also return a `Result`.

in line 5 (`let c = 30_i32;`), you'll see that Rust permits the use of underscores within numeric literals. These increase readability but are insignificant to the compiler. In line 6 (`let e = add(add(a, b), add(c, d));`), it should be easy to see that calling functions looks like what you've experienced in most other programming languages.

In line 8 (`println!("( a + b ) + ( c + d ) = {} ", e);`), `println!()` is a *macro*, which is function-like but returns code rather than values. When printing to the console, every input data type has its own way of being represented as a text string. `println!()` takes care of figuring out the exact methods to call on its arguments.

Strings use double quotes ("") rather than single quotes (''). Rust uses single quotes for single characters, which are a distinct type, `char`. And with Rust, string formatting uses {} as a placeholder, rather than the C-like `printf` style of %s or other variants.

Finally, in line 10 (`fn add(...) -> i32 {}`), you can see that Rust's syntax for defining functions is similar to those programming languages that use explicit type declarations. Commas delimit parameters, and type declarations follow variable names. The dagger (->) or thin arrow syntax indicates the return type.

## 2.3 **Numbers**

Computers have been associated with numbers for longer than you have been able to say "formula translator." This section discusses how to create numeric types in Rust and how to perform operations on these.

### 2.3.1 **Integers and decimal (floating-point) numbers**

Rust uses a relatively conventional syntax for creating integers (1, 2, ...) and floating-point numbers (1.0, 1.1, ...). Operations on numbers use *infix notation*, meaning that numeric expressions look like those that you're used to seeing in most programming languages. To operate on multiple types, Rust also allows the same token (+) for addition. This is called *operator overloading*. Some notable differences from other languages follow:

- *Rust includes a large number of numeric types.* You will become used to declaring the size in bytes, which affects how many numbers the type can represent and whether your type is able to represent negative numbers.
- *Conversions between types are always explicit.* Rust does not automatically convert your 16-bit integer into a 32-bit integer.
- *Rust's numbers can have methods.* For example, to round 24.5 to the nearest integer, Rust programmers use `24.5_f32.round()` rather than `(round(24.5_f32))`. Here, the type suffix is required because a concrete type is necessary.

To start, let's consider a small example. You'll find the code in `ch2/ch2-intro-to-numbers.rs` in the examples for this book. Listing 2.3 prints these few lines to the console:

```
20 + 21 + 22 = 63
1000000000000
42
```

**Listing 2.3 Numeric literals and basic operations on numbers in Rust**

Numbers have methods.  
Floating-point literals can also have type suffixes...  
...and optional underscores.

```

1 fn main() {
2     let twenty = 20;           ← Rust infers a type
3     let twenty_one: i32 = 21;   ← on your behalf if you
4     let twenty_two = 22i32;    ← don't supply one...
5
6     let addition = twenty + twenty_one + twenty_two;
7     println!("{} + {} + {} = {}", twenty, twenty_one, twenty_two, addition);
8
9     let one_million: i64 = 1_000_000;      ← ...which is done
10    println!("{}", one_million.pow(2));       ← by adding type
                                              ← annotations
                                              ← (i32)...
                                              ← ...or type suffixes.
11
12    let forty_twos = [           ← Underscores increase readability
13        42.0,                   ← and are ignored by the compiler.
14        42f32,
15        42.0_f32,
16    ];                         ← Creates an array of numbers, which must all be the
17
18    /   println!("{:02}", forty_twos[0]);   ← same type, by surrounding those with square brackets
19 }
```

Floating-point literals without an explicit type annotation become 32-bit or 64-bit, depending on context.

Elements within arrays can be indexed numerically, starting at 0.

**2.3.2 Integers with base 2, base 8, and base 16 notation**

Rust also has built-in support for numeric literals that allow you to define integers in base 2 (binary), base 8 (octal), and base 16 (hexadecimal). This notation is also available within the formatting macros like `println!`. Listing 2.4 demonstrates the three styles. You can find the source code for this listing in `ch2/ch2-non-base2.rs`. It produces the following output:

```
base 10: 3 30 300
base 2: 11 11110 100101100
base 8: 3 36 454
base 16: 3 1e 12c
```

**Listing 2.4 Using base 2, base 8, and base 16 numeric literals**

```

1 fn main() {
2     let three = 0b11;           ← The 0b prefix indicates
3     let thirty = 0o36;          ← binary (base 2) numerals.
4     let three_hundred = 0x12C;   ← The 0o prefix indicates
5
6     println!("base 10: {} {} {}", three, thirty, three_hundred);
7     println!("base 2: {:b} {:b} {:b}", three, thirty, three_hundred);
8     println!("base 8: {:o} {:o} {:o}", three, thirty, three_hundred);
9     println!("base 16: {:x} {:x} {:x}", three, thirty, three_hundred);
10 }
```

The 0x prefix indicates hexadecimal (base 16) numerals.

In binary (base 2) numerals, 0b11 equals 3 because  $3 = 2 \times 1 + 1 \times 1$ . With octal (base 8) numerals, 0o36 equals 30 because  $30 = 8 \times 3 + 1 \times 6$ . And with hexadecimal (base 16) numerals, 0x12C equals 300 because  $300 = 256 \times 1 + 16 \times 2 + 1 \times 12$ . Table 2.1 shows the types that represent scalar numbers.

**Table 2.1 Rust types for representing scalar (single) numbers**

i8, i16, i32, i64	Signed integers ranging from 8 bit to 64 bit.
u8, u16, u32, u64	Unsigned integers ranging from 8 bit to 64 bit.
f32, f64	Floating-point numbers in 32-bit and 64-bit variants.
isize, usize	Integers that assume the CPU's "native" width. For example, in 64-bit CPUs, usize and isize will be 64-bits wide.

Rust contains a full complement of numeric types. The types are grouped into a few families:

- Signed integers (i) represent negative as well as positive integers.
- Unsigned integers (u) only represent positive integers but can go twice as high as their signed counterparts.
- Floating-point types (f) represent real numbers with special bit patterns to represent infinity, negative infinity, and "not a number" values.

Integer width is the number of bits that the type uses in RAM and in the CPU. Types that take up more space, such as u32 vs. i8, can represent a wider range of numbers. But this incurs the expense of needing to store extra zeros for smaller numbers, as table 2.2 shows.

**Table 2.2 Multiple bit patterns can represent the same number.**

Number	Type	Bit pattern in memory
20	u32	000000000000000000000000000010100
20	i8	00010100
20	f32	01000001101000000000000000000000

Although we've only touched on numbers, we nearly have enough exposure to Rust to create a prototype of our pattern-matching program. But let's look at comparing numbers before we create our program.

### 2.3.3 Comparing numbers

Rust's numeric types support a large suite of comparisons that you're probably familiar with. Enabling support for these comparisons is provided by a feature that you have not encountered yet. It is called *traits*.<sup>2</sup> Table 2.3 summarizes the comparison operators available to you.

<sup>2</sup> For the curious and eager, the traits involved here are std::cmp::PartialOrd and std::cmp::PartialEq.

**Table 2.3 Mathematical operators supported by Rust's numeric types**

Operator	Rust syntax	Example
Less than (<)	<	1.0 < 2.0
Greater than (>)	>	2.0 > 1.0
Equal to (==)	==	1.0 == 1.0
Unequal to (!=)	!=	1.0 != 2.0
Equal to or less than ( $\leq$ )	<=	1.0 <= 2.0
Equal to greater than or ( $\geq$ )	>=	2.0 >= 1.0

That support does include a few caveats. We'll look at these conditions in the rest of this section.

#### IMPOSSIBLE TO COMPARE DIFFERENT TYPES

Rust's type safety requirements prevent comparisons between types. For example, this code does not compile:

```
fn main() {
    let a: i32 = 10;
    let b: u16 = 100;

    if a < b {
        println!("Ten is less than one hundred.");
    }
}
```

To appease the compiler, we need to use an `as` operator to cast one of the operands to the other's type. The following code shows this type cast: `b` as `i32`:

```
fn main() {
    let a: i32 = 10;
    let b: u16 = 100;

    if a < (b as i32) {
        println!("Ten is less than one hundred.");
    }
}
```

It is safest to cast the smaller type to a larger one (for example, a 16-bit type to a 32-bit type). This is sometimes referred to as *promotion*. In this case, we could have demoted `a` down to a `u16`, but such a move is generally more risky.

**WARNING** Using type casts carelessly will cause your program to behave unexpectedly. For example, the expression `300_i32 as i8` returns `44`.

In some cases, using the `as` keyword is too restrictive. It's possible to regain fuller control over the type conversion process at the cost of introducing some bureaucracy. The

following listing shows a Rust method to use instead of the `as` keyword when the conversion might fail.

### Listing 2.5 The `try_into()` method converts between types

```

1 use std::convert::TryInto;           ← Enables try_into() to be
2
3 fn main() {                         called on those types that have
4     let a: i32 = 10;                implemented it (such as u16)
5     let b: u16 = 100;
6
7     let b_ = b.try_into()           ← try_into() returns a Result
8         .unwrap();                 type that provides access to
9
10    if a < b_ {                   the conversion attempt.
11        println!("Ten is less than one hundred.");
12    }
13 }
```

Listing 2.5 introduces two new Rust concepts: traits and error handling. On line 1, the `use` keyword brings the `std::convert::TryInto` trait into local scope. This unlocks the `try_into()` method of the `b` variable. We'll bypass a full explanation of why this occurs for now. In the meantime, consider a *trait* as a collection of methods. If you are from an object-oriented background, traits can be thought of as *abstract classes* or *interfaces*. If your programming experience is in functional languages, you can think of traits as *type classes*.

Line 7 provides a glimpse of error handling in Rust. `b.try_into()` returns an `i32` value wrapped within a `Result`. `Result` is introduced properly in chapter 3. It can contain either a success value or an error value. The `unwrap()` method can handle the success value and returns the value of `b` as an `i32` here. If the conversion between `u16` and `i32` were to fail, then calling `unsafe()` would crash the program. As the book progresses, you will learn safer ways of dealing with `Result` rather than risking the program's stability!

A distinguishing characteristic of Rust is that it only allows a type's methods to be called when the trait is within local scope. An implicit prelude enables common operations such as addition and assignment to be used without explicit imports.

**TIP** To understand what is included in local scope by default, you should investigate the `std::prelude` module. Its documentation is available online at <https://doc.rust-lang.org/std/prelude/index.html>.

### Floating-point hazards

Floating-point types (`f32` and `f64`, for example) can cause serious errors for the unwary. There are (at least) two reasons for this:

- These often approximate the numbers that they're representing. Floating-point types are implemented in base 2, but we often want to calculate numbers in

base 10. This mismatch creates ambiguity. Moreover, although often described as representing the real numbers, floating point values have a limited precision. Representing all of the reals would require infinite precision.

- These can represent values that have *unintuitive semantics*. Unlike integers, floating-point types have some values that do not play well together (by design). Formally, these only have a *partial equivalence relation*. This is encoded in Rust's type system. `f32` and `f64` types only implement the `std::cmp::PartialEq` trait, whereas other numeric types also implement `std::cmp::Eq`.

To prevent these hazards, here are two guidelines to follow:

- Avoid testing floating-point numbers for equality.
- Be wary when results may be mathematically undefined.

Using equality to compare floating-point numbers can be highly problematic. Floating-point numbers are implemented by computing systems that use binary (base 2) mathematics, but are often asked to perform operations on decimal (base 10) numbers. This poses a problem because many values we care about, such as 0.1, have no exact representation in binary.<sup>a</sup>

To illustrate the problem, consider the following snippet. Should it run successfully, or should it crash? Although the expression that is being evaluated ( $0.1 + 0.2 = 0.3$ ) is a mathematical tautology, it crashes on most systems that run it:

```
fn main() {
    assert!(0.1 + 0.2 == 0.3);           ← assert! crashes the program
}                                         unless its argument evaluates
                                            to true.
```

But not all. It turns out that the data type can affect whether the program succeeds or fails. The following code, available at `ch2/ch2-add-floats.rs`, interrogates the internal bit patterns of each value to find where the differences lie. It then performs the test in the previous example against both `f32` and `f64` types. Only one test passes:

```
1 fn main() {
2     let abc: (f32, f32, f32) = (0.1, 0.2, 0.3);
3     let xyz: (f64, f64, f64) = (0.1, 0.2, 0.3);
4
5     println!("abc (f32)");
6     println!("    0.1 + 0.2: {:x}", (abc.0 + abc.1).to_bits());
7     println!("    0.3: {:x}", (abc.2).to_bits());
8     println!();
9
10    println!("xyz (f64)");
11    println!("    0.1 + 0.2: {:x}", (xyz.0 + xyz.1).to_bits());
12    println!("    0.3: {:x}", (xyz.2).to_bits());
13    println!();
14
15    assert!(abc.0 + abc.1 == abc.2);      ← Runs successfully
16    assert!(xyz.0 + xyz.1 == xyz.2);      ← Triggers a crash
17 }
```

**(continued)**

When executed, the program successfully generates the short report that follows, which reveals the error. After that, it crashes. Significantly, it crashes on line 14, when it compares the result of the f64 values:

```
abc (f32)
0.1 + 0.2: 3e99999a
0.3: 3e99999a

xyz (f64)
0.1 + 0.2: 3fd333333333334
0.3: 3fd333333333333

thread 'main' panicked at 'assertion failed: xyz.0 + xyz.1 == xyz.2',
  ↪ ch2-add-floats.rs.rs:14:5
note: run with `RUST_BACKTRACE=1` environment variable to display
  ↪ a backtrace
```

Generally speaking, it is safer to test whether mathematical operations fall within an acceptable margin of their true mathematical result. This margin is often referred to as the *epsilon*.

Rust includes some tolerances to allow comparisons between floating-point values. These tolerances are defined as f32::EPSILON and f64::EPSILON. To be more precise, it's possible to get closer to how Rust is behaving under the hood, as the following small example shows:

```
fn main() {
    let result: f32 = 0.1 + 0.1;
    let desired: f32 = 0.2;
    let absolute_difference = (desired - result).abs();
    assert!(absolute_difference <= f32::EPSILON);
}
```

In the example, what actually happens is interesting, but mostly irrelevant. The Rust compiler actually delegates the comparison to the CPU. Floating-point operations are implemented using bespoke hardware within the chip.<sup>b</sup>

Operations that produce mathematically undefined results, such as taking the square root of a negative number (-42.0.sqrt()), present particular problems. Floating-point types include “not a number” values (represented in Rust syntax as NAN values) to handle these cases.

NAN values poison other numbers. Almost all operations interacting with NAN return NAN. Another thing to be mindful of is that, by definition, NAN values are never equal. This small program will always crash:

```
fn main() {
    let x = (-42.0_f32).sqrt();
    assert_eq!(x, x);
}
```

To program defensively, make use of the `is_nan()` and `is_finite()` methods. Inducing a crash, rather than silently proceeding with a mathematical error, allows you to debug close to what has caused the problem. The following illustrates using the `is_finite()` method to bring about this condition:

```
fn main() {
    let x: f32 = 1.0 / 0.0;
    assert!(x.is_finite());
}
```

<sup>a</sup> If this is confusing to think about, consider that many values, such as  $1/3$  (one third), have no exact representation within the decimal number system.

<sup>b</sup> Illegal or undefined operations trigger a CPU exception. You will read about those in chapter 12.

### 2.3.4 Rational, complex numbers, and other numeric types

Rust's standard library is comparatively slim. It excludes numeric types that are often available within other languages. These include

- Many mathematical objects for working with rational numbers and complex numbers
- Arbitrary size integers and arbitrary precision floating-point numbers for working with very large or very small numbers
- Fixed-point decimal numbers for working with currencies

To access these specialized numeric types, you can use the `num` crate. *Crates* are Rust's name for packages. Open source crates are shared at the <https://crates.io> repository, which is where cargo downloads `num` from.

Listing 2.6 demonstrates adding two complex numbers together. If you're unfamiliar with the term *complex numbers*, these are two-dimensional, whereas numbers that you deal with day to day are one-dimensional. Complex numbers have "real" and "imaginary" parts and are denoted as `<real> + <imaginary>i`.<sup>3</sup> For example,  $2.1 + -1.2i$  is a single complex number. That's enough mathematics. Let's look at the code.

Here is the recommended workflow to compile and run listing 2.6:

- 1 Execute the following commands in a terminal:

```
git clone --depth=1 https://github.com/rust-in-action/code rust-in-action
cd rust-in-action/ch2/ch2-complex
cargo run
```

- 2 For those readers who prefer to learn by doing everything by hand, the following instructions will achieve the same end result:

- a Execute the following commands in a terminal:

```
cargo new ch2-complex
cd ch2-complex
```

<sup>3</sup> Mechanical engineers use *j* rather than *i*.

- b Add version 0.4 of the num crate into the [dependencies] section of Cargo.toml. That section will look like this:

```
[dependencies]
num = "0.4"
```

- c Replace src/main.rs with the source code from listing 2.6 (available at ch2/ch2-complex/src/main.rs).  
d Execute cargo run.

After several lines of intermediate output, cargo run should produce the following output:

```
13.2 + 21.02i
```

#### Listing 2.6 Calculating values with complex numbers

```
1 use num::complex::Complex;           ← The use keyword brings the
2                                         Complex type into local scope.
3 fn main() {                         ← Every Rust type
4     let a = Complex { re: 2.1, im: -1.2 };   has a literal syntax.
5     let b = Complex::new(11.1, 22.2);       ← Most types implement
6     let result = a + b;                   a new() static method.
7
8     println!("{} + {}i", result.re, result.im) ← Accesses fields with the dot operator
9 }
```

Some points from the listing are worth pausing to consider:

- *The use keyword pulls crates into local scope, and the namespace operator (:) restricts what's imported.* In our case, only a single type is required: Complex.
- *Rust does not have constructors; instead, every type has a literal form.* You can initialize types by using the type name (Complex) and assigning their fields (re, im) values (such as 2.1 or -1.2) within curly braces ({}).
- *Many types implement a new() method for simplicity.* This convention, however, is not part of the Rust language.
- *To access fields, Rust programmers use the dot operator (.)*. For example, the num::complex::Complex type has two fields: re represents the real part, and im represents the imaginary part. Both are accessible with the dot operator.

Listing 2.6 also introduces some new commands. It demonstrates two forms of initializing non-primitive data types.

One is a *literal syntax* available as part of the Rust language (line 4). The other is the new() static method, which is implemented by convention only and isn't defined as part of the language (line 5). A *static method* is a function that's available for a type, but it's not an instance of that type.<sup>4</sup>

<sup>4</sup> Although Rust is not object-oriented (it's impossible to create a subclass, for example), Rust makes use of some terminology from that domain. It's common to hear of Rust programmers discussing instances, methods, and objects.

The second form is often preferred in real-world code because library authors use a type's `new()` method to set defaults. It also involves less clutter.

### Shortcut for adding a third-party dependency to a project

I recommend that you install the `cargo-edit` crate to enable the `cargo add` subcommand. You can do this with the following code:

```
$ cargo install cargo-edit
    Updating crates.io index
    Installing cargo-edit v0.6.0
    ...
    Installed package `cargo-edit v0.6.0` (executables `cargo-add`,
    `cargo-rm`, `cargo-upgrade`)
```

Up to this point, we have manually added dependencies to `Cargo.toml`. The `cargo add` command simplifies this process by editing the file correctly on your behalf:

```
$ cargo add num
    Updating 'https://github.com/rust-lang/crates.io-index' index
    Adding num v0.4.0 to dependencies
```

We've now addressed how to access built-in numeric types and types available from third-party libraries. We'll move on to discussing some more of Rust's features.

## 2.4 Flow control

Programs execute from top to bottom, except when you don't want that. Rust has a useful set of *flow control* mechanisms to facilitate this. This section provides a brief tour of the fundamentals.

### 2.4.1 For: The central pillar of iteration

The `for` loop is the workhorse of iteration in Rust. Iterating through collections of things, including iterating over collections that may have infinitely many values, is easy. The basic form is

```
for item in container {
    // ...
}
```

This basic form makes each successive element in `container` available as `item`. In this way, Rust emulates many dynamic languages with an easy-to-use, high-level syntax. However, it does have some pitfalls.

Counterintuitively, once the block ends, accessing the container another time becomes invalid. Even though the `container` variable remains within local scope, its *lifetime* has ended. For reasons that are explained in chapter 4, Rust assumes that `container` is no longer needed once the block finishes.

When you want to reuse container later in your program, use a reference. Again, for reasons that are explained in chapter 4, when a reference is omitted, Rust assumes that container is no longer needed. To add a reference to the container, prefix it with an ampersand (&) as this example shows:

```
for item in &container {
    // ...
}
```

If you need to modify each `item` during the loop, you can use a *mutable reference* by including the `mut` keyword:

```
for item in &mut collection {
    // ...
}
```

As an implementation detail, Rust's `for` loop construct is expanded to method calls by the compiler. As the following table shows, these three forms of `for` each map to a different method.

Shorthand	Equivalent to	Access
<code>for item in collection</code>	<code>for item in IntoIterator::into_iter(collection)</code>	Ownership
<code>for item in &amp;collection</code>	<code>for item in collection.iter()</code>	Read-only
<code>for item in &amp;mut collection</code>	<code>for item in collection.iter_mut()</code>	Read-write

### ANONYMOUS LOOPS

When a local variable is not used within a block, by convention, you'll use an underscore (\_). Using this pattern in conjunction with the *\_exclusive range syntax\_* (`n..m`) and the *inclusive range syntax* (`n..=m`) makes it clear that the intent is to perform a loop for a fixed number of times. Here's an example:

```
for _ in 0..10 {
    // ...
}
```

### AVOID MANAGING AN INDEX VARIABLE

In many programming languages, it's common to loop through things by using a temporary variable that's incremented at the end of each iteration. Conventionally, this variable is named `i` (for index). A Rust version of that pattern is

```
let collection = [1, 2, 3, 4, 5];
for i in 0..collection.len() {
    let item = collection[i];
    // ...
}
```

This is legal Rust. It's also essential in cases when iterating directly over collection via `for item in collection` is impossible. However, it is generally discouraged. The manual approach introduces two problems with this:

- *Performance*—Indexing values with the `collection[index]` syntax incurs runtime costs for *bounds checking*. That is, Rust checks that `index` currently exists within `collection` as valid data. Those checks are not necessary when iterating directly over `collection`. The compiler can use compile-time analysis to prove that illegal access is impossible.
- *Safety*—Periodically accessing `collection` over time introduces the possibility that it has changed. Using a `for` loop over `collection` directly allows Rust to guarantee that the `collection` remains untouched by other parts of the program.

## 2.4.2 Continue: Skipping the rest of the current iteration

The `continue` keyword operates as you would expect. Here's an example:

```
for n in 0..10 {
    if n % 2 == 0 {
        continue;
    }
    // ...
}
```

## 2.4.3 While: Looping until a condition changes its state

The `while` loop proceeds as long as a condition holds. The condition, formally known as a *predicate*, can be any expression that evaluates to `true` or `false`. This (non-functioning) snippet takes air quality samples, checking to avoid anomalies:

```
let mut samples = vec![];

while samples.len() < 10 {
    let sample = take_sample();
    if is_outlier(sample) {
        continue;
    }

    samples.push(sample);
}
```

### USING WHILE TO STOP ITERATING ONCE A DURATION IS REACHED

Listing 2.7 (source code available at `ch2/ch2-while-true-incr-count.rs`) provides a working example of `while`. It isn't an ideal method for implementing benchmarks, but can be a useful tool to have in your toolbox. In the listing, `while` continues to execute a block when a time limit is not reached.

### Listing 2.7 Testing how fast your computer can increment a counter

```

1 use std::time::{Duration, Instant};      ← This form of an import hasn't been seen
2
3 fn main() {
4     let mut count = 0;
5     let time_limit = Duration::new(1, 0);   ← Creates a Duration that
6     let start = Instant::now();           ← represents 1 second
7
8     while (Instant::now() - start) < time_limit { ← An Instant minus an Instant
9         count += 1;                      ← returns a Duration.
10    }
11    println!("{} {}", count);
12 }
```

#### AVOID WHILE WHEN ENDLESSLY LOOPING

Most Rust programmers avoid the following idiom to express looping forever. The preferred alternative is to use the `loop` keyword, explained in the next section.

```
while true {
    println!("Are we there yet?");
```

#### 2.4.4 Loop: The basis for Rust's looping constructs

Rust contains a `loop` keyword for providing more control than `for` and `while`. `loop` executes a code block again and again, never stopping for a tea (or coffee) break. `loop` continues to execute until a `break` keyword is encountered or the program is terminated from the outside. Here's an example showing the `loop` syntax:

```
loop {
    // ...
}
```

`loop` is often seen when implementing long-running servers, as the following example shows:

```
loop {
    let requester, request = accept_request();
    let result = process_request(request);
    send_response(requester, result);
}
```

#### 2.4.5 Break: Aborting a loop

The `break` keyword breaks out of a loop. In this regard, Rust's generally operates as you are used to:

```
for (x, y) in (0..).zip(0..) {
    if x + y > 100 {
        break;
    }
}
```

```
// ...
}
```

### BREAK FROM NESTED LOOPS

You can break out of a nested loop with loop labels.<sup>5</sup> A *loop label* is an identifier prefixed with an apostrophe ('), like this example shows:

```
'outer: for x in 0.. {
    for y in 0.. {
        for z in 0.. {
            if x + y + z > 1000 {
                break 'outer;
            }
        }
    }
}
```

Rust does not include the `goto` keyword, which provides the ability to jump to other parts of the program. The `goto` keyword can make control flow confusing, and its use is generally discouraged. One place where it is still commonly used, though, is to jump to and clean up a section of a function when an error condition is detected. Use loop labels to enable that pattern.

### 2.4.6 If, if else, and else: Conditional branching

So far, we've indulged in the exciting pursuit of looking for numbers within lists of numbers. Our tests have involved utilizing the `if` keyword. Here's an example:

```
if item == 42 {
    // ...
}
```

`if` accepts any expression that evaluates to a Boolean value (e.g., `true` or `false`). When you want to test multiple expressions, it's possible to add a chain of `if` `else` blocks. The `else` block matches anything that has not already been matched. For example

```
if item == 42 {
    // ...
} else if item == 132 {
    // ...
} else {
    // ...
}
```

---

<sup>5</sup> This functionality is also available with `continue`, but it's less common.

Rust has no concept of “truthy” or “falsey” types. Other languages allow special values such as 0 or an empty string to stand in for false and for other values to represent true, but Rust doesn’t allow this. The only value that can be used for true is true, and for false, use false.

### Rust is an expression-based language

In programming languages from this heritage, all expressions return values and almost everything is an expression. This heritage reveals itself through some constructs that are not legal in other languages. In idiomatic Rust, the `return` keyword is omitted from functions as shown in the following snippet:

```
fn is_even(n: i32) -> bool {
    n % 2 == 0
}
```

For example, Rust programmers assign variables from conditional expressions:

```
fn main() {
    let n = 123456;
    let description = if is_even(n) {
        "even"
    } else {
        "odd"
    };
    println!("{} is {}", n, description);    ↪ Prints "123456
                                                is even"
```

This can be extended to other blocks including `match` like this:

```
fn main() {
    let n = 654321;
    let description = match is_even(n) {
        true => "even",
        false => "odd",
    };
    println!("{} is {}", n, description);    ↪ Prints "654321
                                                is odd"
```

Perhaps most surprisingly, the `break` keyword also returns a value. This can be used to allow “infinite” loops to return values:

```
fn main() {
    let n = loop {
        break 123;
    };
    println!("{}", n);    ↪ Prints "123"
```

You may wonder what parts of Rust are *not* expressions and, thus, do not return values. Statements are not expressions. These appear in Rust in three places:

- Expressions delimited by the semicolon (;
- Binding a name to a value with the assignment operator (=)
- Type declarations, which include functions (`fn`) and data types created with the `struct` and `enum` keywords

Formally, the first form is referred to as an *expression statement*. The last two are both called *declaration statements*. In Rust, no value is represented as `()` (the “unit” type).

## 2.4.7 Match: Type-aware pattern matching

While it’s possible to use `if/else` blocks in Rust, `match` provides a safer alternative. `match` warns you if you haven’t considered a relevant alternative. It is also elegant and concise:

```
match item {
    0           => {},
    10 ..= 20   => {},
    40 | 80    => {},
} -           => {}
```

To match a single value, provide the value. No operator is required.

The ..= syntax matches an inclusive range.

The vertical bar (|) matches values on either side of it.

The underscore (\_) matches every value.

`match` offers a sophisticated and concise syntax for testing multiple possible values. Some examples are

- Inclusive ranges (`10 ..= 20`) to match any value within the range.
- A Boolean OR (`|`) will match when either side matches.
- The underscore (`_`) to match everything.

`match` is analogous to the `switch` keyword in other languages. Unlike C’s `switch`, however, `match` guarantees that all possible options for a type are explicitly handled. Failing to provide a branch for every possible value triggers a compiler error. Additionally, a `match` does not “fall through” to the next option by default. Instead, `match` returns immediately when a match is found.

Listing 2.8 demonstrates a larger example of `match`. The source code for this listing is in `ch2/ch2-match-needles.rs`. The code prints these two lines to the screen:

```
42: hit!
132: hit!
```

**Listing 2.8 Using match to match multiple values**

```

1 fn main() {
2     let needle = 42;           ← The variable needle
3     let haystack = [1, 1, 2, 5, 14, 42, 132, 429, 1430, 4862];
4
5     for item in &haystack {
6         let result = match item {           ← This match expression returns a value
7             42 | 132 => "hit!",           ← that can be bound to a variable.
8             _ => "miss",              ← Success! 42 | 132 matches
9         };                            ← both 42 and 132.
10
11         if result == "hit!" {
12             println!("{}: {}", item, result);
13         }
14     }
15 }
```

The variable needle  
is now redundant.

This match expression returns a value  
that can be bound to a variable.

Success! 42 | 132 matches  
both 42 and 132.

A wildcard pattern that  
matches everything

The `match` keyword plays an important role within the Rust language. Many control structures (like looping) are defined in terms of `match` under the hood. These really shine when combined with the `Option` type that's discussed in depth in the next chapter.

Now that we have taken a good look at defining numbers and working with some of Rust's flow control mechanisms, let's move on to adding structure to programs with functions.

## 2.5 Defining functions

Looking back to where the chapter begins, the snippet in listing 2.2 contained a small function, `add()`. `add` takes two `i32` values and returns their sum. The following listing repeats the function.

**Listing 2.9 Defining a function (extract of listing 2.2)**

```

10 fn add(i: i32, j: i32) -> i32 {           ← add() takes two integer parameters and
11     i + j                                ← returns an integer. The two arguments
12 }
```

add() takes two integer parameters and  
returns an integer. The two arguments  
are bound to the local variables i and j.

For the moment, let's concentrate on the syntax of each of the elements in listing 2.9. Figure 2.2 provides a visual picture of each of the pieces. Anyone who has programmed in a strongly-typed programming language should be able to squint their way through the diagram.

Rust's functions require that you specify your parameter's types and the function's return type. This is the foundational knowledge that we'll need for the majority of our work with Rust. Let's put it to use with our first non-trivial program.




Figure 2.2 Rust's function definition syntax

## 2.6 Using references

If you have only used a dynamic programming language so far in your career, the syntax and semantics of references can be frustrating. It can be difficult to form a mental picture of what is happening. That makes it difficult to understand which symbols to put where. Thankfully, the Rust compiler is a good coach.

A *reference* is a value that stands in place for another value. For example, imagine that variable `a` is a large array that is costly to duplicate. In some sense, a reference `r` is a cheap copy of `a`. But instead of creating a duplicate, the program stores `a`'s address in memory. When the data from `a` is required, `r` can be *dereferenced* to make `a` available. The following listing shows the code for this.

### Listing 2.10 Creating a reference to a large array

```
fn main() {
    let a = 42;
    let r = &a;
    let b = a + *r;           r is a reference to a.
                            Adds a to a (via dereferencing
                            r) and assigns it to b
    println!("a + a = {}", b);   Prints "a + a = 84"
}
```

References are created with the *reference operator* (`&`) and dereferencing occurs with the *dereference operator* (`*`). These operators act as *unary operators*, meaning that these only take one operand. One of the limitations of source code written in ASCII text is that multiplication and dereferencing use the same symbol. Let's see these in use as part of a larger example.

Listing 2.11 searches for a number (the `needle` defined on line 2) within an array of numbers (the `haystack` defined on line 3). The code then prints 42 to the console when compiled. The code for this listing is in `ch2/ch2-needle-in-haystack.rs`.

### Listing 2.11 Searching for an integer in an array of integers

```
1 fn main() {
2     let needle = 0o204;
3     let haystack = [1, 1, 2, 5, 15, 52, 203, 877, 4140, 21147];
4
5     for item in &haystack {           Iterates over references to
                                      elements within haystack
}
```

```

6     if *item == needle {      <-- The syntax *item
7         println!("{}", item);
8     }
9 }
10 }
```


The syntax `*item`  
returns the item's  
referent.

Each iteration changes the value of `item` to refer to the next item within `haystack`. On the first iteration, `*item` returns 1, and on the last, it returns 21147.

## 2.7 Project: Rendering the Mandelbrot set

So far, we haven't learned much Rust, but we already have the tools to create some interesting pictures of fractals. So let's do that now with listing 2.12. To begin

- 1 In a terminal window, execute the following commands to create a project that can render the Mandelbrot set:
  - a `cd $TMP` (or `cd %TMP%` on MS Windows) to move to a directory that's not critical.
  - b `cargo new mandelbrot --vcs none` creates a new blank project.
  - c `cd mandelbrot` moves into the new project root.
  - d `cargo add num` to edit `Cargo.toml`, adding the `num` crate as a dependency (see the sidebar entitled "2.2" in section 2.3.4 for instructions to enable this `cargo` feature).
- 2 Replace `src/main.rs` with the code in listing 2.12, which you'll also find in `ch2/ch2-mandelbrot/src/main.rs`.
- 3 Execute `cargo run`. You should see the Mandelbrot set rendered in the terminal:



**Listing 2.12** Rendering the Mandelbrot set

```

Imports the Complex number type from
num crate and its complex submodule
1 use num::complex::Complex;           ←
2
3 fn calculate_mandelbrot(           ←
4
5     max_iters: usize,               ←
6     x_min: f64,                   ←
7     x_max: f64,                   ←
8     y_min: f64,                   ←
9     y_max: f64,                   ←
10    width: usize,                 ←
11    height: usize,                ←
12 ) -> Vec<Vec<usize>> {
13
14     let mut rows: Vec<_> = Vec::with_capacity(width);           ←
15     for img_y in 0..height {                                     ←
16
17         let mut row: Vec<usize> = Vec::with_capacity(height);       ←
18         for img_x in 0..width {                                     ←
19
20             let x_percent = (img_x as f64 / width as f64);          ←
21             let y_percent = (img_y as f64 / height as f64);          ←
22             let cx = x_min + (x_max - x_min) * x_percent;            ←
23             let cy = y_min + (y_max - y_min) * y_percent;            ←
24             let escaped_at = mandelbrot_at_point(cx, cy, max_iters); ←
25             row.push(escaped_at);
26         }
27
28         all_rows.push(row);
29     }
30     rows
31 }
32
33 fn mandelbrot_at_point(           ←
34     cx: f64,                  ←
35     cy: f64,                  ←
36     max_iters: usize,          ←
37 ) -> usize {
38     let mut z = Complex { re: 0.0, im: 0.0 };
39     let c = Complex::new(cx, cy);           ←
40
41     for i in 0..=max_iters {
42         if z.norm() > 2.0 {           ←
43             return i;
44         }
45         z = z * z + c;           ←
46     }
47     max_iters           ←
48 }                                ←
49

```

Converts between the output space (a grid of rows and columns) and a range that surrounds the Mandelbrot set (a continuous region near (0,0))

If a value has not escaped before reaching the maximum number of iterations, it's considered to be within the Mandelbrot set.

Parameters that specify the space we're searching for to look for members of the set

Parameters that represent the size of the output in pixels

Creates a container to house the data from each row

Iterates row by row, allowing us to print the output line by line

Calculates the proportion of the space covered in our output and converts that to points within the search space

Called at every pixel (e.g., every row and column that's printed to stdout)

Initializes a complex number at the origin with real (re) and imaginary (im) parts at 0.0

Initializes a complex number from the coordinates provided as function arguments

Checks the escape condition and calculates the distance from the origin (0, 0), an absolute value of a complex number

Repeatedly mutates z to check whether c lies within the Mandelbrot set

As i is no longer in scope, we fall back to max\_iters.

```

50 fn render_mandelbrot(escape_vals: Vec<Vec<usize>>) {
51     for row in escape_vals {
52         let mut line = String::with_capacity(row.len());
53         for column in row {
54             let val = match column {
55                 0..=2 => ' ',
56                 2..=5 => '.',
57                 5..=10 => '•',
58                 11..=30 => '*',
59                 30..=100 => '+',
60                 100..=200 => 'x',
61                 200..=400 => '$',
62                 400..=700 => '#',
63                 _ => '%',
64             };
65             line.push(val);
66         }
67     }
68     println!("{}", line);
69 }
70 }
71
72 fn main() {
73     let mandelbrot = calculate_mandelbrot(1000, 2.0, 1.0, -1.0,
74                                         1.0, 100, 24);
75
76     render_mandelbrot(mandelbrot);
77 }
```

So far in this section, we've put the basics of Rust into practice. Let's continue our exploration by learning how to define functions and types.

## 2.8 Advanced function definitions

Rust's functions can get somewhat scarier than the `add(i: i32, j: i32) -> i32` from listing 2.2. To assist those who are reading more Rust source code than writing it, the following sections provide some extra content.

### 2.8.1 Explicit lifetime annotations

As a bit of forewarning, allow me to introduce some more complicated notation. As you read through Rust code, you might encounter definitions that are hard to decipher because those look like hieroglyphs from an ancient civilizations. Listing 2.13 provides an extract from listing 2.14 that shows one such example.

#### Listing 2.13 A function signature with explicit lifetime annotations

```

1 fn add_with_lifetimes<'a, 'b>(i: &'a i32, j: &'b i32) -> i32 {
2     *i + *j
3 }
```

Like all unfamiliar syntax, it can be difficult to know what's happening at first. This improves with time. Let's start by explaining *what* is happening, and then go on to

discuss *why* it is happening. The following bullet points break line 1 of the previous snippet into its parts:

- fn add\_with\_lifetimes(...) -> i32 should be familiar to you already. From this we can infer that `add_with_lifetimes()` is a function that returns an `i32` value.
- `<'a, 'b>` declares two lifetime variables, '`a`' and '`b`', within the scope of `add_with_lifetimes()`. These are normally spoken as *lifetime a* and *lifetime b*.
- `i: &'a i32` binds lifetime variable '`a`' to the lifetime of `i`. The syntax reads as "parameter `i` is a reference to an `i32` with lifetime `a`."
- `j: &'b i32` binds the lifetime variable '`b`' to the lifetime of `j`. The syntax reads as "parameter `j` is a reference to an `i32` with lifetime `b`."

The significance of binding a lifetime variable to a value probably isn't obvious. Underpinning Rust's safety checks is a lifetime system that verifies that all attempts to access data are valid. Lifetime annotations allow programmers to declare their intent. All values bound to a given lifetime must live as long as the last access to any value bound to that lifetime.

The lifetime system usually works unaided. Although every parameter has a lifetime, these checks are typically invisible as the compiler can infer most lifetimes by itself.<sup>6</sup> But the compiler needs assistance in difficult cases. Functions that accept multiple references as arguments or return a reference are often when the compiler will request assistance via an error message.

No lifetime annotations are required when calling a function. When used in a complete example as in the next listing, you can see lifetime annotations at the function definition (line 1), but not when it's used (line 8). The source code for the listing is in `ch2-add-with-lifetimes.rs`.

#### Listing 2.14 Type signature of a function with lifetime explicit annotations

```

1 fn add_with_lifetimes<'a, 'b>(i: &'a i32, j: &'b i32) -> i32 {
2     *i + *j      ← Adds the values referred to by
3 }                i and j rather than adding the
4                  references directly
5 fn main() {
6     let a = 10;
7     let b = 20;
8     let res = add_with_lifetimes(&a, &b);    ← &10 and &20 mean reference
9
10    println!("{}", res);
11 }
```

&10 and &20 mean reference  
10 and 20, respectively. No  
lifetime notation is required  
when calling a function.

On line 2, `*i + *j` adds together the referent values held by the `i` and `j` variables. It's common to see lifetime parameters when using references. While Rust can infer lifetimes

<sup>6</sup> Omitting lifetime annotations is formally referred to as *lifetime elision*.

in other cases, references require the programmer to specify the intent. Using two lifetime parameters (a and b) indicates that the lifetimes of i and j are decoupled.

**NOTE** Lifetime parameters are a way of providing control to the programmer while maintaining high-level code.

## 2.8.2 Generic functions

Another special case of function syntax appears when programmers write Rust functions to handle many possible input types. So far, we have seen functions that accept 32-bit integers (i32). The following listing shows a function signature that can be called by many input types as long as these are all the same.

### Listing 2.15 Type signature of a generic function

```
fn add<T>(i: T, j: T) -> T {
    i + j
}
```

The type variable T is introduced with angle brackets (<T>). This function takes two arguments of the same type and returns a value of that type.


Capital letters in place of a type indicate a *generic type*. Conventionally, the variables T, U, and V are used as placeholder values, but this is arbitrary. E is often used to denote an error type. We'll look at error handling in detail in chapter 3.

Generics enable significant code reuse and can greatly increase the usability of a strongly-typed language. Unfortunately, listing 2.15 doesn't compile as is. The Rust compiler complains that it cannot add two values of any type T together. The following shows the output produced when attempting to compile listing 2.15:

```
error[E0369]: cannot add `T` to `T`
--> add.rs:2:5
2 |     i + j
|     - ^ - T
|     |
|     T
|
help: consider restricting type parameter `T`
1 | fn add<T: std::ops::Add<Output = T>>(i: T, j: T) -> T {
|          ^^^^^^
error: aborting due to previous error

For more information about this error, try `rustc --explain E0369`.
```

This issue arises because T really means any type at all, even types where addition is not supported. Figure 2.3 provides a visual representation of the problem. Listing 2.15 attempts to refer to the outer ring, whereas addition is only supported by types within the inner ring.



**Figure 2.3** Only a subset of types have implement operators. When creating generic functions that include such an operator, that operation's trait must be included as a trait bound.

How do we specify that type T must implement addition? Answering this requires introducing some new terminology.

All of Rust's operators, including addition, are defined within *traits*. To require that type T must support addition, we include a trait bound alongside the type variable in the function's definition. The following listing gives an example of this syntax.

#### Listing 2.16 Type signature of a generic function with trait bounds

```
fn add<T: std::ops::Add<Output = T>>(i: T, j: T) -> T {
    i + j
}
```

The fragment `<T: std::ops::Add<Output = T>>` says that T must implement `std::ops::Add`. Using a single type variable T with the trait bound ensures that arguments i and j, as well as the result type, are the same type and that their type supports addition.

What is a trait? A *trait* is a language feature that is analogous to an interface, protocol, or contract. If you have a background in object-oriented programming, consider a trait to be an abstract base class. If you have a background in functional programming, Rust's traits are close to Haskell's type classes. For now, it's enough to say that traits enable types to advertise that they are using common behavior.

All of Rust's operations are defined with traits. For example, the addition operator (+) is defined as the `std::ops::Add` trait. Traits are properly introduced in chapter 3 and are progressively explained in depth during the course of the book.

To reiterate: all of Rust's operators are syntactic sugar for a trait's methods. Rust supports operator overloading this way. During the compilation process, `a + b` is converted to `a.add(b)`.

Listing 2.17 is a full example that demonstrates that generic functions can be called by multiple types. The listing prints these three lines to the console:

```
4.6
30
15s
```

**Listing 2.17 A generic function with a type variable and trait bounds**

```

Brings the Add trait from
std::ops into local scope
1 use std::ops::{Add};           ←
2 use std::time::Duration;       ←
3
4 fn add<T: Add<Output = T>>(i: T, j: T) -> T {
5     i + j
6 }
7
8 fn main() {
9     let floats = add(1.2, 3.4);
10    let ints = add(10, 20);
11    let durations = add(
12        Duration::new(5, 0),
13        Duration::new(10, 0)
14    );
15
16    println!("{}", floats);
17    println!("{}", ints);
18    println!("{:?})", durations);
19
20 }

```

The annotations provide context for the code's behavior:

- Annotations for lines 1 and 2 explain the import statements that bring the `Add` trait from `std::ops` and the `Duration` type from `std::time` into the local scope.
- An annotation for line 4 specifies that the generic function `add` can accept any type that implements the `Add` trait.
- Annotations for lines 9, 10, and 12 describe the specific types and contexts in which the generic function `add` is called: floating-point values, integers, and `Duration` values representing time intervals.
- An annotation for line 18 explains that since `Duration` does not implement the `Display` trait, the program falls back to requesting `Debug` instead.

As you can see, function signatures can become somewhat convoluted. Interpreting these can take some patience. Hopefully, you now have the tools to break the pieces apart in case you get stuck down the track. Here are a few principles that should assist you when reading Rust code:

- Terms in lowercase (*i*, *j*) denote variables.
- Single uppercase letters (*T*) denote generic type variables.
- Terms beginning with uppercase (*Add*) are either traits or concrete types, such as *String* or *Duration*.
- Labels ('*a*) denote lifetime parameters.

## 2.9 Creating grep-lite

We've spent most of the chapter discussing numbers. It's time for another practical example. We'll use it to learn a little bit about how Rust handles text.

Listing 2.18 is our first iteration of grep-lite. The code for this program is in the `ch2-str-simple-pattern.rs` file. Its hard-coded parameters restrict flexibility somewhat, but these are useful illustrations of string literals. The code prints a line to the console:

```
dark square is a picture feverishly turned--in search of what?
```

**Listing 2.18 Searching for a simple pattern within lines of a string**

```

1 fn main() {
2     let search_term = "picture";

```

```

3   let quote = "\n"
4 Every face, every shop, bedroom window, public-house, and
5 dark square is a picture feverishly turned--in search of what?
6 It is the same with books.
7 What do we seek through millions of pages?";
8
9   for line in quote.lines() {           ←
10     if line.contains(search_term) {
11       println!("{}", line);
12     }
13   }
14 }
```

**Multilined strings do not require special syntax.**  
The \ character on line 3 escapes the new line.

**lines() returns an iterator over quote where each iteration is a line of text. Rust uses each operating system's conventions on what constitutes a new line.**

As you can see, Rust's strings can do quite a lot by themselves. Some features of listing 2.18 that are worth highlighting include the following. From here, we'll expand the functionality of our proto-application:

- Line 9 (`quote.lines()`) demonstrates iterating line-by-line in a platform-independent manner.
- Line 10 (`line.contains()`) demonstrates searching for text using the method syntax.

### Navigating Rust's rich collection of string types

Strings are complicated for newcomers to Rust. Implementation details tend to bubble up from below and make comprehension difficult. How computers represent text is complicated, and Rust chooses to expose some of that complexity. This enables programmers to have full control but does place a burden on those learning the language.

`String` and `&str` both represent text, yet are distinct types. Interacting with values from both types can be an annoying exercise at first as different methods are required to perform similar actions. Prepare yourself for irritating type errors as your intuition develops. Until that intuition develops, however, you will usually have fewer issues if you convert your data to the `String` type.

A `String` is (probably) closest to what you know as a string type from other languages. It supports familiar operations such as concatenation (joining two strings together), appending new text onto an existing string, and trimming whitespace.

`str` is a high-performance, relatively feature-poor type. Once created, `str` values cannot expand or shrink. In this sense, these are similar to interacting with a raw memory array. Unlike a raw memory array, though, `str` values are guaranteed to be valid UTF-8 characters.

`str` is usually seen in this form: `&str`. A `&str` (pronounced *string slice*) is a small type that contains a reference to `str` data and a length. Attempting to assign a variable to type `str` will fail. The Rust compiler wants to create fixed-sized variables within a function's stack frame. As `str` values can be of arbitrary length, these can only be stored as local variables by reference.

**(continued)**

For those readers that have prior experience with systems programming, `String` uses dynamic memory allocation to store the text that it represents. Creating `&str` values avoids a memory allocation.

`String` is an *owned* type. Ownership has a particular meaning within Rust. An owner is able to make any changes to the data and is responsible for deleting values that it owns when it leaves scope (this is fully explained in chapter 3). A `&str` is a *borrowed* type. In practical terms, this means that `&str` can be thought of as read-only data, whereas `String` is read-write.

`String` literals (e.g., "Rust in Action") have the type `&str`. The full type signature including the lifetime parameter is `&'static str`. The '`static`' lifetime is somewhat special. It too owes its name to implementation details. Executable programs can contain a section of memory that is hard-coded with values. That section is known as *static memory* because it is read-only during execution.

Some other types may be encountered in your travels. Here's a short list:<sup>a</sup>

- `char`—A single character encoded as 4 bytes. The internal representation of `char` is equivalent to UCS-4/UTF-32. This differs from `&str` and `String`, which encodes single characters as UTF-8. Conversion does impose a penalty, but it means that `char` values are of fixed-width and are, therefore, easier for the compiler to reason about. Characters encoded as UTF-8 can span 1 to 4 bytes.
- `[u8]`—A slice of raw bytes, usually found when dealing with streams of binary data.
- `Vec<u8>`—A vector of raw bytes, usually created when consuming `[u8]` data. `String` is to `Vec<u8>` as `str` is to `[u8]`.
- `std::ffi::OSString`—A platform-native string. Its behavior is close to `String` but without a guarantee that it's encoded as UTF-8 and that it won't contain the zero byte (`0x00`).
- `std::path::Path`—A string-like type that is dedicated to handling filesystem paths.

Fully understanding the distinction between `String` and `&str` requires knowledge of arrays and vectors. Textual data is similar to these two types with added convenience methods applied over the top.

---

<sup>a</sup> Unfortunately, this is not an exhaustive list. Specific use cases sometimes require special handling.

Let's start adding functionality to grep-lite by printing the line number along with the match. This is equivalent to the `-n` option within the POSIX.1-2008 standard for the `grep` utility (<http://mng.bz/ZPdZ>).

Adding a few lines to our previous example, we now see the following line printed to the screen. Listing 2.19 shows the code that adds this functionality, which you'll find in `ch2/ch2-simple-with-linenums.rs`:

```
2: dark square is a picture feverishly turned-- in search of what?
```

**Listing 2.19 Manually incrementing an index variable**

```

1 fn main() {
2     let search_term = "picture";
3     let quote = "\n
4 Every face, every shop, bedroom window, public-house, and
5 dark square is a picture feverishly turned--in search of what?
6 It is the same with books. What do we seek through millions of pages?";
7     let mut line_num: usize = 1;           ← A backslash escapes the newline
8
9     for line in quote.lines() {          ← character in the string literal.
10        if line.contains(search_term) {
11            println!("{}: {}", line_num, line); ← Declares line_num as mutable via
12        }
13        line_num += 1;                 ← let mut and initializes it with 1
14    }
15 }
```

Updates the `println!` macro to allow for both values to be printed

Increments line\_num in place

Listing 2.20 shows a more ergonomic approach to incrementing `i`. The output is the same, but here the code makes use of the `enumerate()` method and method chaining. `enumerate()` takes an iterator `I`, returning another `(N, I)`, where `N` is a number that starts at 0 and increments by 1 each iteration. The source code for this listing can be found in `ch2/ch2-simple-with-enumerate.rs`.

**Listing 2.20 Automatically incrementing an index variable**

```

1 fn main() {
2     let search_term = "picture";
3     let quote = "\n
4 Every face, every shop, bedroom window, public-house, and
5 dark square is a picture feverishly turned--in search of what?
6 It is the same with books. What do we seek through millions of pages?";
7
8     for (i, line) in quote.lines().enumerate() { ← Because lines()
9         if line.contains(search_term) {           returns an iterator,
10             let line_num = i + 1;                  it can be chained
11             println!("{}: {}", line_num, line); ← with enumerate().
12         }
13     }           ← Performs addition to calculate the line
14 }           ← number, avoiding calculations at every step
```

Another feature of grep that is extremely useful is to print some context before and after the line that matches. In the GNU grep implementation, this is the `-C NUM` switch. To add support for that feature in grep-lite, we need to be able to create lists.

## 2.10 Making lists of things with arrays, slices, and vectors

Lists of things are incredibly common. The two types that you will work with most often are *arrays* and *vectors*. Arrays are fixed-width and extremely lightweight. Vectors are growable but incur a small runtime penalty because of the extra bookkeeping that

these do. To understand the underlying mechanisms with text data in Rust, it helps to have a cursory understanding of what is happening.

The goal of this section is to support printing out  $n$  lines of context that surround a match. To get there, we need to segue somewhat and explain more fully arrays, slices, and vectors. The most useful type for this exercise is the vector. To learn about vectors, though, we need to start by learning about its two simpler cousins: arrays and slices.

### 2.10.1 Arrays

An *array*, at least as far as Rust is concerned, is a tightly-packed collection of the same thing. It's possible to replace items within an array, but its size cannot change. Because variable-length types like `String` add a degree of complication, we'll revert back to discussing numbers for a little while.

Creating arrays takes two forms. We can provide a comma-delimited list within square brackets (for example, `[1, 2, 3]`) or a *repeat expression*, where you furnish two values delimited by a semicolon (for example, `[0; 100]`). The value on the left (`0`) is repeated by the number of times on the right (`100`). Listing 2.21 shows each variation on lines 2–5. The source code for this listing is in the `ch2-3arrays.rs` file. It prints these four lines to the console:

```
[1, 2, 3]:      1 + 10 = 11      2 + 10 = 12      3 + 10 = 13      (Σ[1, 2, 3] = 6)
[1, 2, 3]:      1 + 10 = 11      2 + 10 = 12      3 + 10 = 13      (Σ[1, 2, 3] = 6)
[0, 0, 0]:      0 + 10 = 10      0 + 10 = 10      0 + 10 = 10      (Σ[0, 0, 0] = 0)
[0, 0, 0]:      0 + 10 = 10      0 + 10 = 10      0 + 10 = 10      (Σ[0, 0, 0] = 0)
```

**Listing 2.21 Defining arrays and iterating over their elements**

```
1 fn main() {
2     let one                  = [1, 2, 3];
3     let two: [u8; 3]         = [1, 2, 3];
4     let blank1                = [0; 3];
5     let blank2: [u8; 3] = [0; 3];
6
7     let arrays = [one, two, blank1, blank2];
8
9     for a in &arrays {
10         print!("{:?}: ", a);
11         for n in a.iter() {
12             print!("\t{} + 10 = {}", n, n+10);
13         }
14
15         let mut sum = 0;
16         for i in 0..a.len() {
17             sum += a[i];
18         }
19         println!("\t(Σ{:?} = {})", a, sum);
20     }
21 }
```

Arrays are a simple data structure from the machine’s point of view. These are a contiguous block of memory with elements of a uniform type. The simplicity is still somewhat deceptive. Arrays can cause a few learning difficulties for newcomers:

- *The notation can be confusing.*  $[T; n]$  describes an array’s type, where  $T$  is the elements’ type and  $n$  is a non-negative integer.  $[f32; 12]$  denotes an array of 12 32-bit floating-point numbers. It’s easy to get confused with slices  $[T]$ , which do not have a compile-time length.
- *$[u8; 3]$  is a different type than  $[u8; 4]$ .* The size of the array matters to the type system.
- *In practice, most interaction with arrays occurs via another type called a slice ( $[T]$ ).* The slice is itself interacted with by reference ( $\&[T]$ ). And to add some linguistic confusion into the mix, both slices and references to slices are called *slices*.

Rust maintains its focus on safety. Array indexing is bounds checked. Requesting an item that’s out of bounds crashes (*panics* in Rust terminology) the program rather than returning erroneous data.

## 2.10.2 Slices

Slices are dynamically sized array-like objects. The term *dynamically sized* means that their size is not known at compile time. Yet, like arrays, these don’t expand or contract. The use of the word *dynamic* in dynamically sized is closer in meaning to *dynamic typing* rather than movement. The lack of compile-time knowledge explains the distinction in the type signature between an array ( $[T; n]$ ) and a slice ( $[T]$ ).

Slices are important because it’s easier to implement traits for slices than arrays. Traits are how Rust programmers add methods to objects. As  $[T; 1]$ ,  $[T; 2]$ , ...,  $[T; n]$  are all different types, implementing traits for arrays can become unwieldy. Creating a slice from an array is easy and cheap because it doesn’t need to be tied to any specific size.

Another important use for slices is their ability to act as a view on arrays (and other slices). The term *view* here is taken from database technology and means that slices can gain fast, read-only access to data without needing to copy anything around.

The problem with slices is that Rust wants to know the size of every object in your program, and slices are defined as not having a compile-time size. References to the rescue. As mentioned in the discussion about the use of the term dynamically sized, slice size is fixed in memory. These are made up of two `usize` components (a pointer and a length). That’s why you typically see slices referred to in their referenced form,  $\&[T]$  (like string slices that take the notation  $\&\text{str}$ ).

**NOTE** Don’t worry too much about the distinctions between arrays and slices yet. In practice, it’s not material. Each term is an artifact of implementation details. Those implementation details are important when dealing with performance-critical code but not when learning the basics of the language.

### 2.10.3 Vectors

Vectors (`Vec<T>`) are growable lists of `T`. Using vectors is extremely common in Rust code. These incur a small runtime penalty compared to arrays because of the extra bookkeeping that must be done to enable their size to change over time. But vectors almost always make up for this with their added flexibility.

The task at hand is to expand the feature set of the grep-lite utility. Specifically, we want the ability to store  $n$  lines of context around a match. Naturally, there are many ways to implement such a feature.

To minimize code complexity, we'll use a two-pass strategy. In the first pass, we'll tag lines that match. During the second pass, we'll collect lines that are within  $n$  lines of each of the tags.

The code in listing 2.22 (available at `ch2/ch2-introducing-vec.rs`) is the longest you've seen so far. Take your time to digest it.

The most confusing syntax in the listing is probably `Vec<Vec<(usize, String)>>`, which appears on line 15. `Vec<Vec<(usize, String)>>` is a vector of vectors (e.g., `Vec<Vec<T>>`), where `T` is a pair of values of type `(usize, String)`. `(usize, String)` is a tuple that we'll use to store line numbers along with the text that's a near match. When the `needle` variable on line 3 is set to "oo", the following text is printed to the console:

```

1: Every face, every shop,
2: bedroom window, public-house, and
3: dark square is a picture
4: feverishly turned--in search of what?
3: dark square is a picture
4: feverishly turned--in search of what?
5: It is the same with books.
6: What do we seek
7: through millions of pages?
```

**Listing 2.22 Enabling context lines to be printed out with a `Vec<Vec<T>>`**

```

1 fn main() {
2     let ctx_lines = 2;
3     let needle = "oo";
4     let haystack = "\n"
5     Every face, every shop,
6     bedroom window, public-house, and
7     dark square is a picture
8     feverishly turned--in search of what?
9     It is the same with books.
10    What do we seek
11    through millions of pages?" ;
12
13    let mut tags: Vec<usize> = vec![];
14    let mut ctx: Vec<Vec<(
15                                usize, String)>> = vec![];
16
17    for (i, line) in haystack.lines().enumerate() {
```

tags holds line numbers where matches occur.

ctx contains a vector per match to hold the context lines.

Iterates through the lines, recording line numbers where matches are encountered

```

18     if line.contains(needle) {
19         tags.push(i);
20
21         let v = Vec::with_capacity(2*ctx_lines + 1);
22         ctx.push(v);
23     }
24 }
25
26 if tags.is_empty() { ← When there are no
27     return; ← matches, exits early
28 }
29
30 for (i, line) in haystack.lines().enumerate() {
31     for (j, tag) in tags.iter().enumerate() {
32         let lower_bound =
33             tag.saturating_sub(ctx_lines); ←
34         let upper_bound =
35             tag + ctx_lines;
36
37         if (i >= lower_bound) && (i <= upper_bound) {
38             let line_as_string = String::from(line); ←
39             let local_ctx = (i, line_as_string);
40             ctx[j].push(local_ctx);
41         }
42     }
43 }
44
45 for local_ctx in ctx.iter() {
46     for &(i, ref line) in local_ctx.iter() { ←
47         let line_num = i + 1;
48         println!("{}: {}", line_num, line);
49     }
50 }
51 }
```

**Vec::with\_capacity(n)** reserves space for n items. No explicit type signature is required as it can be inferred via the definition of ctx on line 15.

For each tag, at every line, checks to see if we are near a match. When we are, adds that line to the relevant `Vec<T>` within ctx.

`saturating_sub()` is subtraction that returns 0 on integer underflow rather than crashing the program (CPUs don't like attempting to send usize below zero).

Copies line into a new String and stores that locally for each match

ref line informs the compiler that we want to borrow this value rather than move it. These two terms are explained fully in later chapters.

`Vec<T>` performs best when you can provide it with a size hint via `Vec::with_capacity()`. Providing an estimate minimizes the number of times memory will need to be allocated from the OS.

**NOTE** When considering this approach in real text files, encodings can cause issues. `String` is guaranteed to be UTF-8. Naively reading in a text file to a `String` causes errors if invalid bytes are detected. A more robust approach is to read in data as `[u8]` (a slice of `u8` values), then decode those bytes with help from your domain knowledge.

## 2.11 Including third-party code

Incorporating third-party code is essential to productive Rust programming. Rust's standard library tends to lack many things that other languages provide, like random number generators and regular expression support. That means it's common to incorporate third-party crates into your project. To get your feet wet, let's start with the `regex` crate.

Crates are the name the Rust community uses where others use terms such as package, distribution, or library. The regex crate provides the ability to match regular expressions rather than simply looking for exact matches.

To use third-party code, we'll rely on the cargo command-line tool. Follow these instructions:

- 1 Open a command prompt.
- 2 Move to a scratch directory with `cd /tmp` (`cd %TMP%` on MS Windows).
- 3 Run `cargo new grep-lite --vcs none`. It produces a short confirmation message:

```
Created binary (application) `grep-lite` package
```

- 4 Run `cd grep-lite` to move into the project directory.
- 5 Execute `cargo add regex@1` to add version 1 of the regex crate as a dependency. This alters the file `/tmp/grep-lite/Cargo.toml`. If `cargo add` is unavailable for you, see the sidebar, “2.2,” in section 2.3.4.
- 6 Run `cargo build`. You should see output fairly similar to the following begin to appear:

```
Updating crates.io index
Downloaded regex v1.3.6
Compiling lazy_static v1.4.0
Compiling regex-syntax v0.6.17
Compiling thread_local v1.0.1
Compiling aho-corasick v0.7.10
Compiling regex v1.3.6
Compiling grep-lite v0.1.0 (/tmp/grep-lite)
Finished dev [unoptimized + debuginfo] target(s) in 4.47s
```

Now that you have the crate installed and compiled, let's put it into action. First, we'll support searching for exact matches in listing 2.23. Later, in listing 2.26, the project grows to support regular expressions.

### 2.11.1 Adding support for regular expressions

Regular expressions add great flexibility to the patterns that we are able to search for. The following listing is a copy of an early example that we'll modify.

#### Listing 2.23 Matching on exact strings with the `contains()` method

```
fn main() {
    let search_term = "picture";
    let quote = "Every face, every shop, bedroom window, public-house, and
dark square is a picture feverishly turned--in search of what?
It is the same with books. What do we seek through millions of pages?";

    for line in quote.lines() {
        if line.contains(search_term) {
            println!("{}: {}", search_term, line);
        }
    }
}
```

← | Implements a `contains()` method that searches for a substring

```

        }
    }
}

```

Make sure that you have updated grep-lite/Cargo.toml to include regex as a dependency as described in the previous section. Now, open grep-lite/src/main.rs in a text editor and fill it in with the code in the following listing. The source code for this listing is available in ch2/ch2-with-regex.rs.

#### Listing 2.24 Searching for patterns with regular expressions

```

use regex::Regex;           ← Brings the Regex type from the
                           regex crate into local scope
fn main() {
    let re = Regex::new("picture").unwrap();   ← unwrap() unwraps a Result,
                                                crashing if an error occurs.
                                                Handling errors more robustly
                                                is discussed in depth later in
                                                the book.

    let quote = "Every face, every shop, bedroom window, public-house, and
dark square is a picture feverishly turned--in search of what?
It is the same with books. What do we seek through millions of pages?";

    for line in quote.lines() {
        let contains_substring = re.find(line);
        match contains_substring {               ← Replaces the contains() method
                                              from listing 2.23 with a match block
                                              that requires that we handle all
                                              possible cases

            Some(_) => println!("{}: {}", line),
            None => (),   ← Some(T) is the positive case of an
                           Option, meaning that re.find() was
                           successful: it matches all values.

        }
    }
}

```

**None is the negative case of an Option; () can be thought of as a null placeholder value here.**

Open a command prompt and move to the root directory of your grep-lite project. Executing cargo run should produce output similar to the following text:

```

$ cargo run
Compiling grep-lite v0.1.0 (file:///tmp/grep-lite)
Finished dev [unoptimized + debuginfo] target(s) in 0.48s
Running `target/debug/grep-lite`
dark square is a picture feverishly turned--in search of what?

```

Admittedly, the code within listing 2.24 hasn't taken significant advantage of its newfound regular expression capabilities. Hopefully, you'll have the confidence to be able to slot those into some of the more complex examples.

### 2.112 Generating the third-party crate documentation locally

Documentation for third-party crates is typically available online. Still, it can be useful to know how to generate a local copy in case the internet fails you:

- 1 Move to the root of the project directory in a terminal: /tmp/grep-lite or %TMP%\grep-lite

- 2 Execute cargo doc. It will inform you of its progress in the console:

```
$ cargo doc
    Checking lazy_static v1.4.0
  Documenting lazy_static v1.4.0
    Checking regex-syntax v0.6.17
  Documenting regex-syntax v0.6.17
    Checking memchr v2.3.3
  Documenting memchr v2.3.3
    Checking thread_local v1.0.1
    Checking aho-corasick v0.7.10
  Documenting thread_local v1.0.1
  Documenting aho-corasick v0.7.10
    Checking regex v1.3.6
  Documenting regex v1.3.6
  Documenting grep-lite v0.1.0 (file:///tmp/grep-lite)
    Finished dev [unoptimized + debuginfo] target(s) in 3.43s
```

Congratulations. You have now created HTML documentation. By opening /tmp/grep-lite/target/doc/grep\_lite/index.html in a web browser (also try cargo doc --open from the command line), you'll be able to view the documentation for all the crates that yours depend on. It's also possible to inspect the output directory to take a look at what is available to you:

```
$ tree -d -L 1 target/doc/
target/doc/
├── aho_corasick
├── grep_lite
├── implementors
├── memchr
├── regex
├── regex_syntax
├── src
└── thread_local
```

### **2.113 Managing Rust toolchains with rustup**

rustup is another handy command-line tool, along with cargo. Where cargo manages projects, rustup manages your Rust installation(s). rustup cares about Rust toolchains and enables you to move between versions of the compiler. This means it's possible to compile your projects for multiple platforms and experiment with nightly features of the compiler while keeping the stable version nearby.

rustup also simplifies accessing Rust's documentation. Typing rustup doc opens your web browser to a local copy of Rust's standard library.

### **2.12 Supporting command-line arguments**

Our program is rapidly increasing its feature count. Yet, there is no way for any options to be specified. To become an actual utility, grep-lite needs to be able to interact with the world.

Sadly, though, Rust has a fairly tight standard library. As with regular expressions, another area with relatively minimalist support is handling command-line arguments. A nicer API is available through a third-party crate called `clap` (among others).

Now that we've seen how to bring in third-party code, let's take advantage of that to enable users of `grep-lite` to choose their own pattern. (We'll get to choosing their own input source in the next section.) First, add `clap` as a dependency in your `Cargo.toml`:

```
$ cargo add clap@2
Updating 'https://github.com/rust-lang/crates.io-index' index
Adding clap v2 to dependencies
```

You can confirm that the crate has been added to your project by inspecting its `Cargo.toml` file.

#### Listing 2.25 Adding a dependency to grep-lite/Cargo.toml

```
[package]
name = "grep-lite"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]

[dependencies]
regex = "1"
clap = "2"
```

Now, adjust `src/main.rs`.

#### Listing 2.26 Editing grep-lite/src/main.rs

```
1 use regex::Regex;
2 use clap::{App, Arg};      ← Brings clap::App and
3                               ← clap::Arg objects into
4 fn main() {                  ← local scope
5     let args = App::new("grep-lite")    ← Incrementally builds a command
6         .version("0.1")                 ← argument parser, where each
7         .about("searches for patterns") ← argument takes an Arg. In our
8         .arg(Arg::with_name("pattern")) ← case, we only need one.
9             .help("The pattern to search for")
10            .takes_value(true)
11            .required(true))
12            .get_matches();
13
14    let pattern = args.value_of("pattern").unwrap();   ← Extracts the
15    let re = Regex::new(pattern).unwrap();                ← pattern argument
16
17    let quote = "Every face, every shop, bedroom window, public-house, and
18 dark square is a picture feverishly turned--in search of what?
19 It is the same with books. What do we seek through millions of pages?" ;
20
21    for line in quote.lines() {
22        match re.find(line) {
```

```

23     Some(_) => println!("{}", line),
24     None => (),
25   }
26 }
27 }
```

With your project updated, executing cargo run should set off a few lines in your console:

```

$ cargo run
    Finished dev [unoptimized + debuginfo] target(s) in 2.21 secs
      Running `target/debug/grep-lite`
error: The following required arguments were not provided:
      <pattern>

USAGE:
      grep-lite <pattern>

For more information try --help
```

The error is due to the fact that we haven't passed sufficient arguments through to our resulting executable. To pass arguments through, cargo supports some special syntax. Any arguments appearing after -- are sent through to the resulting executable binary:

```

$ cargo run -- picture
    Finished dev [unoptimized + debuginfo] target(s) in 0.0 secs
      Running `target/debug/grep-lite picture`
dark square is a picture feverishly turned--in search of what?
```

But clap does more than provide parsing. It also generates usage documentation on your behalf. Running grep-lite --help provides an expanded view:

```

$ ./target/debug/grep-lite --help
grep-lite 0.1
searches for patterns

USAGE:
      grep-lite <pattern>

FLAGS:
      -h, --help            Prints help information
      -V, --version          Prints version information

ARGS:
      <pattern>    The pattern to search for
```

## 2.13 *Reading from files*

Searching for text wouldn't be complete without being able to search within files. File I/O can be surprisingly finicky and so has been left until last.

Before adding this functionality to grep-lite, let's take a look at a standalone example in listing 2.27. The code for this listing is in the ch2-read-file.rs file. The general pattern

is to open a `File` object, then wrap that in a `BufReader`. `BufReader` takes care of providing *buffered I/O*, which can reduce system calls to the OS if the hard disk is congested.

### Listing 2.27 Reading a file manually line by line

```

1 use std::fs::File;
2 use std::io::BufReader;
3 use std::io::prelude::*;
4
5 fn main() {
6     let f = File::open("readme.md").unwrap();
7     let mut reader = BufReader::new(f);
8
9     let mut line = String::new(); ←
10
11    loop {
12        let len = reader.read_line(&mut line)
13            .unwrap(); ←
14        if len == 0 { ←
15            break
16        }
17
18        println!("{} ({} bytes long)", line, len);
19
20        line.truncate(0); ←
21    }
22 }
```

Creates a `File` object that requires a path argument and error handling if the file does not exist. This program crashes if a `readme.md` is not present.

Reuses a single `String` object over the lifetime of the program

Because reading from disk can fail, we need to explicitly handle this. In our case, errors crash the program.

Shrinks the `String` back to length 0, preventing lines from persisting into the following ones

Manually looping through a file can be cumbersome, despite its usefulness in some cases. For the common case of iterating through lines, Rust provides a helper iterator as the following listing shows. The source code for this listing is in the file `ch2/ch2-bufreader-lines.rs`.

### Listing 2.28 Reading a file line by line via `BufReader::lines()`

```

1 use std::fs::File;
2 use std::io::BufReader;
3 use std::io::prelude::*;
4
5 fn main() {
6     let f = File::open("readme.md").unwrap();
7     let reader = BufReader::new(f);
8
9     for line_ in reader.lines() { ←
10         let line = line_.unwrap(); ←
11         println!("{} ({} bytes long)", line, line.len());
12     }
13 }
```

A subtle behavior change occurs here. `BufReader::lines()` removes the trailing newline character from each line.

Unwraps the Result, but at the risk of crashing the program if an error occurs

We're now in a position to add reading from a file into `grep-lite`'s feature list. The following listing creates a complete program that takes a regular expression pattern and an input file as arguments.

**Listing 2.29** Reading lines from a file

```

1 use std::fs::File;
2 use std::io::BufReader;
3 use std::io::prelude::*;
4 use regex::Regex;
5 use clap::{App,Arg};
6
7 fn main() {
8     let args = App::new("grep-lite")
9         .version("0.1")
10        .about("searches for patterns")
11        .arg(Arg::with_name("pattern")
12            .help("The pattern to search for")
13            .takes_value(true)
14            .required(true))
15        .arg(Arg::with_name("input")
16            .help("File to search")
17            .takes_value(true)
18            .required(true))
19        .get_matches();
20
21     let pattern = args.value_of("pattern").unwrap();
22     let re = Regex::new(pattern).unwrap();
23
24     let input = args.value_of("input").unwrap();
25     let f = File::open(input).unwrap();
26     let reader = BufReader::new(f);
27
28     for line_ in reader.lines() {
29         let line = line_.unwrap();
30         match re.find(&line) {
31             Some(_) => println!("{}", line),
32             None => (),
33         }
34     }
35 }
```

line is a String, but  
re.find() takes an &str  
as an argument.

**2.14** *Reading from stdin*

A command-line utility wouldn't be complete if it wasn't able to read from stdin. Unfortunately for those readers who skimmed over earlier parts of this chapter, some of the syntax on line 8 might look quite unfamiliar. In short, rather than duplicate code within `main()`, we'll use a generic function to abstract away the details of whether we are dealing with files or stdin:

**Listing 2.30** Searching through a file or stdin

```

1 use std::fs::File;
2 use std::io;
3 use std::io::BufReader;
4 use std::io::prelude::*;
5 use regex::Regex;
```

```

6 use clap::{App,Arg};
7
8 fn process_lines<T: BufRead + Sized>(reader: T, re: Regex) {
9     for line_ in reader.lines() {
10         let line = line_.unwrap();
11         match re.find(&line) {
12             Some(_) => println!("{}", line),
13             None => (),
14         }
15     }
16 }
17
18 fn main() {
19     let args = App::new("grep-lite")
20         .version("0.1")
21         .about("searches for patterns")
22         .arg(Arg::with_name("pattern")
23             .help("The pattern to search for")
24             .takes_value(true)
25             .required(true))
26         .arg(Arg::with_name("input")
27             .help("File to search")
28             .takes_value(true)
29             .required(false))
30         .get_matches();
31
32     let pattern = args.value_of("pattern").unwrap();
33     let re = Regex::new(pattern).unwrap();
34
35     let input = args.value_of("input").unwrap_or("-");
36
37     if input == "-" {
38         let stdin = io::stdin();
39         let reader = stdin.lock();
40         process_lines(reader, re);
41     } else {
42         let f = File::open(input).unwrap();
43         let reader = BufReader::new(f);
44         process_lines(reader, re);
45     }
46 }
```

line is a String, but  
re.find() takes an &str  
as an argument.

## Summary

- Rust has full support for primitive types, such as integers and floating-point numbers.
- Functions are strongly typed and require types to be specified for their parameters and return values.
- Rust features, such as iteration and mathematical operations, rely on traits. The for loop is a shorthand for the std::iter::IntoIterator trait, for example.
- List-like types are tailored to specific use cases. You will typically reach for Vec<T> first.

- All Rust programs have a single entry function: `main()`.
- Every crate has a `Cargo.toml` file that specifies its metadata.
- The `cargo` tool is able to compile your code and fetch its dependencies.
- The `rustup` tool provides access to multiple compiler toolchains and to the language's documentation.

# Compound data types

## This chapter covers

- Composing data with structs
- Creating enumerated data types
- Adding methods and handling errors in a type-safe manner
- Defining and implementing common behavior with traits
- Understanding how to keep implementation details private
- Using cargo to build documentation for your project

Welcome to chapter 3. If we spent the last chapter looking at Rust's atoms, this chapter is focused more on its molecules.

This chapter focuses on two key building blocks for Rust programmers, `struct` and `enum`. Both are forms of *compound data types*. Together, `struct` and `enum` can compose other types to create something more useful than what those other types would be alone. Consider how a 2D point ( $x,y$ ) is composed from two numbers,  $x$  and  $y$ . We wouldn't want to maintain two variables,  $x$  and  $y$ , in our program. Instead,

we would like to refer to the point as a whole entity. In this chapter, we also discuss how to add methods to types with `impl` blocks. Lastly, we take a deeper look at *traits*, Rust’s system for defining interfaces.

Throughout this chapter, you’ll work through how to represent files in code. Although conceptually simple—if you’re reading this book, it’s highly likely you’ve interacted with a file through code before—there are enough edge cases to make things interesting. Our strategy will be to create a mock version of everything using our own imaginary API. Then, toward the latter part of the chapter, you’ll learn how to interact with your actual operating system (OS) and its filesystem(s).

### 3.1 Using plain functions to experiment with an API

To start, let’s see how far we can get by making use of the tools we already know. Listing 3.1 lays out a few things that we would expect, such as opening and closing a file. We’ll use a rudimentary mock type to model one: a simple alias around `String` that holds a filename and little else.

To make things slightly more interesting than writing lots of boilerplate code, listing 3.1 sprinkles in a few new concepts. These show you how to tame the compiler while you’re experimenting with your design. It provides attributes (`#![allow(unused_variables)]`) to relax compiler warnings. The `read` function illustrates how to define a function that never returns. The code actually doesn’t do anything, however. That will come shortly. You’ll find the source for this listing in the file `ch3/ch3-not-quite-file-1.rs`.

**Listing 3.1** Using type aliases to stub out a type

```

1 #![allow(unused_variables)]           ← Relaxes compiler warnings
2
3 type File = String;                ← Creates a type alias. The compiler
4
5 fn open(f: &mut File) -> bool {      ← won't distinguish between String &
6   true                                ← File, but your source code will.
7
8 fn close(f: &mut File) -> bool {       ← Let's assume for the moment that
9   true                                ← these two functions always succeed.
10 }
11
12 #[allow(dead_code)]                  ← Relaxes a compiler warning
13 fn read(f: &mut File,                 ← about an unused function
14   save_to: &mut Vec<u8>) -> ! {    ←
15     unimplemented!()                   ← A macro that crashes
16 }                                         ← the program if it's
17
18 fn main() {
19   let mut f1 = File::from("f1.txt");   ← The ! return type
20   open(&mut f1);                      ← indicates to the Rust
21   //read(f1, vec![]);                  ← compiler that this
22   close(&mut f1);                     ← function never returns.
23 }
```

The annotations provide the following insights:

- Line 1: `#![allow(unused_variables)]` - Relaxes compiler warnings while working through ideas.
- Line 3: `type File = String;` - Creates a type alias. The compiler won't distinguish between `String` & `File`, but your source code will.
- Line 12: `#[allow(dead_code)]` - Relaxes a compiler warning about an unused function.
- Line 14: `unimplemented!()` - A macro that crashes the program if it's encountered.
- Line 21: `//read(f1, vec![]);` - With the type declaration at line 3, `File` inherits all of `String`'s methods.
- Line 23: `}` - There's little point in calling this method.

There are *lots* of things that needs to be built on from listing 3.1. For example

- *We haven't created a persistent object that would represent a file.* There's only so much that can be encoded in a string.
- *There's no attempt to implement read().* If we did, how would we handle the failure case?
- *open() and close() return bool.* Perhaps there is a way to provide a more sophisticated result type that might be able to contain an error message if the OS reports one.
- *None of our functions are methods.* From a stylistic point of view, it might be nice to call `f.open()` rather than `open(f)`.

Let's begin at the top and work our way through this list. Brace yourself for a few scenic detours along the way as we encounter a few side roads that will be profitable to explore.

## Special return types in Rust

If you are new to the language, some return types are difficult to interpret. These are also especially difficult to search for because they are made from symbols rather than words.

Known as the *unit type*, `()` formally is a zero-length tuple. It is used to express that a function returns no value. Functions that appear to have no return type return `()`, and expressions that are terminated with a semicolon `(;)` return `()`. For example, the `report()` function in the following code block returns the unit type implicitly:

```
use std::fmt::Debug;
fn report<T: Debug>(item: T) {
    println!("{}: {:?}", item);
}
```

And this example returns the unit type explicitly:

```
fn clear(text: &mut String) -> () {
    *text = String::from("");
}
```

The unit type often occurs in error messages. It's common to forget that the last expression of a function shouldn't end with a semicolon.

The exclamation symbol, `!`, is known as the “Never” type. `Never` indicates that a function never returns, especially when it is guaranteed to crash. For example, take this code:

```
fn dead_end() -> ! {
    panic!("you have reached a dead end");
}
```

**(continued)**

The following example creates an infinite loop that prevents the function from returning:

```
fn forever() -> ! {
    loop {
        //...
    };
}
```

Unless it contains a break, the loop never finishes. This prevents the function from returning.

As with the unit type, `Never` sometimes occurs within error messages. The Rust compiler complains about mismatched types when you forget to add a `break` in your `loop` block if you've indicated that the function returns a non-`Never` type.

## 3.2 Modeling files with struct

We need something to represent that thing we're trying to model. `struct` allows you to create a composite type made up of other types. Depending on your programming heritage, you may be more familiar with terms such as object or record.

We'll start with requiring that our files have a name and zero or more bytes of data. Listing 3.2 prints the following two lines to the console:

```
File { name: "f1.txt", data: [] }
f1.txt is 0 bytes long
```

To represent data, listing 3.2 uses `Vec<u8>`, which is a growable list of `u8` (single byte) values. The bulk of the `main()` function demonstrates usage (e.g., field access). The file `ch3/ch3-mock-file.rs` contains the code for this listing.

**Listing 3.2 Defining an instance of `struct` to represent files**

Here the  
`vec!` macro  
simulates  
an empty  
file.

```
1 #[derive(Debug)]           ← Allows println! to print File. The std::fmt::Debug trait works in conjunction with {:?} within the macro to enable File as a printable string.
2 struct File {             ← Using Vec<u8>, provides access to some useful conveniences like dynamic sizing, which makes it possible to simulate writing to a file
3     name: String,          ← String::from generates owned strings from string literals, which are slices.
4     data: Vec<u8>,          ← Accessing fields uses the . operator.
5 }
6
7 fn main() {                ← Accessing fields by reference prevents their use after move issues.
8     let f1 = File {         ←
9         name: String::from("f1.txt"),   ←
10        data: Vec::new(),           ←
11    };                      ←
12
13    let f1_name = &f1.name;      ←
14    let f1_length = &f1.data.len();  ←
15
16    println!("{}: {:?}", f1);      ←
17    println!("{} is {} bytes long", f1_name, f1_length);  ←
18 }
```

Here is a detailed overview of listing 3.2:

- *Lines 1–5 define the `File` struct.* Definitions include fields and their associated types. These also include each field's lifetimes, which happened to be elided here. Explicit lifetimes are required when a field is a reference to another object.
- *Lines 8–11 create our first instance of `File`.* We use a literal syntax here, but typically structs in the wild are created via a convenience method. `String::from()` is one of those convenience methods. It takes a value of another type; in this case, a string slice (`&str`), which returns a `String` instance. `Vec::new()` is the more common case.
- *Lines 13–17 demonstrate accessing our new instance's fields.* We prepend an ampersand to indicate that we want to access this data by reference. In Rust parlance, this means that the variables `f1_name` and `f1_length` are borrowing the data these refer to.

You have probably noticed that our `File` struct doesn't actually store anything to disk at all. That's actually OK for now. If you're interested, figure 3.1 shows its internals. In the figure, its two fields (`name` and `data`) are themselves both created by structs. If you're unfamiliar with the term pointer (`ptr`), consider pointers to be the same thing as references for now. Pointers are variables that refer to some location in memory. The details are explained at length in chapter 6.




Figure 3.1 Inspecting the internals of the `File` struct

We'll leave interacting with the hard disk drive or other persistent storage until later in the chapter. For the meantime, let's recreate listing 3.1 and add the `File` type as promised.

### The newtype pattern

Sometimes the `type` keyword is all that you need. But what about when you need the compiler to treat your new “type” as a fully-fledged, distinct type rather than just an alias? Enter `newtype`. The `newtype` pattern consists of wrapping a core type within a single field struct (or perhaps a tuple). The following code shows how to distinguish network hostnames from ordinary strings. You'll find this code in `ch3/ch3-newtype-pattern.rs`:

**(continued)**

```

struct Hostname(String);           ← Hostname is
fn connect(host: Hostname) {      our new type.
    println!("connected to {}", host.0); ← Uses the type system
}                                  to guard against
                                    invalid usage
fn main() {
    let ordinary_string = String::from("localhost");
    let host = Hostname(ordinary_string.clone());
    connect(ordinary_string);
}

```

Accesses the underlying data with a numeric index

Here is the compiler output from rustc:

```

$ rustc ch3-newtype-pattern.rs
error[E0308]: mismatched types
--> ch3-newtype-pattern.rs:11:13
|
11 |     connect(ordinary_string);
|     ^^^^^^^^^^^^^^^^^^^^^ expected struct `Hostname`,
|                           found struct `String`

error: aborting due to previous error

```

For more information about this error, try `rustc --explain E0308`.

Using the newtype pattern can strengthen a program by preventing data from being silently used in inappropriate contexts. The downside of using the pattern is that each new type must opt in to all of its intended behavior. This can feel cumbersome.

We can now add a little bit of functionality to the first listing of the chapter. Listing 3.3 (available at ch3/ch3-not-quite-file-2.rs) adds the ability to read a file that has some data in it. It demonstrates how to use a struct to mimic a file and simulate reading its contents. It then converts opaque data into a String. All functions are assumed to always succeed, but the code is still littered with hard-coded values. Still, the code finally prints something to the screen. Here is partially obscured output from the program:

```

File { name: "2.txt", data: [114, 117, 115, 116, 33] }
2.txt is 5 bytes long
*****   ← Revealing this line would
                      spoil all of the fun!

```

### **Listing 3.3 Using struct to mimic a file and simulate reading its contents**

```

1 #![allow(unused_variables)]
2
3 #[derive(Debug)]   ← Enables File to work with println!
4 struct File {      and its fmt! sibling macros (used
                        at the bottom of the listing)

```

Silences warnings

```

5     name: String,
6     data: Vec<u8>,
7 }
8
9 fn open(f: &mut File) -> bool {      ←
10    true
11 }
12
13 fn close(f: &mut File) -> bool {      ←
14    true
15 }
16
17 fn read(          ← These two
18   f: &File,           functions remain
19   save_to: &mut Vec<u8>, inert for now.
20 ) -> usize {        ←
21   let mut tmp = f.data.clone();       ←
22   let read_length = tmp.len();       ←
23
24   save_to.reserve(read_length);      ← Returns the number
25   save_to.append(&mut tmp);          ← of bytes read
26   read_length
27 }
28
29 fn main() {           ←
30   let mut f2 = File {           ← Makes a copy of the data here
31     name: String::from("2.txt"), because save_to.append()
32     data: vec![114, 117, 115, 116, 33], shrinks the input Vec<T>
33   };
34
35   let mut buffer: Vec<u8> = vec![];   ←
36
37   open(&mut f2);                   ← Ensures that there is
38   let f2_length = read(&f2, &mut buffer); sufficient space to fit
39   close(&mut f2);                 ← the incoming data
40
41   let text = String::from_utf8_lossy(&buffer);   ← Allocates sufficient data in the save_to
42                                         buffer to hold the contents of f
43   println!("{}:?", f2);             ← Does the hard work of
44   println!("{} is {} bytes long", &f2.name, f2_length); interacting with the file
45   println!("{}: {}", text)         ←
46 }                                ← Converts Vec<u8> to
                                         String. Any bytes that
                                         are not valid UTF-8 are
                                         replaced with ⚡.
                                         Views the bytes 114, 117, 115,
                                         116, and 33 as an actual word

```

The code so far has tackled two of the four issues raised at the end of listing 3.1:

- Our `File` struct is a bona fide type.
- `read()` is implemented, albeit in a memory-inefficient manner.

These last two points remain:


- `open()` and `close()` return `bool`.
- None of our functions are methods.

### 3.3 Adding methods to a struct with `impl`

This section explains briefly what methods are and describes how to make use of them in Rust. Methods are functions that are coupled to some object. From a syntactic point of view, these are just functions that don't need to specify one of their arguments. Rather than calling `open()` and passing a `File` object in as an argument (`read(f, buffer)`), methods allow the main object to be implicit in the function call (`f.read(buffer)`) using the dot operator.<sup>1</sup>

Rust is different than other languages that support methods: there is no `class` keyword. Types created with `struct` (and `enum`, which is described later) feel like classes at times, but as they don't support inheritance, it's probably a good thing that they're named something different.

To define methods, Rust programmers use an `impl` block, which is physically distinct in source code from the `struct` and `enum` blocks that you have already encountered. Figure 3.2 shows the differences.



**Figure 3.2** Illustrating syntactic differences between Rust and most object oriented languages. Within Rust, methods are defined separately from fields.

#### 3.3.1 Simplifying object creation by implementing `new()`

Creating objects with reasonable defaults is done through the `new()` method. Every struct can be instantiated through a literal syntax. This is handy for getting started, but leads to unnecessary verbosity in most code.

Using `new()` is a convention within the Rust community. Unlike other languages, `new` is not a keyword and isn't given some sort of blessed status above other methods. Table 3.1 summarizes the conventions.

---

<sup>1</sup> There are a number of theoretical differences between methods and functions, but a detailed discussion of those computer science topics is available in other books. Briefly, functions are regarded as *pure*, meaning their behavior is determined solely by their arguments. Methods are inherently *impure*, given that one of their arguments is effectively a side effect. These are muddy waters, though. Functions are perfectly capable of acting on side effects themselves. Moreover, methods are implemented with functions. And, to add an exception to an exception, objects sometimes implement *static methods*, which do not include implicit arguments.

**Table 3.1 Comparing Rust's literal syntax for creating objects with the use of the `new()` method**

Current usage	With <code>File::new()</code>
<pre>1 File { 2     name: String::from("f1.txt"), 3     data: Vec::new(), 4 }</pre>	<code>File::new("f1.txt", vec![]);</code>
<pre>1 File { 2     name: String::from("f2.txt"), 3     data: vec![114, 117, 115, 116, 33], 4 }</pre>	<code>File::new("f2.txt", vec![114, 117, 115, 116, 33]);</code>

To enable these changes, make use of an `impl` block as the next listing shows (see ch3/ch3-defining-files-neatly.rs). The resulting executable should print out the same message as listing 3.3, substituting `f3.txt` for the original's `f1.txt`.

**Listing 3.4 Using `impl` blocks to add methods to a struct**

```
1 #[derive(Debug)]
2 struct File {
3     name: String,
4     data: Vec<u8>,
5 }
6
7 impl File {
8     fn new(name: &str) -> File { ←
9         File {
10             name: String::from(name),
11             data: Vec::new(),
12         }
13     }
14 }
15
16 fn main() {
17     let f3 = File::new("f3.txt");
18
19     let f3_name = &f3.name; ←
20     let f3_length = f3.data.len();
21
22     println!("{}: {:?}", f3);
23     println!("{} is {} bytes long", f3_name, f3_length);
24 }
```

As `File::new()` is a completely normal function, we need to tell Rust that it will return a `File` from this function.

`File::new()` does little more than encapsulate the object creation syntax, which is normal.

Fields are private by default but can be accessed within the module that defines the struct. The module system is discussed later in the chapter.

Merging this new knowledge with the example that we already have, listing 3.5 is the result (see ch3/ch3-defining-files-neatly.rs). It prints the following three lines to the console:

```
File { name: "2.txt", data: [114, 117, 115, 116, 33] }
2.txt is 5 bytes long
*****
```

← Still hidden!

**Listing 3.5 Using impl to improve the ergonomics of File**

```

1  #![allow(unused_variables)]
2
3  #[derive(Debug)]
4  struct File {
5      name: String,
6      data: Vec<u8>,
7  }
8
9  impl File {
10     fn new(name: &str) -> File {
11         File {
12             name: String::from(name),
13             data: Vec::new(),
14         }
15     }
16
17     fn new_with_data(
18         name: &str,
19         data: &Vec<u8>,
20     ) -> File {           ← This method sneaked in to deal with
21         let mut f = File::new(name);
22         f.data = data.clone();
23         f
24     }
25
26     fn read(
27         self: &File,
28         save_to: &mut Vec<u8>,
29     ) -> usize {           ← Replaces the f
30         let mut tmp = self.data.clone();
31         let read_length = tmp.len();
32         save_to.reserve(read_length);
33         save_to.append(&mut tmp);
34         read_length
35     }
36 }
37
38 fn open(f: &mut File) -> bool {           ← An explicit type needs to be
39     true
40 }
41
42 fn close(f: &mut File) -> bool {
43     true
44 }
45
46 fn main() {
47     let f3_data: Vec<u8> = vec![           ← provided as vec! and can't
48         114, 117, 115, 116, 33
49     ];
50     let mut f3 = File::new_with_data("2.txt", &f3_data);
51
52     let mut buffer: Vec<u8> = vec![];
53 }
```

```

54     open(&mut f3);
55     let f3_length = f3.read(&mut buffer);      <--|
56     close(&mut f3);
57
58     let text = String::from_utf8_lossy(&buffer);
59
60     println!("{}: {}", f3);
61     println!("{} is {} bytes long", &f3.name, f3_length);
62     println!("{}: {}", f3, text);
63 }
```

Here is the change in the calling code.

## 3.4 Returning errors

Early on in the chapter, two points were raised discussing dissatisfaction with being unable to properly signify errors:

- *There was no attempt at implementing read().* If we did, how would we handle the failure case?
- *The methods open() and close() return bool.* Is there a way to provide a more sophisticated result type to contain an error message if the OS reports one?

The issue arises because dealing with hardware is unreliable. Even ignoring hardware faults, the disk might be full or the OS might intervene and tell you that you don't have permission to delete a particular file. This section discusses different methods for signalling that an error has occurred, beginning with approaches common in other languages and finishing with idiomatic Rust.

### 3.4.1 Modifying a known global variable

One of the simplest methods for signalling that an error has occurred is by checking the value of a global variable. Although notoriously error-prone, this is a common idiom in systems programming.

C programmers are used to checking the value of `errno` once system calls return. As an example, the `close()` system call closes a *file descriptor* (an integer representing a file with numbers assigned by the OS) and can modify `errno`. The section of the POSIX standard discussing the `close()` system call includes this snippet:

*"If close() is interrupted by a signal that is to be caught, it shall return -1 with errno set to EINTR and the state of fildes [file descriptor] is unspecified. If an I/O error occurred while reading from or writing to the file system during close(), it may return -1 with errno set to EIO; if this error is returned, the state of fildes is unspecified."*

—The Open Group Base Specifications (2018)

Setting `errno` to either `EIO` or `EINTR` means to set it to some magical internal constant. The specific values are arbitrary and defined per OS. With the Rust syntax, checking global variables for error codes would look something like the following listing.

**Listing 3.6 Rust-like code that checks error codes from a global variable**

```

static mut ERROR: i32 = 0;      ← A global variable, static mut (or
// ...                         mutable static), with a static lifetime
                                that's valid for the life of the program

fn main() {
    let mut f = File::new("something.txt");

    read(f, buffer);
    unsafe { ←
        if ERROR != 0 {
            panic!("An error has occurred while reading the file ")
        }
    }

    close(f);
    unsafe { ←
        if ERROR != 0 {
            panic!("An error has occurred while closing the file ")
        }
    }
}

```

**Checks the ERROR value. Error checking relies on the convention that 0 means no error.**

**Accessing and modifying static mut variables requires the use of an unsafe block. This is Rust's way of disclaiming all responsibility.**

Listing 3.7, presented next, introduces some new syntax. The most significant is probably the `unsafe` keyword, whose significance we'll discuss later in the book. In the meantime, consider `unsafe` to be a warning sign rather than an indicator that you're embarking on anything illegal. `Unsafe` means “the same level of safety offered by C at all times.” There are also some other small additions to the Rust language that you know already:

- Mutable global variables are denoted with `static mut`.
- By convention, global variables use ALL CAPS.
- A `const` keyword is included for values that never change.

Figure 3.3 provides a visual overview of the flow control error and error handling in listing 3.7.




Figure 3.3 A visual overview of listing 3.7, including explanations of problems with using global error codes

**Listing 3.7 Using global variables to propagate error information**

```

1 use rand::random;           ← Brings the rand crate
2
3 static mut ERROR: isize = 0; ← into local scope
4
5 struct File;               ← Creates a zero-sized type to stand in for
6
7 #[allow(unused_variables)]   a struct while we're experimenting
8 fn read(f: &File, save_to: &mut Vec<u8>) -> usize {
9     if random() && random() && random() {           ← Returns true one out
10        unsafe {                                of eight times this
11            ERROR = 1;                         function is called
12        }
13    }
14    0      ← Always reads 0 bytes
15 }
16
17 #[allow(unused_mut)]         ← Keeping buffer mutable for
18 fn main() {                  consistency with other code even
19     let mut f = File;
20     let mut buffer = vec![];
21
22     read(&f, &mut buffer);          ← Accessing static mut variables is
23     unsafe {                      an unsafe operation.
24         if ERROR != 0 {
25             panic!("An error has occurred!")
26         }
27     }
28 }
```

Here are the commands that you will need to use to experiment with the project at listing 3.7:

- 1 git clone --depth=1 https://github.com/rust-in-action/code rust-in-action to download the book's source code
- 2 cd rust-in-action/ch3/globalerror to move into the project directory
- 3 cargo run to execute the code

If you prefer to do things manually, there are more steps to follow:

- 1 cargo new --vcs none globalerror to create a new blank project.
- 2 cd globalerror to move into the project directory.
- 3 cargo add rand@0.8 to add version 0.8 of the rand crate as a dependency (run cargo install cargo-edit if you receive an error message that cargo add command is unavailable).
- 4 As an optional step, you can verify that the rand crate is now a dependency by inspecting Cargo.toml at the root of the project. It will contain the following two lines:

```
[dependencies]
rand = "0.8"
```

- 5 Replace the contents of src/main.rs with the code in listing 3.7 (see ch3/globalerror/src/main.rs).
- 6 Now that your source code is in place, execute cargo run.

You should see output like this:

```
$ cargo run
Compiling globalerror v0.1.0 (file:///path/to/globalerror)
*Finished* dev [unoptimized + debuginfo] target(s) in 0.74 secs
*Running* `target/debug/globalerror`
```

Most of the time, the program will not do anything. Occasionally, if the book has enough readers with sufficient motivation, it will print a much louder message:

```
$ cargo run
thread 'main' panicked at 'An error has occurred!',
<newline> />src/main.rs:27:13
note: run with `RUST_BACKTRACE=1` environment variable to display
      a backtrace
```

Experienced programmers will know that using the global variable `errno` is commonly adjusted by the OS during system calls. This style of programming would typically be discouraged in Rust because it omits both type safety (errors are encoded as plain integers) and can reward sloppy programmers with unstable programs when they forget to check the `errno` value. However, it's an important style to be aware of because

- Systems programmers may need to interact with OS-defined global values.
- Software that interacts with CPU registers and other low-level hardware needs to get used to inspecting flags to check that operations were completed successfully.

### The difference between `const` and `let`

If variables defined with `let` are immutable, then why does Rust include a `const` keyword? The short answer is that data behind `let` can change. Rust allows types to have an apparently contradictory property of *interior mutability*.

Some types such as `std::sync::Arc` and `std::rc::Rc` present an immutable façade, yet change their internal state over time. In the case of those two types, these increment a *reference count* as references to those are made and decrement that count when those references expire.

At the level of the compiler, `let` relates more to aliasing than immutability. *Aliasing* in compiler terminology refers to having multiple references to the same location in memory at the same time. Read-only references (borrows) to variables declared with `let` can alias the same data. Read-write references (mutable borrows) are guaranteed to never alias data.

### 3.4.2 Making use of the Result return type

Rust's approach to error handling is to use a type that stands for both the standard case and the error case. This type is known as `Result`. `Result` has two states, `Ok` and `Err`. This two-headed type is versatile and is put to work all through the standard library.

We'll consider *how* a single type can act as two later on. For the moment, let's investigate the mechanics of working with it. Listing 3.8 makes changes from previous iterations:

- Functions that interact with the file system, such as `open()` on line 39, return `Result<File, String>`. This effectively allows two types to be returned. When the function successfully executes, `File` is returned within a wrapper as `Ok(File)`. When the function encounters an error, it returns a `String` within its own wrapper as `Err(String)`. Using a `String` as an error type provides an easy way to report error messages.
- Calling functions that return `Result<File, String>` requires an extra method (`unwrap()`) to actually extract the value. The `unwrap()` call unwraps `Ok(File)` to produce `File`. It will crash the program if it encounters `Err(String)`. More sophisticated error handling is explained in chapter 4.
- `open()` and `close()` now take full ownership of their `File` arguments. While we'll defer a full explanation of the term ownership until chapter 4, it deserves a short explanation here.

Rust's ownership rules dictate when values are deleted. Passing the `File` argument to `open()` or `close()` without prepending an ampersand, e.g. `&File` or `&mut File`, passes ownership to the function that is being called. This would ordinarily mean that the argument is deleted when the function ends, but these two also return their arguments at the end.

- The `f4` variable now needs to reclaim ownership. Associated with the changes to the `open()` and `close()` functions is a change to the number of times that `let f4` is used. `f4` is now rebound after each call to `open()` and `close()`. Without this, we would run into issues with using data that is no longer valid.

To run the code in listing 3.8, execute these commands from a terminal window:

```
$ git clone --depth=1 https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch3/fileresult
$ cargo run
```

To do things by hand, here are the recommended steps:

- 1 Move to a scratch directory, such as `/tmp`; for example, `cd $TMP` (`cd %TMP%` on MS Windows).
- 2 Execute `cargo new --bin --vcs none fileresult`.
- 3 Ensure that the crate's `Cargo.toml` file specifies the 2018 edition and includes the `rand` crate as a dependency:

```
[package]
name = "fileresult"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
rand = "0.8"
```

- 4 Replace the contents of fileresult/src/main.rs with the code in listing 3.8 (ch3/fileresult/src/main.rs).
- 5 Execute cargo run.

Executing cargo run produces debugging output, but nothing from the executable itself:

```
$ cargo run
Compiling fileresult v0.1.0 (file:///path/to/fileresult)
Finished dev [unoptimized + debuginfo] target(s) in 1.04 secs
Running `target/debug/fileresult`
```

### Listing 3.8 Using Result to mark functions liable to filesystem errors

```
1 use rand::prelude::*;

2
3 fn one_in(denominator: u32) -> bool {
4     thread_rng().gen_ratio(1, denominator)
5 }
6
7 #[derive(Debug)]
8 struct File {
9     name: String,
10    data: Vec<u8>,
11 }
```

**Brings common traits and types from the rand crate into this crate's scope**

```
12
13 impl File {
14     fn new(name: &str) -> File {
15         File {
16             name: String::from(name),
17             data: Vec::new()
18         }
19     }
20
21     fn new_with_data(name: &str, data: &Vec<u8>) -> File {
22         let mut f = File::new(name);
23         f.data = data.clone();
24         f
25     }
26
27     fn read(
28         self: &File,
29         save_to: &mut Vec<u8>,
30     ) -> Result<u32, String> {
```

**Helper function that triggers sporadic errors**

**Stylistic change to shorten the code block**

**First appearance of Result<T, E>, where T is an integer of type usize and E is a String. Using String provides arbitrary error messages.**

```

31     let mut tmp = self.data.clone();
32     let read_length = tmp.len();
33     save_to.reserve(read_length);
34     save_to.append(&mut tmp);
35     Ok(read_length)           ← In this code, read() never fails, but
36   }                         we still wrap read_length in Ok
37 }                           because we're returning Result.
38
39 fn open(f: File) -> Result<File, String> {
40     if one_in(10_000) {        ← Once in 10,000
41         let err_msg = String::from("Permission denied");
42         return Err(err_msg);
43     }
44     Ok(f)
45 }
46
47 fn close(f: File) -> Result<File, String> {
48     if one_in(100_000) {       ← Once in 100,000
49         let err_msg = String::from("Interrupted by signal!");
50         return Err(err_msg);
51     }
52     Ok(f)
53 }
54
55 fn main() {
56     let f4_data: Vec<u8> = vec![114, 117, 115, 116, 33];
57     let mut f4 = File::new_with_data("4.txt", &f4_data);
58
59     let mut buffer: Vec<u8> = vec![];
60
61     f4 = open(f4).unwrap();
62     let f4_length = f4.read(&mut buffer).unwrap();
63     f4 = close(f4).unwrap();    ← Unwraps T from
64
65     let text = String::from_utf8_lossy(&buffer);
66
67     println!("{}:?", f4);
68     println!("{} is {} bytes long", &f4.name, f4_length);
69     println!("{}", text);
70 }

```

**NOTE** Calling `.unwrap()` on a `Result` is often considered poor style. When called on an error type, the program crashes without a helpful error message. As the chapter progresses, we'll encounter sophisticated mechanisms to handle errors.

Using `Result` provides compiler-assisted code correctness: your code won't compile unless you've taken the time to handle the edge cases. This program will fail on error, but at least we have made this explicit.

So, what is a `Result`? `Result` is an enum defined in Rust's standard library. It has the same status as any other type but is tied together with the rest of the language through strong community conventions. You may be wondering, "Wait. What is an enum?" I'm glad you asked. That's the topic of our next section.

## 3.5 Defining and making use of an enum

An *enum*, or enumeration, is a type that can represent multiple known variants. Classically, an enum represents several predefined known options like the suits of playing cards or planets in the solar system. The following listing shows one such enum.

**Listing 3.9 Defining an enum to represent the suits in a deck of cards**

```
enum Suit {
    Clubs,
    Spades,
    Diamonds,
    Hearts,
}
```

If you haven't programmed in a language that makes use of enums, understanding their value takes some effort. As you program with these for a while, though, you're likely to experience a minor epiphany.

Consider creating some code that parses event logs. Each event has a name, perhaps UPDATE or DELETE. Rather than storing those values as strings in your application, which can lead to subtle bugs later on when string comparisons become unwieldy, enums allow you to give the compiler some knowledge of the event codes. Later, you'll be given a warning such as "Hi there, I see that you have considered the UPDATE case, but it looks like you've forgotten the DELETE case. You should fix that."

Listing 3.10 shows the beginnings of an application that parses text and emits structured data. When run, the program produces the following output. You'll find the code for this listing in ch3/ch3-parse-log.rs:

```
(Unknown, "BEGIN Transaction XK342")
(Update, "234:LS/32231 {\\"price\\": 31.00} -> {\\"price\\": 40.00}")
(Delete, "342:LO/22111")
```

**Listing 3.10 Defining an enum and using it to parse an event log**

**Vec<\_>**  
asks Rust  
to infer the  
elements'  
type.

```
1 #[derive(Debug)]           ← Prints this enum to the screen
2 enum Event {               ← via auto-generated code
3     Update,               ← Creates three variants of
4     Delete,               ← Event, including a value
5     Unknown,              ← for unrecognized events
6 }
7
8 type Message = String;   ← A convenient name for String
                           ← for use in this crate's context
9
10 fn parse_log(line: &str) -> (Event, Message) {          ← A function for
11     let parts: Vec<_> = line                            ← parsing a line and
12         .splitn(2, ' ')                                     ← converting it into
13         .collect();                                      ← semi-structured
14     if parts.len() == 1 {                                ← data
15         return (Event::Unknown, String::from(line))       ← collect() consumes an iterator from
16     }                                               ← line.splitn() and returns Vec<T>.
17 }
```

If line.splitn() doesn't split log into two parts, returns an error

```

17
18 let event = parts[0];
19 let rest = String::from(parts[1]); | Assigns each part of parts to a
20
21 match event { | variable to ease future use
22     "UPDATE" | "update" => (Event::Update, rest),
23     "DELETE" | "delete" => (Event::Delete, rest),
24     _ => (Event::Unknown, String::from(line)), | When we match a known event,
25 } | returns structured data
26 } | If we don't recognize
27
28 fn main() {
29     let log = "BEGIN Transaction XK342
30 UPDATE 234:LS/32231 {"price": 31.00} -> {"price": 40.00}
31 DELETE 342:LO/22111";
32
33     for line in log.lines() {
34         let parse_result = parse_log(line);
35         println!("{}: {}", parse_result);
36     }
37 }
```

Enums have a few tricks up their sleeves:

- These work together with Rust’s pattern-matching capabilities to help you build robust, readable code (visible on lines 19–3 of listing 3.10).
- Like structs, enums support methods via `impl` blocks.
- Rust’s enums are more powerful than a set of constants.

It’s possible to include data within an enum’s variants, granting them a struct-like persona. For example

```

enum Suit {
    Clubs,
    Spades,
    Diamonds,
    Hearts, | The last element of enums
} | also ends with a comma to
| ease refactoring.

enum Card {
    King(Suit),
    Queen(Suit),
    Jack(Suit),
    Ace(Suit),
    Pip(Suit, usize), | Face cards
} | have a suit.

| Pip cards have a
| suit and a rank.
```

### 3.5.1 Using an enum to manage internal state

Now that you’ve seen how to define and use an enum, how is this useful when applied to modelling files? We can expand our `File` type and allow it to change as it is opened and closed. Listing 3.11 (`ch3/ch3-file-states.rs`) produces code that prints a short alert to the console:

```
Error checking is working
File { name: "5.txt", data: [], state: Closed }
5.txt is 0 bytes long
```

**Listing 3.11 An enum that represents a File being open or closed**

```
1 #[derive(Debug, PartialEq)]
2 enum FileState {
3     Open,
4     Closed,
5 }
6
7 #[derive(Debug)]
8 struct File {
9     name: String,
10    data: Vec<u8>,
11    state: FileState,
12 }
13
14 impl File {
15     fn new(name: &str) -> File {
16         File {
17             name: String::from(name),
18             data: Vec::new(),
19             state: FileState::Closed,
20         }
21     }
22
23     fn read(
24         self: &File,
25         save_to: &mut Vec<u8>,
26     ) -> Result<u8, String> {
27         if self.state != FileState::Open {
28             return Err(String::from("File must be open for reading"));
29         }
30         let mut tmp = self.data.clone();
31         let read_length = tmp.len();
32         save_to.reserve(read_length);
33         save_to.append(&mut tmp);
34         Ok(read_length)
35     }
36 }
37
38 fn open(mut f: File) -> Result<File, String> {
39     f.state = FileState::Open;
40     Ok(f)
41 }
42
43 fn close(mut f: File) -> Result<File, String> {
44     f.state = FileState::Closed;
45     Ok(f)
46 }
47
48 fn main() {
49     let mut f5 = File::new("5.txt");
```

```

50
51 let mut buffer: Vec<u8> = vec![] ;
52
53 if f5.read(&mut buffer).is_err() {
54     println!("Error checking is working");
55 }
56
57 f5 = open(f5).unwrap();
58 let f5_length = f5.read(&mut buffer).unwrap();
59 f5 = close(f5).unwrap();
60
61 let text = String::from_utf8_lossy(&buffer);
62
63 println!("{}:?}", f5);
64 println!("{} is {} bytes long", &f5.name, f5_length);
65 println!("{}: {}", f5, text);
66 }
```

Enums can be a powerful aide in your quest to produce reliable, robust software. Consider them for your code when you discover yourself introducing “stringly-typed” data, such as message codes.

## 3.6 Defining common behavior with traits

A robust definition of the term *file* needs to be agnostic to storage medium. Files support two main operations: reading and writing streams of bytes. Focusing on those two capabilities allows us to ignore where the reads and writes are actually taking place. These actions can be from a hard disk drive, an in-memory cache, over a network, or via something more exotic.

Irrespective of whether a file is a network connection, a spinning metal platter, or a superposition of an electron, it’s possible to define rules that say, “To call yourself a file, you must implement this.”

You have already seen traits in action several times. Traits have close relatives in other languages. These are often named interfaces, protocols, type classes, abstract base classes, or, perhaps, contracts.

Every time you’ve used `#[derive(Debug)]` in a type definition, you’ve implemented the `Debug` trait for that type. Traits permeate the Rust language. Let’s see how to create one.

### 3.6.1 Creating a Read trait

Traits enable the compiler (and other humans) to know that multiple types are attempting to perform the same task. Types that use `#[derive(Debug)]` all print to the console via the `println!` macro and its relatives. Allowing multiple types to implement a `Read` trait enables code reuse and allows the Rust compiler to perform its *zero cost abstraction* wizardry.

For the sake of brevity, listing 3.12 (`ch3/ch3-skeleton-read-trait.rs`) is a bare-bones version of the code that we’ve already seen. It shows the distinction between the `trait` keyword, which is used for definitions, and the `impl` keyword, which attaches a trait to

a specific type. When built with rustc and executed, listing 3.12 prints the following line to the console:

```
0 byte(s) read from File
```

### Listing 3.12 Defining the bare bones of a Read trait for File

```

1 #![allow(unused_variables)]           ← Silences any warnings relating to
2 #[derive(Debug)]                   unused variables within functions
3 struct File;                      ← Defines a stub File type
4
5 trait Read {                      ← Provides a specific
6     fn read(                     name for the trait
7         self: &Self,             ←
8         save_to: &mut Vec<u8>, ← A trait block includes the type
9         ) -> Result<usize, String>; ← signatures of functions that
10    }                           implementors must comply with. The
11
12 impl Read for File {            ←
13     fn read(self: &File, save_to: &mut Vec<u8>) -> Result<usize, String> {
14         Ok(0)                ←
15     }
16 }
17 }
18
19 fn main() {
20     let f = File{};
21     let mut buffer = vec!();
22     let n_bytes = f.read(&mut buffer).unwrap();
23     println!("{} byte(s) read from {:?}", n_bytes, f);
24 }
```

A simple stub value that complies with the type signature required

Defining a trait and implementing it on the same page can feel quite drawn out in small examples such as this. `File` is spread across three code blocks within listing 3.12. The flip side of this is that many common traits become second nature as your experience grows. Once you've learned what the `PartialEq` trait does for one type, you'll understand it for every other type.

What does `PartialEq` do for types? It enables comparisons with the `==` operator. "Partial" allows for cases where two values that match exactly should not be treated as equal, such as the floating point's `NAN` value or SQL's `NULL`.

**NOTE** If you've spent some time looking through the Rust community's forums and documentation, you might have noticed that they've formed their own idioms of English grammar. When you see a sentence with the following structure, "...`T` is `Debug`...", what they're saying is that `T` implements the `Debug` trait.

## 3.6.2 Implementing `std::fmt::Display` for your own types

The `println!` macro and a number of others live within a family of macros that all use the same underlying machinery. The macros `println!`, `print!`, `write!`, `writeln!`, and `format!` all rely on the `Display` and `Debug` traits, and these rely on trait implementations provided by programmers to convert from `{}` to what is printed to the console.

Looking back a few pages to listing 3.11, the `File` type was composed of a few fields and a custom subtype, `FileState`. If you recall, that listing illustrated the use of the `Debug` trait as repeated in the following listing.

### Listing 3.13 Snippets from listing 3.11

```
# [derive(Debug, PartialEq)]
enum FileState {
    Open,
    Closed,
}

#[derive(Debug)]
struct File {
    name: String,
    data: Vec<u8>,
    state: FileState,
}

// ...

fn main() {
    let f5 = File::new("f5.txt");
    //...
    println!("{}: {:?}", f5);
    // ...
}
```

Lines skipped from the original

Debug relies on the colon and question mark syntax.

It's possible to rely on the `Debug` trait auto-implementations as a crutch, but what should you do if you want to provide custom text? `Display` requires that types implement a `fmt` method, which returns `fmt::Result`. The following listing shows this implementation.

### Listing 3.14 Using `std::fmt::Display` for `File` and its associated `FileState`

```
impl Display for FileState {
    fn fmt(&self, f:
           &mut fmt::Formatter,
           ) -> fmt::Result { ←
        match *self {
            FileState::Open => write!(f, "OPEN"),
            FileState::Closed => write!(f, "CLOSED"),
        }
    }
}

impl Display for File {
    fn fmt(&self, f:
           &mut fmt::Formatter,
           ) -> fmt::Result { ←
        write!(f, "<{}> ({})", self.name, self.data),
    }
}
```

To implement `std::fmt::Display`, a single `fmt` method must be defined for your type.

```

        self.name, self.state)
    }
}

```

It is common to defer to the inner types' `Display` implementation via the `write!` macro.

The following listing shows how to implement `Display` for a struct that includes fields that also need to implement `Display`. You'll find the code for this listing in `ch3/ch3-implementing-display.rs`.

### Listing 3.15 Working code snippet to implement `Display`

```

1 #![allow(dead_code)]
2
3 use std::fmt;
4 use std::fmt::{Display};
5 #[derive(Debug, PartialEq)]
6 enum FileState {
7     Open,
8     Closed,
9 }
10
11
12 #[derive(Debug)]
13 struct File {
14     name: String,
15     data: Vec<u8>,
16     state: FileState,
17 }
18
19 impl Display for FileState {
20     fn fmt(&self, f: &mut fmt::Formatter) -> fmt::Result {
21         match *self {
22             FileState::Open => write!(f, "OPEN"),
23             FileState::Closed => write!(f, "CLOSED"),
24         }
25     }
26 }
27
28 impl Display for File {
29     fn fmt(&self, f: &mut fmt::Formatter) -> fmt::Result {
30         write!(f, "{} ({})", self.name, self.state)
31     }
32 }
33
34 impl File {
35     fn new(name: &str) -> File {
36         File {
37             name: String::from(name),
38             data: Vec::new(),
39             state: FileState::Closed,
40         }
41     }
42 }
43 }

```

Silences warnings related to `FileState::Open` not being used

Brings the `std::fmt` crate into local scope, making use of `fmt::Result`

Brings `Display` into local scope, avoiding the need to prefix it as `fmt::Display`

Sneakily, we can make use of `write!` to do the grunt work for us. Strings already implement `Display`, so there's little left for us to do.

We can rely on this `FileState` `Display` implementation.

```

44
45 fn main() {
46     let f6 = File::new("f6.txt");
47     //...
48     println!("{}: {}", f6);    ←
49     println!("{}: {}", f6);    ←
50 }

```

The Debug implementation prints a familiar message in common with all other implementors of Debug: File { ... }.

Our Display implementation follows its own rules, displaying itself as <f6.txt (CLOSED)>.

We'll see many uses of traits throughout the course of the book. These underlie Rust's generics system and the language's robust type checking. With a little bit of abuse, these also support a form of inheritance that's common in most object oriented languages. For now, though, the thing to remember is that traits represent common behavior that types opt into via the syntax `impl Trait` for Type.

## 3.7 Exposing your types to the world

Your crates will interact with others that you build over time. You might want to make that process easier for your future self by hiding internal details and documenting what's public. This section describes some of the tooling available within the language and within cargo to make that process easier.

### 3.7.1 Protecting private data

Rust defaults to keeping things private. If you were to create a library with only the code that you have seen so far, importing your crate would provide no extra benefit. To remedy this, use the `pub` keyword to make things public.

Listing 3.16 provides a few examples of prefixing types and methods with `pub`. As you'll note, its output is not very exciting:

```
File { name: "f7.txt", data: [], state: Closed }
```

**Listing 3.16 Using pub to mark the name and state fields of File public**

```

1 #[derive(Debug,PartialEq)]
2 pub enum FileState {    ←
3     Open,
4     Closed,
5 }
6
7 #[derive(Debug)]
8 pub struct File {    ←
9     pub name: String,
10    data: Vec,
11    pub state: FileState,
12 }
13
14 impl File {
15     pub fn new(name: &str) -> File {    ←
16         File {
17             name: String::from(name),

```

An enum's variants are assumed to be public if the overall type is made public.

File.data remains private if a third party were to import this crate via use.

Even though the File struct is public, its methods must also be explicitly marked as public.

```

18         data: Vec::new(),
19         state: FileState::Closed
20     }
21 }
22
23
24 fn main() {
25     let f7 = File::new("f7.txt");
26     //...
27     println!("{}:{}", f7);
28 }
```

### 3.8 Creating inline documentation for your projects

When software systems become larger, it becomes more important to document one's progress. This section walks through adding documentation to your code and generating HTML versions of that content.

In listing 3.17, you'll see the familiar code with some added lines beginning with `///` or `//!`. The first form is much more common. It generates documents that refer to the item that immediately follows. The second form refers to the current item as the compiler scans the code. By convention, it is only used to annotate the current module but is available in other places as well. The code for this listing is in the file ch3-file-doced.rs.

**Listing 3.17 Adding doc comments to code**

```

1 //! Simulating files one step at a time.           ←
2
3 /// Represents a "file",
4 /// which probably lives on a file system.        ←
5 #[derive(Debug)]
6 pub struct File {
7     name: String,
8     data: Vec<u8>,
9 }
10
11 impl File {
12     /// New files are assumed to be empty, but a name is required.
13     pub fn new(name: &str) -> File {
14         File {
15             name: String::from(name),
16             data: Vec::new(),
17         }
18     }
19
20     /// Returns the file's length in bytes.
21     pub fn len(&self) -> usize {
22         self.data.len()
23     }
24
25     /// Returns the file's name.
26     pub fn name(&self) -> String {
```

//! refers to the current item, the module that's just been entered by the compiler.

/// annotates whatever immediately follows it.

```

27     self.name.clone()
28 }
29 }
30
31 fn main() {
32     let f1 = File::new("f1.txt");
33
34     let f1_name = f1.name();
35     let f1_length = f1.len();
36
37     println!("{}:{}\n", f1);
38     println!("{} is {} bytes long", f1_name, f1_length);
39 }
```

### 3.8.1 Using rustdoc to render docs for a single source file

You may not know it, but you also installed a command-line tool called `rustdoc` when you installed Rust. `rustdoc` is like a special-purpose Rust compiler. Instead of producing executable code, it produces HTML versions of your inline documentation.

Here is how to use it. Assuming that you have the code from listing 3.17 saved as `ch3-file-doced.rs`, follow these steps:

- 1 Open a terminal.
- 2 Move to the location of your source file.
- 3 Execute `rustdoc ch3-file-doced.rs`.

`rustdoc` creates a directory (`doc/`) for you. The documentation's entry point is actually within a subdirectory: `doc/ch3_file_doced/index.html`.


When your programs start to get larger and span multiple files, invoking `rustdoc` manually can become a bit of a pain. Thankfully, `cargo` can do the grunt work on your behalf. That's discussed in the next section.

### 3.8.2 Using cargo to render docs for a crate and its dependencies

Your documentation can be rendered as rich HTML output with `cargo`. `cargo` works with crates rather than the individual files as we've worked with so far. To get around this, we'll move our project into a crate documentation: To manually create the crate, following these instructions:

- 1 Open a terminal.
- 2 Move to a working directory, such as `/tmp/`, or for Windows, type `cd %TEMP%`.
- 3 Run `cargo new filebasics`.

You should end up with a project directory tree that looks like this:



- 4 Now save the source code from listing 3.17 to `filebasics/src/main.rs`, overwriting the "Hello World!" boilerplate code that is already in the file.

To skip a few steps, clone the repository. Execute these commands from a terminal:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch3/filebasics
```

To build an HTML version of the crate's documentation, follow these steps:

- 1 Move to the project's root directory (`filebasics/`), which includes the `Cargo.toml` file.
- 2 Run `cargo doc --open`.

Rust will now start to compile an HTML version of your code's documentation. You should see output similar to the following in the console:

```
Documenting filebasics v0.1.0 (file:///C:/.../Temp/filebasics)
  Finished dev [unoptimized + debuginfo] target(s) in 1.68 secs
    Opening C:\...\Temp\files\target\doc\filebasics\index.html
  Launching cmd /C
```

If you added the `--open` flag, your web browser will automatically. Figure 3.4 shows the documentation that should now be visible.




Figure 3.4 Rendered output of `cargo doc`

**TIP** If you have lots of dependencies in your crate, the build process may take a while. A useful flag is `cargo doc --no-deps`. Adding `--no-deps` can significantly restrict the work `rustdoc` has to do.

`rustdoc` supports rendering rich text written in Markdown. That allows you to add headings, lists, and links within your documentation. Code snippets that are wrapped in triple backticks (``` ) are given syntax highlighting.

#### Listing 3.18 Documenting Rust code with in-line comments

```

1 //! Simulating files one step at a time.
2
3
4 impl File {
5     /// Creates a new, empty `File`.
6     ///
7     /// # Examples
8     ///
9     /// ```
10    /// let f = File::new("f1.txt");
11    /// ```
12    pub fn new(name: &str) -> File {
13        File {
14            name: String::from(name),
15            data: Vec::new(),
16        }
17    }
18 }
```

## Summary

- A struct is the foundational compound data type. Paired with traits, structs are the closest thing to objects from other domains.
- An enum is more powerful than a simple list. Enum's strength lies in its ability to work with the compiler to consider all edge cases.
- Methods are added to types via `impl` blocks.
- You can use global error codes in Rust, but this can be cumbersome and generally is frowned on.
- The `Result` type is the mechanism the Rust community prefers to use to signal the possibility of error.
- Traits enable common behavior through Rust programs.
- Data and methods remain private until they are declared public with `pub`.
- You can use `cargo` to build the documentation for your crate and all of its dependencies.

# Lifetimes, ownership, and borrowing

---

## This chapter covers

- Discovering what the term *lifetime* means in Rust programming
- Working with the borrow checker rather than against it
- Multiple tactics for dealing with issues when these crop up
- Understanding the responsibilities of an owner
- Learning how to borrow values that are owned elsewhere

This chapter explains one of the concepts that trip up most newcomers to Rust—its borrow checker. The *borrow checker* checks that all access to data is legal, which allows Rust to prevent safety issues. Learning how this works will, at the very least, speed up your development time by helping you avoid run-ins with the compiler. More significantly though, learning to work with the borrow checker allows you to build larger software systems with confidence. It underpins the term *fearless concurrency*.

This chapter will explain how this system operates and help you learn how to comply with it when an error is discovered. It uses the somewhat lofty example of

simulating a satellite constellation to explain the trade-offs relating to different ways to provide shared access to data. The details of borrow checking are thoroughly explored within the chapter. However, a few points might be useful for readers wanting to quickly get the gist. Borrow checking relies on three interrelated concepts—lifetimes, ownership, and borrowing:

- *Ownership is a stretched metaphor.* There is no relationship to property rights. Within Rust, ownership relates to cleaning values when these are no longer needed. For example, when a function returns, the memory holding its local variables needs to be freed. Owners cannot prevent other parts of the program from accessing their values or report data theft to some overarching Rust authority.
- *A value's lifetime is the period when accessing that value is valid behavior.* A function's local variables live until the function returns, while global variables might live for the life of the program.
- *To borrow a value means to access it.* This terminology is somewhat confusing as there is no obligation to return the value to its owner. Its meaning is used to emphasize that while values can have a single owner, it's possible for many parts of the program to share access to those values.

## 4.1 **Implementing a mock CubeSat ground station**

Our strategy for this chapter is to use an example that compiles. Then we'll make a minor change that triggers an error that appears to emerge without any adjustment to the program's flow. Working through the fixes to those issues should make the concepts more complete.

The learning example for the chapter is a CubeSat constellation. If you've never encountered that phrase before, here are some definitions:

- *CubeSat*—A miniature artificial satellite, as compared to a conventional satellite, that has increasingly expanded the accessibility of space research.
- *Ground station*—An intermediary between the operators and the satellites themselves. It listens on a radio, checking the status of every satellite in the constellation and transmitting messages to and fro. When introduced in our code, it acts as the gateway between the user and the satellites.
- *Constellation*—The collective noun for satellites in orbit.

Figure 4.1 shows several CubeSats orbiting our ground station.




Figure 4.1 CubeSats in orbit

In figure 4.1, we have three CubeSats. To model this, we'll create a variable for each. This model can happily implement integers for the moment. We don't need to model the ground station explicitly because we're not yet sending messages around the constellations. We'll omit that model for now. These are the variables:

```
let sat_a = 0;
let sat_b = 1;
let sat_c = 2;
```

To check on the status of each of our satellites, we'll use a stub function and an enum to represent potential status messages:

```
# [derive(Debug)]
enum StatusMessage {
    Ok,
}

fn check_status(sat_id: u64) -> StatusMessage {
    StatusMessage::Ok
}
```

For now, all of  
our CubeSats  
function  
perfectly all  
the time.

The `check_status()` function would be extremely complicated in a production system. For our purposes, though, returning the same value every time is perfectly sufficient. Pulling these two snippets into a whole program that “checks” our satellites twice, we end up with something like the following listing. You'll find this code in the file `ch4/ch4-check-sats-1.rs`.

#### Listing 4.1 Checking the status of our integer-based CubeSats

```
1 #![allow(unused_variables)]
2
3 # [derive(Debug)]
4 enum StatusMessage {
5     Ok,
6 }
7
8 fn check_status(sat_id: u64) -> StatusMessage {
9     StatusMessage::Ok
10 }
11
12 fn main () {
13     let sat_a = 0;           | Each satellite variable
14     let sat_b = 1;           | is represented by an
15     let sat_c = 2;           | integer.
16
17     let a_status = check_status(sat_a);
18     let b_status = check_status(sat_b);
19     let c_status = check_status(sat_c);
20     println!("a: {:+?}, b: {:+?}, c: {:+?}", a_status, b_status, c_status);
21
22     // "waiting" ...
23     let a_status = check_status(sat_a);
```

```

24 let b_status = check_status(sat_b);
25 let c_status = check_status(sat_c);
26 println!("a: {:+?}, b: {:+?}, c: {:+?}", a_status, b_status, c_status);
27 }
```

Running the code in listing 4.1 should be fairly uneventful. The code compiles, albeit begrudgingly. We encounter the following output from our program:

```
a: Ok, b: Ok, c: Ok
a: Ok, b: Ok, c: Ok
```

### 4.1.1 **Encountering our first lifetime issue**

Let's move closer to idiomatic Rust by introducing *type safety*. Instead of integers, let's create a type to model our satellites. A real implementation of a CubeSat type would probably include lots of information about its position, its RF frequency band, and more. In the following listing, we stick with only recording an identifier.

#### **Listing 4.2 Modeling a CubeSat as its own type**

```

#[derive(Debug)]
struct CubeSat {
    id: u64,
}
```

Now that we have a struct definition, let's inject it into our code. The next listing will not compile (yet). Understanding the details of why it won't is the goal of much of this chapter. The source for this listing is in ch4/ch4-check-sats-2.rs.

#### **Listing 4.3 Checking the status of our integer-based CubeSats**

```

1 #[derive(Debug)]           ↪ Modification 1
2 struct CubeSat {          | adds the
3     id: u64,               | definition.
4 }
5
6 #[derive(Debug)]
7 enum StatusMessage {
8     Ok,
9 }
10
11 fn check_status(         ↪ Modification 2 uses
12     sat_id: CubeSat      | the new type within
13 ) -> StatusMessage {    | check_status().
14     StatusMessage::Ok
15 }
16
17 fn main() {               ↪ Modification 3
18     let sat_a = CubeSat { id: 0 };    | creates three
19     let sat_b = CubeSat { id: 1 };    | new instances.
20     let sat_c = CubeSat { id: 2 };    |
21 }
```

```

22 let a_status = check_status(sat_a);
23 let b_status = check_status(sat_b);
24 let c_status = check_status(sat_c);
25 println!("a: {:+?}, b: {:+?}, c: {:+?}", a_status, b_status, c_status);
26
27 // "waiting" ...
28 let a_status = check_status(sat_a);
29 let b_status = check_status(sat_b);
30 let c_status = check_status(sat_c);
31 println!("a: {:+?}, b: {:+?}, c: {:+?}", a_status, b_status, c_status);
32 }
```

When you attempt to compile the code for listing 4.3, you will receive a message similar to the following (which has been edited for brevity):

```

error[E0382]: use of moved value: `sat_a`
--> code/ch4-check-sats-2.rs:26:31
|
20 |     let a_status = check_status(sat_a);
|                         ----- value moved here
...
26 |     let a_status = check_status(sat_a);
|                         ^^^^^^ value used here after move
|
|= note: move occurs because `sat_a` has type `CubeSat`,
|= which does not implement the `Copy` trait

...      ← Lines removed
for brevity

error: aborting due to 3 previous errors
```

To trained eyes, the compiler’s message is helpful. It tells us exactly where the problem is and provides us with a recommendation on how to fix it. To less experienced eyes, it’s significantly less useful. We are using a “moved” value and are fully advised to implement the `Copy` trait on `CubeSat`. Huh? It turns out that although it is written in English, the term *move* means something very specific within Rust. Nothing physically moves.

Movement within Rust code refers to movement of ownership, rather than the movement of data. *Ownership* is a term used within the Rust community to refer to the compile-time process that checks that every use of a value is valid and that every value is destroyed cleanly.

Every value in Rust is *owned*. In both listings 4.1 and 4.3, `sat_a`, `sat_b`, and `sat_c` own the data that these refer to. When calls to `check_status()` are made, ownership of the data moves from the variables in the scope of `main()` to the variable `sat_id` within the `check_status()` function. The significant difference is that listing 4.3 places that integer within a `CubeSat` struct.<sup>1</sup> This type change alters the semantics of how the program behaves.

---

<sup>1</sup> Remember the phrase *zero-cost abstractions*? One of the ways this manifests is by not adding extra data around values within structs.

The next listing provides a stripped-down version of the `main()` function from listing 4.3. It is centered on `sat_a` and attempts to show how ownership moves from `main()` into `check_status()`.

#### **Listing 4.4 Extract of listing 4.3, focusing on `main()`**

```
fn main() {
    let sat_a = CubeSat { id: 0 };
    // ...
    let a_status = check_status(sat_a);
    // ...
    // "waiting" ...
    let a_status = check_status(sat_a);
    // ...
}
```

#### **Rebinding is legal when values are not borrowed**

If you have experience with programming languages such as JavaScript (from 2015 onward), you may have been surprised to see that the variables for each of the CubeSats were redefined in listing 4.3. In that listing on line 20, `a_status` is assigned to the result of the first call to `check_status(sat_a)`. On line 26, it is reassigned to the result of the second call. The original value is overwritten.

This is legal Rust code, but one must be aware of ownership issues and lifetime here too. It's possible in this context because there are no live borrows to contend with. Attempting to overwrite a value that's still available from elsewhere in the program causes the compiler to refuse to compile your program.

Figure 4.2 provides a visual walk-through of the interrelated processes of control flow, ownership, and lifetimes. During the call to `check_status(sat_a)`, ownership moves to the `check_status()` function. When `check_status()` returns a `StatusMessage`, it drops the `sat_a` value. The lifetime of `sat_a` ends here. Yet, `sat_a` remains in the local scope of `main()` after the first call to `check_status()`. Attempting to access that variable will incur the wrath of the borrow checker.

The distinction between a value's lifetime and its scope—which is what many programmers are trained to rely on—can make things difficult to disentangle. Avoiding and overcoming this type of issue makes up the bulk of this chapter. Figure 4.2 helps to shed some light on this.

#### **4.1.2 Special behavior of primitive types**

Before carrying on, it might be wise to explain why listing 4.1 compiled at all. Indeed, the only change that we made in listing 4.3 was to wrap our satellite variables in a custom type. As it happens, primitive types in Rust have special behavior. These implement the `Copy` trait.

## Program flow of listing 4.4




Figure 4.2 Visual explanation of Rust's ownership movement

Types implementing `Copy` are duplicated at times that would otherwise be illegal. This provides some day-to-day convenience at the expense of adding a trap for newcomers. As you grow out from toy programs using integers, your code suddenly breaks.

Formally, primitive types are said to possess *copy semantics*, whereas all other types have *move semantics*. Unfortunately, for learners of Rust, that special case looks like the default case because beginners typically encounter primitive types first. Listings 4.5 and 4.6 illustrate the difference between these two concepts. The first compiles and runs; the other does not. The only difference is that these listings use different types. The following listing shows not only the primitive types but also the types that implement `Copy`.

## Listing 4.5 The copy semantics of Rust's primitive types

```

1 fn use_value(_val: i32) { ←
2 }
3
4 fn main() {
5   let a = 123 ;
6   use_value(a) ;
7 }
  
```

use\_value() takes ownership of the \_val argument. The use\_value() function is generic as it's used in the next example.

```

8   println!("{}", a);      ← It's perfectly legal to access a
9
10 }                         after use_value() has returned.

```

The following listing focuses on those types that do not implement the `Copy` trait. When used as an argument to a function that takes ownership, values cannot be accessed again from the outer scope.

#### Listing 4.6 The move semantics of types not implementing Copy

```

1 fn use_value(_val: Demo) {      ← use_value() takes
2 }                                ownership of _val.
3
4 struct Demo {
5     a: i32,
6 }
7
8 fn main() {
9     let demo = Demo { a: 123 };
10    use_value(demo);
11
12    println!("{}", demo.a);      ← It's illegal to access
13 }                                demo.a, even after
                                         use_value() has returned.

```

## 4.2 Guide to the figures in this chapter

The figures used in this chapter use a bespoke notation to illustrate the three interrelated concepts of scope, lifetimes, and ownership. Figure 4.3 illustrates this notation.

### Symbols

	<code>sat_a</code>		<code>base</code>
	<code>sat_b</code>		<code>StatusMessage::Ok</code>
	<code>sat_c</code>		<code>Console</code>

### Actions

Create value		Symbol appears
Delete value		Symbol struck through
Function call		Arguments
		Function name
		Return values




Figure 4.3 How to interpret the figures in this chapter

## 4.3 What is an owner? Does it have any responsibilities?

In the world of Rust, the notion of *ownership* is rather limited. An owner cleans up when its values' lifetimes end.

When values go out of scope or their lifetimes end for some other reason, their destructors are called. A *destructor* is a function that removes traces of the value from the program by deleting references and freeing memory. You won't find a call to any destructors in most Rust code. The compiler injects that code itself as part of the process of tracking every value's lifetime.

To provide a custom destructor for a type, we implement `Drop`. This typically is needed in cases where we have used unsafe blocks to allocate memory. `Drop` has one method, `drop(&mut self)`, that you can use to conduct any necessary wind-up activities.

An implication of this system is that values cannot outlive their owner. This kind of situation can make data structures built with references, such as trees and graphs, feel slightly bureaucratic. If the root node of a tree is the owner of the whole tree, it can't be removed without taking ownership into account.

Finally, unlike the Lockean notion of personal property, ownership does not imply control or sovereignty. In fact, the "owners" of values do not have special access to their owned data. Nor do these have the ability to restrict others from trespassing. Owners don't get a say on other sections of code borrowing their values.

## 4.4 How ownership moves

There are two ways to shift ownership from one variable to another within a Rust program. The first is by assignment.<sup>2</sup> The second is by passing data through a function barrier, either as an argument or a return value. Revisiting our original code from listing 4.3, we can see that `sat_a` starts its life with ownership over a `CubeSat` object:

```
fn main() {
    let sat_a = CubeSat { id: 0 };
    // ...
```

The `CubeSat` object is then passed into `check_status()` as an argument. This moves ownership to the local variable `sat_id`:

```
fn main() {
    let sat_a = CubeSat { id: 0 };
    // ...
    let a_status = check_status(sat_a);
    // ...
```

Another possibility is that `sat_a` relinquishes its ownership to another variable within `main()`. That would look something like this:

---

<sup>2</sup> Within the Rust community, the term *variable binding* is preferred because it is more technically correct.

```
fn main() {
    let sat_a = CubeSat { id: 0 };
    // ...
    let new_sat_a = sat_a;
    // ...
```

Lastly, if there is a change in the `check_status()` function signature, it too could pass ownership of the `CubeSat` to a variable within the calling scope. Here is our original function:

```
fn check_status(sat_id: CubeSat) -> StatusMessage {
    StatusMessage::Ok
}
```

And here is an adjusted function that achieves its message notification through a side effect:

```
fn check_status(sat_id: CubeSat) -> CubeSat {
    println!("{}: {}", sat_id, StatusMessage::Ok);
    sat_id
}
```

Uses the Debug formatting syntax  
as our types have been annotated  
with #[derive(Debug)]

Returns a value by omitting the  
semicolon at the end of the last line

With the adjusted `check_status()` function used in conjunction with a new `main()`, it's possible to send ownership of the `CubeSat` objects back to their original variables. The following listing shows the code. Its source is found in `ch4/ch4-check-sats-3.rs`.

#### **Listing 4.7 Returning ownership back to the original scope**

```
1 #![allow(unused_variables)]
2
3 #[derive(Debug)]
4 struct CubeSat {
5     id: u64,
6 }
7
8 #[derive(Debug)]
9 enum StatusMessage {
10     Ok,
11 }
12
13 fn check_status(sat_id: CubeSat) -> CubeSat {
14     println!("{}: {}", sat_id, StatusMessage::Ok);
15     sat_id
16 }
17
18 fn main () {
19     let sat_a = CubeSat { id: 0 };
20     let sat_b = CubeSat { id: 1 };
21     let sat_c = CubeSat { id: 2 };
```

```

22
23   let sat_a = check_status(sat_a);
24   let sat_b = check_status(sat_b);
25   let sat_c = check_status(sat_c);
26
27   // "waiting" ...
28
29   let sat_a = check_status(sat_a);
30   let sat_b = check_status(sat_b);
31   let sat_c = check_status(sat_c);
32 }
```

Now that the return value of `check_status()` is the original `sat_a`, the new `let` binding is reset.

The output from the new `main()` function in listing 4.7 now looks like this:

```

CubeSat { id: 0 }: Ok
CubeSat { id: 1 }: Ok
CubeSat { id: 2 }: Ok
CubeSat { id: 0 }: Ok
CubeSat { id: 1 }: Ok
CubeSat { id: 2 }: Ok
```

Figure 4.4 shows a visual overview of the ownership movements within listing 4.7.




Figure 4.4 The ownership changes within listing 4.7


## 4.5 Resolving ownership issues

Rust's ownership system is excellent. It provides a route to memory safety without needing a garbage collector. There is a “but,” however.

The ownership system can trip you up if you don't understand what's happening. This is particularly the case when you bring the programming style from your past experience to a new paradigm. Four general strategies can help with ownership issues:

- Use references where full ownership is not required.
- Duplicate the value.
- Refactor code to reduce the number of long-lived objects.
- Wrap your data in a type designed to assist with movement issues.

To examine each of these strategies, let's extend the capabilities of our satellite network. Let's give the ground station and our satellites the ability to send and receive messages. Figure 4.5 shows what we want to achieve: create a message at Step 1, then transfer it at Step 2. After Step 2, no ownership issues should arise.



**Figure 4.5 Goal: Enable messages to be sent while avoiding ownership issues**

Ignoring the details of implementing the methods, we want to avoid code that looks like the following. Moving ownership of `sat_a` to a local variable in `base.send()` ends up hurting us. That value will no longer be accessible for the rest of `main()`:

```
base.send(sat_a, "hello!");      ← Moves ownership of sat_a to a
sat_a.recv();                   local variable in base.send()
```

To get to a “toy” implementation, we need a few more types to help us out somewhat. In listing 4.8, we add a new field, `mailbox`, to `CubeSat`. `CubeSat.mailbox` is a `Mailbox` struct that contains a vector of `Messages` within its `messages` field. We alias `String` to `Message`, giving us the functionality of the `String` type without needing to implement it ourselves.

### Listing 4.8 Adding a Mailbox type to our system

```
1 #[derive(Debug)]
2 struct CubeSat {
3     id: u64,
```

```

4     mailbox: Mailbox,
5 }
6
7 #[derive(Debug)]
8 enum StatusMessage {
9     Ok,
10 }
11
12 #[derive(Debug)]
13 struct Mailbox {
14     messages: Vec<Message>,
15 }
16
17 type Message = String;

```

Creating a `CubeSat` instance has become slightly more complicated. To create one now, we also need to create its associated `Mailbox` and the mailbox's associated `Vec<Message>`. The following listing shows this addition.

#### **Listing 4.9 Creating a new CubeSat with Mailbox**

```
CubeSat { id: 100, mailbox: Mailbox { messages: vec![] } }
```

Another type to add is one that represents the ground station itself. We will use a bare struct for the moment, as shown in the following listing. That allows us to add methods to it and gives us the option of adding a mailbox as a field later on as well.

#### **Listing 4.10 Defining a struct to represent our ground station**

```
struct GroundStation;
```

Creating an instance of `GroundStation` should be trivial for you now. The following listing shows this implementation.

#### **Listing 4.11 Creating a new ground station**

```
GroundStation {};
```

Now that we have our new types in place, let's put these to work. You'll see how in the next section.

### **4.5.1 Use references where full ownership is not required**

The most common change you will make to your code is to reduce the level of access you require. Instead of requesting ownership, you can use a “borrow” in your function definitions. For read-only access, use `& T`. For read-write access, use `&mut T`.

Ownership might be needed in advanced cases, such as when functions want to adjust the lifetime of their arguments. Table 4.1 compares the two different approaches.

**Table 4.1 Comparing ownership and mutable references**

Using ownership	Using a mutable reference
<pre>fn send(to: CubeSat, msg: Message) {     to.mailbox.messages.push(msg); }</pre> <p>Ownership of the <code>to</code> variable moves into <code>send()</code>. When <code>send()</code> returns, <code>to</code> is deleted.</p>	<pre>fn send(to: &amp;mut CubeSat, msg: Message) {     to.mailbox.messages.push(msg); }</pre> <p>Adding the <code>&amp;mut</code> prefix to the <code>CubeSat</code> type allows the outer scope to retain ownership of data referred to by the <code>to</code> variable.</p>

Sending messages will eventually be wrapped up in a method, but with essence functions, implementing that modifies the internal mailbox of the `CubeSat`. For simplicity's sake, we'll return `()` and hope for the best in case of transmission difficulties caused by solar winds.

The following snippet shows the flow that we want to end up with. The ground station can send a message to `sat_a` with its `send()` method, and `sat_a` then receives the message with its `recv()` method:

```
base.send(sat_a, "hello!".to_string());
let msg = sat_a.recv();
println!("sat_a received: {:?}", msg); // -> Option("hello!")
```

The next listing shows the implementations of these methods. To achieve that flow, add the implementations to `GroundStation` and `CubeSat` types.

**Listing 4.12 Adding the `GroundStation.send()` and `CubeSat.recv()` methods**

```
1 impl GroundStation {
2     fn send(
3         &self,
4         to: &mut CubeSat,
5         msg: Message,
6     ) {
7         to.mailbox.messages.push(msg);
8     }
9 }
10
11 impl CubeSat {
12     fn recv(&mut self) -> Option<Message> {
13         self.mailbox.messages.pop()
14     }
15 }
```

`&self` indicates that `GroundStation.send()` only requires a read-only reference to `self`. The recipient takes a mutable borrow (`&mut`) of the `CubeSat` instance, and `msg` takes full ownership of its `Message` instance.

Ownership of the `Message` instance transfers from `msg` to `messages.push()` as a local variable.

Notice that both `GroundStation.send()` and `CubeSat.recv()` require mutable access to a `CubeSat` instance because both methods modify the underlying `CubeSat.messages` vector. We move ownership of the message that we're sending into the `messages.push()`. This provides us with some quality assurance later, notifying us if we access a message after it's already sent. Figure 4.6 illustrates how we can avoid ownership issues.




Figure 4.6 Game plan:  
Use references to avoid  
ownership issues.

Listing 4.13 (ch4/ch4-sat-mailbox.rs) brings together all of the code snippets in this section thus far and prints the following output. The messages starting with `t0` through `t2` are added to assist your understanding of how data is flowing through the program:

```
t0: CubeSat { id: 0, mailbox: Mailbox { messages: [] } }
t1: CubeSat { id: 0, mailbox: Mailbox { messages: ["hello there!"] } }
t2: CubeSat { id: 0, mailbox: Mailbox { messages: [] } }
msg: Some("hello there!")
```

### Listing 4.13 Avoiding ownership issues with references

```
1 #[derive(Debug)]
2 struct CubeSat {
3     id: u64,
4     mailbox: Mailbox,
5 }
6
7 #[derive(Debug)]
8 struct Mailbox {
9     messages: Vec<Message>,
10 }
11
12 type Message = String;
13
14 struct GroundStation;
15
16 impl GroundStation {
17     fn send(&self, to: &mut CubeSat, msg: Message) {
18         to.mailbox.messages.push(msg);
19     }
20 }
21
22 impl CubeSat {
23     fn recv(&mut self) -> Option<Message> {
24         self.mailbox.messages.pop()
25     }
26 }
27
28 fn main() {
29     let base = GroundStation {};
30     let mut sat_a = CubeSat {
31         id: 0,
32         mailbox: Mailbox {
33             messages: vec![],
34         },
35     };
36     println!("t0: {:?}", sat_a);
37     base.send(&mut sat_a,
38               Message::from("hello there!"));
39 }
```

We don't have a completely ergonomic way to create `Message` instances yet. Instead, we'll take advantage of the `String.from()` method that converts `&str` to `String` (aka `Message`). ↗

```

41     println!("t1: {:?}", sat_a);
42
43     let msg = sat_a.recv();
44     println!("t2: {:?}", sat_a);
45
46     println!("msg: {:?}", msg);
47
48 }
```

### 4.5.2 Use fewer long-lived values

If we have a large, long-standing object such as a global variable, it can be somewhat unwieldy to keep this around for every component of your program that needs it. Rather than using an approach involving long-standing objects, consider making objects that are more discrete and ephemeral. Ownership issues can sometimes be resolved by considering the design of the overall program.

In our CubeSat case, we don't need to handle much complexity at all. Each of our four variables—`base`, `sat_a`, `sat_b`, and `sat_c`—live for the duration of `main()`. In a production system, there can be hundreds of different components and many thousands of interactions to manage. To increase the manageability of this kind of scenario, let's break things apart. Figure 4.7 presents the game plan for this section.

To implement this kind of strategy, we will create a function that returns CubeSat identifiers. That function is assumed to be a black box that's responsible for communicating with some store of identifiers, such as a database. When we need to communicate with a satellite, we'll create a new object, as the following code snippet shows. In this way, there is no requirement for us to maintain live objects for the whole of the program's duration. It also has the dual benefit that we can afford to transfer ownership of our short-lived variables to other functions:

```

fn fetch_sat_ids() -> Vec<u64> {
    vec![1, 2, 3]
} ← Returns a vector
                                | of CubeSat IDs
```

We'll also create a method for `GroundStation`. This method allows us to create a `CubeSat` instance on demand once:

```

impl GroundStation {
    fn connect(&self, sat_id: u64) -> CubeSat {
        CubeSat { id: sat_id, mailbox: Mailbox { messages: vec![] } }
    }
}
```

Now we are a bit closer to our intended outcome. Our main function looks like the following code snippet. In effect, we've implemented the first half of figure 4.7.




Figure 4.7 Game plan: Short-lived variables to avoid ownership issues

```
fn main() {
    let base = GroundStation();

    let sat_ids = fetch_sat_ids();

    for sat_id in sat_ids {
        let mut sat = base.connect(sat_id);

        base.send(&mut sat, Message::from("hello"));
    }
}
```

But there's a problem. Our CubeSat instances die at the end of the `for` loop's scope, along with any messages that `base` sends to them. To carry on with our design decision of short-lived variables, the messages need to live somewhere outside of the CubeSat instances. In a real system, these would live on the RAM of a device in zero gravity. In our not-really-a-simulator, let's put these in a buffer object that lives for the duration of our program.

Our message store will be a `Vec<Message>` (our `Mailbox` type defined in one of the first code examples of this chapter). We'll change the `Message` struct to add a sender and recipient field, as the following code shows. That way our now-proxy CubeSat instances can match their IDs to receive messages:

```
#[derive(Debug)]
struct Mailbox {
    messages: Vec<Message>,
}

#[derive(Debug)]
struct Message {
    to: u64,
    content: String,
}
```

We also need to reimplement sending and receiving messages. Up until now, CubeSat objects have had access to their own mailbox object. The central `GroundStation` also had the ability to sneak into those mailboxes to send messages. That needs to change now because only one mutable borrow can exist per object.

In the modifications in listing 4.14, the `Mailbox` instance is given the ability to modify its own message vector. When any of the satellites transmit messages, these take a mutable borrow to the mailbox. These then defer the delivery to the mailbox object. According to this API, although our satellites are able to call `Mailbox` methods, these are not allowed to touch any internal `Mailbox` data themselves.

#### **Listing 4.14 Modifications to Mailbox**

```
1 impl GroundStation {
2     fn send(
3         &self,
```

```

4      mailbox: &mut Mailbox,
5      to: &CubeSat,
6      msg: Message,
7      ) {
8          mailbox.post(to, msg); ← Calls Mailbox.post() to
9      } send messages, yielding
10 } ownership of a Message
11
12 impl CubeSat {
13     fn recv(
14         &self,
15         mailbox: &mut Mailbox
16     ) -> Option<Message> { ← Calls Mailbox.deliver() to
17         mailbox.deliver(&self) receive messages, gaining
18     } ownership of a Message
19 }
20
21 impl Mailbox {
22     fn post(&mut self, msg: Message) { ← Mailbox.post() requires
23         self.messages.push(msg); mutable access to itself
24     } and ownership over a
25
26     fn deliver( ← Mailbox.deliver() requires a
27         &mut self, shared reference to a CubeSat
28         recipient: &CubeSat to pull out its id field.
29     ) -> Option<Message> { ←
30         for i in 0..self.messages.len() {
31             if self.messages[i].to == recipient.id {
32                 let msg = self.messages.remove(i);
33                 return Some(msg); ← When we find a message,
34             } returns early with the
35         } Message wrapped in Some
36     }
37     None ← per the Option type
38 }
39 }
```

When no messages are found, returns None

**NOTE** Astute readers of listing 4.14 will notice a strong anti-pattern. On line 32, the `self.messages` collection is modified while it is being iterated over. In this instance, this is legal because of the `return` on the next line. The compiler can prove that another iteration will not occur and allows the mutation to proceed.

With that groundwork in place, we're now able to fully implement the strategy laid out in figure 4.7. Listing 4.15 (`ch4/ch4-short-lived-strategy.rs`) is the full implementation of the short-lived variables game plan. The output from a compiled version of that listing follows:

```

CubeSat { id: 1 }: Some(Message { to: 1, content: "hello" })
CubeSat { id: 2 }: Some(Message { to: 2, content: "hello" })
CubeSat { id: 3 }: Some(Message { to: 3, content: "hello" })
```

**Listing 4.15 Implementing the short-lived variables strategy**

```
1 #![allow(unused_variables)]
2
3 #[derive(Debug)]
4 struct CubeSat {
5     id: u64,
6 }
7
8 #[derive(Debug)]
9 struct Mailbox {
10    messages: Vec<Message>,
11 }
12
13 #[derive(Debug)]
14 struct Message {
15     to: u64,
16     content: String,
17 }
18
19 struct GroundStation {}
20
21 impl Mailbox {
22     fn post(&mut self, msg: Message) {
23         self.messages.push(msg);
24     }
25
26     fn deliver(&mut self, recipient: &CubeSat) -> Option<Message> {
27         for i in 0..self.messages.len() {
28             if self.messages[i].to == recipient.id {
29                 let msg = self.messages.remove(i);
30                 return Some(msg);
31             }
32         }
33
34         None
35     }
36 }
37
38 impl GroundStation {
39     fn connect(&self, sat_id: u64) -> CubeSat {
40         CubeSat {
41             id: sat_id,
42         }
43     }
44
45     fn send(&self, mailbox: &mut Mailbox, msg: Message) {
46         mailbox.post(msg);
47     }
48 }
49
50 impl CubeSat {
51     fn recv(&self, mailbox: &mut Mailbox) -> Option<Message> {
52         mailbox.deliver(&self)
53     }
54 }
```

```

54 }
55 fn fetch_sat_ids() -> Vec<u64> {
56     vec![1, 2, 3]
57 }
58
59
60 fn main() {
61     let mut mail = Mailbox { messages: vec![] };
62
63     let base = GroundStation {};
64
65     let sat_ids = fetch_sat_ids();
66
67     for sat_id in sat_ids {
68         let sat = base.connect(sat_id);
69         let msg = Message { to: sat_id, content: String::from("hello") };
70         base.send(&mut mail, msg);
71     }
72
73     let sat_ids = fetch_sat_ids();
74
75     for sat_id in sat_ids {
76         let sat = base.connect(sat_id);
77
78         let msg = sat.recv(&mut mail);
79         println!("{}: {:?}", sat, msg);
80     }
81 }
```

### 4.5.3 **Duplicate the value**

Having a single owner for every object can mean significant up-front planning and/or refactoring of your software. As we saw in the previous section, it can be quite a lot of work to wriggle out of an early design decision.

One alternative to refactoring is to simply copy values. Doing this often is typically frowned upon, however, but it can be useful in a pinch. Primitive types like integers are a good example of that. Primitive types are cheap for a CPU to duplicate—so cheap, in fact, that Rust always copies these if it would otherwise worry about ownership being moved.

Types can opt into two modes of duplication: cloning and copying. Each mode is provided by a trait. Cloning is defined by `std::clone::Clone`, and the copying mode is defined by `std::marker::Copy`. Copy acts implicitly. Whenever ownership would otherwise be moved to an inner scope, the value is duplicated instead. (The bits of object *a* are replicated to create object *b*.) Clone acts explicitly. Types that implement `Clone` have a `.clone()` method that is permitted to do whatever it needs to do to create a new value. Table 4.2 outlines the major differences between the two modes.

**Table 4.2 Distinguishing cloning from copying**

Cloning ( <code>std::clone::Clone</code> )	Copying ( <code>std::marker::Copy</code> )
<ul style="list-style-type: none"> <li>■ May be slow and expensive.</li> <li>■ Never implicit. A call to the <code>.clone()</code> method is always required.</li> <li>■ May differ from original. Crate authors define what cloning means for their types.</li> </ul>	<ul style="list-style-type: none"> <li>■ Always fast and cheap.</li> <li>■ Always implicit.</li> <li>■ Always identical. Copies are bit-for-bit duplicates of the original value.</li> </ul>

So why do Rust programmers not always use `Copy`? There are three main reasons:

- *The Copy trait implies that there will only be negligible performance impact.* This is true for numbers but not true for types that are arbitrarily large, such as `String`.
- *Because Copy creates exact copies, it cannot treat references correctly.* Naively copying a reference to `T` would (attempt to) create a second owner of `T`. That would cause problems later on because there would be multiple attempts to delete `T` as each reference is deleted.
- *Some types overload the Clone trait.* This is done to provide something similar to, yet different from, creating duplicates. For example, `std::rc::Rc<T>` uses `Clone` to create additional references when `.clone()` is called.

**NOTE** Throughout your time with Rust, you will normally see the `std::clone::Clone` and `std::marker::Copy` traits referred to simply as `Clone` and `Copy`. These are included in every crate's scope via the standard prelude.

### IMPLEMENTING COPY

Let's go back to our original example (listing 4.3), which caused the original movement issue. Here it is replicated for convenience, with `sat_b` and `sat_c` removed for brevity:

```
# [derive(Debug)]
struct CubeSat {
    id: u64,
}

#[derive(Debug)]
enum StatusMessage {
    Ok,
}

fn check_status(sat_id: CubeSat) -> StatusMessage {
    StatusMessage::Ok
}

fn main() {
    let sat_a = CubeSat { id: 0 };

    let a_status = check_status(sat_a);
    println!("a: {:?}", a_status);
```

```
let a_status = check_status(sat_a);      ←
println!("a: {:?}", a_status);
}
```

The second call to `check_status(sat_a)` is the location of error.

At this early stage, our program consisted of types that contain types, which themselves implement `Copy`. That's good because it means implementing it ourselves is fairly straightforward, as the following listing shows.

#### **Listing 4.16 Deriving Copy for types made up of types that implement Copy**

```
#[derive(Copy, Clone, Debug)] ←
struct CubeSat {
    id: u64,
}

#[derive(Copy, Clone, Debug)] ←
enum StatusMessage {
    Ok,
}
```

`#[derive(Copy, Clone, Debug)]` tells the compiler to add an implementation of each of the traits.

The following listing shows how it's possible to implement `Copy` manually. The `impl` blocks are impressively terse.

#### **Listing 4.17 Implementing the Copy trait manually**

```
impl Copy for CubeSat { }

impl Copy for StatusMessage { }

impl Clone for CubeSat {      ←
    fn clone(&self) -> Self {
        CubeSat { id: self.id }      ←
    }
}

impl Clone for StatusMessage {
    fn clone(&self) -> Self {
        *self                      ←
    }
}
```

Implementing `Copy` requires an implementation of `Clone`.

If desired, we can write out the creation of a new object ourselves...

...but often we can simply dereference `self`.

#### **USING CLONE AND COPY**

Now that we know how to implement them, let's put `Clone` and `Copy` to work. We've discussed that `Copy` is implicit. When ownership would otherwise move, such as during assignment and passing through function barriers, data is copied instead.

`Clone` requires an explicit call to `.clone()`. That's a useful marker in non-trivial cases, such as in listing 4.18, because it warns the programmer that the process may be expensive. You'll find the source for this listing in `ch4/ch4-check-sats-clone-and-copy-traits.rs`.

**Listing 4.18 Using Clone and Copy**

```

1 #[derive(Debug,Clone,Copy)]    ←
2 struct CubeSat {
3     id: u64,
4 }
5
6 #[derive(Debug,Clone,Copy)]    ←
7 enum StatusMessage {
8     Ok,
9 }
10
11 fn check_status(sat_id: CubeSat) -> StatusMessage {
12     StatusMessage::Ok
13 }
14
15 fn main () {
16     let sat_a = CubeSat { id: 0 };
17
18     let a_status = check_status(sat_a.clone());    ←
19     println!("a: {:?}", a_status.clone());          | Cloning each object is as
20
21     let a_status = check_status(sat_a);           | ←
22     println!("a: {:?}", a_status);                | Copy works
23 }
```

Copy implies  
Clone, so we  
can use either  
trait later.

as  
easy as calling .clone().

Copy works  
as expected.

**4.5.4 Wrap data within specialty types**

So far in this chapter, we have discussed Rust’s ownership system and ways to navigate the constraints it imposes. A final strategy that is quite common is to use *wrapper* types, which allow more flexibility than what is available by default. These, however, incur costs at runtime to ensure that Rust’s safety guarantees are maintained. Another way to phrase this is that Rust allows programmers to opt in to garbage collection.<sup>3</sup>

To explain the wrapper type strategy, let’s introduce a wrapper type: `std::rc::Rc`. `std::rc::Rc` takes a type parameter `T` and is typically referred to as `Rc<T>`. `Rc<T>` reads as “R. C. of T” and stands for “a reference-counted value of type `T`.” `Rc<T>` provides *shared ownership* of `T`. Shared ownership prevents `T` from being removed from memory until every owner is removed.

As indicated by the name, *reference counting* is used to track valid references. As each reference is created, an internal counter increases by one. When a reference is dropped, the count decreases by one. When the count hits zero, `T` is also dropped.

Wrapping `T` involves calling `Rc::new()`. The following listing, at `ch4/ch4-rc-groundstation.rs`, shows this approach.

---

<sup>3</sup> Garbage collection (often abbreviated as GC) is a strategy for memory management used by many programming languages, including Python and JavaScript, and all languages built on the JVM (Java, Scala, Kotlin) or the CLR (C#, F#).

**Listing 4.19 Wrapping a user-defined type in Rc**

```

1 use std::rc::Rc;           ← The use keyword brings
2 #![derive(Debug)]           modules from the standard
3 struct GroundStation {}    library into local scope.
4
5 fn main() {
6     let base = Rc::new(GroundStation {});   ← Wrapping involves enclosing
7     println!("{:?}", base);      ← Prints the GroundStation instance
8 }
9
10 }
```

`Rc<T>` implements `Clone`. Every call to `base.clone()` increments an internal counter. Every `Drop` decrements that counter. When the internal counter reaches zero, the original instance is freed.

`Rc<T>` does not allow mutation. To permit that, we need to wrap our wrapper. `Rc<RefCell<T>>` is a type that can be used to perform interior mutability, first introduced at the end of chapter 3 in section 3.4.1. An object that has interior mutability presents an immutable façade while internal values are being modified.

In the following example, we can modify the variable `base` despite being marked as an immutable variable. It's possible to visualize this by looking at the changes to the internal `base.radio_freq`:

```

base: RefCell { value: GroundStation { radio_freq: 87.65 } }
base_2: GroundStation { radio_freq: 75.31 }
base: RefCell { value: GroundStation { radio_freq: 75.31 } }
base: RefCell { value: "<borrowed>" }   ← value: "<borrowed>" indicates that base is
base_3: GroundStation { radio_freq: 118.52000000000001 }  mutably borrowed somewhere else and is no longer generally accessible.
```

The following listing, found at `ch4/ch4-rc-refcell-groundstation.rs`, uses `Rc<RefCell<T>>` to permit mutation within an object marked as immutable. `Rc<RefCell<T>>` incurs some additional runtime cost over `Rc<T>` while allowing shared read/write access to `T`.

**Listing 4.20 Using `Rc<RefCell<T>>` to mutate an immutable object**

```

1 use std::rc::Rc;
2 use std::cell::RefCell;
3
4 #[derive(Debug)]
5 struct GroundStation {
6     radio_freq: f64 // Mhz
7 }
8
9 fn main() {
10     let base: Rc<RefCell<GroundStation>> = Rc::new(RefCell::new(
11         GroundStation {
12             radio_freq: 87.65
13         }
14     ));
15 }
```

```

15
16     println!("base: {:?}", base);
17
18     {
19         let mut base_2 = base.borrow_mut();
20         base_2.radio_freq -= 12.34;
21         println!("base_2: {:?}", base_2);
22     }
23
24     println!("base: {:?}", base);
25
26     let mut base_3 = base.borrow_mut();
27     base_3.radio_freq += 43.21;
28
29     println!("base: {:?}", base);
30     println!("base_3: {:?}", base_3);
31 }
```

Introduces a new scope  
where `base` can be  
mutably borrowed

There are two things to note from this example:

- Adding more functionality (e.g., reference-counting semantics rather than move semantics) to types by wrapping these in other types typically reduces their runtime performance.
- If implementing `Clone` would be prohibitively expensive, `Rc<T>` can be a handy alternative. This allows two places to “share” ownership.

**NOTE** `Rc<T>` is not thread-safe. In multithreaded code, it’s much better to replace `Rc<T>` with `Arc<T>` and `Rc<RefCell<T>>` with `Arc<Mutex<T>>`. *Arc* stands for *atomic reference counter*.

## Summary

- A value’s owner is responsible for cleaning up after that value when its lifetime ends.
- A value’s lifetime is the period when accessing that value is valid behavior. Attempting to access a value after its lifetime has expired leads to code that won’t compile.
- To *borrow* a value means to access that value.
- If you find that the borrow checker won’t allow your program to compile, several tactics are available to you. This often means that you will need to rethink the design of your program.
- Use shorter-lived values rather than values that stick around for a long time.
- Borrows can be read-only or read-write. Only one read-write borrow can exist at any one time.
- Duplicating a value can be a pragmatic way to break an impasse with the borrow checker. To duplicate a value, implement `Clone` or `Copy`.
- It’s possible to opt in to reference counting semantics through `Rc<T>`.
- Rust supports a feature known as interior mutability, which enables types to present themselves as immutable even though their values can change over time.



## *Part 2*

# *Demystifying systems programming*

P

art 2 extends your base Rust knowledge by applying Rust to examples from the field of systems programming. Every chapter includes at least one large project that includes a new language feature. You will build command-line utilities, libraries, graphical applications, networked applications, and even your own operating system kernel.



# *Data in depth*

## **This chapter covers**

- Learning how the computer represents data
- Building a working CPU emulator
- Creating your own numeric data type
- Understanding floating-point numbers

This chapter is all about understanding how zeroes and ones can become much larger objects like text, images, and sound. We will also touch on how computers do computation.

By the end of the chapter, you will have emulated a fully functional computer with CPU, memory, and user-defined functions. You will break apart floating-point numbers to create a numeric data type of your own that only takes a single byte. The chapter introduces a number of terms, such as *endianness* and *integer overflow*, that may not be familiar to programmers who have never done systems programming.

### **5.1 Bit patterns and types**

A small but important lesson is that a single bit pattern can mean different things. The type system of a higher-level language, such as Rust, is just an artificial abstraction over reality. Understanding this becomes important as you begin to unravel some of that abstraction and to gain a deeper understanding of how computers work.

Listing 5.1 (in ch5/int-vs-int.rs) is an example that uses the same bit pattern to represent two different numbers. The type system—not the CPU—is what makes this distinction. The following shows the listing’s output:

```
a: 1100001111000011 50115
b: 1100001111000011 -15421
```

### Listing 5.1 The data type determines what a sequence of bits represents

```
1 fn main() {
2     let a: u16 = 50115;
3     let b: i16 = -15421;
4
5     println!("a: {:016b} {}", a, a);
6     println!("b: {:016b} {}", b, b);
7 }
```

These two values have  
the same bit pattern  
but different types.

The different mapping between bit strings and numbers explains part of the distinction between binary files and text files. Text files are just binary files that happen to follow a consistent mapping between bit strings and characters. This mapping is called an *encoding*. Arbitrary files don’t describe their meaning to the outside world, which makes these opaque.

We can take this process one step further. What happens if we ask Rust to treat a bit pattern produced by one type as another? The following listing provides an answer. The source code for this listing is in ch5/ch5-f32-as-u32.rs.

### Listing 5.2 Interpreting a float’s bit string as an integer

```
1 fn main() {
2     let a: f32 = 42.42;
3     let frankentype: u32 = unsafe {
4         std::mem::transmute(a)
5     };
6
7     println!("{}", frankentype);           ← No semicolon here. We want the
8     println!("{:032b}", frankentype);      ← result of this expression to feed
9
10    let b: f32 = unsafe {
11        std::mem::transmute(frankentype)
12    };
13    println!("{}", b);                  ← Views the bits of a 42.42_f32
14    assert_eq!(a, b);                 ← value as a decimal integer
15 }
```

{:032b} means to format as a binary via the std::fmt::Binary trait with 32 zeroes padded on the left.

Confirms that the operation is symmetrical

When compiled and run, the code from listing 5.2 produces the following output:

```
1110027796
01000010001010011010111000010100
42.42
```

Some further remarks about some of the unfamiliar Rust that listing 5.2 introduces includes the following:

- Line 8 demonstrates a new directive to the `println!()` macro: `{ :032b }`. The `032` reads as “left-pad with 32 zeros” and the right-hand `b` invokes the `std::fmt::Binary` trait. This contrasts with the default syntax `({})`, which invokes the `std::fmt::Display` trait, or the question mark syntax `({:?})`, which invokes `std::fmt::Debug`.
- Unfortunately for us, `f32` doesn’t implement `std::fmt::Binary`. Luckily, Rust’s integer types do. There are two integer types guaranteed to take up the same number of bits as `f32`—`i32` and `u32`. The decision about which to choose is somewhat arbitrary.
- Lines 3–5 perform the conversion discussed in the previous bulleted point. The `std::mem::transmute()` function asks Rust to naïvely interpret an `f32` as an `u32` without affecting any of the underlying bits. The inverse conversion is repeated later on lines 10–12.

Mixing data types in a program is inherently chaotic, so we need to wrap these operation within `unsafe` blocks. `unsafe` tells the Rust compiler, “Stand back, I’ll take care of things from here. I’ve got this.” It’s a signal to the compiler that you have more context than it does to verify the correctness of the program.

Using the `unsafe` keyword does not imply that code is *inherently* dangerous. For example, it does not allow you to bypass Rust’s borrow checker. It indicates that the compiler is not able to guarantee that the program’s memory is safe by itself. Using `unsafe` means that the programmer is fully responsible for maintaining the program’s integrity.

**WARNING** Some functionality allowed within `unsafe` blocks is more difficult to verify than others. For example, the `std::mem::transmute()` function is one of the least safe in the language. It shreds all type safety. Investigate alternatives before using it in your own code.

Needlessly using `unsafe` blocks is heavily frowned upon within the Rust community. It can expose your software to critical security vulnerabilities. Its primary purpose is to allow Rust to interact with external code, such as libraries written in other languages and OS interfaces. This book uses `unsafe` more frequently than many projects because its code examples are teaching tools, not industrial software. `unsafe` allows you to peek at and poke at individual bytes, which is essential knowledge for people seeking to understand how computers work.

## 5.2 Life of an integer

During earlier chapters, we spent some time discussing what it means for an integer to be an `i32`, an `u8`, or an `usize`. Integers are like small, delicate fish. They do what they do remarkably well, but take them outside of their natural range and they die a quick, painful death.

Integers live within a fixed range. When represented inside the computer, these occupy a fixed number of bits per type. Unlike floating-point numbers, integers cannot sacrifice their precision to extend their bounds. Once those bits have been filled with 1s, the only way forward is back to all 0s.

A 16-bit integer can represent numbers between 0 and 65,535, inclusive. What happens when you want to count to 65,536? Let's find out.

The technical term for the class of problem that we are investigating is *integer overflow*. One of the most innocuous ways of overflowing an integer is by incrementing forever. The following listing (ch5/ch5-to-oblivion.rs) is a trivial example of this.

### Listing 5.3 Exploring the effect of incrementing an integer past its range

```

1 fn main() {
2     let mut i: u16 = 0;
3     print!("{}..", i);
4
5     loop {
6         i += 1000;
7         print!("{}..", i);
8         if i % 10000 == 0 {
9             print!{"\n"}
10        }
11    }
12 }
```

When we try to run listing 5.3, things don't end well for our program. Let's look at the output:

```

$ rustc ch5-to-oblivion.rs && ./ch5-to-oblivion
0..1000..2000..3000..4000..5000..6000..7000..8000..9000..10000..
11000..12000..13000..14000..15000..16000..17000..18000..19000..20000..
21000..22000..23000..24000..25000..26000..27000..28000..29000..30000..
31000..32000..33000..34000..35000..36000..37000..38000..39000..40000..
41000..42000..43000..44000..45000..46000..47000..48000..49000..50000..
51000..52000..53000..54000..55000..56000..57000..58000..59000..60000..
thread 'main' panicked at 'attempt to add with overflow',
          ch5-to-oblivion.rs:5:7
note: run with `RUST_BACKTRACE=1` environment variable
      to display a backtrace
61000..62000..63000..64000..65000..
```

A panicked program is a dead program. Panic means that the programmer has asked the program to do something that's impossible. It doesn't know what to do to proceed and shuts itself down.

To understand why this is such a critical class of bugs, let's take a look at what's going on under the hood. Listing 5.4 (ch5/ch5-bit-patterns.rs) prints six numbers with their bit patterns laid out in literal form. When compiled, the listing prints the following short line:

```
0, 1, 2, ..., 65533, 65534, 65535
```

Try compiling the code with optimizations enabled via `rustc -O ch5-to-oblivion.rs` and running the resulting executable. The behavior is quite different. The problem we're interested in is what happens when there's no more bits left. 65,536 cannot be represented by `u16`.

#### Listing 5.4 How `u16` bit patterns translate to a fixed number of integers

```
fn main() {
    let zero: u16 = 0b0000_0000_0000_0000;
    let one: u16 = 0b0000_0000_0000_0001;
    let two: u16 = 0b0000_0000_0000_0010;
    // ...
    let sixtyfivethousand_533: u16 = 0b1111_1111_1111_1101;
    let sixtyfivethousand_534: u16 = 0b1111_1111_1111_1110;
    let sixtyfivethousand_535: u16 = 0b1111_1111_1111_1111;

    println!("{{}, {}, {}, ..., {}, zero, one, two);
    println!("{{}, {}, {}, {}", sixty5_533, sixty5_534, sixty5_535);
}
```

There is another (easy) way to kill a program using a similar technique. In listing 5.5, we ask Rust to fit 400 into an `u8`, which can only count up to 255 values. Look in `ch5/ch5-impossible-addition.rs` for the source code for this listing.

#### Listing 5.5 Impossible addition

```
#[allow(arithmetic_overflow)] ← Required declaration. The
fn main() { ← Rust compiler can detect this
    let (a, b) = (200, 200);
    let c: u8 = a + b; ← obvious overflow situation.
    println!("200 + 200 = {}", c);
}
```

Without the type declaration, Rust won't assume that you're trying to create an impossible situation.

The code compiles, but one of two things happen:

- The program panics:

```
thread 'main' panicked at 'attempt to add with overflow',
5-impossible-add.rs:3:15
note: Run with `RUST_BACKTRACE=1` for a backtrace
```

This behavior can be invoked via executing `rustc` with its default options: `rustc ch5-impossible-add.rs && ch5-impossible-add`.

- The program gives you the wrong answer:

```
200 + 200 = 144
```

This behavior can be invoked by executing `rustc` with the `-O` flag: `rustc -O ch5-impossible-add.rs && ch5-impossible-add`.

There are two small lessons here:

- It's important to understand the limitations of your types.
- Despite Rust's strengths, programs written in Rust can still break.

Developing strategies for preventing integer overflow is one of the ways that system programmers are distinguished from others. Programmers who only have experience with dynamic languages are extremely unlikely to encounter an integer overflow. Dynamic languages typically check to see that the results of integer expressions will fit. When these can't, the variable that's receiving the result is promoted to a wider integer type.

When developing performance critical code, you get to choose which parameters to adjust. If you use fixed-sized types, you gain speed, but you need to accept some risk. To mitigate the risk, you can check to see that overflow won't occur at runtime. Imposing those checks will slow you down, however. Another, much more common option, is to sacrifice space by using a large integer type, such as `i64`. To go higher still, you'll need to move to arbitrarily sized integers, which come with their own costs.

### 5.2.1 ***Understanding endianness***

CPU vendors argue about how the individual bytes that make up integers should be laid out. Some CPUs order multibyte sequences left to right and others are right to left. This characteristic is known as a CPU's *endianness*. This is one of the reasons why copying an executable file from one computer to another might not work.

Let's consider a 32-bit integer that represents a number made up of four bytes: AA, BB, CC, and DD. Listing 5.6 (`ch5/ch5-endianness.rs`), with the help of our friend `sys::mem::transmute()`, demonstrates that byte order matters. When compiled and executed, the code from listing 5.6 prints one of two things, depending on the endianness of your machine. Most computers that people run for day-to-day work print the following:<sup>1</sup>

```
-573785174 vs. -1430532899
```

But more exotic hardware swaps the two numbers around like this:

```
-1430532899 vs. -573785174
```

#### **Listing 5.6 Inspecting endianness**

```
use std::mem::transmute;

fn main() {
    let big_endian: [u8; 4]      = [0xAA, 0xBB, 0xCC, 0xDD];
    let little_endian: [u8; 4]    = [0xDD, 0xCC, 0xBB, 0xAA];
```

---

<sup>1</sup> In 2021, the x86-64/AMD64 CPU architecture is dominant.

```

let a: i32 = unsafe { transmute(big_endian) } ;
let b: i32 = unsafe { transmute(little_endian) } ;
println!("{} vs {}", a, b);
}

```

std::mem::transmute()  
 instructs the compiler to  
 interpret its argument as  
 the type on the left (i32).

The terminology comes from the *significance* of the bytes in the sequence. To take you back to when you learned addition, we can factor the number 123 into three parts:

$100 \times 1$	100
$10 \times 2$	20
$1 \times 3$	3

Summing all of these parts gets us back to our original number. The first part, 100, is labeled as the most significant. When written out in the conventional way, 123 as 123, we are writing in *big endian* format. Were we to invert that ordering by writing 123 as 321, we would be writing in *little endian* format.

Binary numbers work in a similar way. Each number part is a power of 2 ( $2^0, 2^1, 2^2, \dots, 2n$ ), rather than a power of 10 ( $10^0, 10^1, 10^2, \dots, 10n$ ).

Before the late-1990s, endianness was a big issue, especially in the server market. Glossing over the fact that a number of processors can support bidirectional endianness, Sun Microsystems, Cray, Motorola, and SGI went one way. ARM decided to hedge its bet and developed a *bi-endian* architecture. Intel went the other way. The other way won. Integers are almost certainly stored in *little endian* format.

In addition to multibyte sequences, there is a related problem within a byte. Should an `u8` that represents 3 look like `0000_0011`, or should it look like `1100_0000`? The computer's preference for layout of individual bits is known as its *bit numbering* or *bit endianness*. It's unlikely, however, that this internal ordering will affect your day-to-day programming. To investigate further, look for your platform's documentation to find out on which end its *most significant* bit lies.

**NOTE** The abbreviation MSB can be deceptive. Different authors use the same abbreviation to refer to two concepts: most significant *bit* and most significant *byte*. To avoid confusion, this text uses the term *bit numbering* to refer to the most significant bit and *endianness* to refer to most significant byte.

## 5.3 Representing decimal numbers

One of the claims made at the start of this chapter was that understanding more about bit patterns enables you to compress your data. Let's put that into practice. In this section, you will learn how to pull bits out of a floating-point number and inject those into a single byte format of your own creation.

Here is some context for the problem at hand. Machine learning practitioners often need to store and distribute large models. A model for our purposes here is just

a large array of numbers. The numbers within those models often fall within the ranges `0..=1` or `-1..=1` (using Rust's range syntax), depending on the application. Given that we don't need the whole range that `f32` or `f64` supports, why use all of these bytes? Let's see how far we can get with 1. Because there is a known limited range, it's possible to create a decimal number format that can model that range compactly.

To start, we're going to need to learn about how decimal numbers are represented inside today's computers. This means learning about the internals of floating-point numbers.

## 5.4 Floating-point numbers

Each floating-point number is laid out in memory as scientific notation. If you're unfamiliar with scientific notation, here is a quick primer.

Scientists describe the mass of Jupiter as  $1.898 \times 10^{27}$  kg and the mass of an ant as  $3.801 \times 10^{-4}$  kg. The key insight is that the same number of characters are used to describe vastly different scales. Computer scientists have taken advantage of that insight to create a fixed-width format that encodes a wide range of numbers. Each position within a number in scientific notation is given a role:

- A *sign*, which is implied in our two examples, would be present for negative numbers (negative infinity to 0).
- The *mantissa*, also known as the *significand*, can be thought of as being the value in question (1.898 and 3.801, for example).
- The *radix*, also known as the *base*, is the value that is raised to the power of the exponent (10 in both of our examples).
- The *exponent* describes the scale of the values (27 and -4).

This crosses over to floating point quite neatly. A floating-point value is a container with three fields:

- A sign bit
- An exponent
- A mantissa

Where is the radix? The standard defines it as 2 for all floating-point types. This definition allows the radix to be omitted from the bit pattern itself.

### 5.4.1 Looking inside an f32

Figure 5.1 presents the memory layout of the `f32` type in Rust. The layout is called *binary32* within the IEEE 754-2019 and IEEE 754-2008 standards and *single* by their predecessor, IEE 754-1985.

The value `42.42` is encoded as `f32` with the bit pattern `01000010001010011010111000010100`. That bit pattern is more compactly represented as `0x4229AE14`. Table 5.1 shows the values of each of the three fields and what these represent..




Figure 5.1 An overview of the three components encoded within the bits of a floating-point number for the `f32` type in Rust

Table 5.1 The components of 42.42 represented by the bit pattern 0x4229AE14 as a `f32` type

Component name	Component in binary	Component as base-10 ( <code>u32</code> )	Decoded value
Sign bit (s)	0	0	1
Exponent (t)	10000100	132	5
Mantissa/significand (m)	01010011010111000010100	2,731,540	1.325625
Base/radix			2
Exponent bias			127

**NOTE** See lines 32–38 of listing 5.10 and the explanation provided shortly in section 5.3.5 to learn how 01010011010111000010100 represents 1.325625.

The following equation decodes the fields of a floating-point number into a single number. Variables from the standard (Radix, Bias) appear in title case. Variables from the bit pattern (sign\_bit, mantissa, exponent) occur as lowercase and monospace.

$$\begin{aligned}
 n &= -1^{\text{sign\_bit}} \times \text{mantissa} \times \text{Radix}^{(\text{exponent}-\text{Bias})} \\
 n &= -1^{\text{sign\_bit}} \times \text{mantissa} \times \text{Radix}^{(\text{exponent} - 127)} \\
 n &= -1^{\text{sign\_bit}} \times \text{mantissa} \times \text{Radix}^{(132 - 127)} \\
 n &= -1^{\text{sign\_bit}} \times \text{mantissa} \times 2^{(132 - 127)} \\
 n &= -1^{\text{sign\_bit}} \times 1.325625 \times 2^{(132-127)} \\
 n &= -1^0 \times 1.325625 \times 2^5 \\
 n &= 1 \times 1.325625 \times 32 \\
 n &= 42.42
 \end{aligned}$$

One quirk of floating-point numbers is that their sign bits allow for both 0 and  $-0$ . That is, floating-point numbers that have different bit patterns compare as equal (0 and  $-0$ ) and have identical bit patterns (NAN values) that compare as unequal.

### 5.4.2 Isolating the sign bit

To isolate the sign bit, shift the other bits out of the way. For f32, this involves a right shift of 31 places ( $>> 31$ ). The following listing is a short snippet of code that performs the right shift.

#### Listing 5.7 Isolating and decoding the sign bit from an f32

```
1 let n: f32 = 42.42;
2 let n_bits: u32 = n.to_bits();
3 let sign_bit = n_bits >> 31;
```

To provide you with a deeper intuition about what is happening, these steps are detailed graphically here:

- 1 Start with a f32 value:

```
1 let n: f32 = 42.42;
```

- 2 Interpret the bits of the f32 as a u32 to allow for bit manipulation:

```
2 let n_bits: u32 = n.to_bits();
```



The issue that needs to be resolved is the sign bit's position. Treated naively, it represents 4,294,967,296 ( $2^{32}$ ) or 0, rather than 1 ( $2^0$ ) or 0.

- 3 Shift the bits within n 31 places to the right:

```
3 let sign_bit = n_bits >> 31;
```



The sign bit has now been positioned in the least significant position.

### 5.4.3 Isolating the exponent

To isolate the exponent, two bit manipulations are required. First, perform a right shift to overwrite the mantissa's bits ( $>> 23$ ). Then use an AND mask (`& 0xff`) to exclude the sign bit.

The exponent's bits also need to go through a decoding step. To decode the exponent, interpret its 8 bits as a signed integer, then subtract 127 from the result. (As discussed in section 5.3.2, 127 is known as the *bias*.) The following listing shows the code that describes the steps given in the last two paragraphs.

**Listing 5.8 Isolating and decoding the exponent from an f32**

```

1 let n: f32 = 42.42;
2 let n_bits: u32 = n.to_bits();
3 let exponent_ = n_bits >> 23;
4 let exponent_ = exponent_ & 0xff;
5 let exponent = (exponent_ as i32) - 127;

```


And to further explain the process, these steps are repeated graphically as follows:

- 1** Start with an f32 number:

```
1 let n: f32 = 42.42;
```


- 2** Interpret the bits of that f32 as u32 to allow for bit manipulation:

```
2 let n_bits: u32 = n.to_bits();
```




- 3** Shift the exponent's 8 bits to the right, overwriting the mantissa:

```
3 let exponent_ = n_bits >> 23;
```



- 4** Filter the sign bit away with an AND mask. Only the 8 rightmost bits can pass through the mask:

```
4 let exponent_ = exponent_ & 0xff;
```



- 5** Interpret the remaining bits as a signed integer and subtract the bias as defined by the standard:

```
5 let exponent = (exponent_ as i32) - 127;
```

### 5.4.4 Isolate the mantissa

To isolate the mantissa's 23 bits, you can use an AND mask to remove the sign bit and the exponent (`& 0x7fffff`). However, it's actually not necessary to do so because the following decoding steps can simply ignore bits as irrelevant. Unfortunately, the mantissa's decoding step is significantly more complex than the exponent's.

To decode the mantissa's bits, multiply each bit by its weight and sum the result. The first bit's weight is 0.5, and each subsequent bit's weight is half of the current weight; for example, 0.5 ( $2^{-1}$ ), 0.25 ( $2^{-2}$ ),..., 0.00000011920928955078125 ( $2^{-23}$ ). An implicit 24th bit that represents 1.0 ( $2^0$ ) is always considered to be on, except when special cases are triggered. Special cases are triggered by the state of the exponent:

- When the exponent's bits are all 0s, then the treatment of mantissa's bits changes to represent subnormal numbers (also known as “denormal numbers”). In practical terms, this change increases the number of decimal numbers near zero that can be represented. Formally, a subnormal number is one between 0 and the smallest number that the normal behavior would otherwise be able to represent.
- When the exponent's bits are all 1s, then the decimal number is infinity ( $\infty$ ), negative infinity ( $-\infty$ ), or Not a Number (NAN). NAN values indicate special cases where the numeric result is mathematically undefined (such as  $0 \div 0$ ) or that are otherwise invalid.

Operations involving NAN values are often counterintuitive. For example, testing whether two values are equal is always `false`, even when the two bit patterns are exactly the same. An interesting curiosity is that f32 has approximately 4.2 million ( $\sim 2^{22}$ ) bit patterns that represent NAN.

The following listing provides the code that implements nonspecial cases.

#### Listing 5.9 Isolating and decoding the mantissa from an f32

```

1 let n: f32 = 42.42;
2 let n_bits: u32 = n.to_bits();
3 let mut mantissa: f32 = 1.0;
4
5 for i in 0..23 {
6     let mask = 1 << i;
7     let one_at_bit_i = n_bits & mask;
8     if one_at_bit_i != 0 {
9         let i_ = i as f32;
10        let weight = 2_f32.powf( i_ - 23.0 );
11        mantissa += weight;
12    }
13 }
```

Repeating that process slowly:

- 1 Start with an f32 value:

```
1 let n: f32 = 42.42;
```

- 2 Cast f32 as u32 to allow for bit manipulation:

```
2 let n_bits: u32 = n.to_bits();
```

- 3 Create a mutable f32 value initialized to 1.0 ( $2^{-0}$ ). This represents the weight of the implicit 24th bit:

```
3 let mut mantissa: f32 = 1.0;
```

- 4 Iterate through the fractional bits of the mantissa, adding those bit's defined values to the mantissa variable:

```
5 for i in 0..23 {
6     let mask = 1 << i;
7     let one_at_bit_i = n_bits & mask;
8     if one_at_bit_i != 0 {
9         let i_ = i as f32;
10        let weight = 2_f32.powf( i_ - 23.0 );
11        mantissa += weight;
12    }
13 }
```

- a Iterate from 0 to 23 with a temporary variable *i* assigned to the iteration number:

```
5 for i in 0..23 {
```

- b Create a bit mask with the iteration number as the bit allowed to pass through and assign the result to *mask*. For example, when *i* equals 5, the bit mask is 0b00000000\_00000000\_00000000\_00100000:

```
6 let mask = 1 << i;
```

- c Use *mask* as a filter against the bits from the original number stored as *n\_bits*. When the original number's bit at position *i* is non-zero, *one\_at\_bit\_i* will be assigned to a non-zero value:

```
7 let one_at_bit_i = n_bits & mask;
```

- d If *one\_at\_bit\_i* is non-zero, then proceed:

```
8 if one_at_bit_i != 0 {
```

- e Calculate the weight of the bit at position *i*, which is  $2^{-i}$ :

```
9 let i_ = i as f32;
10 let weight = 2_f32.powf( i_ - 23.0 );
```

- f Add the weight to *mantissa* in place:

```
11 mantissa += weight;
```

### Parsing Rust's floating-point literals is harder than it looks

Rust's numbers have methods. To return the nearest integer to 1.2, Rust uses the method `1.2_f32.ceil()` rather than the function call `ceil(1.2)`. While often convenient, this can cause some issues when the compiler parses your source code.

For example, unary minus has lower precedence than method calls, which means unexpected mathematical errors can occur. It is often helpful to use parentheses to make your intent clear to the compiler. To calculate  $-1^0$ , wrap 1.0 in parentheses

```
(-1.0_f32).powf(0.0)
```

rather than

```
-1.0_f32.powf(0.0)
```

which is interpreted as  $-(1^0)$ . Because both  $-1^0$  and  $-(1^0)$  are mathematically valid, Rust will not complain when parentheses are omitted.

#### 5.4.5 Dissecting a floating-point number

As mentioned at the start of section 5.4, floating-point numbers are a container format with three fields. Sections 5.4.1–5.4.3 have given us the tools that we need to extract each of these fields. Let's put those to work.

Listing 5.10 does a round trip. It extracts the fields from the number 42.42 encoded as an f32 into individual parts, then assembles these again to create another number. To convert the bits within a floating-point number to a number, there are three tasks:

- 1 Extract the bits of those values from the container (`to_parts()` on lines 1–26)
- 2 Decode each value from its raw bit pattern to its actual value (`decode()` on lines 28–47)
- 3 Perform the arithmetic to convert from scientific notation to an ordinary number (`from_parts()` on lines 49–55)

When we run listing 5.10, it provides two views of the internals of the number 42.42 encoded as an f32:

field	as bits	as real number
sign	0	1
exponent	10000100	32
mantissa	01010011010111000010100	1.325625

In listing 5.10, `deconstruct_f32()` extracts each field of a floating-point value with bit manipulation techniques. `decode_f32_parts()` demonstrates how to convert those fields to the relevant number. The `f32_from_parts()` method combines these to create a single decimal number. The source for this file is located in `ch5/ch5-visualizing-f32.rs`.

## Listing 5.10 Deconstructing a floating-point value

```

1 const BIAS: i32 = 127;           | Similar constants are accessible
2 const RADIX: f32 = 2.0;          | via the std::f32 module.
3
4 fn main() {
5     let n: f32 = 42.42;          | main() lives happily at
6                               | the beginning of a file.
7     let (sign, exp, frac) = to_parts(n);
8     let (sign_, exp_, mant) = decode(sign, exp, frac);
9     let n_ = from_parts(sign_, exp_, mant);
10
11    println!("{} -> {}", n, n_);
12    println!("field | as bits | as real number");
13    println!("sign | {:01b} | {}", sign, sign_);
14    println!("exponent | {:08b} | {}", exp, exp_);
15    println!("mantissa | {:023b} | {}", frac, mant);
16 }
17
18 fn to_parts(n: f32) -> (u32, u32, u32) {
19     let bits = n.to_bits();
20
21     let sign      = (bits >> 31) & 1;
22     let exponent = (bits >> 23) & 0xff;
23     let fraction = bits & 0xffffffff;
24
25     (sign, exponent, fraction)
26 }
27
28 fn decode(
29     sign: u32,
30     exponent: u32,
31     fraction: u32
32 ) -> (f32, f32, f32) {
33     let signed_1 = (-1.0_f32).powf(sign as f32);
34
35     let exponent = (exponent as i32) - BIAS;
36     let exponent = RADIX.powf(exponent as f32);
37
38     for i in 0..23 {
39         let mask = 1 << i;
40         let one_at_bit_i = fraction & mask;
41         if one_at_bit_i != 0 {
42             let i_ = i as f32;
43             let weight = 2_f32.powf(i_ - 23.0);
44             mantissa += weight;
45         }
46     }
47
48     (signed_1, exponent, mantissa)
49 }
50
51 fn from_parts(        | Cheats a bit by using f32 values
52     sign: f32,            | in intermediate steps. Hopefully,
53     exponent: f32,          | it is a forgivable offense.
54     mantissa: f32
55 )

```

**Decodes the mantissa using the logic described in section 5.4.4**

**Similar constants are accessible via the std::f32 module.**

**main() lives happily at the beginning of a file.**

**Strips 31 unwanted bits away by shifting these nowhere, leaving only the sign bit**

**Filters out the top bit with a logical AND mask, then strips 23 unwanted bits away**

**Retains only the 23 least significant bits via an AND mask**

**The mantissa part is called a fraction here as it becomes the mantissa once it's decoded.**

**Converts the sign bit to 1.0 or -1.0 (-sign). Parentheses are required around -1.0\_f32 to clarify operator precedence as method calls rank higher than a unary minus.**

**exponent must become an i32 in case subtracting the BIAS results in a negative number; then it needs to be cast as a f32 so that it can be used for exponentiation.**

**Cheats a bit by using f32 values in intermediate steps. Hopefully, it is a forgivable offense.**

```

54     mantissa: f32,
55 ) -> f32 {
56     sign * exponent * mantissa
57 }

```

Understanding how to unpack bits from bytes means that you'll be in a much stronger position when you're faced with interpreting untyped bytes flying in from the network throughout your career.

## 5.5 Fixed-point number formats

In addition to representing decimal numbers with floating-point formats, fixed point is also available. These can be useful for representing fractions and are an option for performing calculations on CPUs without a floating point unit (FPU), such as microcontrollers. Unlike floating-point numbers, the decimal place does not move to dynamically accommodate different ranges. In our case, we'll be using a fixed-point number format to compactly represent values between  $-1\dots=1$ . Although it loses accuracy, it saves significant space.<sup>2</sup>

The *Q format* is a fixed-point number format that uses a single byte.<sup>3</sup> It was created by Texas Instruments for embedded computing devices. The specific version of the Q format that we will implement is called *Q7*. This indicates that there are 7 bits available for the represented number plus 1 sign bit. We'll disguise the decimal nature of the type by hiding the 7 bits within an *i8*. That means that the Rust compiler will be able to assist us in keeping track of the value's sign. We will also be able to derive traits such as *PartialEq* and *Eq*, which provide comparison operators for our type, for free.

The following listing, an extract from listing 5.14, provides the type's definition. You'll find the source in ch5/ch5-q/src/lib.rs.

### Listing 5.11 Definition of the Q7 format

```

1 #[derive(Debug, Clone, Copy, PartialEq, Eq)]
2 pub struct Q7(i8);      ← Q7 is a tuple struct.

```

A struct created from unnamed fields (for example, *Q7 (i8)*), is known as a *tuple struct*. It offers a concise notation when the fields are not intended to be accessed directly. While not shown in listing 5.11, tuple structs can include multiple fields by adding further types separated by commas. As a reminder, the `#[derive(...)]` block asks Rust to implement several traits on our behalf:

---

<sup>2</sup> This practice is known as *quantizing the model* in the machine learning community.

<sup>3</sup> *Q*, often written as  $\mathbb{Q}$  (this style is called *blackboard bold*), is the mathematical symbol for the so-called rational numbers. Rational numbers are numbers that can be represented as a fraction of two integers, such as  $1/3$ .

- Debug—Used by the `println!()` macro (and others); allows `Q7` to be converted to a string by the `{ :? }` syntax.
- Clone—Enables `Q7` to be duplicated with a `.clone()` method. This can be derived because `i8` implements the `Clone` trait.
- Copy—Enables cheap and implicit duplications where ownership errors might otherwise occur. Formally, this changes `Q7` from a type that uses *move semantics* to one that uses *copy semantics*.
- PartialEq—Enables `Q7` values to be compared with the equality operator (`==`).
- Eq—Indicates to Rust that all possible `Q7` values can be compared against any other possible `Q7` value.

`Q7` is intended as a compact storage and data transfer type only. Its most important role is to convert to and from floating-point types. The following listing, an extract from listing 5.14, shows the conversion to `f64`. The source for this listing is in `ch5/ch5-q/src/lib.rs`.

### Listing 5.12 Converting from f64 to Q7

```

4 impl From<f64> for Q7 {
5     fn from(n: f64) -> Self {
6         // assert!(n >= -1.0);
7         // assert!(n <= 1.0);
8         if n >= 1.0 {           ←
9             Q7(127)           Coerces any out-of-
10            } else if n <= -1.0 { ← bounds input to fit
11                Q7(-128)
12            } else {
13                Q7((n * 128.0) as i8)
14            }
15        }
16    }
17
18 impl From<Q7> for f64 {
19     fn from(n: Q7) -> f64 {
20         (n.0 as f64) * 2_f64.powf(-7.0)   ←
21     }
22 }
```

Equivalent to the iteration approach taken in section 5.3.5.

The two `impl From<T> for U` blocks in listing 5.12 explain to Rust how to convert from type `T` to type `U`. In the listing

- Lines 4 and 18 introduce the `impl From<T> for U` blocks. The `std::convert::From` trait is included in local scope as `From`, which is part of the standard prelude. It requires type `U` to implement `from()` that takes a `T` value as its sole argument.

- Lines 6–7 present an option for handling unexpected input data: crashes. It is not used here, but is available to you in your own projects.
- Lines 13–16 truncate out-of-bounds input. For our purposes, we know that out-of-bounds input will not occur and so accept the risk of losing information.

**TIP** Conversions using the `From` trait should be mathematically equivalent. For type conversions that can fail, consider implementing the `std::convert::TryFrom` trait instead.

We can also quickly implement converting from `f32` to `Q7` using the `From<f64>` implementation that we've just seen. The following listing, an extract from listing 5.14, shows this conversion. Its source is in `ch5/ch5-q/src/lib.rs`.

### Listing 5.13 Converting from `f32` to `Q7` via `f64`

```

22 impl From<f32> for Q7 {
23     fn from(n: f32) -> Self {
24         Q7::from(n as f64) ← By design, it's safe to convert from f32 to f64.
25     }                                         A number that can be represented in 32 bits,
26 }                                         it can also be represented in 64 bits.
27
28 impl From<Q7> for f32 {
29     fn from(n: Q7) -> f32 {
30         f64::from(n) as f32 ← Generally, converting an f64 into a f32 risks a
31     }                                         loss of precision. In this application, that risk
32 }                                         doesn't apply as we only have numbers
                                            between -1 and 1 to convert from.

```

Now, we've covered both floating-point types. But how do we know that the code that we've written actually does what we intend? And how do we test what we've written? As it happens, Rust has excellent support for unit testing via cargo.

The `Q7` code that you've seen is available as a complete listing. But first, to test the code, enter the root directory of the crate and run `cargo test`. The following shows the output from listing 5.14 (the complete listing):

```

$ cargo test
Compiling ch5-q v0.1.0 (file:///path/to/ch5/ch5-q)
Finished dev [unoptimized + debuginfo] target(s) in 2.86 s
Running target\debug\deps\ch5_q-013c963f84b21f92

running 3 tests
test tests::f32_to_q7 ... ok
test tests::out_of_bounds ... ok
test tests::q7_to_f32 ... ok

```

```
test result: ok. 3 passed; 0 failed; 0 ignored; 0 measured; 0 filtered out

Doc-tests ch5-q

running 0 tests

test result: ok. 0 passed; 0 failed; 0 ignored; 0 measured; 0 filtered out
```

The following listing implements the Q7 format and its conversion to and from f32 and f64 types. You'll find the source for this listing in ch5/ch5-q/src/lib.rs.

#### Listing 5.14 Full code implementation of the Q7 format

```

1 #[derive(Debug,Clone,Copy,PartialEq,Eq)]
2 pub struct Q7(i8);
3
4 impl From<f64> for Q7 {
5     fn from (n: f64) -> Self {
6         if n >= 1.0 {
7             Q7(127)
8         } else if n <= -1.0 {
9             Q7(-128)
10        } else {
11            Q7((n * 128.0) as i8)
12        }
13    }
14 }
15
16 impl From<Q7> for f64 {
17     fn from(n: Q7) -> f64 {
18         (n.0 as f64) * 2f64.powf(-7.0)
19     }
20 }
21
22 impl From<f32> for Q7 {
23     fn from (n: f32) -> Self {
24         Q7::from(n as f64)
25     }
26 }
27
28 impl From<Q7> for f32 {
29     fn from(n: Q7) -> f32 {
30         f64::from(n) as f32
31     }
32 }
33 }
```

```

34 #[cfg(test)]
35 mod tests {           ← Defines a submodule within this file
36     use super::*;

37     #[test]
38     fn out_of_bounds() {
39         assert_eq!(Q7::from(10.), Q7::from(1.));
40         assert_eq!(Q7::from(-10.), Q7::from(-1.));
41     }
42
43     #[test]
44     fn f32_to_q7() {
45         let n1: f32 = 0.7;
46         let q1 = Q7::from(n1);
47
48         let n2 = -0.4;
49         let q2 = Q7::from(n2);
50
51         let n3 = 123.0;
52         let q3 = Q7::from(n3);
53
54         assert_eq!(q1, Q7(89));
55         assert_eq!(q2, Q7(-51));
56         assert_eq!(q3, Q7(127));
57     }
58
59     #[test]
60     fn q7_to_f32() {
61         let q1 = Q7::from(0.7);
62         let n1 = f32::from(q1);
63         assert_eq!(n1, 0.6953125);
64
65         let q2 = Q7::from(n1);
66         let n2 = f32::from(q2);
67         assert_eq!(n1, n2);
68     }
69 }
```

### A brief look at Rust's module system

Rust includes a powerful and ergonomic module system. To keep the examples simple, however, this book does not make heavy use of its system. But here are some basic guidelines:

- Modules are combined into crates.
- Modules can be defined by a project's directory structure. Subdirectories under `src/` become a module when that directory contains a `mod.rs` file.
- Modules can also be defined within a file with the `mod` keyword.
- Modules can be nested arbitrarily.
- All members of a module including its submodules are *private* by default. Private items can be accessed within the module and any of the module's descendants.

- Prefix things that you want to make public with the `pub` keyword. The `pub` keyword has some specialized cases:
  - a `pub(crate)` exposes an item to other modules within the crate.
  - b `pub(super)` exposes an item to the parent module.
  - c `pub(in path)` exposes an item to a module within `path`.
  - d `pub(self)` explicitly keeps the item private.
- Bring items from other modules into local scope with the `use` keyword.

## 5.6

## Generating random probabilities from random bytes

Here is an interesting exercise to test the knowledge that you have developed over the preceding pages. Imagine that you have a source of random bytes (`u8`), and you want to convert one of those into a floating-point (`f32`) value between 0 and 1. Naively interpreting the incoming bytes as `f32/f64` via `mem::transmute` results in massive variations in scale. The following listing demonstrates the division operation that generates an `f32` value that lies between 0 and 1 from an arbitrary input byte.

**Listing 5.15 Generating f32 values in interval [0,1] from a u8 with division**

```
fn mock_rand(n: u8) -> f32 {
    (n as f32) / 255.0
}
```

255 is the maximum value  
that `u8` can represent.

As division is a slow operation, perhaps there is something faster than simply dividing by the largest value that a byte can represent. Perhaps it's possible to assume a constant exponent value, then shift the incoming bits into the mantissa, such that these would form a range between 0 and 1. Listing 5.16 with bit manipulation is the best result that I could achieve.

With an exponent of  $-1$  represented as `0b01111110` (126 in base 10), the source byte achieves a range of 0.5 to 0.998. That can be normalized to 0.0 to 0.996 with subtraction and multiplication. But is there a better way to do this?

**Listing 5.16 Generating f32 values in interval [0,1] from a u8**

```
1 fn mock_rand(n: u8) -> f32 {
2
3     let base: u32 = 0b0_01111110_000000000000000000000000;
4
5     let large_n = (n as u32) << 15;
6
7     let f32_bits = base | large_n;
8
9     let m = f32::from_bits(f32_bits);
10
11    2.0 * (m - 0.5)
12 }
```

Aligns the input byte `n` to 32 bits,  
then increases its value by shifting  
its bits 15 places to the left

Takes a bitwise OR, merging  
the base with the input byte

Normalizes the  
output range

Interprets `f32_bits` (which  
is type `u32`) as an `f32`

As a complete program, you can incorporate `mock_rand()` from listing 5.16 into a test program fairly easily. Listing 5.17 (`ch5/ch5-u8-to-mock-rand.rs`) generates an `f32` value that lies between 0 and 1 from an arbitrary input byte without division. Here's its output:

```
max of input range: 11111111 -> 0.99609375
mid of input range: 01111111 -> 0.49609375
min of input range: 00000000 -> 0
```

#### Listing 5.17 Generating an `f32` value without division

```
1 fn mock_rand(n: u8) -> f32 {
2     let base: u32 = 0b0_0111110_000000000000000000000000;
3     let large_n = (n as u32) << 15;
4     let f32_bits = base | large_n;
5     let m = f32::from_bits(f32_bits);
6     2.0 * (m - 0.5)
7 }
8
9 fn main() {
10    println!("max of input range: {:08b} -> {:?}", 0xff, mock_rand(0xff));
11    println!("mid of input range: {:08b} -> {:?}", 0x7f, mock_rand(0x7f));
12    println!("min of input range: {:08b} -> {:?}", 0x00, mock_rand(0x00));
13 }
```

## 5.7 Implementing a CPU to establish that functions are also data

One of the fairly mundane, yet utterly intriguing details about computing is that instructions are also just numbers. Operations and the data that is being operated on share the same encoding. This means that, as a general computing device, your computer can emulate other computers' *instruction sets* by emulating those in software. While we cannot pull apart a CPU to see how it works, we can construct one with code.

After working through this section, you will learn how a computer operates at a fundamental level. This section shows how functions operate and what the term *pointer* means. We won't have an assembly language; we'll actually be programming directly in hex. This section also introduces you to another term you may have heard of in passing: *the stack*.

We'll implement a subset of a system called CHIP-8, which was available to consumers in the 1970s. CHIP-8 was supported by a number of manufacturers, but it was fairly primitive even by the standards of that time. (It was created to write games rather than for commercial or scientific applications.)

One device that used the CHIP-8 CPU was the COSMAC VIP. It had a single-color display with a resolution of 64x32 (0.0002 megapixels), 2 KB RAM, 1.76 MHz CPU, and sold for \$275 USD. Oh, and you needed to assemble the computer yourself. It also contained games programmed by the world's first female game developer, Joyce Weisbecker.

### 5.7.1 CPU RIA/1: The Adder

We'll build our understanding by starting with a minimal core. Let's first construct an emulator that only supports a single instruction: addition. To understand what's happening within listing 5.22 later in this section, there are three main things to learn:

- Becoming familiar with new terminology
- How to interpret opcodes
- Understanding the main loop

#### TERMS RELATED TO CPU EMULATION

Dealing with CPUs and emulation involves learning some terms. Take a moment to look at and understand the following:

- *An operation (often shortened to "op") refers to procedures that are supported natively by the system.* You might also encounter equivalent phrases such as *implemented in hardware* or *intrinsic operation* as you explore further.
- *Registers are containers for data that the CPU accesses directly.* For most operations, operands must be moved to registers for an operation to function. For the CHIP-8, each register is a u8 value.
- *An opcode is a number that maps to an operation.* On the CHIP-8 platform, opcodes include both the operation and the operands' registers.

#### DEFINING THE CPU

The first operation that we want to support is addition. The operation takes two registers ( $x$  and  $y$ ) as operands and adds the value stored in  $y$  to  $x$ . To implement this, we'll use the minimal amount of code possible, as the following listing shows. Our initial CPU contains only two registers and the space for a single opcode.

#### Listing 5.18 Definition of the CPU used in listing 5.22

```
struct CPU {
    current_operation: u16,           ← All CHIP-8 opcodes
    registers: [u8; 2],               ← are u16 values.
}
```

These two registers are sufficient for addition.

So far, the CPU is inert. To perform addition, we'll need to take the following steps, but there is no ability to store data in memory as yet:

- 1 Initialize a CPU.
- 2 Load u8 values into registers.
- 3 Load the addition opcode into `current_operation`.
- 4 Perform the operation.

#### LOADING VALUES INTO REGISTERS

The process for booting up the CPU consists of writing to the fields of the CPU struct. The following listing, an extract from listing 5.22, shows the CPU initialization process.

**Listing 5.19 Initializing the CPU**

```

32 fn main() {
33     let mut cpu = CPU {
34         current_operation: 0,
35         registers: [0; 2],
36     };
37
38     cpu.current_operation = 0x8014;
39     cpu.registers[0] = 5;           | Registers can only
40     cpu.registers[1] = 10;          | hold u8 values.

```

Line 38 from listing 5.19 is difficult to interpret without context. The constant `0x8014` is the opcode that the CPU will interpret. To decode it, split it into four parts:

- 8 signifies that the operation involves two registers.
- 0 maps to `cpu.registers[0]`.
- 1 maps to `cpu.registers[1]`.
- 4 indicates addition.

**UNDERSTANDING THE EMULATOR'S MAIN LOOP**

Now that we've loaded the data, the CPU is almost able to do some work. The `run()` method performs the bulk of our emulator's work. Using the following steps, it emulates CPU cycles:

- 1 Reads the opcode (eventually, from memory)
- 2 Decodes instruction
- 3 Matches decoded instruction to known opcodes
- 4 Dispatches execution of the operation to a specific function

The following listing, an extract from listing 5.22, shows the first functionality being added to the emulator.

**Listing 5.20 Reading the opcode**

```

6 impl CPU {
7     fn read_opcode(&self) -> u16 {
8         self.current_operation
9     }
10
11    fn run(&mut self) {
12        // loop {           | read_opcode() becomes more
13            let opcode = self.read_opcode(); | complex when we introduce
14
15            let c = ((opcode & 0xF000) >> 12) as u8; | reading from memory.
16            let x = ((opcode & 0x0F00) >> 8) as u8;
17            let y = ((opcode & 0x00F0) >> 4) as u8;
18            let d = ((opcode & 0x000F) >> 0) as u8;
19
20            match (c, x, y, d) {
21                (0x8, _, _, 0x4) => self.add_xy(x, y),

```

Avoids running this code in a loop for now

The opcode decoding process is explained fully in the next section.

Dispatches execution to the hardware circuit responsible for performing it

```

22         } -=> todo! ("opcode { :04x}", opcode),
23     }
24 } // }           ↪ A full emulator
25 }             contains several
26                   dozen operations.
27 fn add_xy(&mut self, x: u8, y: u8) {
28     self.registers[x as usize] += self.registers[y as usize];
29 }
30 }
```

### HOW TO INTERPRET CHIP-8 OPCODES

It is important for our CPU to be able to interpret its opcode (0x8014). This section provides a thorough explanation of the process used in the CHIP-8 and its naming conventions.

CHIP-8 opcodes are `u16` values made up of 4 nibbles. A *nibble* is half of a byte. That is, a nibble is a 4-bit value. Because there isn't a 4-bit type in Rust, splitting the `u16` values into those parts is fiddly. To make matters more complicated, CHIP-8 nibbles are often recombined to form either 8-bit or 12-bit values depending on context.

To simplify talking about the parts of each opcode, let's introduce some standard terminology. Each opcode is made up of two bytes: the *high byte* and the *low byte*. And each byte is made up of two nibbles, the *high nibble* and the *low nibble*, respectively. Figure 5.2 illustrates each term.




Figure 5.2 Terms used to refer to parts of CHIP-8 opcodes

Documentation manuals for the CHIP-8 introduce several variables, including *kk*, *nnn*, *x*, and *y*. Table 5.2 explains their role, location, and width.

Table 5.2 Variables used within CHIP-8 opcode descriptions

Variable	Bit length	Location	Description
<i>n</i> *	4	low byte, low nibble	Number of bytes
<i>x</i>	4	high byte, low nibble	CPU register
<i>y</i>	4	low byte, high nibble	CPU register
<i>c</i> †	4	high byte, high nibble	Opcode group
<i>d</i> ‡*	4	low byte, low nibble	Opcode subgroup
<i>kk</i> ‡	8	low byte, both nibbles	Integer

Table 5.2 Variables used within CHIP-8 opcode descriptions (continued)

Variable	Bit length	Location	Description
nnn <sup>*</sup>	12	high byte, low nibble and low byte, both nibbles	Memory address

\* n and d occupy the same location but are used in mutually exclusive contexts.

<sup>†</sup> The variable names c and d are used within this book but not in other CHIP-8 documentation.

<sup>\*</sup> Used in CPU RIA/3 (listing 5.29).

There are three main forms of opcodes, as illustrated in figure 5.3. The decoding process involves matching on the high nibble of the first byte and then applying one of three strategies.




Figure 5.3 CHIP-8 opcodes are decoded in multiple ways. Which to use depends on the value of the leftmost nibble.

To extract nibbles from bytes, we'll need to use the right shift (`>>`) and logical AND (`&`) bitwise operations. These operations were introduced in section 5.4, especially in sections 5.4.1–5.4.3. The following listing demonstrates applying these bitwise operations to the current problem.

#### Listing 5.21 Extracting variables from an opcode

```
fn main() {
    let opcode: u16 = 0x71E4;

    let c = (opcode & 0xF000) >> 12;
    let x = (opcode & 0x0F00) >> 8;
    let y = (opcode & 0x00F0) >> 4;
    let d = (opcode & 0x000F) >> 0;
```

Select single nibbles with the **AND operator** (`&`) to filter bits that should be retained, then shift to move the bits to the lowest significant place. Hexadecimal notation is convenient for these operations as each hexadecimal digit represents 4 bits. A `0xF` value selects all bits from a nibble.

```

assert_eq!(c, 0x7);
assert_eq!(x, 0x1);
assert_eq!(y, 0xE);
assert_eq!(d, 0x4); | The four nibbles from opcode are
                     | available as individual variables
                     | after processing.

let nnn = opcode & 0xFFFF;
let kk = opcode & 0x00FF; | Select multiple nibbles by
                         | increasing the width of the
                         | filter. For our purposes,
                         | shifting bits rightward is
                         | unnecessary.

assert_eq!(nnn, 0x1E4);
assert_eq!(kk, 0xE4);
}

```

We're now able to decode the instructions. The next step is actually executing these.

## 5.7.2 Full code listing for CPU RIA/1: The Adder

The following listing is the full code for our proto-emulator, the Adder. You'll find its source in ch5/ch5-cpu1/src/main.rs.

**Listing 5.22 Implementing the beginnings of CHIP-8 emulator**

```

1 struct CPU {
2     current_operation: u16,
3     registers: [u8; 2],
4 }
5
6 impl CPU {
7     fn read_opcode(&self) -> u16 {
8         self.current_operation
9     }
10
11    fn run(&mut self) {
12        // loop {
13            let opcode = self.read_opcode();
14
15            let c = ((opcode & 0xF000) >> 12) as u8;
16            let x = ((opcode & 0x0F00) >> 8) as u8;
17            let y = ((opcode & 0x00F0) >> 4) as u8;
18            let d = ((opcode & 0x000F) >> 0) as u8;
19
20            match (c, x, y, d) {
21                (0x8, _, _, 0x4) => self.add_xy(x, y),
22                _ => todo!("opcode {:04x}", opcode),
23            }
24        // }
25    }
26
27    fn add_xy(&mut self, x: u8, y: u8) {
28        self.registers[x as usize] += self.registers[y as usize];
29    }
30
31
32 fn main() {
33     let mut cpu = CPU {

```

```

34     current_operation: 0,
35     registers: [0; 2],
36   };
37
38   cpu.current_operation = 0x8014;
39   cpu.registers[0] = 5;
40   cpu.registers[1] = 10;
41
42   cpu.run();
43
44   assert_eq!(cpu.registers[0], 15);
45
46   println!("5 + 10 = {}", cpu.registers[0]);
47 }
```

The Adder doesn't do much. When executed, it prints the following line:

```
5 + 10 = 15
```

### 5.7.3 CPU RIA/2: The Multiplier

CPU RIA/1 can execute a single instruction: addition. CPU RIA/2, the Multiplier, can execute several instructions in sequence. The Multiplier includes RAM, a working main loop, and a variable that indicates which instruction to execute next that we'll call `position_in_memory`. Listing 5.26 makes the following substantive changes to listing 5.22:

- Adds 4 KB of memory (line 8).
- Includes a fully-fledged main loop and stopping condition (lines 14–31).

At each step in the loop, memory at `position_in_memory` is accessed and decoded into an opcode. `position_in_memory` is then incremented to the next memory address, and the opcode is executed. The CPU continues to run forever until the stopping condition (an opcode of 0x0000) is encountered.

- Removes the `current_instruction` field of the CPU struct, which is replaced by a section of the main loop that decodes bytes from memory (lines 15–17).
- Writes the opcodes into memory (lines 51–53).

#### EXPANDING THE CPU TO SUPPORT MEMORY

We need to implement some modifications to make our CPU more useful. To start, the computer needs memory.

Listing 5.23, an extract from listing 5.26, provides CPU RIA/2's definition. CPU RIA/2 contains general-purpose registers for calculations (`registers`) and one special-purpose register (`position_in_memory`). For convenience, we'll also include the system's memory within the CPU struct itself as the `memory` field.

#### Listing 5.23 Defining a CPU struct

```

1 struct CPU {
2   registers: [u8; 16],
```

```

3     position_in_memory: usize,
4     memory: [u8; 0x1000],
5 }
```

Using `usize` rather than `u16` diverges from the original spec, but we'll use `usize` as Rust allows these to be used for indexing.

Some features of the CPU are quite novel:

- Having 16 registers means that a single hexadecimal number (0 to F) can address those. That allows all opcodes to be compactly represented as `u16` values.
- The CHIP-8 only has 4096 bytes of RAM (`0x1000` in hexadecimal). This allows CHIP-8's equivalent of a `usize` type to only be 12 bits wide:  $2^{12} = 4,096$ . Those 12 bits become the `nnn` variable discussed earlier.

*Rust in Action* deviates from standard practice in two ways:

- What we call the “position in memory” is normally referred to as the “program counter.” As a beginner, it can be difficult to remember what the program counter’s role is. So instead, this book uses a name that reflects its usage.
- Within the CHIP-8 specification, the first 512 bytes (`0x100`) are reserved for the system, while other bytes are available for programs. This implementation relaxes that restriction.

### READING OPCODES FROM MEMORY

With the addition of `memory` within the CPU, the `read_opcode()` method requires updating. The following listing, an extract from listing 5.26, does that for us. It reads an opcode from memory by combining two `u8` values into a single `u16` value.

**Listing 5.24** Reading an opcode from memory

```

8 fn read_opcode(&self) -> u16 {
9     let p = self.position_in_memory;
10    let op_byte1 = self.memory[p] as u16;
11    let op_byte2 = self.memory[p + 1] as u16;
12
13    op_byte1 << 8 | op_byte2
```

To create a `u16` opcode, we combine two values from memory with the logical OR operation. These need to be cast as `u16` to start with; otherwise, the left shift sets all of the bits to 0.

### HANDLING INTEGER OVERFLOW

Within the CHIP-8, we use the last register as a *carry flag*. When set, this flag indicates that an operation has overflowed the `u8` register size. The following listing, an extract from listing 5.26, shows how to handle this overflow.

**Listing 5.25** Handling overflow in CHIP-8 operations

```

34 fn add_xy(&mut self, x: u8, y: u8) {
35     let arg1 = self.registers[x as usize];
36     let arg2 = self.registers[y as usize];
37
38     let (val, overflow) = arg1.overflowing_add(arg2);
39     self.registers[x as usize] = val;
```

The `overflowing_add()` method for `u8` returns `(u8, bool)`. The `bool` is true when overflow is detected.

```

41     if overflow {
42         self.registers[0xF] = 1;
43     } else {
44         self.registers[0xF] = 0;
45     }
46 }
```

### FULL CODE LISTING FOR CPU RIA/2: THE MULTIPLIER

The following listing shows the complete code for our second working emulator, the Multiplier. You'll find the source for this listing in ch5/ch5-cpu2/src/main.rs.

#### Listing 5.26 Enabling the emulator to process multiple instructions

```

1 struct CPU {
2     registers: [u8; 16],
3     position_in_memory: usize,
4     memory: [u8; 0x1000],
5 }
6
7 impl CPU {
8     fn read_opcode(&self) -> u16 {
9         let p = self.position_in_memory;
10        let op_byte1 = self.memory[p] as u16;
11        let op_byte2 = self.memory[p + 1] as u16;
12
13        op_byte1 << 8 | op_byte2
14    }
15
16    fn run(&mut self) {
17        loop {                                ← Continues execution
18            let opcode = self.read_opcode();      ← beyond processing a
19            self.position_in_memory += 2;          ← single instruction
20
21            let c = ((opcode & 0xF000) >> 12) as u8;
22            let x = ((opcode & 0x0F00) >> 8) as u8;
23            let y = ((opcode & 0x00F0) >> 4) as u8;
24            let d = ((opcode & 0x000F) >> 0) as u8;
25
26            match (c, x, y, d) {
27                (0, 0, 0, 0) => { return; },           ← Increments
28                (0x8, _, _, 0x4) => self.add_xy(x, y),   ← position_in_memory to
29                                     => todo!("opcode {:04x}", opcode),       ← point to the next instruction
30            } -
31        }                                     ← Short-circuits the function
32    }                                         ← to terminate execution
33
34    fn add_xy(&mut self, x: u8, y: u8) {
35        let arg1 = self.registers[x as usize];
36        let arg2 = self.registers[y as usize];
37
38        let (val, overflow) = arg1.overflowing_add(arg2);
39        self.registers[x as usize] = val;
40
41        if overflow {
```

```

42         self.registers[0xF] = 1;
43     } else {
44         self.registers[0xF] = 0;
45     }
46 }
47 }
48
49 fn main() {
50     let mut cpu = CPU {
51         registers: [0; 16],
52         memory: [0; 4096],
53         position_in_memory: 0,
54     };
55
56     cpu.registers[0] = 5;
57     cpu.registers[1] = 10;
58     cpu.registers[2] = 10;           | initializes a few
59     cpu.registers[3] = 10;           | registers with values
60
61     let mem = &mut cpu.memory;
62     mem[0] = 0x80; mem[1] = 0x14;    | loads opcode 0x8014, which
63     mem[2] = 0x80; mem[3] = 0x24;    | adds register 1 to register 0
64     mem[4] = 0x80; mem[5] = 0x34;    | loads opcode 0x8024, which
65                               | adds register 2 to register 0
66     cpu.run();                   | loads opcode 0x8034. which
67                               | adds register 3 to register 0
68     assert_eq!(cpu.registers[0], 35);
69
70     println!("5 + 10 + 10 + 10 = {}", cpu.registers[0]);
71 }

```

When executed, CPU RIA/2 prints its impressive mathematical calculations:

```
5 + 10 + 10 + 10 = 35
```

#### 5.7.4 CPU RIA/3: The Caller

We have nearly built all of the emulator machinery. This section adds the ability for you to call functions. There is no programming language support, however, so any programs still need to be written in binary. In addition to implementing functions, this section validates an assertion made at the start—functions are also data.

##### **EXPANDING THE CPU TO INCLUDE SUPPORT FOR A STACK**

To build functions, we need to implement some additional opcodes. These are as follows:

- The CALL opcode (0x2nnn, where nnn is a memory address) sets position\_in\_memory to nnn, the address of the function.
- The RETURN opcode (0x00EE) sets position\_in\_memory to the memory address of the previous CALL opcode.

To enable these to opcodes to work together, the CPU needs to have some specialized memory available for storing addresses. This is known as *the stack*. Each CALL opcode

adds an address to the stack by incrementing the stack pointer and writing *nnn* to that position in the stack. Each RETURN opcode removes the top address by decrementing the stack pointer. The following listing, an extract from listing 5.29, provides the details to emulate the CPU.

### Listing 5.27 Including a stack and stack pointer

```

1 struct CPU {
2     registers: [u8; 16],
3     position_in_memory: usize,
4     memory: [u8; 4096],
5     stack: [u16; 16],           ← The stack's maximum height is 16.
6     stack_pointer: usize,      ← After 16 nested function calls, the
7 }                           ← program encounters a stack overflow.
                                Giving the stack_pointer type usize makes
                                it easier to index values within the stack.

```

#### DEFINING A FUNCTION AND LOADING IT INTO MEMORY

Within computer science, a function is just a sequence of bytes that can be executed by a CPU.<sup>4</sup> CPUs start at the first opcode, then make their way to the end. The next few code snippets demonstrate how it is possible to move from a sequence of bytes, then convert that into executable code within CPU RIA/3.

- 1 Define the function. Our function performs two addition operations and then returns—modest, yet informative. It is three opcodes long. The function’s internals look like this in a notation that resembles assembly language:

```
add_twice:
    0x8014
    0x8014
    0x00EE
```

- 2 Convert opcodes into Rust data types. Translating these three opcodes into Rust’s array syntax involves wrapping them in square brackets and using a comma for each number. The function has now become a [u16;3]:

```
let add_twice: [u16;3] = [
    0x8014,
    0x8014,
    0x00EE,
];
```

We want to be able to deal with one byte in the next step, so we’ll decompose the [u16;3] array further into a [u8;6] array:

```
let add_twice: [u8;6] = [
    0x80, 0x14,
    0x80, 0x14,
    0x00, 0xEE,
];
```

---

<sup>4</sup> The sequence of bytes must also be tagged as executable. The tagging process is explained in section 6.1.4.

- 3 Load the function into RAM. Assuming that we wish to load that function into memory address 0x100, here are two options. First, if we have our function available as a slice, we can copy it across to `memory` with the `copy_from_slice()` method:

```
fn main() {
    let mut memory: [u8; 4096] = [0; 4096];
    let mem = &mut memory;

    let add_twice = [
        0x80, 0x14,
        0x80, 0x14,
        0x00, 0xEE,
    ];

    mem[0x100..0x106].copy_from_slice(&add_twice);

    println!("{:?}", &mem[0x100..0x106]);
}
```

An alternative approach that achieves the same effect within `memory` without requiring a temporary array is to overwrite bytes directly:

```
fn main() {
    let mut memory: [u8; 4096] = [0; 4096];
    let mem = &mut memory;

    mem[0x100] = 0x80; mem[0x101] = 0x14;
    mem[0x102] = 0x80; mem[0x103] = 0x14;
    mem[0x104] = 0x00; mem[0x105] = 0xEE;
    println!("{:?}", &mem[0x100..0x106]);
}
```

The approach taken in the last snippet is exactly what is used within the `main()` function of lines 96–98 of listing 5.29. Now that we know how to load a function into memory, it's time to learn how to instruct a CPU to actually call it.

### IMPLEMENTING THE CALL AND RETURN OPCODES

Calling a function is a three-step process:

- 1 Store the current memory location on the stack.
- 2 Increment the stack pointer.
- 3 Set the current memory location to the intended memory address.

Returning from a function involves reversing the calling process:

- 1 Decrement the stack pointer.
- 2 Retrieve the calling memory address from the stack.
- 3 Set the current memory location to the intended memory address.

The following listing, an extract from listing 5.29, focuses on the `call()` and `ret()` methods.

### Listing 5.28 Adding the `call()` and `ret()` methods

Modifies  
`self.position_in_memory`  
to affect  
jumping to  
that address

```

41 fn call(&mut self, addr: u16) {
42     let sp = self.stack_pointer;
43     let stack = &mut self.stack;
44
45     if sp > stack.len() {
46         panic!("Stack overflow!")
47     }
48
49     stack[sp] = self.position_in_memory as u16; ← Adds the current
50     self.stack_pointer += 1; ← position_in_memory to the
51     self.position_in_memory = addr as usize; ← stack. This memory address
52 } ← is two bytes higher than the
53
54 fn ret(&mut self) {
55     if self.stack_pointer == 0 {
56         panic!("Stack underflow");
57     }
58
59     self.stack_pointer -= 1;
60     let call_addr = self.stack[self.stack_pointer];
61     self.position_in_memory = call_addr as usize; ← Increments self.stack_pointer to
62 } ← prevent self.position_in_memory
          from being overwritten until it
          needs to be accessed again in a
          subsequent return
          Jumps to the position in
          memory where an
          earlier call was made

```

#### FULL CODE LISTING FOR CPU RIA/3: THE CALLER

Now that we have all of the pieces ready, let's assemble those into a working program. Listing 5.29 is able to compute a (hard-coded) mathematical expression. Here's its output:

```
5 + (10 * 2) + (10 * 2) = 45
```

This calculation is made without the source code that you may be used to. You will need to make do with interpreting hexadecimal numbers. To help, figure 5.4 illustrates what happens within the CPU during `cpu.run()`. The arrows reflect the state of the `cpu.position_in_memory` variable as it makes its way through the program.

Listing 5.29 shows our completed emulator for CPU RIA/3, the Caller. You'll find the source code for this listing in `ch5/ch5-cpu3/src/main.rs`.




Figure 5.4 Illustrating the control flow of the function implemented within CPU RIA/3 in listing 5.29

### Listing 5.29 Emulating a CPU that incorporates user-defined functions

```

1 struct CPU {
2     registers: [u8; 16],
3     position_in_memory: usize,
4     memory: [u8; 4096],
5     stack: [u16; 16],
6     stack_pointer: usize,
7 }
8
9 impl CPU {
10    fn read_opcode(&self) -> u16 {
11        let p = self.position_in_memory;
12        let op_byte1 = self.memory[p] as u16;
13        let op_byte2 = self.memory[p + 1] as u16;
14
15        op_byte1 << 8 | op_byte2
16    }
17
18    fn run(&mut self) {
19        loop {
20            let opcode = self.read_opcode();
21            self.position_in_memory += 2;
22
23            let c = ((opcode & 0xF000) >> 12) as u8;
24            let x = ((opcode & 0x0F00) >> 8) as u8;
25            let y = ((opcode & 0x00F0) >> 4) as u8;
26            let d = ((opcode & 0x000F) >> 0) as u8;
27
28            let nnn = opcode & 0xFFFF;
29            // let kk = (opcode & 0x00FF) as u8;
30
31            match (c, x, y, d) {

```

```

32             ( 0,    0,    0) => { return; },
33             ( 0,    0, 0xE, 0xE) => self.ret(),
34             (0x2,    _,    _) => self.call(nnn),
35             (0x8,    _,    _, 0x4) => self.add_xy(x, y),
36                                         => todo!("opcode {:04x}", opcode),
37         }
38     }
39 }
40
41 fn call(&mut self, addr: u16) {
42     let sp = self.stack_pointer;
43     let stack = &mut self.stack;
44
45     if sp > stack.len() {
46         panic!("Stack overflow!")
47     }
48
49     stack[sp] = self.position_in_memory as u16;
50     self.stack_pointer += 1;
51     self.position_in_memory = addr as usize;
52 }
53
54 fn ret(&mut self) {
55     if self.stack_pointer == 0 {
56         panic!("Stack underflow");
57     }
58
59     self.stack_pointer -= 1;
60     let addr = self.stack[self.stack_pointer];
61     self.position_in_memory = addr as usize;
62 }
63
64 fn add_xy(&mut self, x: u8, y: u8) {
65     let arg1 = self.registers[x as usize];
66     let arg2 = self.registers[y as usize];
67
68     let (val, overflow_detected) = arg1.overflowing_add(arg2);
69     self.registers[x as usize] = val;
70
71     if overflow_detected {
72         self.registers[0xF] = 1;
73     } else {
74         self.registers[0xF] = 0;
75     }
76 }
77 }
78
79 fn main() {
80     let mut cpu = CPU {
81         registers: [0; 16],
82         memory: [0; 4096],
83         position_in_memory: 0,
84         stack: [0; 16],
85         stack_pointer: 0,
86     };

```

```

87
88     cpu.registers[0] = 5;
89     cpu.registers[1] = 10;
90
91     let mem = &mut cpu.memory;
92     mem[0x000] = 0x21; mem[0x001] = 0x00; ← Sets opcode to 0x2100: CALL the function at 0x100
93     mem[0x002] = 0x21; mem[0x003] = 0x00; ← Sets opcode to 0x2100: CALL the function at 0x100
94     mem[0x004] = 0x00; mem[0x005] = 0x00; ← Sets opcode to 0x0000: HALT (not strictly necessary as cpu.memory is initialized with null bytes)
95
96     mem[0x100] = 0x80; mem[0x101] = 0x14; ← Sets opcode to 0x8014: ADD register 1's value to register 0
97     mem[0x102] = 0x80; mem[0x103] = 0x14; ← Sets opcode to 0x8014: ADD register 1's value to register 0
98     mem[0x104] = 0x00; mem[0x105] = 0xEE; ← Sets opcode to 0x8014: ADD register 1's value to register 0
99
100    cpu.run();
101
102    assert_eq!(cpu.registers[0], 45);
103    println!("5 + (10 * 2) + (10 * 2) = {}", cpu.registers[0]);
104 }

```

As you delve into systems' documentation, you will find that real-life functions are more complicated than simply jumping to a predefined memory location. Operating systems and CPU architectures differ in calling conventions and in their capabilities. Sometimes operands will need to be added to the stack; sometimes they'll need to be inserted into defined registers. Still, while the specific mechanics can differ, the process is roughly similar to what you have just encountered. Congratulations on making it this far.

### 5.7.5 CPU 4: Adding the rest

With a few extra opcodes, it's possible to implement multiplication and many more functions within your inchoate CPU. Check the source code that comes along with the book, specifically the ch5/ch5-cpu4 directory at <https://github.com/rust-in-action/code> for a fuller implementation of the CHIP-8 specification.

The last step in learning about CPUs and data is to understand how control flow works. Within CHIP-8, control flow works by comparing values in registers, then modifying `position_in_memory`, depending on the outcome. There are no `while` or `for` loops within a CPU. Creating these in programming languages is the art of the compiler writer.

### Summary

- The same bit pattern can represent multiple values, depending on its data type.
- Integer types within Rust's standard library have a fixed width. Attempting to increment past an integer's maximum value is an error called an integer overflow. Decrementing past its lowest value is called integer underflow.
- Compiling programs with optimization enabled (for example, via `cargo build --release`) can expose your programs to integer overflow and underflow as run-time checks are disabled.

- Endianness refers to the layout of bytes in multibyte types. Each CPU manufacturer decides the endianness of its chips. A program compiled for a little-endian CPU malfunctions if one attempts to run it on a system with a big-endian CPU.
- Decimal numbers are primarily represented by floating-point number types. The standard that Rust follows for its `f32` and `f64` types is IEEE 754. These types are also known as single precision and double precision floating point.
- Within `f32` and `f64` types, identical bit patterns can compare as unequal (e.g., `f32::NAN != f32::NAN`), and differing bit patterns can compare as equal (e.g., `-0 == 0`). Accordingly, `f32` and `f64` only satisfy a partial equivalence relation. Programmers should be mindful of this when comparing floating-point values for equality.
- Bitwise operations are useful for manipulating the internals of data structures. However, doing so can often be highly unsafe.
- Fixed-point number formats are also available. These represent numbers by encoding a value as the numerator and using an implicit denominator.
- Implement `std::convert::From` when you want to support type conversions. But in cases where the conversion may fail, the `std::convert::TryFrom` trait is the preferred option.
- A CPU opcode is a number that represents an instruction rather than data. Memory addresses are also just numbers. Function calls are just sequences of numbers.

# Memory

---

## **This chapter covers**

- What pointers are and why some are smart
- What the terms stack and heap mean
- How a program views its memory

This chapter provides you with some of the tacit knowledge held by systems programmers about how a computer's memory operates. It aims to be the most accessible guide to pointers and memory management available. You will learn how applications interact with an operating system (OS). Programmers who understand these dynamics can use that knowledge to maximize their programs' performance, while minimizing their memory footprint.

Memory is a shared resource, and the OS is an arbiter. To make its life easier, the OS lies to your program about how much memory is available and where it's located. Revealing the truth behind those lies requires us to work through some prior knowledge. This is the work of the first two sections of the chapter.

Each of the four sections in this chapter builds on the previous one. None of these sections assume that you've encountered the topic before. There is a fairly large body of theory to cover, but all of it is explained by examples.


In this chapter, you'll create your first graphical application. The chapter introduces little new Rust syntax, as the material is quite dense. You'll learn how to construct pointers, how to interact with an OS via its native API, and how to interact with other programs through Rust's foreign function interface.

## 6.1 Pointers

*Pointers* are how computers refer to data that isn't immediately accessible. This topic tends to have an aura of mystique to it. That's not necessary. If you've ever read a book's table of contents, then you've used a pointer. Pointers are just numbers that refer to somewhere else.

If you've never encountered systems programming before, there is a lot of terminology to grapple with that describes unfamiliar concepts. Thankfully, though, what's sitting underneath the abstraction is not too difficult to understand. The first thing to grasp is the notation used in this chapter's figures. Figure 6.1 introduces three concepts:

- The arrow refers to some location in memory that is determined at runtime rather than at compile time.
- Each box represents a block of memory, and each block refers to a `usize` width. Other figures use a byte or perhaps even a bit as the chunk of memory these refer to.
- The rounded box underneath the `Value` label represents three contiguous blocks of memory.



**Figure 6.1** Depicting notation used in this chapter's figures for illustrating a pointer. In Rust, pointers are most frequently encountered as `&T` and `&mut T`, where `T` is the type of the value.

For newcomers, pointers are scary and, at the same time, awe-inspiring. Their proper use requires that you know exactly how your program is laid out in memory. Imagine reading a table of contents that says chapter 4 starts on page 97, but it actually starts on page 107. That would be frustrating, but at least you could cope with the mistake.

A computer doesn't experience frustration. It also lacks any intuition that it has pointed to the wrong place. It just keeps working, correctly or incorrectly, as if it had been given the correct location. The fear of pointers is that you will introduce some impossible-to-debug error.

We can think of data stored within the program's memory as being scattered around somewhere within physical RAM. To make use of that RAM, there needs to be some sort of retrieval system in place. An *address space* is that retrieval system.

Pointers are encoded as memory addresses, which are represented as integers of type `usize`. An address points to somewhere within the address space. For the moment, think of the address space as all of your RAM laid out end to end in a single line.

Why are memory addresses encoded as `usize`? Surely there's no 64-bit computer with  $2^{64}$  bytes of RAM. The range of the address space is a façade provided by the OS and the CPU. Programs only know an orderly series of bytes, irrespective of the amount of RAM that is actually available in the system. We discuss how this works later in the virtual memory section of this chapter.

**NOTE** Another interesting example is the `Option<T>` type. Rust uses null pointer optimization to ensure that an `Option<T>` occupies 0 bytes in the compiled binary. The `None` variant is represented by a *null pointer* (a pointer to invalid memory), allowing the `Some(T)` variant to have no additional indirection.

### What are the differences between references, pointers, and memory addresses?

References, pointers, and memory addresses are confusingly similar:

- A *memory address*, often shortened to *address*, is a number that happens to refer to a single byte in memory. Memory addresses are abstractions provided by assembly languages.
- A *pointer*, sometimes expanded to *raw pointer*, is a memory address that points to a value of some type. Pointers are abstractions provided by higher-level languages.
- A *reference* is a pointer, or in the case of dynamically sized types, a pointer and an integer with extra guarantees. References are abstractions provided by Rust.

Compilers are able to determine spans of valid bytes for many types. For example, when a compiler creates a pointer to an `i32`, it can verify that there are 4 bytes that encode an integer. This is more useful than simply having a memory address, which may or may not point to any valid data type. Unfortunately, the programmer bears the responsibility for ensuring the validity for types with no known size at compile time.

Rust's references offer substantial benefits over pointers:

- References always refer to valid data. Rust's references can only be used when it's legal to access their referent. I'm sure you're familiar with this core tenet of Rust by now!
- References are correctly aligned to multiples of `usize`. For technical reasons, CPUs become quite temperamental when asked to fetch unaligned memory.

**(continued)**

They operate much more slowly. To mitigate this problem, Rust's types actually include padding bytes so that creating references to these does not slow down your program.

- References are able to provide these guarantees for dynamically sized types. For types with no fixed width in memory, Rust ensures that a length is kept alongside the internal pointer. That way Rust can ensure that the program never overruns the type's space in memory.

**NOTE** The distinguishing characteristic between memory addresses and the two higher abstractions is that the latter two have information about the type of their referent.

## 6.2 *Exploring Rust's reference and pointer types*

This section teaches you how to work with several of Rust's pointer types. *Rust in Action* tries to stick to the following guidelines when discussing these types:

- *References*—Signal that the Rust compiler will provide its safety guarantees.
- *Pointers*—Refer to something more primitive. This also includes the implication that we are responsible for maintaining safety. (There is an implied connotation of being unsafe.)
- *Raw pointers*—Used for types where it's important to make their unsafe nature explicit.

Throughout this section, we'll expand on a common code fragment introduced by listing 6.1. Its source code is available in ch6/ch6-pointer-intro.rs. In the listing, two global variables, `B` and `C`, are pointed to by references. Those references hold the addresses of `B` and `C`, respectively. A view of what's happening follows the code in figures 6.2 and 6.3.

### Listing 6.1 Mimicking pointers with references

```
static B: [u8; 10] = [99, 97, 114, 114, 121, 116, 111, 119, 101, 108];
static C: [u8; 11] = [116, 104, 97, 110, 107, 115, 102, 105, 115, 104, 0];

fn main() {
    let a = 42;
    let b = &B;
    let c = &C;
    println!("a: {}, b: {:p}, c: {:p}", a, b, c);
}
```

For simplicity, uses the same reference type for this example.  
Later examples distinguish smart pointers from raw pointers and require different types.

The `{:p}` syntax asks Rust to format the variable as a pointer and prints the memory address that the value points to.




Figure 6.2 An abstract view of how two pointers operate alongside a standard integer. The important lesson here is that the programmer might not know the location of the referent data beforehand.

Listing 6.1 has three variables within its `main()` function. `a` is rather trivial; it's just an integer. The other two are more interesting. `b` and `c` are references. These refer to two opaque arrays of data, `B` and `C`. For the moment, consider Rust references as equivalent to pointers. The output from one execution on a 64-bit machine is as follows:

`a: 42, b: 0x556fd40eb480, c: 0x556fd40eb48a`

If you run the code, the exact  
memory addresses will be  
different on your machine.

Figure 6.3 provides a view of the same example in an imaginary address space of 49 bytes. It has a pointer width of two bytes (16 bits). You'll notice that the variables `b` and `c` look different in memory, despite being the same type as in listing 6.1. That's due to that because the listing is lying to you. The gritty details and a code example that more closely represents the diagram in figure 6.3 are coming shortly.

As evidenced in figure 6.2, there's one problem with portraying pointers as arrows to disconnected arrays. These tend to de-emphasize that the address space is contiguous and shared between all variables.

For a more thorough examination of what happens under the hood, listing 6.2 produces much more output. It uses more sophisticated types instead of references to




Figure 6.3 An illustrative address space of the program provided in listing 6.1. It provides an illustration of the relationship between addresses (typically written in hexadecimal) and integers (typically written in decimal). White cells represent unused memory.

demonstrate how these differ internally and to correlate more accurately what is presented in figure 6.3. The following shows the output from listing 6.2:

```

a (an unsigned integer):
location: 0x7ffe8f7ddfd0
size:     8 bytes
value:    42

b (a reference to B):
location: 0x7ffe8f7ddfd8
size:     8 bytes
points to: 0x55876090c830

c (a "box" for C):
location: 0x7ffe8f7ddfe0
size:     16 bytes
points to: 0x558762130a40

```

```
B (an array of 10 bytes):
location: 0x55876090c830
size:    10 bytes
value:   [99, 97, 114, 114, 121, 116, 111, 119, 101, 108]

C (an array of 11 bytes):
location: 0x55876090c83a
size:    11 bytes
value:   [116, 104, 97, 110, 107, 115, 102, 105, 115, 104, 0]
```

### Listing 6.2 Comparing references and Box<T> to several types

`&[u8; 10]` reads as “a reference to an array of 10 bytes.” The array is located in static memory, and the reference itself (a pointer of width `usize` bytes) is placed on the stack.

```
1 use std::mem::size_of;
2
3 static B: [u8; 10] = [99, 97, 114, 114, 121, 116, 111, 119, 101, 108];
4 static C: [u8; 11] = [116, 104, 97, 110, 107, 115, 102, 105, 115, 104, 0];
5
6 fn main() {
7     let a: usize      = 42;           ← usize is the memory address size for the
8
9     let b: &[u8; 10] = &B;             ← CPU the code is compiled for. That CPU is
10
11    let c: Box<[u8]> = Box::new(C); ← called the compile target.
12
13    println!("a (an unsigned integer):");
14    println!(" location: {:p}", &a);
15    println!(" size:    {:?} bytes", size_of::<usize>());
16    println!(" value:   {:?}", a);
17    println!();
18
19    println!("b (a reference to B):");
20    println!(" location: {:p}", &b);
21    println!(" size:    {:?} bytes", size_of::<&[u8; 10]>());
22    println!(" points to: {:p}", b);
23    println!();
24
25    println!("c (a "box" for C):");
26    println!(" location: {:p}", &c);
27    println!(" size:    {:?} bytes", size_of::<Box<[u8]>>());
28    println!(" points to: {:p}", c);
29    println!();
30
31    println!("B (an array of 10 bytes):");
32    println!(" location: {:p}", &B);
33    println!(" size:    {:?} bytes", size_of::<[u8; 10]>());
34    println!(" value:   {:?}", B);
35    println!();
36
37    println!("C (an array of 11 bytes):");
38    println!(" location: {:p}", &C);
39    println!(" size:    {:?} bytes", size_of::<[u8; 11]>());
40    println!(" value:   {:?}", C);
41 }
```

The `Box<[u8]>` type is a boxed byte slice. When we place values inside a box, ownership of the value moves to the owner of the box.

For readers who are interested in decoding the text within B and C, listing 6.3 is a short program that (almost) creates a memory address layout that resembles figure 6.3 more closely. It contains a number of new Rust features and some relatively arcane syntax, both of which haven't been introduced yet. These will be explained shortly.

### Listing 6.3 Printing from strings provided by external sources

```

A smart pointer type that reads from its pointer
location without needing to copy it first
use std::borrow::Cow;           ←
use std::ffi::CStr;             ←
use std::os::raw::c_char;        ←
                                CStr is a C-like string type
                                that allows Rust to read in
                                zero-terminated strings.

                                c_char, a type alias for Rust's i8
                                type, presents the possibility of
                                a platform-specific nuances.

static B: [u8; 10] = [99, 97, 114, 114, 121, 116, 111, 119, 101, 108];
static C: [u8; 11] = [116, 104, 97, 110, 107, 115, 102, 105, 115, 104, 0];

fn main() {
    let a = 42;                  ←
                                Introduces each of the variables so that these are accessible
                                from println! later. If we created b and c within the unsafe
                                block, these would be out of scope later.

    let b: String;
    let c: Cow<str>;           ←
                                Cow accepts a type parameter for
                                the data it points to; str is the type
                                returned by CStr::to_string_lossy(),
                                so it is appropriate here.

    unsafe {
        let b_ptr = &B as *const u8 as *mut u8;          ←
        b = String::from_raw_parts(b_ptr, 10, 10);       ←
        let c_ptr = &C as *const u8 as *const c_char;     ←
        c = CStr::from_ptr(c_ptr).to_string_lossy();      ←
    }

    println!("a: {}, b: {}, c: {}", a, b, c);
}

```

**String is a smart pointer type that holds a pointer to a backing array and a field to store its size.**

**CStr is a C-like string type that allows Rust to read in zero-terminated strings.**

**c\_char, a type alias for Rust's i8 type, presents the possibility of a platform-specific nuances.**

**Introduces each of the variables so that these are accessible from println! later. If we created b and c within the unsafe block, these would be out of scope later.**

**Cow accepts a type parameter for the data it points to; str is the type returned by CStr::to\_string\_lossy(), so it is appropriate here.**

**References cannot be cast directly to \*mut T, the type required by String::from\_raw\_parts(). But \*const T can be cast to \*mut T, leading to this double cast syntax.**

**String::from\_raw\_parts() accepts a pointer (\*mut T) to an array of bytes, a size, and a capacity parameter.**

**Converts a \*const u8 to a \*const i8, aliased to c\_char. The conversion to i8 works because we remain under 128, following the ASCII standard.**

In listing 6.3, Cow stands for *copy on write*. This smart pointer type is handy when an external source provides a buffer. Avoiding copies increases runtime performance. std::ffi is the foreign function interface module from Rust's standard library. use std::os::raw::c\_char; is not strictly needed, but it does make the code's intent clear. C does not define the width of its char type in its standard, although it's one byte wide in practice. Retrieving the type alias c\_char from the std::os::raw module allows for differences.

To thoroughly understand the code in listing 6.3, there is quite a bit of ground to cover. We first need to work through what raw pointers are and then discuss a number of feature-rich alternatives that have been built around them.

### 6.2.1 Raw pointers in Rust

A *raw pointer* is a memory address without Rust's standard guarantees. These are inherently unsafe. For example, unlike references (`&T`), raw pointers can be null.

If you'll forgive the syntax, raw pointers are denoted as `*const T` and `*mut T` for immutable and mutable raw pointers, respectively. Even though each is a single type, these contain three tokens: `*`, `const` or `mut`. Their type, `T`, a raw pointer to a `String`, looks like `*const String`. A raw pointer to an `i32` looks like `*mut i32`. But before we put pointers into practice, here are two other things that are useful to know:

- *The difference between a `*mut T` and a `*const T` is minimal.* These can be freely cast between one another and tend to be used interchangeably, acting as in-source documentation.
- *Rust references (`&mut T` and `&T`) compile down to raw pointers.* That means that it's possible to access the performance of raw pointers without needing to venture into unsafe blocks.

The next listing provides a small example that coerces a reference to a value (`&T`), creating a raw pointer from an `i64` value. It then prints the value and its address in memory via the `{ :p }` syntax.

**Listing 6.4 Creating a raw pointer (`*const T`)**

```
fn main() {
    let a: i64 = 42;
    let a_ptr = &a as *const i64;           ← Casts a reference to the
                                            variable a (&a) to a constant
                                            raw pointer i64 (*const i64)

    println!("a: {} ({:p})", a, a_ptr);   ← Prints the value of the variable
}                                         a (42) and its address in
                                            memory (0x7ff...)
```

The terms *pointer* and *memory address* are sometimes used interchangeably. These are integers that represent a location in virtual memory. From the compiler's point of view, though, there is one important difference. Rust's pointer types `*const T` and `*mut T` always point to the starting byte of `T`, and these also know the width of type `T` in bytes. A memory address might refer to anywhere in memory.

An `i64` is 8-bytes wide (64 bits ÷ 8 bits per byte). Therefore, if an `i64` is stored at address `0x7ffffd`, then each of the bytes between `0x7ffd..0x8004` must be fetched from RAM to recreate the integer's value. The process of fetching data from RAM from a pointer is known as *dereferencing a pointer*. The following listing identifies a value's address by casting a reference to it as a raw pointer via `std::mem::transmute`.

### Listing 6.5 Identifying a value's address

```
fn main() {
    let a: i64 = 42;
    let a_ptr = &a as *const i64;
    let a_addr: usize = unsafe {
        std::mem::transmute(a_ptr)           ←
    };
    println!("a: {} ({:p}...{:x})", a, a_ptr, a_addr + 7);
}
```

Interprets `*const i64` as `usize`.  
Using `transmute()` is highly unsafe  
but is used here to postpone  
introducing more syntax.

Under the hood, references (`&T` and `&mut T`) are implemented as raw pointers. These come with extra guarantees and should always be preferred.

**WARNING** Accessing the value of a raw pointer is always unsafe. Handle with care.

Using raw pointers in Rust code is like working with pyrotechnics. Usually the results are fantastic, sometimes they're painful, and occasionally they're tragic. Raw pointers are often handled in Rust code by the OS or a third-party library.

To demonstrate their volatility, let's work through a quick example with Rust's raw pointers. Creating a pointer of arbitrary types from any integer is perfectly legal. Dereferencing that pointer must occur within an `unsafe` block, as the following snippet shows. An `unsafe` block implies that the programmer takes full responsibility for any consequences:

```
fn main() {
    let ptr = 42 as *const Vec<String>;           ←
    unsafe {
        let new_addr = ptr.offset(4);
        println!("{:p} -> {:p}", ptr, new_addr);
    }
}
```

You can create pointers safely from  
any integral value. An `i32` is not a  
`Vec<String>`, but Rust is quite  
comfortable ignoring that here.

To reiterate, raw pointers are not safe. These have a number of properties that mean that their use is strongly discouraged within day-to-day Rust code:

- *Raw pointers do not own their values.* The Rust compiler does not check that the referent data is still valid when these are accessed.
- *Multiple raw pointers to the same data are allowed.* Every raw pointer can have write, read-write access to data. This means that there is no time when Rust can guarantee that shared data is valid.

Notwithstanding those warnings, there are a small number of valid reasons to make use of raw pointers:

- *It's unavoidable.* Perhaps some OS call or third-party code requires a raw pointer. Raw pointers are common within C code that provides an external interface.
- *Shared access to something is essential and runtime performance is paramount.* Perhaps multiple components within your application require equal access to some expensive-to-compute variable. If you're willing to take on the risk of one of those components poisoning every other component with some silly mistake, then raw pointers are an option of last resort.

## 6.2.2 Rust's pointer ecosystem

Given that raw pointers are unsafe, what is the safer alternative? The alternative is to use smart pointers. In the Rust community, a *smart pointer* is a pointer type that has some kind of superpower, over and above the ability to deference a memory address. You will probably encounter the term *wrapper type* as well. Rust's smart pointer types tend to wrap raw pointers and bestow them with added semantics.

A narrower definition of smart pointer is common in the C communities. There authors (generally) imply that the term smart pointer means the C equivalents of Rust's `core::ptr::Unique`, `core::ptr::Shared`, and `std::rc::Weak` types. We will introduce these types shortly.

**NOTE** The term *fat pointer* refers to memory layout. Thin pointers, such as raw pointers, are a single `usize` wide. Fat pointers are usually two `usize` wide, and occasionally more.

Rust has an extensive set of pointer (and pointer-like) types in its standard library. Each has its own role, strengths, and weaknesses. Given their unique properties, rather than writing these out as a list, let's model these as characters in a card-based role-playing game, as shown in figure 6.4.

Each of the pointer types introduced here are used extensively throughout the book. As such, we'll give these fuller treatment when that's needed. For now, the two novel attributes that appear within the Powers section of some of these cards are interior mutability and shared ownership. These two terms warrant some discussion.

With interior mutability, you may want to provide an argument to a method that takes immutable values, yet you need to retain mutability. If you're willing to pay the runtime performance cost, it's possible to fake immutability. If the method requires an owned value, wrap the argument in `Cell<T>`. References can also be wrapped in `RefCell<T>`. It is common when using the reference counted types `Rc<T>` and `Arc<T>`, which only accept immutable arguments, to also wrap those in `Cell<T>` or `RefCell<T>`. The resulting type might look like `Rc<RefCell<T>>`. This means that you pay the runtime cost twice but with significantly more flexibility.

With shared ownership, some objects, such as a network connection or, perhaps, access to some OS service, are difficult to mould into the pattern of having a single place with read-write access at any given time. Code might be simplified if two parts of

<b>Raw Pointer</b>	<b>Box&lt;T&gt;</b>	<b>Rc&lt;T&gt;</b>	<b>Arc&lt;T&gt;</b>
			
The cousins <code>*mut T</code> and <code>*const T</code> are the free radicals of the pointer world. Lightning fast, but wildly unsafe.	Store anything in a box. Accepts almost any type for long-term storage. The workhorse of a new, safe programming era.	The reference counted pointer, <code>Rc&lt;T&gt;</code> is Rust's competent, yet miserly bookkeeper. It knows who has borrowed what and when.	<code>Arc&lt;T&gt;</code> is Rust's ambassador. It can share values across threads, guaranteeing that these will not interfere with each other.
<b>Powers</b> <ul style="list-style-type: none"><li>• Speed</li><li>• Can interact with the outside world</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Unsafe</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Store a value in central storage in a location called "the heap"</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Size increase</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Shared access to values</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Size increase</li><li>• Runtime cost</li><li>• Not threadsafe</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Shared access to values</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Size increase</li><li>• Runtime cost</li></ul>
<b>Cell&lt;T&gt;</b>	<b>RefCell&lt;T&gt;</b>	<b>Cow&lt;T&gt;</b>	<b>String</b>
			
An expert in metamorphosis, <code>Cell&lt;T&gt;</code> confers the ability to mutate immutable values.	Performs mutation on immutable references with <code>RefCell&lt;T&gt;</code> . Its mind-bending powers come with some costs.	Why write something down when you only need to read it? Perhaps you only want to make modifications. This is the role of <code>Cow</code> (copy on write).	Acting as a guide on how to deal with the uncertainties of user input, <code>String</code> shows us how to build safe abstractions.
<b>Powers</b> <ul style="list-style-type: none"><li>• Interior mutability</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Size increase</li><li>• Performance</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Interior mutability</li><li>• Can be nested within Rc and Arc, which only accept immutable refs</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Size increase</li><li>• Runtime cost</li><li>• Lack of compile-time guarantees</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Avoids writes when only read access is used</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Possible size increase</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Grows dynamically as required</li><li>• Guarantees correct encoding at runtime</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Can over allocate size</li></ul>
<b>Arc&lt;T&gt;</b>	<b>RawVec&lt;T&gt;</b>	<b>Unique&lt;T&gt;</b>	<b>Shared&lt;T&gt;</b>
			
Your program's main storage system. <code>Vec&lt;T&gt;</code> keeps your data orderly as values are created and destroyed.	The bedrock of <code>Vec&lt;T&gt;</code> and other dynamically sized types. Understands how to provide a home for your data as needed.	Sole owner of a value, a unique pointer is guaranteed to possess full control.	Sharing ownership is hard. <code>Shared&lt;T&gt;</code> makes life a little bit easier.
<b>Powers</b> <ul style="list-style-type: none"><li>• Grows dynamically as required</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Can over allocate size</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Grows dynamically as required</li><li>• Works with the memory allocator to find space</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Not directly applicable from your code</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Base for types such as Strings, requiring exclusive possession of values.</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Not appropriate for application code directly</li></ul>	<b>Powers</b> <ul style="list-style-type: none"><li>• Shared ownership</li><li>• Can align memory to T's width, even when empty</li></ul> <b>Weaknesses</b> <ul style="list-style-type: none"><li>• Not appropriate for application code directly</li></ul>

Figure 6.4 A fictitious role-playing card game describing the characteristics of Rust's smart pointer types

the program can share access to that single resource. Rust allows you to do this, but again, at the expense of a runtime cost.

### 6.2.3 Smart pointer building blocks

You might find yourself in a situation where you want to build your own smart pointer type with its own semantics. Perhaps a new research paper has been released, and you want to incorporate its results into your own work. Perhaps you're conducting the

research. Regardless, it might be useful to know that Rust's pointer types are extensible—these are designed with extension in mind.

All of the programmer-facing pointer types like `Box<T>` are built from more primitive types that live deeper within Rust, often in its `core` or `alloc` modules. Additionally, the C++ smart pointer types have Rust counterparts. Here are some useful starting points for you when building your own smart pointer types:

- `core::ptr::Unique` is the basis for types such as `String`, `Box<T>`, and the pointer field `Vec<T>`.
- `core::ptr::Shared` is the basis for `Rc<T>` and `Arc<T>`, and it can handle situations where shared access is desired.

In addition, the following tools can also be handy in certain situations:

- *Deeply interlinked data structures can benefit from `std::rc::Weak` and `std::arc::Weak` for single and multi-threaded programs, respectively.* These allow access to data within an `Rc/Arc` without incrementing its reference count. This can prevent never-ending cycles of pointers.
- *The `alloc::raw_vec::RawVec` type underlies `Vec<T>` and `VecDeque<T>`.* An expandable, double-ended queue that hasn't appeared in the book so far, it understands how to allocate and deallocate memory in a smart way for any given type.
- *The `std::cell::UnsafeCell` type sits behind both `Cell<T>` and `RefCell<T>`.* If you would like to provide interior mutability to your types, its implementation is worth investigating.

A full treatment of building new safe pointers touches on some of Rust's internals. These building blocks have their own building blocks. Unfortunately, explaining every detail will diverge too far from our goals for this chapter.

**NOTE** Inquisitive readers should investigate the source code of the standard library's pointer types. For example, the `std::cell::RefCell` type is documented at <https://doc.rust-lang.org/std/cell/struct.RefCell.html>. Clicking the [src] button on that web page directs you to the type's definition.

## 6.3 **Providing programs with memory for their data**

This section attempts to demystify the terms *the stack* and *the heap*. These terms often appear in contexts that presuppose you already know what they mean. That isn't the case here. We'll cover the details of what they are, why they exist, and how to make use of that knowledge to make your programs leaner and faster.

Some people hate wading through the details, though. For those readers, here is the salient difference between the stack and the heap:

- The stack is fast.
- The heap is slow.

That difference leads to the following axiom: "When in doubt, prefer the stack." To place data onto the stack, the compiler must know the type's size at compile time.

Translated to Rust, that means, “When in doubt, use types that implement `Sized`.” Now that you’ve got the gist of those terms, it’s time to learn when to take the slow path and how to avoid it when you want to take a faster one.

### 6.3.1 **The stack**

The stack is often described by analogy. Think of a stack of dinner plates waiting in the cupboard of a commercial kitchen. Cooks are taking plates off the stack to serve food, and dishwashers are placing new plates on the top.

The unit (the plate) of a computing stack is the stack frame, also known as the *allocation record*. You are probably used to thinking of this as a group of variables and other data. Like many descriptions in computing, the stack and the heap are analogies that only partially fit. Even though the stack is often compared by analogy to a stack of dinner plates waiting in the cupboard, unfortunately, that mental picture is inaccurate. Here are some differences:

- The stack actually contains two levels of objects: stack frames and data.
- The stack grants programmers access to multiple elements stored within it, rather than the top item only.
- The stack can include elements of arbitrary size, where the implication of the dinner plate analogy is that all elements must be of the same size.

So why is the stack called the stack? Because of the usage pattern. Entries on the stack are made in a Last In, First Out (LIFO) manner.

The entries in the stack are called *stack frames*. Stack frames are created as function calls are made. As a program progresses, a cursor within the CPU updates to reflect the current address of the current stack frame. The cursor is known as the *stack pointer*.

As functions are called within functions, the stack pointer decreases in value as the stack grows. When a function returns, the stack pointer increases.

Stack frames contain a function’s state during the call. When a function is called within a function, the older function’s values are effectively frozen in time. Stack frames are also known as *activation frames*, and less commonly *allocation records*.<sup>1</sup>

Unlike dinner plates, every stack frame is a different size. The stack frame contains space for its function’s arguments, a pointer to the original call site, and local variables (except the data which is allocated on the heap).

**NOTE** If you are unfamiliar with what the term *call site* means, see the CPU emulation section in chapter 5.

To understand what is happening more fully, let’s consider a thought experiment. Imagine a diligent, yet absurdly single-minded cook in a commercial kitchen. The cook takes each table’s docket and places those in a queue. The cook has a fairly bad memory, so each current order is written down a notebook. As new orders come in,

---

<sup>1</sup> To be precise, the activation frame is called a stack frame when allocated on the stack.

the cook updates the notebook to refer to the new order. When orders are complete, the notebook page is changed to the next item in the queue. Unfortunately, for customers in this restaurant, the book operates in a LIFO manner. Hopefully, you will not be one of the early orders during tomorrow's lunch rush.

In this analogy, the notebook plays the role of the stack pointer. The stack itself is comprised of variable-length dockets, representing stack frames. Like stack frames, restaurant dockets contain some metadata. For example, the table number can act as the return address.

The stack's primary role is to make space for local variables. Why is the stack fast? All of a function's variables are side by side in memory. That speeds up access.

### Improving the ergonomics of functions that can only accept `String` or `&str`

As a library author, it can simplify downstream application code if your functions can accept both `&str` and `String` types. Unfortunately, these two types have different representations in memory. One (`&str`) is allocated on the stack, the other (`String`) allocates memory on the heap. That means that types cannot be trivially cast between one another. It's possible, however, to work around this with Rust's generics.

Consider the example of validating a password. For the purposes of the example, a strong password is one that's at least 6 characters long. The following shows how to validate the password by checking its length:

```
fn is_strong(password: String) -> bool {
    password.len() > 5
}
```

`is_strong` can only accept `String`. That means that the following code won't work:

```
let pw = "justok";
let is_strong = is_strong(pw);
```

But generic code can help. In cases where read-only access is required, use functions with the type signature `fn x<T: AsRef<str>> (a: T)` rather than `fn x(a: String)`. The fairly unwieldy type signature reads “as function `x` takes an argument `password` of type `T`, where `T` implements `AsRef<str>`.” Implementors of `AsRef<str>` behave as a reference to `str` even when these are not.

Here is the code snippet again for the previous listing, accepting any type `T` that implements `AsRef<str>`. It now has the new signature in place:

```
fn is_strong<T: AsRef<str>>(password: T) -> bool {           ←
    password.as_ref().len() > 5
}
```

Provides a  
String or a &str  
as password

When read-write access to the argument is required, normally you can make use of `AsRef<T>`'s sibling trait `AsMut<T>`. Unfortunately for this example, `&'static str` cannot become mutable and so another strategy can be deployed: implicit conversion.

**(continued)**

It's possible to ask Rust to accept only those types that can be converted to String. The following example performs that conversion within the function and applies any required business logic to that newly created String. This can circumvent the issue of &str being an immutable value.

```
fn is_strong<T: Into<String>>(password: T) -> bool {  
    password.into().len() > 5  
}
```

This implicit conversion strategy does have significant risks, though. If a stringified version of the password variable needs to be created multiple times in the pipeline, it would be much more efficient to require an explicit conversion within the calling application. That way the String would be created once and reused.

### 6.3.2 *The heap*

This section introduces the heap. The heap is an area of program memory for types that do not have known sizes at compile time.

What does it mean to have no known size at compile time? In Rust, there are two meanings. Some types grow and shrink over time as required. Obvious cases are String and Vec<T>. Other types are unable to tell the Rust compiler how much memory to allocate even though these don't change size at runtime. These are known as dynamically sized types. Slices ([T]) are the commonly cited example. Slices have no compile-time length. Internally, these are a pointer to some part of an array. But slices actually represent some number of elements within that array.

Another example is a *trait object*, which we've not described in this book so far. Trait objects allow Rust programmers to mimic some features of dynamic languages by allowing multiple types to be wedged into the same container.

#### WHAT IS THE HEAP?

You will gain a fuller understanding of *what* the heap is once you work through the next section on virtual memory. For now, let's concentrate on what it is *not*. Once those points are clarified, we'll then work our way back toward some form of truth.

The word "heap" implies disorganization. A closer analogy would be warehouse space in some medium-sized business. As deliveries arrive (as variables are created), the warehouse makes space available. As the business carries out its work, those materials are used, and the warehouse space can now be made available for new deliveries. At times, there are gaps and perhaps a bit of clutter. But overall, there is a good sense of order.

Another mistake is that the heap has no relationship to the data structure that is also known as a heap. That data structure is often used to create priority queues. It's an incredibly clever tool in its own right, but right now it's a complete distraction. The heap is not a data structure. It's an area of memory.

Now that those two distinctions are made, let's inch toward an explanation. The critical difference from a usage point of view is that variables on the heap must be accessed via a pointer, whereas this is not required with variables accessed on the stack.

Although it's a trivial example, let's consider two variables, `a` and `b`. These both represent the integers 40 and 60, respectively. In one of those cases though, the integer happens to live on the heap, as in this example:

```
let a: i32 = 40;
let b: Box<i32> = Box::new(60);
```

Now, let's demonstrate that critical difference. The following code won't compile:

```
let result = a + b;
```

The boxed value assigned to `b` is only accessible via a pointer. To access that value, we need to dereference it. The dereference operator is a unary `*`, which prefixes the variable name:

```
let result = a + *b;
```

This syntax can be difficult to follow at first because the symbol is also used for multiplication. It does, however, become more natural over time. The following listing shows a complete example where creating variables on the heap implies constructing that variable via a pointer type such as `Box<T>`.

#### Listing 6.6 Creating variables on the heap

```
fn main() {
    let a: i32 = 40;                                ↪ 40 lives on the stack.
    let b: Box<i32> = Box::new(60);                  ↪ 60 lives on the heap.
    println!("{} + {} = {}", a, b, a + *b);          ↪ To access 60, we need
}                                                to dereference it.
```

To get a feel for what the heap is and what is happening within memory as a program runs, let's consider a tiny example. In this example, all we will do is to create some numbers on the heap and then add their values together. When run, the program in listing 6.7 produces some fairly trivial output: two 3s. Still, it's really the internals of the program's memory that are important here, not its results.

The code for the next listing is in the file `ch6/ch6-heap-via-box/src/main.rs`. A pictorial view of the program's memory as it runs (figure 6.5) follows the code. Let's first look at the program's output:

```
3 3
```

**Listing 6.7 Allocating and deallocating memory on the heap via Box<T>**

```

1 use std::mem::drop;           ← Brings manual drop()
2
3 fn main() {
4     let a = Box::new(1);      | Allocates values
5     let b = Box::new(1);      | on the heap
6     let c = Box::new(1);
7
8     let result1 = *a + *b + *c; ← The unary *, the dereference operator,
9
10    drop(a);                ← returns the value within the box, and
11    let d = Box::new(1);      | result1 holds the value 3.
12    let result2 = *b + *c + *d;
13
14    println!("{} {}", result1, result2);
15 }
```

Invokes drop(), freeing  
memory for other uses

Listing 6.7 places four values on the heap and removes one. It contains some new or, at least, less familiar syntax that might be worthwhile to cover and/or recap:

- *Box::new(T) allocates T on the heap.* *Box* is a term that can be deceptive if you don't share its intuition.

Something that has been *boxed* lives on the heap, with a pointer to it on the stack. This is demonstrated in the first column of figure 6.5, where the number 0x100 at address 0xffff points to the value 1 at address 0x100. However, no actual box of bytes encloses a value, nor is the value hidden or concealed in some way.

- *std::mem::drop brings the function drop() into local scope.* *drop()* deletes objects before their scope ends.

Types that implement *Drop* have a *drop()* method, but explicitly calling it is illegal within user code. *std::mem::drop* is an escape hatch from that rule.

- *Asterisks next to variables (\*a, \*b, \*c, and \*d) are unary operators.* This is the *dereference operator*. Dereferencing a *Box::(T)* returns *T*. In our case, the variables *a*, *b*, *c*, and *d* are references that refer to integers.

In figure 6.5, each column illustrates what happens inside memory at 6 lines of code. The stack appears as the boxes along the top, and the heap appears along the bottom. The figure omits several details, but it should help you gain an intuition about the relationship between the stack and the heap.

**NOTE** If you have experience with a debugger and want to explore what is happening, be sure to compile your code with no optimizations. Compile your code with *cargo build* (or *cargo run*) rather than *cargo build --release*. Using the *--release* flag actually ends up optimizing all the allocations and arithmetic. If you are invoking *rustc* manually, use the command *rustc --codegen opt-level=0*.





Figure 6.5 A view into a program's memory layout during the execution of listing 6.7

### 6.3.3 What is dynamic memory allocation?

At any given time, a running program has a fixed number of bytes with which to get its work done. When the program would like more memory, it needs to ask for more from the OS. This is known as *dynamic memory allocation* and is shown in figure 6.6. Dynamic memory allocation is a three-step process:

- 1 Request memory from the OS via a system call. In the UNIX family of operating systems, this system call is `alloc()`. In MS Windows, the call is `HeapAlloc()`.
- 2 Make use of the allocated memory in the program.
- 3 Release memory that isn't needed back to the OS via `free()` for UNIX systems and `HeapFree()` for Windows.



**Figure 6.6** Conceptual view of dynamic memory allocation. Requests for memory originate and terminate at the program level but involve several other components. At each stage, the components may short-circuit the process and return quickly.

As it turns out, there is an intermediary between the program and the OS: the *allocator*, a specialist subprogram that is embedded in your program behind the scenes. It will often perform optimizations that avoid lots of work within the OS and CPU.

Let's examine the performance impact of dynamic memory allocation and strategies to reduce that impact. Before starting, let's recap why there's a performance difference between the stack and the heap. Remember that the stack and the heap are conceptual abstractions only. These do not exist as physical partitions of your computer's memory. What accounts for their different performance characteristics?

Accessing data on the stack is fast because a function's local variables, which are allocated on the stack, reside next to each other in RAM. This is sometimes referred to as a *contiguous layout*.

A contiguous layout is cache-friendly. Alternatively, variables allocated on the heap are unlikely to reside next to each other. Moreover, accessing data on the heap involves dereferencing the pointer. That implies a page table lookup and a trip to main memory. Table 6.1 summarizes these differences.

**Table 6.1 A simplistic, yet practical table for comparing the stack and the heap**

Stack	Heap
Simple	Complex
Safe	Dangerous*
Fast	Slow
Rigid	Flexible

\* Not in safe Rust!

There is a trade-off for the stack's increased speed. Data structures on the stack must stay the same size during the lifetime of the program. Data structures allocated on the heap are more flexible. Because these are accessed via a pointer, that pointer can be changed.

To quantify this impact, we need to learn how to measure the cost. To get a large number of measurements, we need a program that creates and destroys many values. Let's create a toy program. Figure 6.7 shows a background element to a video game.



**Figure 6.7 Screenshots from the result of running listing 6.9**

After running listing 6.9, you should see a window appear on your screen filled with a dark grey background. White snow-like dots will start to float from the bottom and fade as they approach the top. If you check the console output, streams of numbers will appear. Their significance will be explained once we discuss the code. Listing 6.9 contains three major sections:

- A memory allocator (the `ReportingAllocator` struct) records the time that dynamic memory allocations take.
- Definitions of the structs `World` and `Particle` and how these behave over time.
- The `main()` function deals with window creation and initialization.

The following listing shows the dependencies for our toy program (listing 6.9). The source for the following listing is in ch6/ch6-particles/Cargo.toml. The source for listing 6.9 is in ch6/ch6-particles/main.rs.

### Listing 6.8 Build dependencies for listing 6.9

```
[package]
name = "ch6-particles"
version = "0.1.0"
authors = ["TS McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
piston_window = "0.117"           ← Provides a wrapper around the core functionality of
                                    the piston game engine, letting us easily draw things
                                    onscreen; largely irrespective of the host environment
piston2d-graphics = "0.39"          ← Provides vector mathematics, which
                                    is important to simulate movement
rand = "0.8"                      ← Provides random number generators
                                    and associated functionality
```

### Listing 6.9 A graphical application to create and destroy objects on the heap

```
rand provides random number
generators and related functionality.                                     graphics::math::Vec2d provides mathematical operations
                                                                           and conversion functionality for 2D vectors.

1 use graphics::math::{Vec2d, add, mul_scalar};                                ←
2
3 use piston_window::*;

4
5 use rand::prelude::*;

6
7 use std::alloc::{GlobalAlloc, System, Layout};      ← piston_window provides the tools to create
                                                       a GUI program and draws shapes to it.
                                                       ← std::alloc provides
                                                       facilities for controlling
                                                       memory allocation.

std::time
provides
access to the
system's
clock.   9 use std::time::Instant;                                ← #[global_allocator] marks the
                                                       following value (ALLOCATOR) as
                                                       satisfying the GlobalAlloc trait.

10
11
12 #[global_allocator]           ←
13 static ALLOCATOR: ReportingAllocator = ReportingAllocator;
14
15 struct ReportingAllocator;                                              ← Prints the time taken for each
16
17 unsafe impl GlobalAlloc for ReportingAllocator {                         ←
18     unsafe fn alloc(&self, layout: Layout) -> *mut u8 {                ←
19         let start = Instant::now();                                         ←
20         let ptr = System.alloc(layout);                                     ←
21         let end = Instant::now();                                         ←
22         let time_taken = end - start;                                     ←
23         let bytes_requested = layout.size();                            ←
24         eprintln!("{}\t{}", bytes_requested, time_taken.as_nanos());    ←
25         ptr
26     }
27 }
28
29 unsafe fn deallocate(&self, ptr: *mut u8, layout: Layout) {             ← Defers the actual memory
                                                                           allocation to the system's
                                                                           default memory allocator
```

```

30     System.dealloc(ptr, layout);
31 }
32 }
33
34 struct World {
35     current_turn: u64,
36     particles: Vec<Box<Particle>>,
37     height: f64,
38     width: f64,
39     rng: ThreadRng,
40 }
41
42 struct Particle {
43     height: f64,
44     width: f64,
45     position: Vec2d<f64>,
46     velocity: Vec2d<f64>,
47     acceleration: Vec2d<f64>,
48     color: [f32; 4],
49 }
50
51 impl Particle {
52     fn new(world : &World) -> Particle {
53         let mut rng = thread_rng();
54         let x = rng.gen_range(0.0..=world.width);
55         let y = world.height;
56         let x_velocity = 0.0;
57         let y_velocity = rng.gen_range(-2.0...0.0);
58         let x_acceleration = 0.0;
59         let y_acceleration = rng.gen_range(0.0...0.15);
60
61         Particle {
62             height: 4.0,
63             width: 4.0,
64             position: [x, y].into(),
65             velocity: [x_velocity, y_velocity].into(),
66             acceleration: [x_acceleration,
67                             y_acceleration].into(),
68             color: [1.0, 1.0, 1.0, 0.99],
69         }
70     }
71
72     fn update(&mut self) {
73         self.velocity = add(self.velocity,
74                             self.acceleration); ←
75         self.position = add(self.position,
76                             self.velocity); ←
77         self.acceleration = mul_scalar(
78             self.acceleration,
79             0.7
80         );
81         self.color[3] *= 0.995; ←
82     }
83 }
84 }
```

Contains the data that is useful for the lifetime of the program

Defines an object in 2D space

Starts at a random position along the bottom of the window

Rises vertically over time

Increases the speed of the rise over time

into() converts the arrays of type [f64; 2] into Vec2d.

Inserts a fully saturated white that has a tiny amount of transparency

Moves the particle to its next position

Slows down the particle's rate of increase as it travels across the screen

Makes the particle more transparent over time

```

125 impl World {
126     fn new(width: f64, height: f64) -> World {
127         World {
128             current_turn: 0,
129             particles: Vec::<Box<Particle>>::new(),
130             height: height,
131             width: width,
132             rng: thread_rng(),
133         }
134     }
135
136     fn add_shapes(&mut self, n: i32) {
137         for _ in 0..n.abs() {
138             let particle = Particle::new(&self);
139             let boxed_particle = Box::new(particle);
140             self.particles.push(boxed_particle);
141         }
142     }
143
144     fn remove_shapes(&mut self, n: i32) {
145         for _ in 0..n.abs() {
146             let mut to_delete = None;
147
148             let particle_iter = self.particles
149                 .iter()
150                 .enumerate();
151
152             for (i, particle) in particle_iter {
153                 if particle.color[3] < 0.02 {
154                     to_delete = Some(i);
155                 }
156                 break;
157             }
158
159             if let Some(i) = to_delete {
160                 self.particles.remove(i);
161             } else {
162                 self.particles.remove(0);
163             };
164         }
165     }
166
167     fn update(&mut self) {
168         let n = self.rng.gen_range(-3..=3);
169
170         if n > 0 {
171             self.add_shapes(n);
172         } else {
173             self.remove_shapes(n);
174         }
175
176         self.particles.shrink_to_fit();
177         for shape in &mut self.particles {
178             shape.update();
179         }
180     }
181 }
```

Uses `Box<Particle>` rather than `Particle` to incur an extra memory allocation when every particle is created

Creates a Particle as a local variable on the stack

Takes ownership of particle, moving its data to the heap, and creates a reference to that data on the stack

Pushes the reference into `self.shapes`

`particle_iter` is split into its own variable to more easily fit on the page.

For `n` iterations, removes the first particle that's invisible. If there are no invisible particles, then removes the oldest.

Returns a random integer between `-3` and `3`, inclusive

```

140     self.current_turn += 1;
141 }
142 }
143
144 fn main() {
145     let (width, height) = (1280.0, 960.0);
146     let mut window: PistonWindow = WindowSettings::new(
147         "particles", [width, height]
148     )
149     .exit_on_esc(true)
150     .build()
151     .expect("Could not create a window.");
152
153     let mut world = World::new(width, height);
154     world.add_shapes(1000);
155
156     while let Some(event) = window.next() {
157         world.update();
158
159         window.draw_2d(&event, |ctx, renderer, _device| {
160             clear([0.15, 0.17, 0.17, 0.9], renderer);
161
162             for s in &mut world.particles {
163                 let size = [s.position[0], s.position[1], s.width, s.height];
164                 rectangle(s.color, size, ctx.transform, renderer);
165             }
166         });
167     }
168 }
```

Listing 6.9 is a fairly long code example, but hopefully, it does not contain any code that's too alien compared to what you've already seen. Toward the end, the code example introduces Rust's closure syntax. If you look at the call to `window.draw_2d()`, it has a second argument with vertical bars surrounding two variable names (`|ctx, renderer, _device| { ... }`). Those vertical bars provide space for the closure's arguments, and the curly braces are its body.

A *closure* is a function that is defined in line and can access variables from its surrounding scope. These are often called *anonymous* or *lambda* functions.

Closures are a common feature within idiomatic Rust code, but this book tends to avoid those where possible to keep examples approachable to programmers from an imperative or object-oriented background. Closures are explained fully in chapter 11. In the interim, it's sufficient to say that these are a convenient shorthand for defining functions. Let's next focus on generating some evidence that allocating variables on the heap (many millions of times) can have a performance impact on your code.

### 6.3.4 Analyzing the impact of dynamic memory allocation

If you run listing 6.9 from a terminal window, you'll soon see two columns of numbers filling it up. These columns represent the number of bytes allocated, and the duration in nanoseconds taken to fulfil the request. That output can be sent to a file for further

analysis, as shown in the following listing, which redirects stderr from ch6-particles to a file.

#### Listing 6.10 Creating a report of memory allocations

```
$ cd ch6-particles
$ cargo run -q 2> alloc.tsv
```

Runs ch6-particles  
in quiet mode

```
$ head alloc.tsv
```

Views the first 10  
lines of output

Allocation size (bytes)	Allocation duration (ns)
4	219
5	83
48	87
9	78
9	93
19	69
15	960
16	40
14	70
16	53

One interesting aspect from this short extract is that memory allocation speed is not well-correlated with allocation size. When every heap allocation is plotted, this becomes even clearer as figure 6.8 shows.




Figure 6.8 Plotting heap allocation times against allocation size shows that there is no clear relationship between the two. The time taken to allocate memory is essentially unpredictable, even when requesting the same amount of memory multiple times.

To generate your own version of figure 6.8, the following listing shows a gnuplot script that can be tweaked as desired. You'll find this source in the file ch6/alloc.plot.

**Listing 6.11 Script used to generate figure 6.8 with gnuplot**

```
set key off
set rmargin 5
set grid ytics noxtics nocbtics back
set border 3 back lw 2 lc rgbcolor "#222222"

set xlabel "Allocation size (bytes)"
set logscale x 2
set xtics nomirror out
set xrange [0 to 100000]

set ylabel "Allocation duration (ns)"
set logscale y
set yrange [10 to 10000]
set ytics nomirror out

plot "alloc.tsv" with points \
    pointtype 6 \
    pointsize 1.25 \
    linecolor rgbcolor "#22dd3131"
```

Although larger memory allocations do tend to take longer than shorter ones, it's not guaranteed. The range of durations for allocating memory of the same number is over an order of magnitude. It might take 100 nanoseconds; it might take 1,000.

Does it matter? Probably not. But it might. If you have a 3 GHz CPU, then your processor is capable of performing 3 billion operations per second. If there is a 100 nanosecond delay between each of those operations, your computer can only perform 30 million operations in the same time frame. Perhaps those hundreds of microseconds really do count for your application. Some general strategies for minimizing heap allocations include

- *Using arrays of uninitialized objects.* Instead of creating objects from scratch as required, create a bulk lot of those with zeroed values. When the time comes to activate one of those objects, set its values to non-zero. This can be a very dangerous strategy because you're circumventing Rust's lifetime checks.
- *Using an allocator that is tuned for your application's access memory profile.* Memory allocators are often sensitive to the sizes where these perform best.
- *Investigate arena::Arena and arena::TypedArena.* These allow objects to be created on the fly, but `alloc()` and `free()` are only called when the arena is created and destroyed.

## 6.4 Virtual memory

This section explains what the term virtual memory means and why it exists. You will be able to use this knowledge to speed up your programs by building software that goes with the grain. CPUs can compute faster when they're able to access memory quickly. Understanding some of the dynamics of the computer architecture can help to provide CPUs with memory efficiently.

### 6.4.1 Background

I have spent far too much of my life playing computer games. As enjoyable and challenging as I've found these, I've often wondered about whether I would have been better off spending my teenage years doing something more productive. Still, it's left me with plenty of memories. But some of those memories still leave a bitter taste.

Occasionally, someone would enter the game and obliterate everyone with near perfect aim and seemingly impossibly high health ratings. Other players would decry, "Cheater!" but were more or less helpless in defeat. While waiting in in-game purgatory, I would sit wondering, "How is that possible? How are those tweaks to the game actually made?"

By working through this section's examples, you would have built the core of a tool that's capable of inspecting and modifying values of a running program.

#### Terms related to virtual memory

Terminology within this area is particularly arcane. It is often tied to decisions made many decades ago when the earliest computers were being designed. Here is a quick reference to some of the most important terms:

- **Page**—A fixed-size block of words of real memory. Typically 4 KB in size for 64-bit operating systems.
- **Word**—Any type that is size of a pointer. This corresponds to the width of the CPU's registers. In Rust, `usize` and `isize` are word-length types.
- **Page fault**—An error raised by the CPU when a valid memory address is requested that is not currently in physical RAM. This signals to the OS that at least one page must be swapped back into memory.
- **Swapping**—Migrating a page of memory stored temporarily on disk from main memory upon request.
- **Virtual memory**—The program's view of its memory. All data accessible to a program is provided in its address space by the OS.
- **Real memory**—The operating system's view of the physical memory available on the system. In many technical texts, real memory is defined independently from physical memory, which becomes much more of an electrical engineering term.
- **Page table**—The data structure maintained by the OS to manage translating from virtual to real memory.

- **Segment**—A block within virtual memory. Virtual memory is divided into blocks to minimize the space required to translate between virtual and physical addresses.
- **Segmentation fault**—An error raised by the CPU when an illegal memory address is requested.
- **MMU**—A component of the CPU that manages memory address translation. Maintains a cache of recently translated addresses (called the TLB), which stands for the translation lookaside buffer, although that terminology has fallen from fashion.

One term that has not been defined in any technical sense so far in this book is *process*. If you've encountered it before and have been wondering why it has been omitted, it will be introduced properly when we talk about concurrency. For now, consider the terms *process* and its peer *operating system process* to refer to a running program.

#### 6.4.2 Step 1: Having a process scan its own memory

Intuitively, a program's memory is a series of bytes that starts at location 0 and ends at location  $n$ . If a program reports 100 KB of RAM usage, it would seem that  $n$  would be somewhere near 100,000. Let's test that intuition.

We'll create a small command-line program that looks through memory, starting at location 0 and ending at 10,000. As it's a small program, it shouldn't occupy more than 10,000 bytes. But when executed, the program will not perform as intended. Sadly, it will crash. You'll learn why the crash occurs as you follow through this section.

Listing 6.12 shows the command-line program. You can find its source in ch6/ch6-memscan-1/src/main.rs. The listing scans through a running program's memory byte by byte, starting at 0. It introduces the syntax for creating raw pointers and dereferencing (reading) those.

**Listing 6.12 Attempting to scan a running program's memory byte by byte**

```

1 fn main() {
2     let mut n_nonzero = 0;
3
4     for i in 0..10000 {
5         let ptr = i as *const u8;           ← Converts i to a *const T, a raw pointer
6         let byte_at_addr = unsafe { *ptr }; ← of type u8 to inspect raw memory
7
8         if byte_at_addr != 0 {
9             n_nonzero += 1;
10        }
11    }
12
13    println!("non-zero bytes in memory: {}", n_nonzero);
14 }
```

Converts  $i$  to a  $*const T$ , a raw pointer of type  $u8$  to inspect raw memory addresses. We treat every address as a unit, ignoring the fact that most values span multiple bytes.

Dereferences the pointer, it reads the value at address  $i$ . Another way of saying this is “read the value being pointed to.”

Listing 6.12 crashes because it is attempting to dereference a NULL pointer. When *i* equals 0, *ptr* can't really be dereferenced. Incidentally, this is why all raw pointer dereferences must occur within an unsafe block.

How about we attempt to start from a non-zero memory address? Given that the program is executable code, there should be at least several thousand bytes of non-zero data to iterate through. The following listing scans the process's memory starting from 1 to avoid dereferencing a NULL pointer.

### Listing 6.13 Scanning a process's memory

```

1 fn main() {
2     let mut n_nonzero = 0;
3
4     for i in 1..10000 {           ← Starts at 1 rather
5         let ptr = i as *const u8;
6         let byte_at_addr = unsafe { *ptr };
7
8         if byte_at_addr != 0 {
9             n_nonzero += 1;
10        }
11    }
12
13    println!("non-zero bytes in memory: {}", n_nonzero);
14 }
```

This unfortunately does not completely solve the issue. Listing 6.13 still crashes upon execution, and the number of non-zero bytes is never printed to the console. This is due to what's known as a *segmentation fault*.

Segmentation faults are generated when the CPU and OS detect that your program is attempting to access memory regions that they aren't entitled to. Memory regions are divided into segments. That explains the name.

Let's try a different approach. Rather than attempting to scan through bytes, let's look for the addresses of things that we know exist. We've spent lots of time learning about pointers, so let's put that to use. Listing 6.14 creates several values, examining their addresses.

Every run of listing 6.14 may generate unique values. Here is the output of one run:

```

GLOBAL:      0x7ff6d6ec9310
local_str:   0x7ff6d6ec9314
local_int:   0x23d492f91c
boxed_int:   0x18361b78320
boxed_str:   0x18361b78070
fn_int:     0x23d492f8ec
```

As you can see, values appear to be scattered across a wide range. So despite your program (hopefully) only needing a few kilobytes of RAM, a few variables live in giant locations. These are *virtual addresses*.

As explained in the heap versus stack section, the stack starts at the top of the address space and the heap starts near the bottom. In this run, the highest value is 0x7ff6d6ec9314. That's approximately  $2^{64} \div 2$ . That number is due to the OS reserving half of the address space for itself.

The following listing returns the address of several variables within a program to examine its address space. The source for this listing in ch6/ch6-memscan-3/src/main.rs.

#### Listing 6.14 Printing the address of variables within a program

```
static GLOBAL: i32 = 1000;           ← Creates a global static, which is a
fn noop() -> *const i32 {          ← global variable in Rust programs
    let noop_local = 12345;
    &noop_local as *const i32           ← Creates a global static, which is a
}                                     ← global variable in Rust programs
fn main() {
    let local_str = "a";
    let local_int = 123;
    let boxed_str = Box::new('b');
    let boxed_int = Box::new(789);
    let fn_int = noop();
}

println!("GLOBAL:      {:p}", &GLOBAL as *const i32);
println!("local_str:  {:p}", local_str as *const str);
println!("local_int:   {:p}", &local_int as *const i32);
println!("boxed_int:   {:p}", Box::into_raw(boxed_int));
println!("boxed_str:   {:p}", Box::into_raw(boxed_str));
println!("fn_int:      {:p}", fn_int);}
```

By now, you should be pretty good at accessing addresses of stored values. There are actually two small lessons that you may have also picked up on:

- *Some memory addresses are illegal.* The OS will shut your program down if it attempts to access memory that is out of bounds.
- *Memory addresses are not arbitrary.* Although values seem to be spread quite far apart within the address space, values are clustered together within pockets.

Before pressing on with the cheat program, let's step back and look at the system that's operating behind the scenes to translate these virtual addresses to real memory.

### 6.4.3 Translating virtual addresses to physical addresses

Accessing data in a program requires virtual addresses—the only addresses that the program itself has access to. These get translated into physical addresses. This process involves a dance between the program, the OS, the CPU, the RAM hardware, and occasionally hard drives and other devices. The CPU is responsible for performing this translation, but the OS stores the instructions.

CPUs contain a *memory management unit* (MMU) that is designed for this one job. For every running program, every virtual address is mapped to a physical address. Those instructions are stored at a predefined address in memory as well. That means, in the worst case, every attempt at accessing memory addresses incurs two memory lookups. But it's possible to avoid the worst case.

The CPU maintains a cache of recently translated addresses. It has its own (fast) memory to speed up accessing memory. For historic reasons, this cache is known as the *translation lookaside buffer*, often abbreviated as TLB. Programmers optimizing for performance need to keep data structures lean and avoid deeply nested structures. Reaching the capacity of the TLB (typically around 100 pages for x86 processors) can be costly.

Looking into how the translation system operates reveals more, often quite complex, details. Virtual addresses are grouped into blocks called *pages*, which are typically 4 KB in size. This practice avoids the need to store a translation mapping for every single variable in every program. Having a uniform size for each page also assists in avoiding a phenomenon known as *memory fragmentation*, where pockets of empty, yet unusable, space appear within available RAM.

**NOTE** This is a general guide only. The details of how the OS and CPU cooperate to manage memory differs significantly in some environments. In particular, constrained environments such as microcontrollers can use real addressing. For those interested in learning more, the research field is known as *computer architecture*.

The OS and CPU can play some interesting tricks when data lives within pages of virtual memory. For example

- *Having a virtual address space allows the OS to overallocate.* Programs that ask for more memory than the machine can physically provide are able to be accommodated.
- *Inactive memory pages can be swapped to disk in a byte-for-byte manner until it's requested by the active program.* Swapping is often used during periods of high contention for memory but can be used more generally, depending on an operating system's whims.
- *Other size optimizations such as compression can be performed.* A program sees its memory intact. Behind the scenes, the OS compresses the program's wasteful data usage.
- *Programs are able to share data quickly.* If your program requests a large block of zeroes, say, for a newly created array, the OS might point you towards a page filled with zeroes that is currently being used by three other programs. None of the programs are aware that the others are looking at the same physical memory, and the zeroes have different positions within their virtual address space.

- *Paging can speed up the loading of shared libraries.* As a special case of the previous point, if a shared library is already loaded by another program, the OS can avoid loading it into memory twice by pointing the new program to the old data.
- *Paging adds security between programs.* As you discovered earlier in this section, some parts of the address space are illegal to access. The OS has other attributes that it can add. If an attempt is made to write to a read-only page, the OS terminates the program.

Making effective use of the virtual memory system in day-to-day programs requires thinking about how data is represented in RAM. Here are some guidelines:


- *Keep hot working portions of your program within 4 KB of size.* This maintains fast lookups.
- *If 4 KB is unreasonable for your application, then the next target to keep under is 4 KB \* 100.* That rough guide should mean that the CPU can maintain its translation cache (the TLB) in good order to support your program.
- *Avoid deeply nested data structures with pointer spaghetti.* If a pointer points to another page, then performance suffers.
- *Test the ordering of your nested loops.* CPUs read small blocks of bytes, known as a *cache line*, from the RAM hardware. When processing an array, you can take advantage of this by investigating whether you are doing column-wise or row-wise operations.

One thing to note: virtualization makes this situation worse. If you're running an app inside a virtual machine, the hypervisor must also translate addresses for its guest operating systems. This is why many CPUs ship with virtualization support, which can reduce this extra overhead. Running containers within virtual machines adds another layer of indirection and, therefore, latency. For bare-metal performance, run apps on bare metal.

#### How does an executable file turn into a program's virtual address space?

The layout of executable files (aka binaries) has many similarities to the address space diagram that we saw earlier in the heap versus stack section of the chapter.

While the exact process is dependent on the OS and file format, the following figure shows a representative example. Each of the segments of the address space that we have discussed are described by binary files. When the executable is started, the OS loads the right bytes into the right places. Once the virtual address space is created, the CPU can be told to jump to the start of the .text segment, and the program begins executing.



#### 6.4.4 Step 2: Working with the OS to scan an address space

Our task is to scan our program's memory while it's running. As we've discovered, the OS maintains the instructions for mapping between a virtual address and a physical address. Can we ask the OS to tell us what is happening?

Operating systems provide an interface for programs to be able to make requests; this is known as a *system call*. Within Windows, the KERNEL.DLL provides the necessary functionality to inspect and manipulate the memory of a running process.

**NOTE** Why Windows? Well, many Rust programmers use MS Windows as a platform. Also, its functions are well named and don't require as much prior knowledge as the POSIX API.

When you run listing 6.16, you should see lots of output with many sections. This may be similar to the following:

```
MEMORY_BASIC_INFORMATION {
    BaseAddress: 0x00007ffbe8d9b000,
```

← This struct is defined within the Windows API.

```

AllocationBase: 0x0000000000000000,
AllocationProtect: 0,
RegionSize: 17568124928,
State: 65536,
Protect: 1,
Type: 0
}
MEMORY_BASIC_INFORMATION {
    BaseAddress: 0x00007fffffe0000,
    AllocationBase: 0x00007fffffe0000,
    AllocationProtect: 2,
    RegionSize: 65536,
    State: 8192,
    Protect: 1,
    Type: 131072
}

```

These fields are the integer representations of enums defined in the Windows API. It's possible to decode these to the enum variant names, but this isn't available without adding extra code to the listing.

The following listing shows the dependencies for listing 6.16. You can find its source in ch6/ch6-meminfo-win/Cargo.toml.

#### Listing 6.15 Dependencies for listing 6.16

```

[package]
name = "meminfo"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
winapi = "0.2" # Defines some useful type aliases
kernel32-sys = "0.2" # Provides interaction with KERNEL.DLL from the Windows API

```

The following listing shows how to inspect memory via the Windows API. The source code for this listing is in ch6/ch6-meminfo-win/src/main.rs.

#### Listing 6.16 Inspecting a program's memory

```

use kernel32;
use winapi;

use winapi::{
    DWORD,
    HANDLE,
    LPVOID,
    PVOID,
    SIZE_T,
    LPSYSTEM_INFO,
    SYSTEM_INFO,
    MEMORY_BASIC_INFORMATION as MEMINFO,
};

u64 is the usize on this machine.
A pointer to a SYSTEM_INFO struct

```

In Rust, this would be a u32.

Pointer types for various internal APIs without an associated type. In Rust, std::os::raw::c\_void defines void pointers; a HANDLE is a pointer to some opaque resource within Windows.

In Windows, data type names are often prefixed with a shorthand for their type. P stands for pointer; LP stands for long pointer (e.g., 64 bit).

Some structs defined by Windows internally

Rather than use a return value, this function makes use of a C idiom to provide its result to the caller. We provide a pointer to some predefined struct, then read that struct's new values once the function returns to see the results.

```

fn main() {
    let this_pid: DWORD;
    let this_proc: HANDLE;
    let min_addr: LPVOID;
    let max_addr: LPVOID;
    let mut base_addr: PVOID;
    let mut proc_info: SYSTEM_INFO;
    let mut mem_info: MEMORY_BASIC_INFORMATION;

    const MEMINFO_SIZE: usize = std::mem::size_of::<MEMINFO>();

    unsafe {
        base_addr = std::mem::zeroed();
        proc_info = std::mem::zeroed();
        mem_info = std::mem::zeroed();
    }

    unsafe {
        this_pid = kernel32::GetCurrentProcessId();
        this_proc = kernel32::GetCurrentProcess();
        kernel32::GetSystemInfo(
            &mut proc_info as *mut SYSTEM_INFO
        );
    }

    min_addr = proc_info.lpMinimumApplicationAddress;
    max_addr = proc_info.lpMaximumApplicationAddress;
}

println!("{:?} @ {:p}", this_pid, this_proc);
println!("{:?}", proc_info);
println!("min: {:p}, max: {:p}", min_addr, max_addr);

loop {
    let rc: SIZE_T = unsafe {
        kernel32::VirtualQueryEx(
            this_proc,
            base_addr,
            &mut mem_info,
            MEMINFO_SIZE as SIZE_T
        );
    };

    if rc == 0 {
        break
    }

    println!("{:#?}", mem_info);
    base_addr = ((base_addr as u64) + mem_info.RegionSize) as PVOID;
}
}

```

**Initializes these variables from within unsafe blocks. To make these accessible in the outer scope, these need to be defined here.**

**This block guarantees that all memory is initialized.**

**This block of code is where system calls are made.**

**Renaming these variables for convenience**

**This loop does the work of scanning through the address space.**

**Provides information about a specific segment of the running program's memory address space, starting at base\_addr**

Finally, we have been able to explore an address space without the OS killing our program. Now the question remains: How do we inspect individual variables and modify those?

### 6.4.5 Step 3: Reading from and writing to process memory

Operating systems provide tools to read and write memory, even in other programs. This is essential for Just-In-Time compilers (JITs), debuggers, and programs to help people “cheat” at games. On Windows, the general process looks something like this in Rust-like pseudocode:

```
let pid = some_process_id;
OpenProcess(pid);

loop address space {
    *call* VirtualQueryEx() to access the next memory segment

    *scan* the segment by calling ReadProcessMemory(),
    looking for a selected pattern

    *call* WriteProcessMemory() with the desired value
}
```

Linux provides an even simpler API via `process_vm_readv()` and `process_vm_writev()`. These are analogous to `ReadProcessMemory()` and `WriteProcessMemory()` in Windows.

Memory management is a complicated area with many levels of abstraction to uncover. This chapter has tried to focus on those elements that are most salient to your work as a programmer. Now, when you read your next blog post on some low-level coding technique, you should be able to follow along with the terminology.

## Summary

- Pointers, references, and memory addresses are identical from the CPU’s perspective, but these are significantly different at the programming language level.
- Strings and many other data structures are implemented with a backing array pointed to by a pointer.
- The term *smart pointer* refers to data structures that behave like pointers but have additional capabilities. These almost always incur a space overhead. Additionally, data can include integer length and capacity fields or things that are more sophisticated, such as locks.
- Rust has a rich collection of smart pointer types. Types with more features typically incur greater runtime costs.
- The standard library’s smart pointer types are built from building blocks that you can also use to define your own smart pointers if required.
- The heap and the stack are abstractions provided by operating systems and programming languages. These do not exist at the level of the CPU.
- Operating systems often provide mechanisms such as memory allocations to inspect a program’s behavior.



# *Files and storage*

## **This chapter covers**

- Learning how data is represented on physical storage devices
- Writing data structures to your preferred file format
- Building a tool to read from a file and inspect its contents
- Creating a working key-value store that's immune from corruption

Storing data permanently on digital media is trickier than it looks. This chapter takes you through some of the details. To transfer information held by ephemeral electrical charges in RAM to (semi)permanent storage media and then be able to retrieve it again later takes several layers of software indirection.

The chapter introduces some new concepts such as how to structure projects into library crates for Rust developers. This task is needed because one of the projects is ambitious. By the end of the chapter, you'll have built a working key-value store that's guaranteed to be durable to hardware failure at any stage. During the chapter, we'll work through a small number of side quests. For example, we implement parity

bit checking and explore what it means to hash a value. To start with, however, let's see if we can create patterns from the raw byte sequence within files.



## 7.1 What is a file format?

File formats are standards for working with data as a single, ordered sequence of bytes. Storage media like hard disk drives work faster when reading or writing large blocks of data in serial. This contrasts with in-memory data structures, where data layout has less of an impact.


File formats live in a large design space with trade-offs in performance, human-readability, and portability. Some formats are highly portable and self-describing. Others restrict themselves to being accessible within a single environment and are unable to be read by third-party tools, yet they are high performance.

Table 7.1 illustrates some of the design space for file formats. Each row reveals the file format's internal patterns, which are generated from the same source text. By color-coding each byte within the file, it's possible to see structural differences between each representation.

**Table 7.1 The internals of four digital versions of William Shakespeare's *Much Ado About Nothing* produced by Project Gutenberg.**

	<p>The plain text version of the play contains printable characters only. These are indicated by dark grey for letters and punctuation, and white for whitespace. Visually, the image appears to be noisy. It lacks internal structure. That's due to the variation in length of the natural language that the file represents. A file with regular, repeating structures, such as a file format designed to hold arrays of floating-point numbers, tends to look quite different.</p>
	<p>The EPUB format is actually a compressed ZIP archive with a bespoke file extension. There are many bytes within the file that fall out of the range of the printable category as indicated by the mid-grey pixels.</p>
	<p>MOBI includes four bands of NULL bytes (0x00), represented as black pixels. These bands probably represent the result of an engineering trade-off. In some sense, these empty bytes are wasted space. They're probably added as padding so that the file's sections are easy to parse later on. The other notable feature of this file is its size. It's larger than the other versions of the play. This might imply that the file is harboring more data than just the text. Candidates include display elements like fonts, or encryption keys that enforce anti-copying restrictions within the file.</p>

**Table 7.1 The internals of four digital versions of William Shakespeare's *Much Ado About Nothing* produced by Project Gutenberg. (continued)**

	<p>The HTML file contains a high proportion of whitespace characters. These are indicated by white pixels. Markup languages like HTML tend to add whitespace to aid readability.</p>
---	--

## 7.2 Creating your own file formats for data storage

When working with data that needs to be stored over a long time, the proper thing to do is to use a battle-tested database. Despite this, many systems use plain text files for data storage. Configuration files, for example, are commonly designed to be both human-readable and machine-readable. The Rust ecosystem has excellent support for converting data to many on-disk formats.

### 7.2.1 Writing data to disk with `serde` and the `bincode` format

The `serde` crate *serializes* and *deserializes* Rust values to and from many formats. Each format has its own strengths: many are human-readable, while others prefer to be compact so that they can be speedily sent across the network.

Using `serde` takes surprisingly little ceremony. As an example, let's use statistics about the Nigerian city of Calabar and store those in multiple output formats. To start, let's assume that our code contains a `City` struct. The `serde` crate provides the `Serialize` and `Deserialize` traits, and most code implements these with this derived annotation:

```
# [derive(Serialize)]
struct City {
    name: String,
    population: usize,
    latitude: f64,
    longitude: f64,
}
```

Provides the tooling  
to enable external  
formats to interact  
with Rust code

Populating that struct with data about Calabar is straightforward. This code snippet shows the implementation:

```
let calabar = City {
    name: String::from("Calabar"),
    population: 470_000,
    latitude: 4.95,
    longitude: 8.33,
};
```

Now to convert that `calabar` variable to JSON-encoded `String`. Performing the conversion is one line of code:

```
let as_json = to_json(&calabar).unwrap();
```

serde understands many more formats than JSON. The code in listing 7.2 (shown later in this section) also provides similar examples for two lesser-known formats: CBOR and bincode. CBOR and bincode are more compact than JSON but at the expense of being machine-readable only.

The following shows the output, formatted for the page, that's produced by listing 7.2. It provides a view of the bytes of the `calabar` variable in several encodings:

```
$ cargo run
   Compiling ch7-serde-eg v0.1.0 (/rust-in-action/code/ch7/ch7-serde-eg)
   Finished dev [unoptimized + debuginfo] target(s) in 0.27s
     Running `target/debug/ch7-serde-eg`  

json:  

{"name": "Calabar", "population": 470000, "latitude": 4.95, "longitude": 8.33}  

cbor:  

[164, 100, 110, 97, 109, 101, 103, 67, 97, 108, 97, 98, 97, 114, 106,  

112, 111, 112, 117, 108, 97, 116, 105, 111, 110, 26, 0, 7, 43, 240, 104,  

108, 97, 116, 105, 116, 117, 100, 101, 251, 64, 19, 204, 204, 204, 204,  

204, 205, 105, 108, 111, 110, 103, 105, 116, 117, 100, 101, 251, 64, 32,  

168, 245, 194, 143, 92, 41]  

bincode:  

[7, 0, 0, 0, 0, 0, 0, 67, 97, 108, 97, 98, 97, 114, 240, 43, 7, 0, 0,  

0, 0, 0, 205, 204, 204, 204, 204, 19, 64, 41, 92, 143, 194, 245, 168,  

32, 64]  

json (as UTF-8):  

{"name": "Calabar", "population": 470000, "latitude": 4.95, "longitude": 8.33}  

cbor (as UTF-8):  

dnamegCalabarjpopulation+hlatitude@?#?#?#?ilongitude@ ??\()  

bincode (as UTF-8):  

Calabar@+????????@)\ ????? @
```

To download the project, enter these commands in the console:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch7/ch7-serde-eg
```

To create the project manually, create a directory structure that resembles the following snippet and populate its contents with the code in listings 7.1 and 7.2 from the `ch7/ch7-serde-eg` directory:

```
ch7-serde-eg
|--- src
```

```

└── main.rs      ← See listing 7.2.
└── Cargo.toml   ← See listing 7.1.

```

### Listing 7.1 Declaring dependencies and setting metadata for listing 7.2

```
[package]
name = "ch7-serde-eg"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
bincode = "1"
serde = "1"
serde_cbor = "0.8"
serde_derive = "1"
serde_json = "1"
```

### Listing 7.2 Serialize a Rust struct to multiple formats

```

1 use bincode::serialize as to_bincode;
2 use serde_cbor::to_vec as to_cbor;
3 use serde_json::to_string as to_json;
4 use serde_derive::{Serialize};
5
6 #[derive(Serialize)]
7 struct City {
8     name: String,
9     population: usize,
10    latitude: f64,
11    longitude: f64,
12 }
13
14 fn main() {
15     let calabar = City {
16         name: String::from("Calabar"),
17         population: 470_000,
18         latitude: 4.95,
19         longitude: 8.33,
20     };
21
22     let as_json      = to_json(&calabar).unwrap();
23     let as_cbor      = to_cbor(&calabar).unwrap();
24     let as_bincode   = to_bincode(&calabar).unwrap();
25
26     println!("json:\n{}\n", &as_json);
27     println!("cbor:\n{:?}\n", &as_cbor);
28     println!("bincode:\n{:?}\n", &as_bincode);
29     println!("json (as UTF-8):\n{}\n",
30             String::from_utf8_lossy(as_json.as_bytes())
31         );
32     println!("cbor (as UTF-8):\n{:?}\n",
33             String::from_utf8_lossy(&as_cbor)
```

These functions are renamed to shorten lines where used.

Instructs the `serde_derive` crate to write the necessary code to carry out the conversion from an in-memory `City` to on-disk `City`

Serializes into different formats

```

34      );
35      println!("bincode (as UTF-8):\n{:?}\n",
36          String::from_utf8_lossy(&as_bincode)
37      );
38 }

```

### 7.3 Implementing a hexdump clone

A handy utility for inspecting a file's contents is hexdump, which takes a stream of bytes, often from a file, and then outputs those bytes in pairs of hexadecimal numbers. Table 7.2 provides an example. As you know from previous chapters, two hexadecimal numbers can represent all digits from 0 to 255, which is the number of bit patterns representable within a single byte. We'll call our clone `fview` (short for file view).

**Table 7.2** `fview` in operation

<code>fview input</code>	<code>fn main() {     println!("Hello, world!"); }</code>
<code>fview output</code>	<code>[0x00000000] 0a 66 6e 20 6d 61 69 6e 28 29 20 7b 0a 20 20 20 [0x00000010] 20 70 72 69 6e 74 6c 6e 21 28 22 48 65 6c 6c 6f [0x00000020] 2c 20 77 6f 72 6c 64 21 22 29 3b 0a 7d</code>

Unless you're familiar with hexadecimal notation, the output from `fview` can be fairly opaque. If you're experienced at looking at similar output, you may notice that there are no bytes above `0x7e` (127). There are also few bytes less than `0x21` (33), with the exception of `0xa` (10). `0xa` represents the newline character (`\n`). These byte patterns are markers for a plain text input source.

Listing 7.4 provides the source code that builds the complete `fview`. But because a few new features of Rust need to be introduced, we'll take a few steps to get to the full program.

We'll start with listing 7.3, which uses a string literal as input and produces the output in table 7.2. It demonstrates the use of multiline string literals, importing the `std::io` traits via `std::io::prelude`. This enables `&[u8]` types to be read as files via the `std::io::Read` trait. The source for this listing is in `ch7/ch7-fview-str/src/main.rs`.

#### Listing 7.3 A hexdump clone with hard-coded input that mocks file I/O

```

1 use std::io::prelude::*;
2
3 const BYTES_PER_LINE: usize = 16;
4 const INPUT: &'static [u8] = br#"
5 fn main() {
6     println!("Hello, world!");
7 }"#;
8
9 fn main() -> std::io::Result<()> {

```

prelude imports heavily used traits such as `Read` and `Write` in I/O operations. It's possible to include the traits manually, but they're so common that the standard library provides this convenience line to help keep your code compact.

Multiline string literals don't need double quotes escaped when built with raw string literals (the `r` prefix and the `#` delimiters). The additional `b` prefix indicates that this should be treated as bytes (`&[u8]`) not as UTF-8 text (`&str`).

```

10 let mut buffer: Vec<u8> = vec!();           ← Makes space for the
11 INPUT.read_to_end(&mut buffer)?;             ← program's input with
12
13 let mut position_in_input = 0;               ← an internal buffer
14 for line in buffer.chunks(BYTES_PER_LINE) {
15     print!("[0x{:08x}] ", position_in_input); ← Reads our input and
16     for byte in line {                         ← inserts it into our
17         print!("{:02x} ", byte);                ← internal buffer
18     }
19     println!();                                ← Writes the current
20     position_in_input += BYTES_PER_LINE;        ← position with up to 8
21 }
22
23 Ok(())
24 }
```

Shortcut for printing  
a newline to stdout

Now that we have seen the intended operation of `fview`, let's extend its capabilities to read real files. The following listing provides a basic hexdump clone that demonstrates how to open a file in Rust and iterate through its contents. You'll find this source in `ch7/ch7-fview/src/main.rs`.

#### Listing 7.4 Opening a file in Rust and iterating through its contents

```

1 use std::fs::File;
2 use std::io::prelude::*;
3 use std::env;
4
5 const BYTES_PER_LINE: usize = 16;           ← Changing this constant
6                                         changes the program's
7 fn main() {
8     let arg1 = env::args().nth(1);
9
10    let fname = arg1.expect("usage: fview FILENAME");
11
12    let mut f = File::open(&fname).expect("Unable to open file.");
13    let mut pos = 0;
14    let mut buffer = [0; BYTES_PER_LINE];
15
16    while let Ok(_) = f.read_exact(&mut buffer) {
17        print!("[0x{:08x}] ", pos);
18        for byte in &buffer {
19            match *byte {
20                0x00 => print!("."),
21                0xff => print!("##"),
22                _ => print!("{:02x} ", byte),
23            }
24        }
25
26        println!("");
27        pos += BYTES_PER_LINE;
28    }
29 }
```

Listing 7.4 introduces some new Rust. Let's look at some of those constructs now:

- `while let Ok(_) { ... }`— With this control-flow structure, the program continues to loop until `f.read_exact()` returns `Err`, which occurs when it has run out of bytes to read.
- `f.read_exact()`—This method from the `Read` trait transfers data from the source (in our case, `f`) to the buffer provided as an argument. It stops when that buffer is full.

`f.read_exact()` provides greater control to you as a programmer for managing memory than the `chunks()` option used in listing 7.3, but it comes with some quirks. If the buffer is longer than the number of available bytes to read, the file returns an error, and the state of the buffer is undefined. Listing 7.4 also includes some stylistic additions:

- *To handle command-line arguments without using third-party libraries, we make use of `std::env::args()`.* It returns an iterator over the arguments provided to the program. Iterators have an `nth()` method, which extracts the element at the `n`th position.
- *Every iterator's `nth()` method returns an `Option`.* When `n` is larger than the length of the iterator, `None` is returned. To handle these `Option` values, we use calls to `expect()`.
- *The `expect()` method is considered a friendlier version of `unwrap()`.* `expect()` takes an error message as an argument, whereas `unwrap()` simply panics abruptly.

Using `std::env::args()` directly means that input is not validated. That's a problem in our simple example, but is something to consider for larger programs.

## 7.4 File operations in Rust

So far in this chapter, we have invested a lot of time considering how data is translated into sequences of bytes. Let's spend some time considering another level of abstraction—the file. Previous chapters have covered basic operations like opening and reading from a file. This section contains some other helpful techniques, which provide more granular control.

### 7.4.1 Opening a file in Rust and controlling its file mode

Files are an abstraction that's maintained by the operating system (OS). It presents a façade of names and hierarchy above a nest of raw bytes.

Files also provide a layer of security. These have attached permissions that the OS enforces. This (in principle, at least) is what prevents a web server running under its own user account from reading files owned by others.

`std::fs::File` is the primary type for interacting with the filesystem. There are two methods available for creating a file: `open()` and `create()`. Use `open()` when you know the file already exists. Table 7.3 explains more of their differences.

Table 7.3 Creating File values in Rust and the effects on the underlying filesystem

Method	Return value when the file already exists	Effect on the underlying file	Return value when no file exists
File::open	Ok(File) *	Opened as is in read-only mode.	Err
File::create	Ok(File) *	All existing bytes are truncated, and the file is opened at the beginning of the new file.	Ok(File) *

\* Assuming the user account has sufficient permission.

When you require more control, `std::fs::OpenOptions` is available. It provides the necessary knobs to turn for any intended application. Listing 7.16 provides a good example of a case where an append mode is requested. The application requires a writeable file that is also readable, and if it doesn't already exist, it's created. The following shows an excerpt from listing 7.16 that demonstrates the use of `std::fs::OpenOptions` to create a writeable file. The file is not truncated when it's opened.

#### Listing 7.5 Using `std::fs::OpenOptions` to create a writeable file

An example of the Builder pattern where each method returns a new instance of the `OpenOptions` struct with the relevant option set

```
let f = OpenOptions::new()
    .read(true)
    .write(true)
    .create(true)
    .append(true)
    .open(path)?;
```

Opens the file for reading

Enables writing. This line isn't strictly necessary; it's implied by append.

Creates a file at path if it doesn't already exist

Doesn't delete content that's already written to disk

Opens the file at path after unwrapping the intermediate Result

#### 7.4.2 Interacting with the filesystem in a type-safe manner with `std::fs::Path`

Rust provides type-safe variants of `str` and `String` in its standard library: `std::path::Path` and `std::path::PathBuf`. You can use these variants to unambiguously work with path separators in a cross-platform way. `Path` can address files, directories, and related abstractions, such as symbolic links. `Path` and `PathBuf` values often start their lives as plain string types, which can be converted with the `from()` static method:

```
let hello = PathBuf::from("/tmp/hello.txt")
```

From there, interacting with these variants reveals methods that are specific to paths:

```
hello.extension() ← Returns Some("txt")
```

The full API is straightforward for anyone who has used code to manipulate paths before, so it won't be fleshed out here. Still, it may be worth discussing why it's included within the language because many languages omit this.

**NOTE** As an implementation detail, `std::fs::Path` and `std::fs::PathBuf` are implemented on top of `std::ffi::OsStr` and `std::ffi::OsString`, respectively. This means that `Path` and `PathBuf` are *not* guaranteed to be UTF-8 compliant.

Why use `Path` rather than manipulating strings directly? Here are some good reasons for using `Path`:

- *Clear intent*—`Path` provides useful methods like `set_extension()` that describe the intended outcome. This can assist programmers who later read the code. Manipulating strings doesn't provide that level of self-documentation.
- *Portability*—Some operating systems treat filesystem paths as case-insensitive. Others don't. Using one operating system's conventions can result in issues later, when users expect their host system's conventions to be followed. Additionally, path separators are specific to operating systems and, thus, can differ. This means that using raw strings can lead to portability issues. Comparisons require exact matches.
- *Easier debugging*—If you're attempting to extract `/tmp` from the path `/tmp/hello.txt`, doing it manually can introduce subtle bugs that may only appear at runtime. Further, miscounting the correct number of index values after splitting the string on `/` introduces a bug that can't be caught at compile time.

To illustrate the subtle errors, consider the case of separators. Slashes are common in today's operating systems, but those conventions took some time to become established:

- `\` is commonly used on MS Windows.
- `/` is the convention for UNIX-like operating systems.
- `:` was the path separator for the classic Mac OS.
- `>` is used in the Stratus VOS operating system.

Table 7.4 compares the two strings: `std::String` and `std::path::Path`.

**Table 7.4 Using `std::String` and `std::path::Path` to extract a file's parent directory**

<pre>fn main() {     let hello = String::from("/tmp/ hello.txt");     let tmp_dir = hello.split("/").nth(0);     println!("{}: {}", tmp_dir);</pre> <p><b>Splits hello at its backslashes, then takes the 0th element of the resulting Vec&lt;String&gt;.</b></p>	<p><b>Mistake!</b> Prints Some("tmp").</p>	<pre>use std::path::PathBuf;</pre>
		<pre>fn main() {     let mut hello = PathBuf::from("/tmp/ hello.txt");     hello.pop(); // Truncates hello in place     println!("{}: {}", hello.display());</pre> <p><b>Success! Prints "/tmp".</b></p>

**Table 7.4 Using std::String and std::path::Path to extract a file's parent directory (continued)**

The plain String code lets you use familiar methods, but it can introduce subtle bugs that are difficult to detect at compile time. In this instance, we've used the wrong index number to access the parent directory (/tmp).	Using path::Path doesn't make your code immune to subtle errors, but it can certainly help to minimize their likelihood. Path provides dedicated methods for common operations such as setting a file's extension.
--	--

## 7.5 Implementing a key-value store with a log-structured, append-only storage architecture

It's time to tackle something larger. Let's begin to lift the lid on database technology. Along the way, we'll learn the internal architecture of a family of database systems using a *log-structured, append-only* model.

Log-structured, append-only database systems are significant as case studies because these are designed to be extremely resilient while offering optimal read performance. Despite storing data on fickle media like flash storage or a spinning hard disk drive, databases using this model are able to guarantee that data will never be lost and that backed up data files will never be corrupted.

### 7.5.1 The key-value model

The key-value store implemented in this chapter, actionkv, stores and retrieves sequences of bytes ([u8]) of arbitrary length. Each sequence has two parts: the first is a key and the second is a value. Because the &str type is represented as [u8] internally, table 7.5 shows the plain text notation rather than the binary equivalent.

**Table 7.5 Illustrating keys and values by matching countries with their capital cities**

Key	Value
"Cook Islands"	"Avarua"
"Fiji"	"Suva"
"Kiribati"	"South Tarawa"
"Niue"	"Alofi"

The key-value model enables simple queries such as "What is the capital city of Fiji?" But it doesn't support asking broader queries such as "What is the list of capital cities for all Pacific Island states?"

### 7.5.2 Introducing actionkv v1: An in-memory key-value store with a command-line interface

The first version of our key-value store, actionkv, exposes us to the API that we'll use throughout the rest of the chapter and also introduces the main library code. The library code will not change as the subsequent two systems are built on top of it. Before we get to that code, though, there are some prerequisites that need to be covered.

Unlike other projects in this book, this one uses the library template to start with (`cargo new --lib actionkv`). It has the following structure:

```
actionkv
└── src
    └── akv_mem.rs
    └── lib.rs
Cargo.toml
```

Using a library crate allows programmers to build reusable abstractions within their projects. For our purposes, we'll use the same `lib.rs` file for multiple executables. To avoid future ambiguity, we need to describe the executable binaries the `actionkv` project produces.

To do so, provide a `bin` section within two square bracket pairs (`[[bin]]`) to the project's `Cargo.toml` file. See lines 14–16 of the following listing. Two square brackets indicate that the section can be repeated. The source for this listing is in `ch7/ch7-actionkv/Cargo.toml`.

#### Listing 7.6 Defining dependencies and other metadata

```
1 [package]
2 name = "actionkv"
3 version = "1.0.0"
4 authors = ["Tim McNamara <author@rustinaction.com>"]
5 edition = "2018"
6
7 [dependencies]
8 byteorder = "1.2"           ← Extends Rust types with extra traits to write
9 crc = "1.7"                 ← those to disk, then reads those back into a
                               program in a repeatable, easy-to-use way
10
11 [lib]                      ← Provides the checksum functionality that we want to include
12 name = "libactionkv"
13 path = "src/lib.rs"
14
15 [[bin]]                    ← This section of Cargo.toml lets you define a
16 name = "akv_mem"            ← name for the library you're building. Note
17 path = "src/akv_mem.rs"      ← that a crate can only have one library.
                               A [[bin]] section, of which there can be many, defines an
                               executable file that's built from this crate. The double square
                               bracket syntax is required because it unambiguously
                               describes bin as having one or more elements.
```

Our `actionkv` project will end up with several files. Figure 7.1 illustrates the relationships and how these work together to build the `akv_mem` executable, referred to within the `[[bin]]` section of the project's `Cargo.toml` file.




Figure 7.1 An outline of how the different files and their dependencies work together in the `actionkv` project. The project's `Cargo.toml` coordinates lots of activity that ultimately results in an executable.

## 7.6 Actionkv v1: The front-end code

The public API of `actionkv` is comprised of four operations: `get`, `delete`, `insert`, and `update`. Table 7.6 describes these operations.

Table 7.6 Operations supported by `actionkv` v1

Command	Description
<code>get &lt;key&gt;</code>	Retrieves the value at <code>key</code> from the store
<code>insert &lt;key&gt; &lt;value&gt;</code>	Adds a key-value pair to the store
<code>delete &lt;key&gt;</code>	Removes a key-value pair from the store
<code>update &lt;key&gt; &lt;value&gt;</code>	Replaces an old value with a new one

### Naming is difficult

To access stored key-value pairs, should the API provide a `get`, `retrieve`, or, perhaps, `fetch`? Should setting values be `insert`, `store`, or `set`? `actionkv` attempts to stay neutral by deferring these decisions to the API provided by `std::collections::HashMap`.

The following listing, an excerpt from listing 7.8, shows the naming considerations mentioned in the preceding sidebar. For our project, we use Rust's matching facilities to efficiently work with the command-line arguments and to dispatch to the correct internal function.

**Listing 7.7 Demonstrating the public API**

```

32 match action {
33     "get" => match store.get(key).unwrap() {
34         None => eprintln!("{} not found", key),
35         Some(value) => println!("{}: {}", key, value),
36     },
37
38     "delete" => store.delete(key).unwrap(),
39
40     "insert" => {
41         let value = maybe_value.expect(&USAGE).as_ref();
42         store.insert(key, value).unwrap()
43     }
44
45     "update" => {
46         let value = maybe_value.expect(&USAGE).as_ref();
47         store.update(key, value).unwrap()
48     }
49
50     _ => eprintln!("{}: {}", key, &USAGE),
51 }
```

The action command-line argument has the type `&str`.

`println!` needs to use the Debug syntax `({:?})` because `[u8]` contains arbitrary bytes and doesn't implement `Display`.

A future update that can be added for compatibility with Rust's `HashMap`, where `insert` returns the old value if it exists.

In full, listing 7.8 presents the code for actionkv v1. Notice that the heavy lifting of interacting with the filesystem is delegated to an instance of ActionKV called `store`. How ActionKV operates is explained in section 7.7. The source for this listing is in `ch7/ch7-actionkv/src/akv_mem.rs`.

**Listing 7.8 In-memory key-value store command-line application**

```

1 use libactionkv::ActionKV;
2
3 #[cfg(target_os = "windows")]
4 const USAGE: &str =
5 Usage:
6     akv_mem.exe FILE get KEY
7     akv_mem.exe FILE delete KEY
8     akv_mem.exe FILE insert KEY VALUE
9     akv_mem.exe FILE update KEY VALUE
10 ";
11
12 #[cfg(not(target_os = "windows"))]
13 const USAGE: &str =
14 Usage:
15     akv_mem FILE get KEY
16     akv_mem FILE delete KEY
17     akv_mem FILE insert KEY VALUE
18     akv_mem FILE update KEY VALUE
19 ";
20
21 fn main() {
22     let args: Vec<String> = std::env::args().collect();
23     let fname = args.get(1).expect(&USAGE);
```

Although `src/lib.rs` exists within our project, it's treated the same as any other crate within the `src/bin.rs` file.

The `cfg` attribute allows Windows users to see the correct file extension in their help documentation. This attribute is explained in the next section.

```

24 let action = args.get(2).expect(&USAGE).as_ref();
25 let key = args.get(3).expect(&USAGE).as_ref();
26 let maybe_value = args.get(4);
27
28 let path = std::path::Path::new(&fname);
29 let mut store = ActionKV::open(path).expect("unable to open file");
30 store.load().expect("unable to load data");
31
32 match action {
33     "get" => match store.get(key).unwrap() {
34         None => eprintln!("{} not found", key),
35         Some(value) => println!("{}: {}", key, value),
36     },
37
38     "delete" => store.delete(key).unwrap(),
39
40     "insert" => {
41         let value = maybe_value.expect(&USAGE).as_ref();
42         store.insert(key, value).unwrap()
43     }
44
45     "update" => {
46         let value = maybe_value.expect(&USAGE).as_ref();
47         store.update(key, value).unwrap()
48     }
49
50     _ => eprintln!("{}: {}", &USAGE),
51 }
52 }
```

### 7.6.1 Tailoring what is compiled with conditional compilation

Rust provides excellent facilities for altering what is compiled depending on the *compiler target architecture*. Generally, this is the target's OS but can be facilities provided by its CPU. Changing what is compiled depending on some compile-time condition is known as *conditional compilation*.

To add conditional compilation to your project, annotate your source code with `cfg` attributes. `cfg` works in conjunction with the `target` parameter provided to `rustc` during compilation.

Listing 7.8 provides a usage string common as quick documentation for command-line utilities for multiple operating systems. It's replicated in the following listing, which uses conditional compilation to provide two definitions of `const USAGE` in the code. When the project is built for Windows, the usage string contains a .exe file extension. The resulting binary files include only the data that is relevant for their target.

#### Listing 7.9 Demonstrating the use of conditional compilation

```

3 #[cfg(target_os = "windows")]
4 const USAGE: &str = "
5 Usage:
6     akv_mem.exe FILE get KEY
```

```

7     akv_mem.exe FILE delete KEY
8     akv_mem.exe FILE insert KEY VALUE
9     akv_mem.exe FILE update KEY VALUE
10   ";
11
12 #[cfg(not(target_os = "windows"))]
13 const USAGE: &str = "
14 Usage:
15     akv_mem FILE get KEY
16     akv_mem FILE delete KEY
17     akv_mem FILE insert KEY VALUE
18     akv_mem FILE update KEY VALUE
19 ";

```

There is no negation operator for these matches. That is, `#[cfg(target_os != "windows")]` does not work. Instead, there is a function-like syntax for specifying matches. Use `#[cfg(not(...))]` for negation. `#[cfg(all(...))]` and `#[cfg(any(...))]` are also available to match elements of a list. Lastly, it's possible to tweak `cfg` attributes when invoking cargo or rustc via the `--cfg ATTRIBUTE` command-line argument.

The list of conditions that can trigger compilation changes is extensive. Table 7.7 outlines several of these.

**Table 7.7 Options available to match against with `cfg` attributes**

Attribute	Valid options	Notes
<code>target_arch</code>	<code>aarch64, arm, mips, powerpc, powerpc64, x86, x86_64</code>	Not an exclusive list.
<code>target_os</code>	<code>android, bitrig, dragonfly, freebsd, haiku, ios, linux, macos, netbsd, redox, openbsd, windows</code>	Not an exclusive list.
<code>target_family</code>	<code>unix, windows</code>	
<code>target_env</code>	<code>"", gnu, msvc, musl</code>	This is often an empty string ("").
<code>target_endian</code>	<code>big, little</code>	
<code>target_pointer_width</code>	<code>32, 64</code>	The size (in bits) of the target architecture's pointer. Used for <code>isize</code> , <code>usize</code> , <code>* const</code> , and <code>* mut</code> types.
<code>target_has_atomic</code>	<code>8, 16, 32, 64, ptr</code>	Integer sizes that have support for atomic operations. During atomic operations, the CPU takes responsibility for preventing race conditions with shared data at the expense of performance. The word <code>atomic</code> is used in the sense of indivisible.

Table 7.7 Options available to match against with cfg attributes (continued)

Attribute	Valid options	Notes
target_vendor	apple, pc, unknown	
test		No available options; just uses a simple Boolean check.
debug_assertions		No available options; just uses a simple Boolean check. This attribute is present for non-optimized builds and supports the debug_assert! macro.

## 7.7 Understanding the core of actionkv: The libactionkv crate

The command-line application built in section 7.6 dispatches its work to libactionkv::ActionKV. The responsibilities of the ActionKV struct are to manage interactions with the filesystem and to encode and decode data from the on-disk format. Figure 7.2 depicts the relationships.

### 7.7.1 Initializing the ActionKV struct

Listing 7.10, an excerpt from listing 7.8, shows the initialization process of libactionkv::ActionKV. To create an instance of libactionkv::ActionKV, we need to do the following:

- 1 Point to the file where the data is stored
- 2 Load an in-memory index from the data within the file

#### Listing 7.10 Initializing libactionkv::ActionKV

```
30 let mut store = ActionKV::open(path)
31             .expect("unable to open file");    ← Opens the file at path
32
33 store.load().expect("unable to load data"); ← Creates an in-memory index by
                                                loading the data from path
```

Both steps return Result, which is why the calls to .expect() are also present. Let's now look inside the code of ActionKV::open() and ActionKV::load(). open() opens the file from disk, and load() loads the offsets of any pre-existing data into an in-memory index. The code uses two type aliases, ByteStr and ByteString:

```
type ByteStr = [u8];
```



Figure 7.2 Relationship between libactionkv and other components of the actionkv project

We'll use the `ByteString` type alias for data that tends to be used as a string but happens to be in a binary (raw bytes) form. Its text-based peer is the built-in `str`. Unlike `str`, `ByteString` is not guaranteed to contain valid UTF-8 text.

Both `str` and `[u8]` (or its alias `ByteStr`) are seen in the wild as `&str` and `&[u8]` (or `&ByteStr`). These are both called *slices*.

```
type ByteString = Vec<u8>;
```

The alias `ByteString` will be the workhorse when we want to use a type that behaves like a `String`. It's also one that can contain arbitrary binary data. The following listing, an excerpt from listing 7.16, demonstrates the use of `ActionKV::open()`.

#### Listing 7.11 Using ActionKV::open()

```
12 type ByteString = Vec<u8>;           ← This code processes lots of Vec<u8> data.
13
14 type ByteStr = [u8];                   ← Because that's used in the same way as String
15
16 #[derive(Debug, Serialize, Deserialize)] ← Instructs the compiler to generate
17 pub struct KeyValuePair {             serialized code to enable writing
18     pub key: ByteString,            KeyValuePair data to disk. Serialize
19     pub value: ByteString,         and Deserialize are explained in
20 }                                     section 7.2.1.
21
22 #[derive(Debug)]
23 pub struct ActionKV {
24     f: File,
25     pub index: HashMap<ByteString, u64>, ← Maintains a mapping
26 }                                     between keys and
27
28 impl ActionKV {
29     pub fn open(path: &Path) -> io::Result<Self> {
30         let f = OpenOptions::new()
31             .read(true)
32             .write(true)
33             .create(true)
34             .append(true)
35             .open(path)?;
36         let index = HashMap::new();
37         Ok(ActionKV { f, index })
38     }
39
40     pub fn load(&mut self) -> io::Result<()> { ← ActionKV::load() populates the
41
42         let mut f = BufReader::new(&mut self.f);
43
44         loop {                               index of the ActionKV struct,
45             let position = f.seek(SeekFrom::Current(0))?; ← mapping keys to file positions.
46
47             let maybe_kv = ActionKV::process_record(&mut f); ← File::seek() returns the
48
49             let kv = match maybe_kv {                         number of bytes from the
50                 ActionKV::process_record() reads a record
51             }                                              in the file at its current position.
52         }
53     }
54 }
```

**ByteStr is to &str what ByteString is to Vec<u8>.**

```

89     Ok(kv) => kv,
90     Err(err) => {
91         match err.kind() {
92             io::ErrorKind::UnexpectedEof => { ←
93                 break;
94             }
95             _ => return Err(err),
96         }
97     }
98 };
99
100    self.index.insert(kv.key, position);
101 }
102
103 Ok(())
104 }
```

Unexpected is relative. The application might not have expected to encounter the end of the file, but we expect files to be finite, so we'll deal with that eventuality.

### What is EOF?

File operations in Rust might return an error of type `std::io::ErrorKind::UnexpectedEof`, but what is `Eof`? The end of file (EOF) is a convention that operating systems provide to applications. There is no special marker or delimiter at the end of a file within the file itself.

EOF is a zero byte (`0u8`). When reading from a file, the OS tells the application how many bytes were successfully read from storage. If no bytes were successfully read from disk, yet no error condition was detected, then the OS and, therefore, the application assume that EOF has been reached.

This works because the OS has the responsibility for interacting with physical devices. When a file is read by an application, the application notifies the OS that it would like to access the disk.

## 7.7.2 Processing an individual record

`actionkv` uses a published standard for its on-disk representation. It is an implementation of the Bitcask storage backend that was developed for the original implementation of the Riak database. Bitcask belongs to a family of file formats known in the literature as *Log-Structured Hash Tables*.

### What is Riak?

Riak, a NoSQL database, was developed during the height of the NoSQL movement and competed against similar systems such as MongoDB, Apache CouchDB, and Tokyo Tyrant. It distinguished itself with its emphasis on resilience to failure.

Although it was slower than its peers, it guaranteed that it never lost data. That guarantee was enabled in part because of its smart choice of a data format.

Bitcask lays every record in a prescribed manner. Figure 7.3 illustrates a single record in the Bitcask file format.




Figure 7.3 A single record in the Bitcask file format. To parse a record, read the header information, then use that information to read the body. Lastly, verify the body’s contents with the checksum provided in the header.

Every key-value pair is prefixed by 12 bytes. Those bytes describe its length (key\_len + val\_len) and its content (checksum).

The `process_record()` function does the processing for this within ActionKV. It begins by reading 12 bytes that represent three integers: a checksum, the length of the key, and the length of the value. Those values are then used to read the rest of the data from disk and verify what’s intended. The following listing, an extract from listing 7.16, shows the code for this process.

#### Listing 7.12 Focusing on the ActionKV::process\_record() method

```

43 fn process_record<R: Read>(
44     f: &mut R
45 ) -> io::Result<KeyValuePair> {
46     let saved_checksum =
47         f.read_u32::<LittleEndian>()?;
48     let key_len =
49         f.read_u32::<LittleEndian>()?;
50     let val_len =
51         f.read_u32::<LittleEndian>()?;
52     let data_len = key_len + val_len;
53
54     let mut data = ByteString::with_capacity(data_len as usize);
55
56     {
57         f.by_ref()
58             .take(data_len as u64)
59             .read_to_end(&mut data)?;
60     }

```

f may be any type that implements Read, such as a type that reads files, but can also be &[u8].

The byteorder crate allows on-disk integers to be read in a deterministic manner as discussed in the following section.

f.by\_ref() is required because take(n) creates a new Read value. Using a reference within this short-lived block sidesteps ownership issues.

```

61     debug_assert_eq!(data.len(), data_len as usize); ←
62
63     let checksum = crc32::checksum_ieee(&data);
64     if checksum != saved_checksum {
65         panic!(
66             "data corruption encountered ({:08x} != {:08x})",
67             checksum, saved_checksum
68         );
69     }
70
71     let value = data.split_off(key_len as usize); ←
72     let key = data;
73
74     Ok( KeyValuePair { key, value } )
75 }
```

**debug\_assert!** tests are disabled in optimized builds, enabling debug builds to have more runtime checks.

The `split_off(n)` method splits a `Vec<T>` in two at `n`.

A checksum (a number) verifies that the bytes read from disk are the same as what was intended. This process is discussed in section 7.7.4.

### 7.7.3 Writing multi-byte binary data to disk in a guaranteed byte order

One challenge that our code faces is that it needs to be able to store multi-byte data to disk in a deterministic way. This sounds easy, but computing platforms differ as to how numbers are read. Some read the 4 bytes of an `i32` from left to right; others read from right to left. That could potentially be a problem if the program is designed to be written by one computer and loaded by another.

The Rust ecosystem provides some support here. The `byteorder` crate can extend types that implement the standard library's `std::io::Read` and `std::io::Write` traits. `std::io::Read` and `std::io::Write` are commonly associated with `std::io::File` but are also implemented by other types such as `[u8]` and `TcpStream`. The extensions can guarantee how multi-byte sequences are interpreted, either as little endian or big endian.

To follow what's going on with our key-value store, it will help to have an understanding of how `byteorder` works. Listing 7.14 is a toy application that demonstrates the core functionality. Lines 11–23 show how to write to a file and lines 28–35 show how to read from one. The two key lines are

```
use byteorder::{LittleEndian};
use byteorder::{ReadBytesExt, WriteBytesExt};
```

`byteorder::LittleEndian` and its peers `BigEndian` and `NativeEndian` (not used in listing 7.14) are types that declare how multi-byte data is written to and read from disk. `byteorder::ReadBytesExt` and `byteorder::WriteBytesExt` are traits. In some sense, these are invisible within the code.

These extend methods to primitive types such as `f32` and `i16` without further ceremony. Bringing those into scope with a `use` statement immediately adds powers to the types that are implemented within the source of `byteorder` (in practice, that means primitive types). Rust, as a statically-typed language, makes this transformation at

compile time. From the running program's point of view, integers always have the ability to write themselves to disk in a predefined order.

When executed, listing 7.14 produces a visualization of the byte patterns that are created by writing `1_u32`, `2_i8`, and `3.0_f32` in little-endian order. Here's the output:

```
[1, 0, 0, 0]
[1, 0, 0, 0, 2]
[1, 0, 0, 0, 2, 0, 0, 0, 0, 0, 0, 8, 64]
```

The following listing shows the metadata for the project in listing 7.14. You'll find the source code for the following listing in `ch7/ch7-write123/Cargo.toml`. The source code for listing 7.14 is in `ch7/ch7-write123/src/main.rs`.

### Listing 7.13 Metadata for listing 7.14

```
[package]
name = "write123"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
byteorder = "1.2"
```

### Listing 7.14 Writing integers to disk

As files support the ability to seek(), moving backward and forward to different positions, something is necessary to enable a `Vec<T>` to mock being a file. `io::Cursor` plays that role, enabling an in-memory `Vec<T>` to be file-like.

```
1 use std::io::Cursor;           ← Used as a type argument for a
2 use byteorder::{LittleEndian}; ← program's various read_*() and write_*() methods
3 use byteorder::{ReadBytesExt, WriteBytesExt}; ← Traits that provide read_*() and write_*()
4
5 fn write_numbers_to_file() -> (u32, i8, f64) { ←
6     let mut w = vec![];          ← The variable w stands for writer.
7
8     let one: u32    = 1;          ←
9     let two: i8     = 2;          ← Single byte types i8 and u8 don't take an endianness parameter.
10    let three: f64 = 3.0;         ←
11
12    w.write_u32::<LittleEndian>(one).unwrap(); ← Writes values to disk. These
13    println!("{}:{:?}", &w);        ← methods return io::Result, which we swallow here as these won't fail unless something is seriously wrong with the computer that's
14
15    w.write_i8(two).unwrap();      ←
16    println!("{}:{:?}", &w);        ←
17
18    w.write_f64::<LittleEndian>(three).unwrap(); ←
19    println!("{}:{:?}", &w);        ←
20
21    (one, two, three)
```

```

22 }
23
24 fn read_numbers_from_file() -> (u32, i8, f64) {
25     let mut r = Cursor::new(vec![1, 0, 0, 0, 2, 0, 0, 0, 0, 0, 0, 0, 8, 64]);
26     let one_ = r.read_u32::<LittleEndian>().unwrap();
27     let two_ = r.read_i8().unwrap();
28     let three_ = r.read_f64::<LittleEndian>().unwrap();
29
30     (one_, two_, three_)
31 }
32
33 fn main() {
34     let (one, two, three) = write_numbers_to_file();
35     let (one_, two_, three_) = read_numbers_from_file();
36
37     assert_eq!(one, one_);
38     assert_eq!(two, two_);
39     assert_eq!(three, three_);
40 }
```

#### 7.7.4 Validating I/O errors with checksums

actionkv v1 has no method of validating that what it has read from disk is what was written to disk. What if something is interrupted during the original write? We may not be able to recover the original data if this is the case, but if we could recognize the issue, then we would be in a position to alert the user.

A well-worn path to overcome this problem is to use a technique called a *checksum*. Here's how it works:

- *Saving to disk*—Before data is written to disk, a checking function (there are many options as to which function) is applied to those bytes. The result of the checking function (the checksum) is written alongside the original data.  
No checksum is calculated for the bytes of the checksum. If something breaks while writing the checksum's own bytes to disk, this will be noticed later as an error.
- *Reading from disk*—Read the data and the saved checksum, applying the checking function to the data. Then compare the results of the two checking functions. If the two results do not match, an error has occurred, and the data should be considered corrupted.

Which checking function should you use? Like many things in computer science, it depends. An ideal checksum function would

- Return the same result for the same input
- Always return a different result for different inputs
- Be fast
- Be easy to implement

Table 7.8 compares the different checksum approaches. To summarize

- The parity bit is easy and fast, but it is somewhat prone to error.
- CRC32 (cyclic redundancy check returning 32 bits) is much more complex, but its results are more trustworthy.
- Cryptographic hash functions are more complex still. Although being significantly slower, they provide high levels of assurance.

**Table 7.8 A simplistic evaluation of different checksum functions**

Checksum technique	Size of result	Simplicity	Speed	Reliability
Parity bit	1 bit	★★★★★	★★★★★	★★☆☆☆
CRC32	32 bits	★★★★☆	★★★★★	★★☆☆☆
Cryptographic hash function	128–512 bits (or more)	★☆☆☆☆	★☆☆☆☆	★★★★★

Functions that you might see in the wild depend on your application domain. More traditional areas might see the use of simpler systems, such as a parity bit or CRC32.

#### IMPLEMENTING PARITY BIT CHECKING

This section describes one of the simpler checksum schemes: *parity checking*. Parity checks count the number of 1s within a bitstream. These store a bit that indicates whether the count was even or odd.

Parity bits are traditionally used for error detection within noisy communication systems, such as transmitting data over analog systems such as radio waves. For example, the ASCII encoding of text has a particular property that makes it quite convenient for this scheme. Its 128 characters only require 7 bits of storage ( $128 = 2^7$ ). That leaves 1 spare bit in every byte.

Systems can also include parity bits in larger streams of bytes. Listing 7.15 presents an (overly chatty) implementation. The `parity_bit()` function in lines 1–10 takes an arbitrary stream of bytes and returns a u8, indicating whether the count of the input's bits was even or odd. When executed, listing 7.15 produces the following output:

```
input: [97, 98, 99]           ←
97 (0b01100001) has 3 one bits
98 (0b01100010) has 3 one bits
99 (0b01100011) has 4 one bits
output: 00000001

input: [97, 98, 99, 100]       ←
97 (0b01100001) has 3 one bits
98 (0b01100010) has 3 one bits
99 (0b01100011) has 4 one bits
100 (0b01100100) has 3 one bits
result: 00000000

input: [97, 98, 99]           ←
97 (0b01100001) has 3 one bits
98 (0b01100010) has 3 one bits
99 (0b01100011) has 4 one bits
100 (0b01100100) has 3 one bits
result: 00000000
```

input: [97, 98, 99] represents  
b"abc" as seen by the internals  
of the Rust compiler.

input: [97, 98, 99,  
100] represents  
b"abcd".

**NOTE** The code for the following listing is in `ch7/ch7-paritybit/src/main.rs`.

### Listing 7.15 Implementing parity bit checking

All of Rust's integer types come equipped with `count_ones()` and `count_zeros()` methods.

```

1 fn parity_bit(bytes: &[u8]) -> u8 {
2     let mut n_ones: u32 = 0;
3
4     for byte in bytes {
5         let ones = byte.count_ones();
6         n_ones += ones;
7         println!("{} (0b{:08b}) has {} one bits", byte, byte, ones);
8     }
9     (n_ones % 2 == 0) as u8
10 }
11
12 fn main() {
13     let abc = b"abc";
14     println!("input: {:?}", abc);
15     println!("output: {:08x}", parity_bit(abc));
16     println!();
17     let abcd = b"abcd";
18     println!("input: {:?}", abcd);
19     println!("result: {:08x}", parity_bit(abcd))
20 }
```

Takes a byte slice as the `bytes` argument and returns a single byte as output. This function could have easily returned a `bool` value, but returning `u8` allows the result to be shifted into some future desired position.

There are plenty of methods to optimize this function. One fairly simple approach is to hard code a `const [u8; 256]` array of 0s and 1s, corresponding to the intended result, then index that array with each byte.

#### 7.7.5 Inserting a new key-value pair into an existing database

As discussed in section 7.6, there are four operations that our code needs to support: insert, get, update, and delete. Because we're using an append-only design, this means that the last two operations can be implemented as variants of insert.

You may have noticed that during `load()`, the inner loop continues until the end of the file. This allows more recent updates to overwrite stale data, including deletions. Inserting a new record is almost the inverse of `process_record()`, described in section 7.7.2. For example

```

164 pub fn insert(
165     &mut self,
166     key: &ByteStr,
167     value: &ByteStr
168 ) -> io::Result<()> {
169     let position = self.insert_but_ignore_index(key, value)?;
170
171     self.index.insert(key.to_vec(), position); ←
172     Ok(())
173 }
174
175 pub fn insert_but_ignore_index(
176     &mut self,
177     key: &ByteStr,
178     value: &ByteStr
179 ) -> io::Result<u64> {
180     let mut f = BufWriter::new(&mut self.f); ←
181 }
```

`key.to_vec()` converts the `&ByteStr` to a `ByteString`.

The `std::io::BufWriter` type batches multiple short `write()` calls into fewer actual disk operations, resulting in a single one. This increases throughput while keeping the application code neater.

```

182 let key_len = key.len();
183 let val_len = value.len();
184 let mut tmp = ByteString::with_capacity(key_len + val_len);
185
186 for byte in key {
187     tmp.push(*byte);
188 }
189 for byte in value {
190     tmp.push(*byte);
191 }
192
193 let checksum = crc32::checksum_ieee(&tmp);
194
195 let next_byte = SeekFrom::End(0);
196 let current_position = f.seek(SeekFrom::Current(0))?;
197 f.seek(next_byte)?;
198 f.write_u32::<LittleEndian>(checksum)?;
199 f.write_u32::<LittleEndian>(key_len as u32)?;
200 f.write_u32::<LittleEndian>(val_len as u32)?;
201 f.write_all(&mut tmp)?;
202
203 Ok(current_position)
204 }

```

Iterating through one collection to populate another is slightly awkward, but gets the job done.

### 7.7.6 The full code listing for actionkv

libactionkv performs the heavy lifting in our key-value stores. You have already explored much of the actionkv project throughout section 7.7. The following listing, which you'll find in the file ch7/ch7-actionkv1/src/lib.rs, presents the project code in full.

#### Listing 7.16 The actionkv project (full code)

```

1 use std::collections::HashMap;
2 use std::fs::{File, OpenOptions};
3 use std::io;
4 use std::io::prelude::*;
5 use std::io::{BufReader, BufferedWriter, SeekFrom};
6 use std::path::Path;
7
8 use byteorder::{LittleEndian, ReadBytesExt, WriteBytesExt};
9 use crc::crc32;
10 use serde_derive::{Deserialize, Serialize};
11
12 type ByteString = Vec<u8>;
13 type ByteStr = [u8];
14
15 #[derive(Debug, Serialize, Deserialize)]
16 pub struct KeyValuePair {
17     pub key: ByteString,
18     pub value: ByteString,
19 }
20

```

```

21 #[derive(Debug)]
22 pub struct ActionKV {
23     f: File,
24     pub index: HashMap<ByteString, u64>,
25 }
26
27 impl ActionKV {
28     pub fn open(
29         path: &Path
30     ) -> io::Result<Self> {
31         let f = OpenOptions::new()
32             .read(true)
33             .write(true)
34             .create(true)
35             .append(true)
36             .open(path)?;
37         let index = HashMap::new();
38         Ok(ActionKV { f, index })
39     }
40
41     fn process_record<R: Read>(<span style="float: right; margin-left: 10px;">process_record() assumes  
that f is already at the right  
place in the file.
42         f: &mut R
43     ) -> io::Result<KeyValuePair> {
44         let saved_checksum =
45             f.read_u32::<LittleEndian>()?;
46         let key_len =
47             f.read_u32::<LittleEndian>()?;
48         let val_len =
49             f.read_u32::<LittleEndian>()?;
50         let data_len = key_len + val_len;
51
52         let mut data = ByteString::with_capacity(data_len as usize);
53
54         {
55             f.by_ref() <span style="float: right; margin-left: 10px;">f.by_ref() is required because .take(n)  
creates a new Read instance. Using a  
reference within this block allows us to  
sidestep ownership issues.
56                 .take(data_len as u64)
57                 .read_to_end(&mut data)?;
58         }
59         debug_assert_eq!(data.len(), data_len as usize);
60
61         let checksum = crc32::checksum_ieee(&data);
62         if checksum != saved_checksum {
63             panic!(
64                 "data corruption encountered ({:08x} != {:08x})",
65                 checksum, saved_checksum
66             );
67         }
68
69         let value = data.split_off(key_len as usize);
70         let key = data;
71
72         Ok(KeyValuePair { key, value })
73     }
74
75     pub fn seek_to_end(&mut self) -> io::Result<u64> {

```

```

76     self.f.seek(SeekFrom::End(0))
77 }
78
79 pub fn load(&mut self) -> io::Result<()> {
80     let mut f = BufReader::new(&mut self.f);
81
82     loop {
83         let current_position = f.seek(SeekFrom::Current(0))?;
84
85         let maybe_kv = ActionKV::process_record(&mut f);
86         let kv = match maybe_kv {
87             Ok(kv) => kv,
88             Err(err) => {
89                 match err.kind() {
90                     io::ErrorKind::UnexpectedEof => { ←
91                         break;
92                     }
93                     _ => return Err(err),
94                 }
95             }
96         };
97
98         self.index.insert(kv.key, current_position);
99     }
100
101     Ok(())
102 }
103
104 pub fn get(
105     &mut self,
106     key: &ByteStr
107 ) -> io::Result<Option<ByteString>> { ←
108     let position = match self.index.get(key) { ←
109         None => return Ok(None),
110         Some(position) => *position,
111     };
112
113     let kv = self.get_at(position)?;
114
115     Ok(Some(kv.value))
116 }
117
118 pub fn get_at(
119     &mut self,
120     position: u64
121 ) -> io::Result<KeyValuePair> {
122     let mut f = BufReader::new(&mut self.f);
123     f.seek(SeekFrom::Start(position))?;
124     let kv = ActionKV::process_record(&mut f)?;
125
126     Ok(kv)
127 }
128
129 pub fn find(
130     &mut self,

```

"Unexpected" is relative.  
The application may not have expected it, but we expect files to be finite.

Wraps Option within Result to allow for the possibility of an I/O error as well as tolerating missing values

```

131     target: &ByteStr
132 ) -> io::Result<Option<(u64, ByteString)>> {
133     let mut f = BufReader::new(&mut self.f);
134
135     let mut found: Option<(u64, ByteString)> = None;
136
137     loop {
138         let position = f.seek(SeekFrom::Current(0))?;
139
140         let maybe_kv = ActionKV::process_record(&mut f);
141         let kv = match maybe_kv {
142             Ok(kv) => kv,
143             Err(err) => {
144                 match err.kind() {
145                     io::ErrorKind::UnexpectedEof => {           ←
146                         break;
147                     }
148                     _ => return Err(err),
149                 }
150             }
151         };
152
153         if kv.key == target {
154             found = Some((position, kv.value));
155         }
156
157         // important to keep looping until the end of the file,
158         // in case the key has been overwritten
159     }
160
161     Ok(found)
162 }
163
164 pub fn insert(
165     &mut self,
166     key: &ByteStr,
167     value: &ByteStr
168 ) -> io::Result<()> {
169     let position = self.insert_but_ignore_index(key, value)?;
170
171     self.index.insert(key.to_vec(), position);
172     Ok(())
173 }
174
175 pub fn insert_but_ignore_index(
176     &mut self,
177     key: &ByteStr,
178     value: &ByteStr
179 ) -> io::Result<u64> {
180     let mut f = BufferedWriter::new(&mut self.f);
181
182     let key_len = key.len();
183     let val_len = value.len();
184     let mut tmp = ByteString::with_capacity(key_len + val_len);
185

```

"Unexpected" is relative.  
The application may not  
have expected it, but we  
expect files to be finite.

```

186     for byte in key {
187         tmp.push(*byte);
188     }
189
190     for byte in value {
191         tmp.push(*byte);
192     }
193
194     let checksum = crc32::checksum_ieee(&tmp);
195
196     let next_byte = SeekFrom::End(0);
197     let current_position = f.seek(SeekFrom::Current(0))?;
198     f.seek(next_byte)?;
199     f.write_u32::<LittleEndian>(checksum)?;
200     f.write_u32::<LittleEndian>(key_len as u32)?;
201     f.write_u32::<LittleEndian>(val_len as u32)?;
202     f.write_all(&tmp)?;
203
204     Ok(current_position)
205 }
206
207 #[inline]
208 pub fn update(
209     &mut self,
210     key: &ByteStr,
211     value: &ByteStr
212 ) -> io::Result<()> {
213     self.insert(key, value)
214 }
215
216 #[inline]
217 pub fn delete(
218     &mut self,
219     key: &ByteStr
220 ) -> io::Result<()> {
221     self.insert(key, b"")
222 }
223 }
```

If you've made it this far, you should congratulate yourself. You've implemented a key-value store that will happily store and retrieve whatever you have to throw at it.

## 7.7.7 Working with keys and values with HashMap and BTreeMap

Working with key-value pairs happens in almost every programming language. For the tremendous benefit of learners everywhere, this task and the data structures that support it have many names:

- You might encounter someone with a computer science background who prefers to use the term *hash table*.
- Perl and Ruby call these *hashes*.
- Lua does the opposite and uses the term *table*.

- Many communities name the structure after a metaphor such as a *dictionary* or a *map*.
- Other communities prefer naming based on the role that the structure plays.
- PHP describes these as *associative arrays*.
- JavaScript's objects tend to be implemented as a key-value pair collection and so the generic term *object* suffices.
- Static languages tend to name these according to how they are implemented.
- C++ and Java distinguish between a *hash map* and a *tree map*.

Rust uses the terms `HashMap` and `BTreeMap` to define two implementations of the same abstract data type. Rust is closest to C++ and Java in this regard. In this book, the terms *collection of key-value pairs* and *associative array* refer to the abstract data type. *Hash table* refers to associative arrays implemented with a hash table, and a `HashMap` refers to Rust's implementation of hash tables.

### What is a hash? What is hashing?

If you've ever been confused by the term *hash*, it may help to understand that this relates to an implementation decision made to enable non-integer keys to map to values. Hopefully, the following definitions will clarify the term:

- A *HashMap* is implemented with a *hash function*. Computer scientists will understand that this implies a certain behavior pattern in common cases. A hash map has a constant time lookup in general, formally denoted as  $O(1)$  in big O notation. (Although a hash map's performance can suffer when its underlying hash function encounters some pathological cases as we'll see shortly.)
- A *hash function maps between values of variable-length to fixed-length*. In practice, the return value of a hash function is an integer. That fixed-width value can then be used to build an efficient lookup table. This internal lookup table is known as a *hash table*.

The following example shows a basic hash function for `&str` that simply interprets the first character of a string as an unsigned integer. It, therefore, uses the first character of the string as an hash value:

```
fn basic_hash(key: &str) -> u32 {
    let first = key.chars()           | The .chars() iterator converts
                                      | the string into a series of char
                                      | values, each 4 bytes long.
                                      |
                                      | Returns an Option that's
                                      | either Some(char) or None
                                      | for empty strings
    .next()                         |
    .unwrap_or('0')                 |
    unsafe {                        | Interprets the memory
        std::mem::transmute::<char, u32>(first)
    }
}
```

If an empty string, provides NULL as the default.  
`unwrap_or()` behaves as `unwrap()` but provides a value rather than panicking when it encounters None.

`basic_hash` can take any string as input—an infinite set of possible inputs—and return a fixed-width result for all of those in a deterministic manner. That's great! But, although `basic_hash` is fast, it has some significant faults.

If multiple inputs start with the same character (for example, *Tonga* and *Tuvalu*), these result in the same output. This happens in every instance when an infinite input space is mapped into a finite space, but it's particularly bad here. Natural language text is not uniformly distributed.

Hash tables, including Rust's `HashMap`, deal with this phenomenon, which is called a *hash collision*. These provide a backup location for keys with the same hash value. That secondary storage is typically a `Vec<T>` that we'll call the *collision store*. When collisions occur, the collision store is scanned from front to back when it is accessed. That linear scan takes longer and longer to run as the store's size increases. Attackers can make use of this characteristic to overload the computer that is performing the hash function.

In general terms, faster hash functions do less work to avoid being attacked. These will also perform best when their inputs are within a defined range.

Fully understanding the internals of how hash tables are implemented is too much detail for this sidebar. But it's a fascinating topic for programmers who want to extract optimum performance and memory usage from their programs.

### 7.7.8 Creating a `HashMap` and populating it with values

The next listing provides a collection of key-value pairs encoded as JSON. It uses some Polynesian island nations and their capital cities to show the use of an associative array.

#### Listing 7.17 Demonstrating the use of an associative array in JSON notation

```
{  
    "Cook Islands": "Avarua",  
    "Fiji": "Suva",  
    "Kiribati": "South Tarawa",  
    "Niue": "Alofi",  
    "Tonga": "Nuku'alofa",  
    "Tuvalu": "Funafuti"  
}
```

Rust does not provide a literal syntax for `HashMap` within the standard library. To insert items and get them out again, follow the example provided in listing 7.18, whose source is available in `ch7/ch7-pacific-basic/src/main.rs`. When executed, listing 7.18 produces the following line in the console:

```
Capital of Tonga is: Nuku'alofa
```

#### Listing 7.18 An example of the basic operations of `HashMap`

```
1 use std::collections::HashMap;  
2  
3 fn main() {
```

```

4  let mut capitals = HashMap::new();           ← Type declarations of keys and
5
6  capitals.insert("Cook Islands", "Avarua");
7  capitals.insert("Fiji", "Suva");
8  capitals.insert("Kiribati", "South Tarawa");
9  capitals.insert("Niue", "Alofi");
10 capitals.insert("Tonga", "Nuku'alofa");
11 capitals.insert("Tuvalu", "Funafuti");
12
13 let tongan_capital = capitals["Tonga"];      ← HashMap implements Index,
14
15 println!("Capital of Tonga is: {}", tongan_capital);
16 }
```

Type declarations of keys and values are not required here as these are inferred by the Rust compiler.

HashMap implements Index, which allows for values to be retrieved via the square bracket indexing style.

Writing everything out as method calls can feel needlessly verbose at times. With some support from the wider Rust ecosystem, it's possible to inject JSON string literals into Rust code. It's best that the conversion is done at compile time, meaning no loss of runtime performance. The output of listing 7.19 is also a single line:

```
Capital of Tonga is: "Nuku'alofa" ← Uses double quotes because the json!
macro returns a wrapper around
String, its default representation
```

The next listing uses a serde-json crate to include JSON literals within your Rust source code. Its source code is in the ch7/ch7-pacific-json/src/main.rs file.

#### Listing 7.19 Including JSON literals with serde-json

```

1 #[macro_use]
2 extern crate serde_json;           ← Incorporates the serde_json crate
3
4 fn main() {
5   let capitals = json!({             ← and makes use of its macros, bringing
6     "Cook Islands": "Avarua",
7     "Fiji": "Suva",
8     "Kiribati": "South Tarawa",
9     "Niue": "Alofi",
10    "Tonga": "Nuku'alofa",
11    "Tuvalu": "Funafuti"
12  });
13
14  println!("Capital of Tonga is: {}", capitals["Tonga"])
15 }
```

json! takes a JSON literal and some Rust expressions to implement String values. It converts these into a Rust value of type serde\_json::Value, an enum that can represent every type within the JSON specification.

### 7.7.9 Retrieving values from HashMap and BTreeMap

The main advantage that a key-value store provides is the ability to access its values. There are two ways to achieve this. To demonstrate, let's assume that we have initialized capitals from listing 7.19. The approach (already demonstrated) is to access values via square brackets:

```
capitals["Tonga"] ← Returns "Nuku'alofa"
```

This approach returns a read-only reference to the value, which is deceptive when dealing with examples containing string literals because their status as references is somewhat disguised. In the syntax used by Rust's documentation, this is described as `&V`, where `&` denotes a read-only reference and `V` is the type of the value. If the key is not present, the program will panic.

**NOTE** Index notation is supported by all types that implement the `Index` trait. Accessing `capitals["Tonga"]` is syntactic sugar for `capitals.index("Tonga")`.

It's also possible to use the `.get()` method on `HashMap`. This returns an `Option<&V>`, providing the opportunity to recover from cases where values are missing. For example

`capitals.get("Tonga")` ←———— Returns Some("Nuku'alofa")

Other important operations supported by `HashMap` include

- Deleting key-value pairs with the `.remove()` method
- Iterating over keys, values, and key-value pairs with the `.keys()`, `.values()`, and `.iter()` methods, respectively, as well as their read-write variants, `.keys_mut()`, `.values_mut()`, and `.iter_mut()`

There is no method for iterating through a subset of the data. For that, we need to use `BTreeMap`.

### 7.7.10 How to decide between `HashMap` and `BTreeMap`

If you're wondering about which backing data structure to choose, here is a simple guideline: use `HashMap` unless you have a good reason to use `BTreeMap`. `BTreeMap` is faster when there is a natural ordering between the keys, and your application makes use of that arrangement. Table 7.9 highlights the differences.

Let's demonstrate these two use cases with a small example from Europe. The Dutch East India Company, known as VOC after the initials of its Dutch name, Verenigde Oostindische Compagnie, was an extremely powerful economic and political force at its peak. For two centuries, VOC was a dominant trader between Asia and Europe. It had its own navy and currency, and established its own colonies (called trading posts). It was also the first company to issue bonds. In the beginning, investors from six business chambers (kamers) provided capital for the business.

Let's use these investments as key-value pairs. When listing 7.20 is compiled, it produces an executable that generates the following output:

```
$ cargo run -q
Rotterdam invested 173000
Hoorn invested 266868
Delft invested 469400
Enkhuizen invested 540000
Middelburg invested 1300405
Amsterdam invested 3697915
smaller chambers: Rotterdam Hoorn Delft
```

**Listing 7.20 Demonstrating range queries and ordered iteration of BTreemap**

```

1 use std::collections::BTreemap;
2
3 fn main() {
4     let mut voc = BTreemap::new();
5
6     voc.insert(3_697_915, "Amsterdam");
7     voc.insert(1_300_405, "Middelburg");
8     voc.insert(-540_000, "Enkhuizen");
9     voc.insert(-469_400, "Delft");
10    voc.insert(-266_868, "Hoorn");
11    voc.insert(-173_000, "Rotterdam");
12
13    for (guilders, kamer) in &voc {
14        println!("{} invested {}", kamer, guilders);
15    }
16
17    print!("smaller chambers: ");
18    for (_guilders, kamer) in voc.range(0..500_000) { ←
19        print!("{} ", kamer);
20    }
21    println!("");
22 }
```

Prints in sorted order

BTreemap lets you select a portion of the keys that are iterated through with the range syntax.

**Table 7.9 Deciding on which implementation to use to map keys to values**

std::collections::HashMap with a default hash function (known as SipHash in the literature)	Cryptographically secure and resistant to denial of service attacks but slower than alternative hash functions
std::collections::BTreemap	Useful for keys with an inherent ordering, where cache coherence can provide a boost in speed

### 7.7.11 Adding a database index to actionkv v2.0

Databases and filesystems are much larger pieces of software than single files. There is a large design space involved with storage and retrieval systems, which is why new ones are always being developed. Common to all of those systems, however, is a component that is the real smarts behind the database.

Built in section 7.5.2, actionkv v1 contains a major issue that prevents it from having a decent startup time. Every time it's run, it needs to rebuild its index of where keys are stored. Let's add the ability for actionkv to store its own data that indexes *within* the same file that's used to store its application data. It will be easier than it sounds. No changes to libactionkv are necessary. And the front-end code only requires minor additions. The project folder now has a new structure with an extra file (shown in the following listing).

**Listing 7.21 The updated project structure for actionkv v2.0**

```

actionkv
└── src
    ├── akv_disk.rs
    ├── akv_mem.rs
    └── lib.rs
Cargo.toml

```

The project's Cargo.toml adds some new dependencies along with a second `[[bin]]` entry, as the last three lines of the following listing show. The source for this listing is in ch7/ch7-actionkv2/Cargo.toml.

**Listing 7.22 Updating the Cargo.toml file for actionkv v2.0**

```

[package]
name = "actionkv"
version = "2.0.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
bincode = "1"
byteorder = "1"
crc = "1"
serde = "1"
serde_derive = "1"

[lib]
name = "libactionkv"
path = "src/lib.rs"

[[bin]]
name = "akv_mem"
path = "src/akv_mem.rs"

[[bin]]
name = "akv_disk"
path = "src/akv_disk.rs"

```

When a key is accessed with the get operation, to find its location on disk, we first need to load the index from disk and convert it to its in-memory form. The following listing is an excerpt from listing 7.24. The on-disk implementation of actionkv includes a hidden `INDEX_KEY` value that allows it to quickly access other records in the file.

**Listing 7.23 Highlighting the main change from listing 7.8**

```

48 match action {           INDEX_KEY is an internal hidden name
49   "get" => {           of the index within the database.
50     let index_as_bytes = a.get(&INDEX_KEY)   <
51         .unwrap()          |
52         .unwrap();          |

```

Two `unwrap()` calls are required because `a.index` is a `HashMap` that returns `Option`, and values themselves are stored within an `Option` to facilitate possible future deletes.

```

53
54     let index_decoded = bincode::deserialize(&index_as_bytes);
55
56     let index: HashMap<ByteString, u64> = index_decoded.unwrap();
57
58     match index.get(key) {
59         None => eprintln!("{} not found", key),
60         Some(&i) => {
61             let kv = a.get_at(i).unwrap();
62             println!("{} {}", kv.key, kv.value)
63         }
64     }
65 }
```

Retrieving a value now involves fetching the index first, then identifying the correct location on disk.

The following listing shows a key-value store that persists its index data between runs. The source for this listing is in ch7/ch7-actionkv2/src/akv\_disk.rs.

#### Listing 7.24 Persisting index data between runs

```

1 use libactionkv::ActionKV;
2 use std::collections::HashMap;
3
4 #[cfg(target_os = "windows")]
5 const USAGE: &str = "
6 Usage:
7     akv_disk.exe FILE get KEY
8     akv_disk.exe FILE delete KEY
9     akv_disk.exe FILE insert KEY VALUE
10    akv_disk.exe FILE update KEY VALUE
11 ";
12
13 #[cfg(not(target_os = "windows"))]
14 const USAGE: &str = "
15 Usage:
16     akv_disk FILE get KEY
17     akv_disk FILE delete KEY
18     akv_disk FILE insert KEY VALUE
19     akv_disk FILE update KEY VALUE
20 ";
21
22 type ByteStr = [u8];
23 type ByteString = Vec<u8>;
24
25 fn store_index_on_disk(a: &mut ActionKV, index_key: &ByteStr) {
26     a.index.remove(index_key);
27     let index_as_bytes = bincode::serialize(&a.index).unwrap();
28     a.index = std::collections::HashMap::new();
29     a.insert(index_key, &index_as_bytes).unwrap();
30 }
31
32 fn main() {
33     const INDEX_KEY: &ByteStr = b"+index";
34
35     let args: Vec<String> = std::env::args().collect();
```

```

36 let fname = args.get(1).expect(&USAGE);
37 let action = args.get(2).expect(&USAGE).as_ref();
38 let key = args.get(3).expect(&USAGE).as_ref();
39 let maybe_value = args.get(4);
40
41 let path = std::path::Path::new(&fname);
42 let mut a = ActionKV::open(path).expect("unable to open file");
43
44 a.load().expect("unable to load data");
45
46 match action {
47     "get" => {
48         let index_as_bytes = a.get(&INDEX_KEY)
49                         .unwrap()
50                         .unwrap();
51
52         let index_decoded = bincode::deserialize(&index_as_bytes);
53
54         let index: HashMap<ByteString, u64> = index_decoded.unwrap();
55
56         match index.get(key) {
57             None => eprintln!("{} not found", key),
58             Some(&i) => {
59                 let kv = a.get_at(i).unwrap();
60                 println!("{}: {}", kv.key, kv.value)    ← To print values, we need to
61             }
62         }
63     }
64
65     "delete" => a.delete(key).unwrap(),
66
67     "insert" => {
68         let value = maybe_value.expect(&USAGE).as_ref();
69         a.insert(key, value).unwrap();
70         store_index_on_disk(&mut a, INDEX_KEY);   ← The index must
71     }
72
73     "update" => {
74         let value = maybe_value.expect(&USAGE).as_ref();
75         a.update(key, value).unwrap();
76         store_index_on_disk(&mut a, INDEX_KEY);   ← also be updated
77     }
78     _ => eprintln!("{}: &USAGE"),
79 }
80 }
```

## Summary

- Converting between in-memory data structures and raw byte streams to be stored in files or sent over the network is known as *serialization* and *deserialization*. In Rust, `serde` is the most popular choice for these two tasks.
- Interacting with the filesystem almost always implies handling `std::io::Result`. `Result` is used for errors that are not part of normal control flow.

- Filesystem paths have their own types: `std::path::Path` and `std::path::PathBuf`. While it adds to the learning burden, implementing these allows you to avoid common mistakes that can occur by treating paths directly as strings.
- To mitigate the risk of data corruption during transit and storage, use checksums and parity bits.
- Using a library crate makes it easier to manage complex software projects. Libraries can be shared between projects, and you can make these more modular.
- There are two primary data structures for handling key-value pairs within the Rust standard library: `HashMap` and `BTreeMap`. Use `HashMap` unless you know that you want to make use of the features offered by `BTreeMap`.
- The `cfg` attribute and `cfg!` macro allow you to compile platform-specific code.
- To print to standard error (`stderr`), use the `eprintln!` macro. Its API is identical to the `println!` macro that is used to print to standard output (`stdout`).
- The `Option` type is used to indicate when values may be missing, such as asking for an item from an empty list.

# *Networking*

---

## **This chapter covers**


- Implementing a networking stack
- Handling multiple error types within local scope
- When to use trait objects
- Implementing state machines in Rust

This chapter describes how to make HTTP requests multiple times, stripping away a layer of abstraction each time. We start by using a user-friendly library, then boil that away until we're left with manipulating raw TCP packets. When we're finished, you'll be able to distinguish an IP address from a MAC address. And you'll learn why we went straight from IPv4 to IPv6.

You'll also learn lots of Rust in this chapter, most of it related to advanced error handling techniques that become essential for incorporating upstream crates. Several pages are devoted to error handling. This includes a thorough introduction to trait objects.

Networking is a difficult subject to cover in a single chapter. Each layer is a fractal of complexity. Networking experts will hopefully overlook my lack of depth in treating such a diverse topic.

Figure 8.1 provides an overview of the topics that the chapter covers. Some of the projects that we cover include implementing DNS resolution and generating standards-compliant MAC addresses, including multiple examples of generating HTTP requests. A bit of a role-playing game is added for light relief.



**Figure 8.1** Networking chapter map. The chapter incorporates a healthy mix of theory and practical exercises.

## 8.1 All of networking in seven paragraphs

Rather than trying to learn the whole networking stack, let's focus on something that's of practical use. Most readers of this book will have encountered web programming. Most web programming involves interacting with some sort of framework. Let's look there.

HTTP is the protocol that web frameworks understand. Learning more about HTTP enables us to extract the most performance out of our web frameworks. It can also help us to more easily diagnose any problems that occur. Figure 8.2 shows networking protocols for content delivery over the internet.

Networking is comprised of layers. If you're new to the field, don't be intimidated by a flood of acronyms. The most important thing to remember is that lower levels are

## How computers talk to each other

### ABOUT

A view of the networking stack. Each layer relies upon the layers below it.

Occasionally layers bleed together. For example, HTML files can include directives that overwrite those provided by HTTP.

For a message to be received, each layer must be traversed from bottom to top. To send messages, the steps are reversed.

### HOW TO READ

Vertical positioning typically indicates that two levels interact at that location.

Exceptions include encryption provided by TLS. Network addressing provided by either IPv4 or IPv6, and virtual layers are largely ignorant of physical links. (Shadows from physics do appear on upper layers in the form of latency and reliability.)

Gaps indicate that a higher level can pass directly through to the lower level. A domain name or TLS security is not necessary for HTTP to function, for example.

### LEGEND

-  Protocol discussed in this chapter
-  Protocol in use at this level
-  Represents hundreds of other protocols that exist at this level
-  This protocol is available, but may not be deployed.




Figure 8.2 Several layers of networking protocols involved with delivering content over the internet. The figure compares some common models, including the seven-layer OSI model and the four-layer TCP/IP model.

unaware of what's happening above them, and higher levels are agnostic to what's happening below them. Lower levels receive a stream of bytes and pass it on. Higher levels don't care how messages are sent; they just want them sent.

Let's consider one example: HTTP. HTTP is known as an *application-level protocol*. Its job is to transport content like HTML, CSS, JavaScript, WebAssembly modules, images, video, and other formats. These formats often include other embedded formats via compression and encoding standards. HTTP itself often redundantly includes information provided by one of the layers below it, TCP. Between HTTP and TCP sits TLS. TLS (Transport Layer Security), which has replaced SSL (Secure Sockets Layer), adds the S to HTTPS.

TLS provides encrypted messaging over an unencrypted connection. TLS is implemented on top of TCP. TCP sits upon many other protocols. These go all the way down to specifying how voltages should be interpreted as 0s and 1s. And yet, as complicated as this story is so far, it gets worse. These layers, as you have probably seen in your dealings with those as a computer user, bleed together like watercolor paint.

HTML includes a mechanism to supplement or overwrite directives omitted or specified within HTTP: the `<meta>` tag's `http-equiv` attribute. HTTP can make adjustments downwards to TCP. The "Connection: keep-alive" HTTP header instructs TCP to maintain its connection after this HTTP message has been received. These sorts of interactions occur all through the stack. Figure 8.2 provides one view of the networking stack. It is more complicated than most attempts. And even that complicated picture is highly simplified.

Despite all of that, we're going to try to implement as many layers as possible within a single chapter. By the end of it, you will be sending HTTP requests with a virtual networking device and a minimal TCP implementation that you created yourself, using a DNS resolver that you also created yourself.

## 8.2 Generating an HTTP GET request with reqwest

Our first implementation will be with a high-level library that is focused on HTTP. We'll use the `reqwest` library because its focus is primarily on making it easy for Rust programmers to create an HTTP request.

Although it's the shortest, the `reqwest` implementation is the most feature-complete. As well as being able to correctly interpret HTTP headers, it also handles cases like content redirects. Most importantly, it understands how to handle TLS properly.

In addition to expanded networking capabilities, `reqwest` also validates the content's encoding and ensures that it is sent to your application as a valid `String`. None of our lower-level implementations do any of that. The following shows the project structure for listing 8.2:

```
ch8-simple/
├── src
│   └── main.rs
└── Cargo.toml
```

The following listing shows the metadata for listing 8.2. The source code for this listing is in ch8/ch8-simple/Cargo.toml.

### Listing 8.1 Crate metadata for listing 8.2

```
[package]
name = "ch8-simple"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
reqwest = "0.9"
```

The following listing illustrates how to make an HTTP request with the reqwest library. You'll find the source in ch8/ch8-simple/src/main.rs.

### Listing 8.2 Making an HTTP request with reqwest

```
1 use std::error::Error;
2
3 use reqwest;
4
5 fn main() -> Result<(), Box<dyn Error>> {    ←
6     let url = "http://www.rustinaction.com/";
7     let mut response = reqwest::get(url)?;
8
9     let content = response.text()?;
10    print!("{}", content);
11
12    Ok(())
13 }
```

**Box<dyn Error>**  
represents a trait object, which we'll cover in section 8.3.

If you've ever done any web programming, listing 8.2 should be straightforward. `reqwest::get()` issues an HTTP GET request to the URL represented by `url`. The `response` variable holds a struct representing the server's response. The `response.text()` method returns a `Result` that provides access to the HTTP body after validating that the contents are a legal `String`.

One question, though: What on earth is the error side of the `Result` return type `Box<dyn std::error::Error>`? This is an example of a trait object that enables Rust to support polymorphism at runtime. *Trait objects* are proxies for concrete types. The syntax `Box<dyn std::error::Error>` means a `Box` (a pointer) to any type that implements `std::error::Error`'s.

Using a library that knows about HTTP allows our programs to omit many details. For example

- *Knowing when to close the connection.* HTTP has rules for telling each of the parties when the connection ends. This isn't available to us when manually making requests. Instead, we keep the connection open for as long as possible and hope that the server will close.

- *Converting the byte stream to content.* Rules for translating the message body from `[u8]` to `String` (or perhaps an image, video, or some other content) are handled as part of the protocol. This can be tedious to handle manually as HTTP allows content to be compressed into several methods and encoded into several plain text formats.
- *Inserting or omitting port numbers.* HTTP defaults to port 80. A library that is tailored for HTTP, such as `reqwest`, allows you to omit port numbers. When we're building requests by hand with generic TCP crates, however, we need to be explicit.
- *Resolving the IP addresses.* The TCP protocol doesn't actually know about domain names like `www.rustinaction.com`, for example. The library resolves the IP address for `www.rustinaction.com` on our behalf.

## 8.3 Trait objects

This section describes trait objects in detail. You will also develop the world's next best-selling fantasy role-playing game—the `rpg` project. If you would like to focus on networking, feel free to skip ahead to section 8.4.

There is a reasonable amount of jargon in the next several paragraphs. Brace yourself. You'll do fine. Let's start by introducing trait objects by what they achieve and what they do, rather than focusing on what they are.

### 8.3.1 What do trait objects enable?

While trait objects have several uses, they are immediately helpful by allowing you to create containers of multiple types. Although players of our role-playing game can choose different races, and each race is defined in its own `struct`, you'll want to treat those as a single type. A `Vec<T>` won't work here because we can't easily have types `T`, `U`, and `V` wedged into `Vec<T>` without introducing some type of wrapper object.

### 8.3.2 What is a trait object?

Trait objects add a form of *polymorphism*—the ability to share an interface between types—to Rust via *dynamic dispatch*. Trait objects are similar to generic objects. Generics offer polymorphism via *static dispatch*. Choosing between generics and type objects typically involves a trade off between disk space and time:

- Generics use more disk space with faster runtimes.
- Trait objects use less disk space but incur a small runtime overhead caused by pointer indirection.

Trait objects are *dynamically-sized types*, which means that these are always seen in the wild behind a pointer. Trait objects appear in three forms: `&dyn Trait`, `&mut dyn Trait`, and `Box<dyn Trait>`.<sup>1</sup> The primary difference between the three forms is that `Box<dyn Trait>` is an owned trait object, whereas the other two are borrowed.

---

<sup>1</sup> In old Rust code, you may see `&Trait`, and `Box<Trait>`. While legal syntax, these are officially deprecated. Adding `dyn` keyword is strongly encouraged.

### 8.3.3 Creating a tiny role-playing game: The rpg project

Listing 8.4 is the start of our game. Characters in the game can be one of three races: humans, elves, and dwarves. These are represented by the Human, Elf, and Dwarf structs, respectively.

Characters interact with things. Things are represented by the Thing type.<sup>2</sup> Thing is an enum that currently represents swords and trinkets. There's only one form of interaction right now: enchantment. Enchanting a thing involves calling the enchant() method:

```
character.enchant(&mut thing)
```

When enchantment is successful, thing glows brightly. When a mistake occurs, thing is transformed into a trinket. Within listing 8.4, we create a party of characters with the following syntax:

```
58 let d = Dwarf {};
59 let e = Elf {};
60 let h = Human {};
61
62 let party: Vec<&dyn Enchanter> = vec![&d, &h, &e];
```

Although d, e, and h are different types, using the type hint &dyn Enchanter tells the compiler to treat each value as a trait object. These now all have the same type.

Casting the spell involves choosing a spellcaster. We make use of the rand crate for that:

```
58 let spellcaster = party.choose(&mut rand::thread_rng()).unwrap();
59 spellcaster.enchant(&mut it)
```

The choose() method originates from the rand::seq::SliceRandom trait that is brought into scope in listing 8.4. One of the party is chosen at random. The party then attempts to enchant the object it. Compiling and running listing 8.4 results in a variation of this:

```
$ cargo run
...
Compiling rpg v0.1.0 (/rust-in-action/code/ch8/ch8-rpg)
Finished dev [unoptimized + debuginfo] target(s) in 2.13s
    Running `target/debug/rpg`
Human mutters incoherently. The Sword glows brightly.

$ target/debug/rpg
Elf mutters incoherently. The Sword fizzes, then turns into a worthless
trinket.
```

Re-executes  
the command  
without  
recompiling

The following listing shows the metadata for our fantasy role-playing game. The source code for the rpg project is in ch8/ch8-rpg/Cargo.toml.

<sup>2</sup> Naming is hard.

**Listing 8.3 Crate metadata for the rpg project**

```
[package]
name = "rpg"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
rand = "0.7"
```

Listing 8.4 provides an example of using a trait object to enable a container to hold several types. You'll find its source in ch8/ch8-rpg/src/main.rs.

**Listing 8.4 Using the trait object &dyn Enchanter**

```
1 use rand;
2 use rand::seq::SliceRandom;
3 use rand::Rng;
4
5 #[derive(Debug)]
6 struct Dwarf {}
7
8 #[derive(Debug)]
9 struct Elf {}
10
11 #[derive(Debug)]
12 struct Human {}
13
14 #[derive(Debug)]
15 enum Thing {
16     Sword,
17     Trinket,
18 }
19
20 trait Enchanter: std::fmt::Debug {
21     fn competency(&self) -> f64;
22
23     fn enchant(&self, thing: &mut Thing) {
24         let probability_of_success = self.competency();
25         let spell_is_successful = rand::thread_rng()
26             .gen_bool(probability_of_success); ←
27
28         print!("{} mutters incoherently. ", self);
29         if spell_is_successful {
30             println!("The {} glows brightly.", thing);
31         } else {
32             println!("The {} fizzes, \
33             then turns into a worthless trinket.", thing);
34             *thing = Thing::Trinket {};
35         }
36     }
37 }
```

`gen_bool()` generates a Boolean value, where `true` occurs in proportion to its argument. For example, a value of `0.5` returns `true` 50% of the time.

```

39 impl Enchanter for Dwarf {
40     fn competency(&self) -> f64 {
41         0.5
42     }
43 }
44 impl Enchanter for Elf {
45     fn competency(&self) -> f64 {
46         0.95
47     }
48 }
49 impl Enchanter for Human {
50     fn competency(&self) -> f64 {
51         0.8
52     }
53 }
54
55 fn main() {
56     let mut it = Thing::Sword;
57
58     let d = Dwarf {};
59     let e = Elf {};
60     let h = Human {};
61
62     let party: Vec<&dyn Enchanter> = vec![&d, &h, &e];
63     let spellcaster = party.choose(&mut rand::thread_rng()).unwrap();
64
65     spellcaster.enchant(&mut it);
66 }

```

The annotations are as follows:

- Line 41: A callout points to the value 0.5 with the text "Dwarves are poor spellcasters, and their spells regularly fail."
- Line 47: A callout points to the value 0.95 with the text "Spells cast by elves rarely fail."
- Line 51: A callout points to the value 0.8 with the text "Humans are proficient at enchanting things. Mistakes are uncommon."
- Line 62: A callout points to the variable declaration "let party: Vec<&dyn Enchanter>" with the text "We can hold members of different types within the same Vec as all these implement the Enchanter trait."

Trait objects are a powerful construct in the language. In a sense, they provide a way to navigate Rust's rigid type system. As you learn about this feature in more detail, you will encounter some jargon. For example, trait objects are a form of *type erasure*. The compiler does not have access to the original type during the call to `enchant()`.

### Trait vs. type

One of the frustrating things about Rust's syntax for beginners is that trait objects and type parameters look similar. But types and traits are used in different places. For example, consider these two lines:

```
use rand::Rng;
use rand::rngs::ThreadRng;
```

Although these both have something to do with random number generators, they're quite different. `rand::Rng` is a trait; `rand::rngs::ThreadRng` is a struct. Trait objects make this distinction harder.

When used as a function argument and in similar places, the form `&dyn Rng` is a reference to something that implements the `Rng` trait, whereas `&ThreadRng` is a reference to a value of `ThreadRng`. With time, the distinction between traits and types becomes easier to grasp. Here's some common use cases for trait objects:

**(continued)**

- Creating collections of heterogeneous objects.
- Returning a value. Trait objects enable functions to return multiple concrete types.
- Supporting dynamic dispatch, whereby the function that is called is determined at runtime rather than at compile time.

Before the Rust 2018 edition, the situation was even more confusing. The `dyn` keyword did not exist. This meant that context was needed to decide between `&Rng` and `&ThreadRng`.

Trait objects are not objects in the sense that an object-oriented programmer would understand. They're perhaps closer to a mixin class. Trait objects don't exist on their own; they are agents of some other type.

An alternative analogy would be a singleton object that is delegated with some authority by another concrete type. In listing 8.4, the `&Enchanter` is delegated to act on behalf of three concrete types.

## 8.4 TCP

Dropping down from HTTP, we encounter TCP (Transmission Control Protocol). Rust's standard library provides us with cross-platform tools for making TCP requests. Let's use those. The file structure for listing 8.6, which creates an HTTP GET request, is provided here:

```
ch8-stdlib
├── src
│   └── main.rs
└── Cargo.toml
```

The following listing shows the metadata for listing 8.6. You'll find the source for this listing in `ch8/ch8-stdlib/Cargo.toml`.

### **Listing 8.5 Project metadata for listing 8.6**

```
[package]
name = "ch8-stdlib"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
```

The next listing shows how to use the Rust standard library to construct an HTTP GET request with `std::net::TcpStream`. The source for this listing is in `ch8/ch8-stdlib/src/main.rs`.

### Listing 8.6 Constructing an HTTP GET request

```

1 use std::io::prelude::*;
2 use std::net::TcpStream;
3
4 fn main() -> std::io::Result<()> {
5     let host = "www.rustinaction.com:80";           ←
6
7     let mut conn =
8         TcpStream::connect(host)?;                  ←
9
10    conn.write_all(b"GET / HTTP/1.0")?;            ←
11    conn.write_all(b"\r\n")?;                      ←
12
13    conn.write_all(b"Host: www.rustinaction.com")?; ←
14    conn.write_all(b"\r\n\r\n")?;                   ←
15
16    std::io::copy(                                ←
17        &mut conn,                                ←
18        &mut std::io::stdout()                    ←
19    )?;                                         ←
20
21    Ok(())
22 }
```

**Explicitly specifying the port (80) is required.**  
**TcpStream does not know that this will become a HTTP request.**

**In many networking protocols, \r\n signifies a new line.**

**Two blank new lines signify end of request**

**std::io::copy()**  
**streams bytes from a Reader to a Writer.**

Some remarks about listing 8.6:

- On line 10, we specify HTTP 1.0. Using this version of HTTP ensures that the connection is closed when the server sends its response. HTTP 1.0, however, does not support “keep alive” requests. Specifying HTTP 1.1 actually confuses this code as the server will refuse to close the connection until it has received another request, and the client will never send one.
- On line 13, we include the hostname. This may feel redundant given that we used that exact hostname when we connected on lines 7–8. However, one should remember that the connection is established over IP, which does not have host names. When `TcpStream::connect()` connects to the server, it only uses an IP address. Adding the Host HTTP header allows us to inject that information back into the context.

#### 8.4.1 What is a port number?

Port numbers are purely virtual. They are simply `u16` values. Port numbers allow a single IP address to host multiple services.

#### 8.4.2 Converting a hostname to an IP address

So far, we’ve provided the hostname `www.rustinaction.com` to Rust. But to send messages over the internet, the IP (internet protocol) address is required. TCP knows nothing about domain names. To convert a domain name to an IP address, we rely on the Domain Name System (DNS) and its process called *domain name resolution*.

We're able to resolve names by asking a server, which can recursively ask other servers. DNS requests can be made over TCP, including encryption with TLS, but are also sent over UDP (User Datagram Protocol). We'll use DNS here because it's more useful for learning purposes.

To explain how the translation from a domain name to an IP address works, we'll create a small application that does the translation. We'll call the application *resolve*. You'll find its source code in listing 8.9. The application makes use of public DNS services, but you can easily add your own with the `-s` argument.

### Public DNS providers

At the time of writing, several companies provide DNS servers for public use. Any of the IP addresses listed here should offer roughly equivalent service:

- 1.1.1.1 and 1.0.0.1 by Cloudflare
- 8.8.8 and 8.8.4.4. by Google
- 9.9.9.9 by Quad9 (founded by IBM)
- 64.6.64.6 and 64.6.65.6 by VeriSign

Our `resolve` application only understands a small portion of DNS protocol, but that portion is sufficient for our purposes. The project makes use of an external crate, `trust-dns`, to perform the hard work. The `trust-dns` crate implements RFC 1035, which defines DNS and several later RFCs quite faithfully using terminology derived from it. Table 8.1 outlines some of the terms that are useful to understand.

**Table 8.1** Terms that are used in RFC 1035, the `trust_dns` crate, and listing 8.9, and how these interlink

Term	Definition	Representation in code
Domain name	<p>A domain name is almost what you probably think of when you use the term <i>domain name</i> in your everyday language.</p> <p>The technical definition includes some special cases such as the root domain, which is encoded as a single dot, and domain names that need to be case-insensitive.</p>	<pre>Defined in trust_dns::domain::Name pub struct Name {     is_fqdn: bool,     labels: Vec&lt;Label&gt;, }</pre> <p>fqdn stands for fully-qualified domain name.</p>

**Table 8.1 Terms that are used in RFC 1035, the trust\_dns crate, and listing 8.9, and how these interlink (continued)**

Term	Definition	Representation in code
Message	<p>A message is a container for both requests to DNS servers (called <i>queries</i>) and responses back to clients (called <i>answers</i>).</p> <p>Messages must contain a header, but other fields are not required. A Message struct represents this and includes several <code>Vec&lt;T&gt;</code> fields. These do not need to be wrapped in <code>Option</code> to represent missing values as their length can be 0.</p>	<pre data-bbox="766 273 1209 511">Defined in trust_dns::domain::Name struct Message {     header: Header,     queries: Vec&lt;Query&gt;,     answers: Vec&lt;Record&gt;,     name_servers: Vec&lt;Record&gt;,     additional: Vec&lt;Record&gt;,     sig0: Vec&lt;Record&gt;,     edns: Option&lt;Edns&gt;, }</pre> <p data-bbox="860 534 1172 582"><b>edns indicates whether the message includes extended DNS.</b></p> <p data-bbox="851 605 1200 689"><b>sig0</b>, a cryptographically signed record, verifies the message's integrity. It is defined in RFC 2535.</p>
Message type	<p>A message type identifies the message as a query or as an answer. Queries can also be updates, which are functionality that our code ignores.</p>	<pre data-bbox="766 706 1209 836">Defined in trust_dns::op::MessageType pub enum MessageType {     Query,     Response, }</pre>
Message ID	<p>A number that is used for senders to link queries and answers.</p>	<p data-bbox="766 854 808 877">u16</p>
Resource record type	<p>The resource record type refers to the DNS codes that you've probably encountered if you've ever configured a domain name.</p> <p>Of note is how trust_dns handles invalid codes. The RecordType enum contains an Unknown(u16) variant that can be used for codes that it doesn't understand.</p>	<pre data-bbox="766 925 1251 1221">Defined in trust_dns::rr::record_type::RecordType pub enum RecordType {     A,     AAAA,     ANAME,     ANY,     // ...     Unknown(u16),     ZERO, }</pre>
Query	<p>A Query struct holds the domain name and the record type that we're seeking the DNS details for. These traits also describe the DNS class and allow queries to distinguish between messages sent over the internet from other transport protocols.</p>	<pre data-bbox="766 1227 1134 1387">Defined in trust_dns::op::Query pub struct Query {     name: Name,     query_type: RecordType,     query_class: DNSClass, }</pre>

**Table 8.1 Terms that are used in RFC 1035, the trust\_dns crate, and listing 8.9, and how these interlink (continued)**

Term	Definition	Representation in code
Opcode	An OpCode enum is, in some sense, a subtype of MessageType. This is an extensibility mechanism that allows future functionality. For example, RFC 1035 defines the Query and Status opcodes but others were defined later. The Notify and Update opcodes are defined by RFC 1996 and RFC 2136, respectively.	Defined in <code>trust_dns::op::OpCode</code> <code>pub enum OpCode {</code> <code>    Query,</code> <code>    Status,</code> <code>    Notify,</code> <code>    Update,</code> <code>}</code>

An unfortunate consequence of the protocol, which I suppose is a consequence of reality, is that there are many options, types, and subtypes involved. Listing 8.7, an excerpt from listing 8.9, shows the process of constructing a message that asks, “Dear DNS server, what is the IPv4 address for domain\_name?” The listing constructs the DNS message, whereas the trust-dns crate requests an IPv4 address for domain\_name.

#### Listing 8.7 Constructing a DNS message in Rust

```

A Message is a container for
queries (or answers).
35 let mut msg = Message::new();           ← Generates a random
36 msg                                     ← ul6 number
37     .set_id(rand::random::<u16>())      ← Multiple queries can be
38     .set_message_type(MessageType::Query) ← included in the same
39     .add_query(                           ← message.
40         Query::query(domain_name, RecordType::A) ← The equivalent
41     )                                     ← type for IPv6
42     .set_op_code(OpCode::Query)           ← addresses is
43     .set_recursion_desired(true);        ← AAAA.

```

We’re now in a position where we can meaningfully inspect the code. It has the following structure:

- Parses command-line arguments
- Builds a DNS message using trust\_dns types
- Converts the structured data into a stream of bytes
- Sends those bytes across the wire

After that, we need to accept the response from the server, decode the incoming bytes, and print the result. Error handling remains relatively ugly, with many calls to `unwrap()` and `expect()`. We’ll address that problem shortly in section 8.5. The end process is a command-line application that’s quite simple.

Running our resolve application involves little ceremony. Given a domain name, it provides an IP address:

```
$ resolve www.rustinaction.com 35.185.44.232
```

Listings 8.8 and 8.9 are the project's source code. While you are experimenting with the project, you may want to use some features of cargo run to speed up your process:

```
$ cargo run -q -- www.rustinaction.com
35.185.44.232
```

Sends arguments to the right of -- to the executable it compiles. The -q option mutes any intermediate output.

To compile the resolve application from the official source code repository, execute these commands in the console:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
```

```
$ cd rust-in-action/ch8/ch8-resolve
```

```
$ cargo run -q -- www.rustinaction.com
35.185.44.232
```

It may take a while to download the project's dependencies and compile the code. The -q flag mutes intermediate output. Adding two dashes (--) sends further arguments to the compiled executable.

To compile and build from scratch, follow these instructions to establish the project structure:

- At the command-line, enter these commands:

```
$ cargo new resolve
    Created binary (application) `resolve` package

$ cargo install cargo-edit
...

$ cd resolve

$ cargo add rand@0.6
    Updating 'https://github.com/rust-lang/crates.io-index' index
        Adding rand v0.6 to dependencies

$ cargo add clap@2
    Updating 'https://github.com/rust-lang/crates.io-index' index
        Adding rand v2 to dependencies

$ cargo add trust-dns@0.16 --no-default-features
    Updating 'https://github.com/rust-lang/crates.io-index' index
        Adding trust-dns v0.16 to dependencies
```

- Once the structure has been established, you check that your Cargo.toml matches listing 8.8, available in ch8/ch8-resolve/Cargo.toml.
- Replace the contents of src/main.rs with listing 8.9. It is available from ch8/ch8-resolve/src/main.rs.

The following snippet provides a view of how the files of the project and the listings are interlinked:

```
ch8-resolve
├── Cargo.toml      ← See listing 8.8
└── src
    └── main.rs      ← See listing 8.9
```

### Listing 8.8 Crate metadata for the resolve app

```
[package]
name = "resolve"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
rand = "0.6"
clap = "2.33"
trust-dns = { version = "0.16", default-features = false }
```

### Listing 8.9 A command-line utility to resolve IP addresses from hostnames

```
1 use std::net::{SocketAddr, UdpSocket};
2 use std::time::Duration;
3
4 use clap::{App, Arg};
5 use rand;
6 use trust_dns::op::{Message, MessageType, OpCode, Query};
7 use trust_dns::rr::domain::Name;
8 use trust_dns::rr::record_type::RecordType;
9 use trust_dns::serialize::binary::*;

10
11 fn main() {
12     let app = App::new("resolve")
13         .about("A simple to use DNS resolver")
14         .arg(Arg::with_name("dns-server").short("s").default_value("1.1.1.1"))
15         .arg(Arg::with_name("domain-name").required(true))
16         .get_matches();
17
18     let domain_name_raw = app
19         .value_of("domain-name").unwrap();
20     let domain_name =
21         Name::from_ascii(&domain_name_raw).unwrap();
22
23     let dns_server_raw = app
24         .value_of("dns-server").unwrap();
25     let dns_server: SocketAddr =
26         format!("{}:53", dns_server_raw)
27         .parse()
28         .expect("invalid address");
29
```

Converts the command-line argument to a typed domain name

Converts the command-line argument to a typed DNS server

```

30 let mut request_as_bytes: Vec<u8> =
31     Vec::with_capacity(512);
32 let mut response_as_bytes: Vec<u8> =
33     vec![0, 512];
34
35 let mut msg = Message::new();           ←
36 msg
37     .set_id(rand::random::<u16>())
38     .set_message_type(MessageType::Query) ←
39     .add_query(Query::query(domain_name, RecordType::A))
40     .set_op_code(OpCode::Query)
41     .set_recursion_desired(true);
42
43 let mut encoder =
44     BinEncoder::new(&mut request_as_bytes); ←
45 msg.emit(&mut encoder).unwrap();
46
47 let localhost = UdpSocket::bind("0.0.0.0:0") ←
48     .expect("cannot bind to local socket");
49 let timeout = Duration::from_secs(3);
50 localhost.set_read_timeout(Some(timeout)).unwrap();
51 localhost.set_nonblocking(false).unwrap();
52
53 let _amt = localhost
54     .send_to(&request_as_bytes, dns_server)
55     .expect("socket misconfigured");
56
57 let (_amt, _remote) = localhost
58     .recv_from(&mut response_as_bytes)
59     .expect("timeout reached");
60
61 let dns_message = Message::from_vec(&response_as_bytes)
62     .expect("unable to parse response");
63
64 for answer in dns_message.answers() {
65     if answer.record_type() == RecordType::A {
66         let resource = answer.rdata();
67         let ip = resource
68             .to_ip_addr()
69             .expect("invalid IP address received");
70         println!("{}: {}", ip.to_string());
71     }
72 }
73 }
```

An explanation of why two forms of initializing are used is provided after the listing.

Message represents a DNS message, which is a container for queries and other information such as answers.

Specifies that this is a DNS query, not a DNS answer. Both have the same representation over the wire, but not in Rust's type system.

Converts the Message type into raw bytes with BinEncoder

0.0.0.0:0 means listen to all addresses on a random port. The OS selects the actual port.

Listing 8.9 includes some business logic that deserves explaining. Lines 30–33, repeated here, use two forms of initializing a `Vec<u8>`. Why?

```

30 let mut request_as_bytes: Vec<u8> =
31     Vec::with_capacity(512);
32 let mut response_as_bytes: Vec<u8> =
33     vec![0, 512];
```

Each form creates a subtly different outcome:

- `Vec::with_capacity(512)` creates a `Vec<T>` with length 0 and capacity 512.
- `vec![0; 512]` creates a `Vec<T>` with length 512 and capacity 512.

The underlying array looks the same, but the difference in length is significant. Within the call to `recv_from()` at line 58, the `trust-dns` crate includes a check that `response_as_bytes` has sufficient space. That check uses the `length` field, which results in a crash. Knowing how to wriggle around with initialization can be handy for satisfying an APIs' expectations.

### How DNS supports connections within UDP

UDP does not have a notion of long-lived connections. Unlike TCP, all messages are short-lived and one-way. Put another way, UDP does not support two-way (*duplex*) communications. But DNS requires a response to be sent from the DNS server back to the client.

To enable two-way communications within UDP, both parties must act as clients and servers, depending on context. That context is defined by the protocol built on top of UDP. Within DNS, the client becomes a DNS server to receive the server's reply. The following table provides a flow chart of the process.

Stage	DNS client role	DNS server role
Request sent from DNS client	UDP client	UDP server
Reply sent from DNS server	UDP server	UDP client

It's time to recap. Our overall task in this section was to make HTTP requests. HTTP is built on TCP. Because we only had a domain name (`www.rustinaction.com`) when we made the request, we needed to use DNS. DNS is primarily delivered over UDP, so we needed to take a diversion and learn about UDP.

Now it's almost time to return to TCP. Before we're able to do that, though, we need to learn how to combine error types that emerge from multiple dependencies.

## 8.5 Ergonomic error handling for libraries

Rust's error handling is safe and sophisticated. However, it offers a few challenges. When a function incorporates `Result` types from two upstream crates, the `?` operator no longer works because it only understands a single type. This proves to be important when we refactor our domain resolution code to work alongside our TCP code. This section discusses some of those challenges as well as strategies for managing them.

### 8.5.1 Issue: Unable to return multiple error types

Returning a `Result<T, E>` works great when there is a single error type `E`. But things become more complicated when we want to work with multiple error types.

**TIP** For single files, compile the code with `rustc <filename>` rather than using cargo build. For example, if a file is named `io-error.rs`, then the shell command is `rustc io-error.rs && ./io-error[.exe]`.

To start, let's look at a small example that covers the easy case of a single error type. We'll try to open a file that does not exist. When run, listing 8.10 prints a short message in Rust syntax:

```
$ rustc ch8/misc/io-error.rs && ./io-error
Error: Os { code: 2, kind: NotFound, message: "No such file or directory" }
```

We won't win any awards for user experience here, but we get a chance to learn a new language feature. The following listing provides the code that produces a single error type. You'll find its source in `ch8/misc/io-error.rs`.

**Listing 8.10 A Rust program that always produces an I/O error**

```
1 use std::fs::File;
2
3 fn main() -> Result<(), std::io::Error> {
4     let _f = File::open("invisible.txt")?;
5
6     Ok(())
7 }
```

Now, let's introduce another error type into `main()`. The next listing produces a compiler error, but we'll work through some options to get the code to compile. The code for this listing is in `ch8/misc/multierror.rs`.

**Listing 8.11 A function that attempts to return multiple `Result` types**

```
1 use std::fs::File;
2 use std::net::Ipv6Addr;
3
4 fn main() -> Result<(), std::io::Error> {
5     let _f = File::open("invisible.txt")?;
6
7     let _localhost = "::1"
8     .parse::<Ipv6Addr>()?;
9
10    Ok(())
11 }
```

`File::open()`  
returns `Result<(),  
std::io::Error>`.

`".parse::<Ipv6Addr>()` returns `Result<Ipv6Addr,  
std::net::AddrParseError>`.

To compile listing 8.11, enter the `ch8/misc` directory and use `rustc`. This produces quite a stern, yet helpful, error message:

```
$ rustc multiorerror.rs
error[E0277]: `?` couldn't convert the error to `std::io::Error`
--> multiorerror.rs:8:25
   |
4 | fn main() -> Result<(), std::io::Error> {
   |           ----- expected `std::io::Error`  
because of this
...
8 |     .parse::<Ipv6Addr>()?;
   |           ^ the trait `From<AddrParseError>`  
is not implemented for `std::io::Error`  

   |
= note: the question mark operation (`?`) implicitly performs a  
conversion on the error value using the `From` trait
= help: the following implementations were found:  
    <std::io::Error as From<ErrorKind>>  
    <std::io::Error as From<IntoInnerError<W>>>  
    <std::io::Error as From<NulError>>
= note: required by `from`  
  
error: aborting due to previous error
```

For more information about this error, try `rustc --explain E0277`.

The error message can be difficult to interpret if you don't know what the question mark operator (?) is doing. Why are there multiple messages about std::convert::From? Well, the ? operator is syntactic sugar for the try! macro. try! performs two functions:

- When it detects Ok(value), the expression evaluates to value.
- When Err(err) occurs, try!/? returns early after attempting to convert err to the error type defined in the calling function.

In Rust-like pseudocode, the try! macro could be defined as

```
macro try {  
    match expression {  
        Result::Ok(val) => val,           |<br/>Uses val when an  
        Result::Err(err) => {  
            let converted = convert::From::from(err);  
            return Result::Err(converted);      |<br/>Converts err to the  
        }  
    );  
}
```

Converts err to the outer function's error type when it matches Result::Err(err) and then returns early

Returns from the calling function, not the try! macro itself

Looking at listing 8.11 again, we can see the try! macro in action as ?:

```
4 fn main() -> Result<(), std::io::Error> {  
5     let _f = File::open("invisible.txt")?;    |<br/>File::open() returns  
6  
7     let _localhost = "::1"                      |<br/>std::io::Error, so no  
8     .parse::<Ipv6Addr>()?;                   |<br/>conversion is necessary.  
                                         |<br/>".parse() presents ? with a std::net::AddrParseError. We  
                                         |<br/>don't define how to convert std::net::AddrParseError  
                                         |<br/>to std::io::Error, so the program fails to compile.
```

```

9
10    Ok(())
11 }
```

In addition to saving you from needing to use explicit pattern matching to extract the value or return an error, the ? operator also attempts to convert its argument into an error type if required. Because the signature of main is `main() ? Result<(), std::io::Error>`, Rust attempts to convert the `std::net::AddrParseError` produced by `parse:::<Ipv6Addr>()` into a `std::io::Error`. Don't worry, though; we can fix this! Earlier, in section 8.3, we introduced trait objects. Now we'll be able to put those to good use.

Using `Box<dyn Error>` as the error variant in the `main()` function allows us to progress. The `dyn` keyword is short for *dynamic*, implying that there is a runtime cost for this flexibility. Running listing 8.12 produces this output:

```
$ rustc ch8/misc/traiterror.rs && ./traiterror
Error: Os { code: 2, kind: NotFound, message: "No such file or directory" }
```

I suppose it's a limited form of progress, but progress nonetheless. We've circled back to the error we started with. But we've passed through the compiler error, which is what we wanted.

Going forward, let's look at listing 8.12. It implements a trait object in a return value to simplify error handling when errors originate from multiple upstream crates. You can find the source for this listing in `ch8/misc/traiterror.rs`.

### Listing 8.12 Using a trait object in a return value

```

1 use std::fs::File;
2 use std::error::Error;
3 use std::net::Ipv6Addr;
4
5 fn main() -> Result<(), Box<dyn Error>> {
6
7     let _f = File::open("invisible.txt")?;
8
9     let _localhost = "::1"
10    .parse:::<Ipv6Addr>()?;
11
12    Ok(())
13 }
```

The code in Listing 8.12 is annotated with three callout boxes pointing to specific parts of the code:

- A callout box points to the line `Box<dyn Error>` in the return type of the `main` function. It contains the text: "A trait object, `Box<dyn Error>`, represents any type that implements `Error`".
- A callout box points to the line `let _f = File::open("invisible.txt")?`. It contains the text: "Error type is `std::io::Error`".
- A callout box points to the line `.parse:::<Ipv6Addr>()?`. It contains the text: "Error type is `std::net::AddrParseError`".

Wrapping trait objects in `Box` is necessary because their size (in bytes on the stack) is unknown at compile time. In the case of listing 8.12, the trait object might originate from either `File::open()` or `::1.parse()`. What actually happens depends on the circumstances encountered at runtime. A `Box` has a known size on the stack. Its raison d'être is to point to things that don't, such as trait objects.

## 8.5.2 Wrapping downstream errors by defining our own error type

The problem that we are attempting to solve is that each of our dependencies defines its own error type. Multiple error types in one function prevent returning `Result`. The first strategy we looked at was to use trait objects, but trait objects have a potentially significant downside.

Using trait objects is also known as *type erasure*. Rust is no longer aware that an error has originated upstream. Using `Box<dyn Error>` as the error variant of a `Result` means that the upstream error types are, in a sense, lost. The original errors are now converted to exactly the same type.

It is possible to retain the upstream errors, but this requires more work on our behalf. We need to bundle upstream errors in our own type. When the upstream errors are needed later (say, for reporting errors to the user), it's possible to extract these with pattern matching. Here is the process:

- 1 Define an enum that includes the upstream errors as variants.
- 2 Annotate the enum with `# [derive(Debug)]`.
- 3 Implement `Display`.
- 4 Implement `Error`, which almost comes for free because we have implemented `Debug` and `Display`.
- 5 Use `map_err()` in your code to convert the upstream error to your omnibus error type.

**NOTE** You haven't previously encountered the `map_err()` function. We'll explain what it does when we get there later in this section.

It's possible to stop with the previous steps, but there's an optional extra step that improves the ergonomics. We need to implement `std::convert::From` to remove the need to call `map_err()`. To begin, let's start back with listing 8.11, where we know that the code fails:

```
use std::fs::File;
use std::net::Ipv6Addr;

fn main() -> Result<(), std::io::Error> {
    let _f = File::open("invisible.txt")?;

    let _localhost = "::1"
        .parse:::<Ipv6Addr>()?;
    Ok(())
}
```

This code fails because `" ".parse:::<Ipv6Addr>()` does not return a `std::io::Error`. What we want to end up with is code that looks a little more like the following listing.

**Listing 8.13 Hypothetical example of the kind of code we want to write**

```

1 use std::fs::File;
2 use std::io::Error;
3 use std::net::AddrParseError;           | Brings upstream errors
4 use std::net::Ipv6Addr;                | into local scope
5
6 enum UpstreamError{
7     IO(std::io::Error),
8     Parsing(AddrParseError),
9 }
10
11 fn main() -> Result<(), UpstreamError> {
12     let _f = File::open("invisible.txt")?
13         .maybe_convert_to(UpstreamError);
14
15     let _localhost = "::1"?
16         .parse::<Ipv6Addr>()?
17         .maybe_convert_to(UpstreamError);
18
19     Ok(())
20 }
```

**DEFINE AN ENUM THAT INCLUDES THE UPSTREAM ERRORS AS VARIANTS**

The first thing to do is to return a type that can hold the upstream error types. In Rust, an enum works well. Listing 8.13 does not compile, but does do this step. We'll tidy up the imports slightly, though:

```

use std::io;
use std::net;

enum UpstreamError{
    IO(io::Error),
    Parsing(net::AddrParseError),
}
```

**ANNOTATE THE ENUM WITH #[**derive(Debug)**]**

The next change is easy. It's a single-line change—the best kind of change. To annotate the enum, we'll add `# [derive(Debug)]`, as the following shows:

```

use std::io;
use std::net;

#[derive(Debug)]
enum UpstreamError{
    IO(io::Error),
    Parsing(net::AddrParseError),
}
```

**IMPLEMENT `STD::FMT::DISPLAY`**

We'll cheat slightly and implement `Display` by simply using `Debug`. We know that this is available to us because errors must define `Debug`. Here's the updated code:

```

use std::fmt;
use std::io;
use std::net;

#[derive(Debug)]
enum UpstreamError{
    IO(io::Error),
    Parsing(net::AddrParseError),
}

impl fmt::Display for UpstreamError {
    fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
        write!(f, "{:?}", self)           ←
    }
}

```

Implements Display in terms of Debug via the "{:?"} syntax

### IMPLEMENT STD::ERROR::ERROR

Here's another easy change. To end up with the kind of code that we'd like to write, let's make the following change:

```

use std::error;           ← Brings the
use std::fmt;             std::error::Error trait
use std::io;              into local scope
use std::net;

#[derive(Debug)]
enum UpstreamError{
    IO(io::Error),
    Parsing(net::AddrParseError),
}

impl fmt::Display for UpstreamError {
    fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
        write!(f, "{:?}", self)
    }
}

impl error::Error for UpstreamError { }           ← Defers to default method
                                                implementations. The compiler
                                                will fill in the blanks.

```

The `impl` block is—well, we can rely on default implementations provided by the compiler—especially terse. Because there are default implementations of every method defined by `std::error::Error`, we can ask the compiler to do all of the work for us.

### USE MAP\_ERR()

The next fix is to add `map_err()` to our code to convert the upstream error to the omnibus error type. Back at listing 8.13, we wanted to have a `main()` that looks like this:

```

fn main() -> Result<(), UpstreamError> {
    let _f = File::open("invisible.txt")?
        .maybe_convert_to(UpstreamError);

    let _localhost = "::1"
        .parse::<Ipv6Addr>()?;
}

```

```

    .maybe_convert_to(UpstreamError);

    Ok(())
}

```

I can't offer you that. I can, however, give you this:

```

fn main() -> Result<(), UpstreamError> {
    let _f = File::open("invisible.txt")
        .map_err(UpstreamError::IO)?;

    let _localhost = "::1"
        .parse::<Ipv6Addr }()
        .map_err(UpstreamError::Parsing)?;

    Ok(())
}

```

This new code works! Here's how. The `map_err()` function maps an error to a function. (Variants of our `UpstreamError` enum can be used as functions here.) Note that the `?` operator needs to be at the end. Otherwise, the function can return before the code has a chance to convert the error.

Listing 8.14 provides the new code. When run, it produces this message to the console:

```
$ rustc ch8/misc/wraperror.rs && ./wraperror
Error: IO(Os { code: 2, kind: NotFound, message: "No such file or directory" })
```

To retain type safety, we can use the new code in the following listing. You'll find its source in `ch8/misc/wraperror.rs`.

#### Listing 8.14 Wrapping upstream errors in our own type

```

1 use std::io;
2 use std::fmt;
3 use std::net;
4 use std::fs::File;
5 use std::net::Ipv6Addr;
6
7 #[derive(Debug)]
8 enum UpstreamError{
9     IO(io::Error),
10    Parsing(net::AddrParseError),
11 }
12
13 impl fmt::Display for UpstreamError {
14     fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
15         write!(f, "{}", self)
16     }
17 }
18
19 impl error::Error for UpstreamError { }

```

```

20
21 fn main() -> Result<(), UpstreamError> {
22     let _f = File::open("invisible.txt")
23         .map_err(UpstreamError::IO)?;
24
25     let _localhost = "::1"
26         .parse::<Ipv6Addr>()
27         .map_err(UpstreamError::Parsing)?;
28
29     Ok(())
30 }
```

It's also possible to remove the calls to `map_err()`. But to enable that, we need to implement `From`.

#### **IMPLEMENT STD::CONVERT::FROM TO REMOVE THE NEED TO CALL MAP\_ERR()**

The `std::convert::From` trait has a single required method, `from()`. We need two `impl` blocks to enable our two upstream error types to be convertible. The following snippet shows how:

```

impl From<io::Error> for UpstreamError {
    fn from(error: io::Error) -> Self {
        UpstreamError::IO(error)
    }
}

impl From<net::AddrParseError> for UpstreamError {
    fn from(error: net::AddrParseError) -> Self {
        UpstreamError::Parsing(error)
    }
}
```

Now the `main()` function returns to a simple form of itself:

```

fn main() -> Result<(), UpstreamError> {
    let _f = File::open("invisible.txt")?;
    let _localhost = "::1".parse::<Ipv6Addr>()?;
    Ok(())
}
```

The full code listing is provided in listing 8.15. Implementing `From` places the burden of extra syntax on the library writer. It results in a much easier experience when using your crate, simplifying its use by downstream programmers. You'll find the source for this listing in `ch8/misc/wraperror2.rs`.

#### **Listing 8.15 Implementing std::convert::From for our wrapper error type**

```

1 use std::io;
2 use std::fmt;
3 use std::net;
```

```

4 use std::fs::File;
5 use std::net::Ipv6Addr;
6
7 #[derive(Debug)]
8 enum UpstreamError{
9     IO(io::Error),
10    Parsing(net::AddrParseError),
11 }
12
13 impl fmt::Display for UpstreamError {
14     fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
15         write!(f, "{}", self)                                     1((co20-1))
16     }
17 }
18
19 impl error::Error for UpstreamError { }
20
21 impl From<io::Error> for UpstreamError {
22     fn from(error: io::Error) -> Self {
23         UpstreamError::IO(error)
24     }
25 }
26
27 impl From<net::AddrParseError> for UpstreamError {
28     fn from(error: net::AddrParseError) -> Self {
29         UpstreamError::Parsing(error)
30     }
31 }
32
33 fn main() -> Result<(), UpstreamError> {
34     let _f = File::open("invisible.txt")?;
35     let _localhost = "::1".parse::<Ipv6Addr>()?;
36
37     Ok(())
38 }
```

### 8.5.3 Cheating with `unwrap()` and `expect()`

The final approach for dealing with multiple error types is to use `unwrap()` and `expect()`. Now that we have the tools to handle multiple error types in a function, we can continue our journey.

**NOTE** This is a reasonable approach when writing a `main()` function, but it isn't recommended for library authors. Your users don't want their programs to crash because of things outside of their control.

## 8.6 MAC addresses

Several pages ago in listing 8.9, you implemented a DNS resolver. That enabled conversions from a host name such as `www.rustinaction.com` to an IP address. Now we have an IP address to connect to.

The internet protocol enables devices to contact each other via their IP addresses. But that's not all. Every hardware device also includes a unique identifier that's independent of the network it's connected to. Why a second number? The answer is partially technical and partially historical.

Ethernet networking and the internet started life independently. Ethernet's focus was on local area networks (LANs). The internet was developed to enable communication between networks, and Ethernet is the addressing system understood by devices that share a physical link (or a radio link in the case of WiFi, Bluetooth, and other wireless technologies).

Perhaps a better way to express this is that MAC (short for *media access control*) addresses are used by devices that share electrons (figure 8.3). But there are a few differences:

- *IP addresses are hierarchical, but MAC addresses are not.* Addresses appearing close together numerically are not close together physically, or organizationally.
- *MAC addresses are 48 bits (6 bytes) wide.* IP addresses are 32 bits (4 bytes) wide for IPv4 and 128 bits (16 bytes) for IPv6.




Figure 8.3 In-memory layout for MAC addresses

There are two forms of MAC addresses:

- *Universally administered (or universal) addresses are set when devices are manufactured.* Manufacturers use a prefix assigned by the IEEE Registration Authority and a scheme of their choosing for the remaining bits.
- *Locally administered (or local) addresses allow devices to create their own MAC addresses without registration.* When setting a device's MAC address yourself in software, you should make sure that your address is set to the local form.

MAC addresses have two modes: *unicast* and *multicast*. The transmission behavior for these forms is identical. The distinction is made when a device makes a decision about whether to accept a frame. A *frame* is a term used by the Ethernet protocol for a byte slice at this level. Analogies to frame include a packet, wrapper, and envelope. Figure 8.4 shows this distinction.

### Unicast vs. multicast MAC addresses




Figure 8.4 The differences between multicast and unicast MAC addresses

Unicast addresses are intended to transport information between two points that are in direct contact (say, between a laptop and a router). Wireless access points complicate matters somewhat but don't change the fundamentals. A multicast address can be accepted by multiple recipients, whereas unicast has a single recipient. The term *unicast* is somewhat misleading, though. Sending an Ethernet packet involves more than two devices. Using a unicast address alters what devices do when they receive packets but not which data is transmitted over the wire (or through the radio waves).

#### 8.6.1 Generating MAC addresses

When we begin talking about raw TCP in section 8.8, we'll create a virtual hardware device in listing 8.22. To convince anything to talk to us, we need to learn how to assign our virtual device a MAC address. The `macgen` project in listing 8.17 generates

the MAC addresses for us. The following listing shows the metadata for that project. You can find its source in ch8/ch8-mac/Cargo.toml.

#### Listing 8.16 Crate metadata for the macgen project

```
[package]
name = "ch8-macgen"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
rand = "0.7"
```

The following listing shows the macgen project, our MAC address generator. The source code for this project is in the ch8/ch8-mac/src/main.rs file.

#### Listing 8.17 Creating macgen, a MAC address generator

```
1 extern crate rand;
2
3 use rand::RngCore;
4 use std::fmt;
5 use std::fmt::Display;
6
7 #[derive(Debug)]
8 struct MacAddress([u8; 6]);           ← Uses the newtype pattern to
                                         wrap a bare array without
                                         any extra overhead
9
10 impl Display for MacAddress {
11     fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
12         let octet = &self.0;
13         write!(
14             f,
15             "{:02x}:{:02x}:{:02x}:{:02x}:{:02x}:{:02x}",
16             octet[0], octet[1], octet[2],
17             octet[3], octet[4], octet[5]           ← Converts each byte
                                         to hexadecimal
                                         notation
18         )
19     }
20 }
21
22 impl MacAddress {
23     fn new() -> MacAddress {
24         let mut octets: [u8; 6] = [0; 6];
25         rand::thread_rng().fill_bytes(&mut octets);
26         octets[0] |= 0b_0000_0011;           ← Sets the MAC
                                         address to local
                                         and unicast
27         MacAddress { 0: octets }
28     }
29
30     fn is_local(&self) -> bool {
31         (self.0[0] & 0b_0000_0010) == 0b_0000_0010
32     }
33
34     fn is_unicast(&self) -> bool {
35         (self.0[0] & 0b_0000_0001) == 0b_0000_0001
```

```

36     }
37 }
38
39 fn main() {
40     let mac = MacAddress::new();
41     assert!(mac.is_local());
42     assert!(mac.is_unicast());
43     println!("mac: {}", mac);
44 }
```

The code from listing 8.17 should feel legible. Line 25 contains some relatively obscure syntax, though. `octets[0] |= 0b_0000_0011` coerces the two flag bits described at figure 8.3 to a state of 1. That designates every MAC address we generate as locally assigned and unicast.

## 8.7 Implementing state machines with Rust's enums

Another prerequisite for handling network messages is being able to define a state machine. Our code needs to adapt to changes in connectivity.

Listing 8.22 contains a state machine, implemented with a `loop`, a `match`, and a Rust enum. Because of Rust's expression-based nature, control flow operators also return values. Every time around the loop, the state is mutated in place. The following listing shows the pseudocode for how a repeated `match` on a enum works together.

### Listing 8.18 Pseudocode for a state machine implementation

```

enum HttpState {
    Connect,
    Request,
    Response,
}

loop {
    state = match state {
        HttpState::Connect if !socket.is_active() => {
            socket.connect();
            HttpState::Request
        }

        HttpState::Request if socket.may_send() => {
            socket.send(data);
            HttpState::Response
        }

        HttpState::Response if socket.can_recv() => {
            received = socket.recv();
            HttpState::Response
        }

        HttpState::Response if !socket.may_recv() => {
            break;
        }
    }
}
```

```

        _ => state,
    }
}

```

More advanced methods to implement finite state machines do exist. This is the simplest, however. We'll make use of it in listing 8.22. Making use of an enum embeds the state machine's transitions into the type system itself.

But we're still at a level that is far too high! To dig deeper, we're going to need to get some assistance from the OS.

## 8.8 Raw TCP

Integrating with the raw TCP packets typically requires root/superuser access. The OS starts to get quite grumpy when an unauthorized user asks to make raw network requests. We can get around this (on Linux) by creating a proxy device that non-super users are allowed to communicate with directly.

### Don't have Linux?

If you're running another OS, there are many virtualization options available. Here are a few:

- The Multipass project (<https://multipass.run/>) provides fast Ubuntu virtual machines on macOS and Windows hosts.
- WSL, the Windows Subsystem for Linux (<https://docs.microsoft.com/en-us/windows/wsl/about>), is another option to look into.
- Oracle VirtualBox (<https://www.virtualbox.org/>) is an open source project with excellent support for many host operating systems.

## 8.9 Creating a virtual networking device

To proceed with this section, you will need to create virtual networking hardware. Using virtual hardware provides more control to freely assign IP and MAC addresses. It also avoids changing your hardware settings, which could affect its ability to connect to the network. To create a TAP device called `tap-rust`, execute the following command in your Linux console:

```

$ sudo \
> ip tunctl \
> add \
> mode tap \
> name tap-rust \
> user $USER

```

The diagram shows the command being run in a terminal. Annotations explain each part:

- Executes as the root user**: Points to the `sudo` command.
- Tells ip that we're managing TUN/TAP devices**: Points to the first two lines of the command (`ip tunctl` and `add`).`
- Uses the add subcommand**: Points to the `add` subcommand.
- Gives your device a unique name**: Points to the `name tap-rust` part.
- Grants access to your non-root user account**: Points to the `user $USER` part.
- Uses the TUN tunnelling mode**: Points to the entire command, indicating that TUN mode is used for tunnelling.

When successful, `ip` prints no output. To confirm that our tap-rust device was added, we can use the `ip tuntap list` subcommand as in the following snippet. When executed, you should see the tap-rust device in the list of devices in the output:

```
$ ip tuntap list
tap-rust: tap persist user
```

Now that we have created a networking device, we also need to allocate an IP address for it and tell our system to forward packets to it. The following shows the commands to enable this functionality:

```
$ sudo ip link set tap-rust up
$ sudo ip addr add 192.168.42.100/24 dev tap-rust
$ sudo iptables \
>     -t nat\
>     -A POSTROUTING \
>     -s 192.168.42.0/24 \
>     -j MASQUERADE
$ sudo sysctl net.ipv4.ip_forward=1
```

The following shows how to remove the device (once you have completed this chapter) by using `del` rather than `add`:

```
$ sudo ip tuntap del mode tap name tap-rust
```


## 8.10 “Raw” HTTP

We should now have all the knowledge we need to take on the challenge of using HTTP at the TCP level. The mget project (`mget` is short for *manually get*) spans listings 8.20–8.23. It is a large project, but you’ll find it immensely satisfying to understand and build. Each file provides a different role:

- *main.rs* (*listing 8.20*)—Handles command-line parsing and weaves together the functionality provided by its peer files. This is where we combine the error types using the process outlined in section 8.5.2.
- *ethernet.rs* (*listing 8.21*)—Generates a MAC address using the logic from listing 8.17 and converts between MAC address types (defined by the `smoltcp` crate) and our own.
- *http.rs* (*listing 8.22*)—Carries out the work of interacting with the server to make the HTTP request.
- *dns.rs* (*listing 8.23*)—Performs DNS resolution, which converts a domain name to an IP address.

**NOTE** The source code for these listings (and every code listing in the book) is available from <https://github.com/rust-in-action/code> or <https://www.manning.com/books/rust-in-action>.

It's important to acknowledge that listing 8.22 was derived from the HTTP client example within the smoltcp crate itself. whitequark (<https://whitequark.org/>) has built an absolutely fantastic networking library. Here's the file structure for the mget project:



To download and run the mget project from source control, execute these commands at the command line:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
$ cd rust-in-action/ch8/ch8-mget
```

Here are the project setup instructions for those readers who enjoy doing things step by step (with the output omitted).

- 1 Enter these commands at the command-line:

```
$ cargo new mget
$ cd mget
$ cargo install cargo-edit
$ cargo add clap@2
$ cargo add url@02
$ cargo add rand@0.7
$ cargo add trust-dns@0.16 --no-default-features
$ cargo add smoltcp@0.6 --features='proto-igmp proto-ipv4 verbose log'
```

- 2 Check that your project's Cargo.toml matches listing 8.19.
- 3 Within the src directory, listing 8.20 becomes main.rs, listing 8.21 becomes ethernet.rs, listing 8.22 becomes http.rs, and listing 8.23 becomes dns.rs.

The following listing shows the metadata for mget. You’ll find its source code in the ch8/ch8-mget/Cargo.toml file.

#### Listing 8.19 Crate metadata for mget

```
[package]
name = "mget"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
clap = "2"
rand = "0.7"
smoltcp = {
    version = "0.6",
    features = ["proto-igmp", "proto-ipv4", "verbose", "log"]
}
trust-dns = {
    version = "0.16",
    default-features = false
}
url = "2"
```

- `clap = "2"` → Provides command-line argument parsing
- `rand = "0.7"` → Selects a random port number
- `smoltcp = { ... }` → Provides a TCP implementation
- `trust-dns = { ... }` → Enables connecting to a DNS server
- `url = "2"` → Parses and validates URLs

The following listing shows the command-line parsing for our project. You’ll find this source in ch8/ch8-mget/src/main.rs.

#### Listing 8.20 mget command-line parsing and overall coordination

```
1 use clap::{App, Arg};
2 use smoltcp::phy::TapInterface;
3 use url::Url;
4
5 mod dns;
6 mod ethernet;
7 mod http;
8
9 fn main() {
```

- `let app = App::new("mget")` → Requires a URL to download data from
- `.arg(Arg::with_name("url").required(true))` → Requires a URL to download data from
- `.arg(Arg::with_name("tap-device").required(true))` → Requires a TAP networking device to connect with
- `.arg(Arg::with_name("dns-server").default_value("1.1.1.1"))` → Makes it possible for the user to select which DNS server to use
- `.get_matches();` → Parses the command-line arguments

```
10     .about("GET a webpage, manually")
11     .arg(Arg::with_name("url").required(true))
12     .arg(Arg::with_name("tap-device").required(true))
13
14     .arg(
15         Arg::with_name("dns-server")
16         .default_value("1.1.1.1"),
17     )
18     .get_matches();
```

```
19
20     let url_text = app.value_of("url").unwrap();
21     let dns_server_text =
22         app.value_of("dns-server").unwrap();
23     let tap_text = app.value_of("tap-device").unwrap();
24 }
```

```

25 let url = Url::parse(url_text)
26     .expect("error: unable to parse <url> as a URL");
27
28 if url.scheme() != "http" {                                     ←
29     eprintln!("error: only HTTP protocol supported");
30     return;
31 }
32
33 let tap = TapInterface::new(&tap_text)                         ←
34     .expect(
35         "error: unable to use <tap-device> as a \
36         network interface",
37     );
38
39 let domain_name =
40     url.host_str()                                         ←
41     .expect("domain name required");
42
43 let _dns_server: std::net::Ipv4Addr =
44     dns_server_text
45     .parse()                                              ←
46     .expect(
47         "error: unable to parse <dns-server> as an \
48         IPv4 address",
49     );
50
51 let addr =                                                 ←
52     dns::resolve(dns_server_text, domain_name)
53     .unwrap()                                             ←
54     .unwrap();
55
56 let mac = ethernet::MacAddress::new().into();                  ←
57
58 http::get(tap, mac, addr, url).unwrap();                      ←
59 }                                                               ←
60 }
```

Validates the command-line arguments

Converts the URL's domain name into an IP address that we can connect to

Generates a random unicode MAC address

Makes the HTTP GET request

The following listing generates our MAC address and converts between MAC address types defined by the smoltcp crate and our own. The code for this listing is in ch8/ch8-mget/src/ethernet.rs.

#### Listing 8.21 Ethernet type conversion and MAC address generation

```

1 use rand;
2 use std::fmt;
3 use std::fmt::Display;
4
5 use rand::RngCore;
6 use smoltcp::wire;
7
8 #[derive(Debug)]
9 pub struct MacAddress([u8; 6]);
10
```

```

11 impl Display for MacAddress {
12     fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
13         let octet = self.0;
14         write!((
15             f,
16             "{:02x}:{:02x}:{:02x}:{:02x}:{:02x}:{:02x}",
17             octet[0], octet[1], octet[2],
18             octet[3], octet[4], octet[5]
19         ))
20     }
21 }
22
23 impl MacAddress {
24     pub fn new() -> MacAddress {
25         let mut octets: [u8; 6] = [0; 6];
26         rand::thread_rng().fill_bytes(&mut octets);
27         octets[0] |= 0b_0000_0010;           ← Generates
28         octets[0] &= 0b_1111_1110;           ← a random
29         MacAddress { 0: octets }           ← number
30     }
31 }
32
33 impl Into<wire::EthernetAddress> for MacAddress {
34     fn into(self) -> wire::EthernetAddress {
35         wire::EthernetAddress { 0: self.0 }
36     }
37 }

```

The following listing shows how to interact with the server to make the HTTP request. The code for this listing is in ch8/ch8-mget/src/http.rs.

#### Listing 8.22 Manually creating an HTTP request using TCP primitives

```

1 use std::collections::BTreeMap;
2 use std::fmt;
3 use std::net::IpAddr;
4 use std::os::unix::io::AsRawFd;
5
6 use smoltcp::iface::{EthernetInterfaceBuilder, NeighborCache, Routes};
7 use smoltcp::phy::{wait as phy_wait, TapInterface};
8 use smoltcp::socket::{SocketSet, TcpSocket, TcpSocketBuffer};
9 use smoltcp::time::Instant;
10 use smoltcp::wire::{EthernetAddress, IpAddress, IpCidr, Ipv4Address};
11 use url::Url;
12
13 #[derive(Debug)]
14 enum HttpState {
15     Connect,
16     Request,
17     Response,
18 }
19
20 #[derive(Debug)]
21 pub enum UpstreamError {

```

```
22     Network(smoltcp::Error),
23     InvalidUrl,
24     Content(std::string::Utf8Error),
25   }
26
27 impl fmt::Display for UpstreamError {
28   fn fmt(&self, f: &mut fmt::Formatter<'_>) -> fmt::Result {
29     write!(f, "{}", self)
30   }
31 }
32
33 impl From<smoltcp::Error> for UpstreamError {
34   fn from(error: smoltcp::Error) -> Self {
35     UpstreamError::Network(error)
36   }
37 }
38
39 impl From<std::string::Utf8Error> for UpstreamError {
40   fn from(error: std::string::Utf8Error) -> Self {
41     UpstreamError::Content(error)
42   }
43 }
44
45 fn random_port() -> u16 {
46   49152 + rand::random::<u16>() % 16384
47 }
48
49 pub fn get(
50   tap: TapInterface,
51   mac: EthernetAddress,
52   addr: IpAddr,
53   url: Url,
54 ) -> Result<(), UpstreamError> {
55   let domain_name = url.host_str().ok_or(UpstreamError::InvalidUrl)?;
56
57   let neighbor_cache = NeighborCache::new(BTreeMap::new());
58
59   let tcp_rx_buffer = TcpSocketBuffer::new(vec![0; 1024]);
60   let tcp_tx_buffer = TcpSocketBuffer::new(vec![0; 1024]);
61   let tcp_socket = TcpSocket::new(tcp_rx_buffer, tcp_tx_buffer);
62
63   let ip_addrs = [IpCidr::new(IpAddress::v4(192, 168, 42, 1), 24)];
64
65   let fd = tap.as_raw_fd();
66   let mut routes = Routes::new(BTreeMap::new());
67   let default_gateway = Ipv4Address::new(192, 168, 42, 100);
68   routes.add_default_ipv4_route(default_gateway).unwrap();
69   let mut iface = EthernetInterfaceBuilder::new(tap)
70     .ethernet_addr(mac)
71     .neighbor_cache(neighbor_cache)
72     .ip_addrs(ip_addrs)
73     .routes(routes)
74     .finalize();
75
76   let mut sockets = SocketSet::new(vec![]);
```

```

77  let tcp_handle = sockets.add(tcp_socket);
78
79  let http_header = format!(
80      "GET {} HTTP/1.0\r\nHost: {}\r\nConnection: close\r\n\r\n",
81      url.path(),
82      domain_name,
83  );
84
85  let mut state = HttpState::Connect;
86  'http: loop {
87      let timestamp = Instant::now();
88      match iface.poll(&mut sockets, timestamp) {
89          Ok(_) => {}
90          Err(smoltcp::Error::Unrecognized) => {}
91          Err(e) => {
92              eprintln!("error: {:?}", e);
93          }
94      }
95
96      {
97          let mut socket = sockets.get::<TcpSocket>(tcp_handle);
98
99          state = match state {
100              HttpState::Connect if !socket.is_active() => {
101                  eprintln!("connecting");
102                  socket.connect((addr, 80), random_port())?;
103                  HttpState::Request
104              }
105
106              HttpState::Request if socket.may_send() => {
107                  eprintln!("sending request");
108                  socket.send_slice(http_header.as_ref())?;
109                  HttpState::Response
110              }
111
112              HttpState::Response if socket.can_recv() => {
113                  socket.recv(|raw_data| {
114                      let output = String::from_utf8_lossy(raw_data);
115                      println!("{}: {}", raw_data.len(), output);
116
117                  })?;
118                  HttpState::Response
119              }
120
121              HttpState::Response if !socket.may_recv() => {
122                  eprintln!("received complete response");
123                  break 'http;
124              }
125              _ => state,
126          }
127      }
128
129      phy_wait(fd, iface.poll_delay(&sockets, timestamp))
130          .expect("wait error");
131  }

```

```

132
133     Ok(())
134 }
```

And finally, the following listing performs the DNS resolution. The source for this listing is in ch8/ch8-mget/src/dns.rs.

### Listing 8.23 Creating DNS queries to translate domain names to IP addresses

```

1 use std::error::Error;
2 use std::net::{SocketAddr, UdpSocket};
3 use std::time::Duration;
4
5 use trust_dns::op::{Message, MessageType, OpCode, Query};
6 use trust_dns::proto::error::ProtoError;
7 use trust_dns::rr::domain::Name;
8 use trust_dns::rr::record_type::RecordType;
9 use trust_dns::serialize::binary::*;

10
11 fn message_id() -> u16 {
12     let candidate = rand::random();
13     if candidate == 0 {
14         return message_id();
15     }
16     candidate
17 }
18
19 #[derive(Debug)]
20 pub enum DnsError {
21     ParseDomainName(ProtoError),
22     ParseDnsServerAddress(std::net::AddrParseError),
23     Encoding(ProtoError),
24     Decoding(ProtoError),
25     Network(std::io::Error),
26     Sending(std::io::Error),
27     Receiving(std::io::Error),
28 }
29
30 impl std::fmt::Display for DnsError {
31     fn fmt(&self, f: &mut std::fmt::Formatter) -> std::fmt::Result {
32         write!(f, "{}", self)
33     }
34 }
35
36 impl std::error::Error for DnsError {} ←
37
38 pub fn resolve(
39     dns_server_address: &str,
40     domain_name: &str,
41 ) -> Result<Option<std::net::IpAddr>, Box<dyn Error>> {
42     let domain_name =
43         Name::from_ascii(domain_name)
44         .map_err(DnsError::ParseDomainName)?;
45 }
```



```

46 let dns_server_address =
47   format!("{}:53", dns_server_address);           ← Attempts to build the
48 let dns_server: SocketAddr = dns_server_address
49   .parse()
50   .map_err(DnsError::ParseDnsServerAddress)?;
51
52 let mut request_buffer: Vec<u8> =           ← Because our DNS request
53   Vec::with_capacity(64);                         will be small, we only need a
54 let mut response_buffer: Vec<u8> =           ← little bit of space to hold it.
55   vec![0; 512];
56
57 let mut request = Message::new();             ← DNS over UDP uses a
58 request.add_query(                           maximum packet size
59   Query::query(domain_name, RecordType::A)    of 512 bytes.
60 );
61
62 request
63   .set_id(message_id())
64   .set_message_type(MessageType::Query)
65   .set_op_code(OpCode::Query)
66   .set_recursion_desired(true);                ← DNS messages can hold
67
68 let localhost =                                ← multiple queries, but here
69   UdpSocket::bind("0.0.0.0:0").map_err(DnsError::Network)?;
70
71 let timeout = Duration::from_secs(5);          ← Asks the DNS server to make
72 localhost
73   .set_read_timeout(Some(timeout))            ← requests on our behalf if it
74   .map_err(DnsError::Network)?;              doesn't know the answer
75
76 localhost
77   .set_nonblocking(false)
78   .map_err(DnsError::Network)?;              ← Binding to port 0 asks
79
80 let mut encoder = BinEncoder::new(&mut request_buffer);
81 request.emit(&mut encoder).map_err(DnsError::Encoding)?;
82
83 let _n_bytes_sent = localhost
84   .send_to(&request_buffer, dns_server)
85   .map_err(DnsError::Sending)?;
86
87 loop {
88   let (_n_bytes_recv, remote_port) = localhost
89     .recv_from(&mut response_buffer)
90     .map_err(DnsError::Receiving)?;
91
92   if remote_port == dns_server {
93     break;
94   }
95 }
96
97 let response =
98   Message::from_vec(&response_buffer)
99   .map_err(DnsError::Decoding)?;
100

```

Binding to port 0 asks the OS to allocate a port on our behalf.

There is a small chance another UDP message will be received on our port from some unknown sender. To avoid that, we ignore packets from IP addresses that we don't expect.

```

101    for answer in response.answers() {
102        if answer.record_type() == RecordType::A {
103            let resource = answer.rdata();
104            let server_ip =
105                resource.to_ip_addr().expect("invalid IP address received");
106            return Ok(Some(server_ip));
107        }
108    }
109
110    Ok(None)
111 }

```

mget is an ambitious project. It brings together all the threads from the chapter, is dozens of lines long, and yet is less capable than the `request::get(url)` call we made in listing 8.2. Hopefully it's revealed several interesting avenues for you to explore. Perhaps, surprisingly, there are several more networking layers to unwrap. Well done for making your way through a lengthy and challenging chapter.

## Summary

- Networking is complicated. Standard models such as OSIs are only partially accurate.
- Trait objects allow for runtime polymorphism. Typically, programmers prefer generics because trait objects incur a small runtime cost. However, this situation is not always clear-cut. Using trait objects can reduce space because only a single version of each function needs to be compiled. Fewer functions also benefits cache coherence.
- Networking protocols are particular about which bytes are used. In general, you should prefer using `&[u8]` literals (`b"..."`) over `&str` literals (`"..."`) to ensure that you retain full control.
- There are three main strategies for handling multiple upstream error types within a single scope:
  - Create an internal wrapper type and implement `From` for each of the upstream types
  - Change the return type to make use of a trait object that implements `std::error::Error`
  - Use `.unwrap()` and its cousin `.expect()`
- Finite state machines can be elegantly modeled in Rust with an enum and a loop. At each iteration, indicate the next state by returning the appropriate enum variant.
- To enable two-way communications in UDP, each side of the conversation must be able to act as a client and a server.

# *Time and timekeeping*

---

## **This chapter covers**

- Understanding how a computer keeps time
- How operating systems represent timestamps
- Synchronizing atomic clocks with the Network Time Protocol (NTP)

In this chapter, you'll produce an NTP (Network Time Protocol) client that requests the current time from the world's network of public time servers. It's a fully functioning client that can be included in your own computer's boot process to keep it in sync with the world.

Understanding how time works within computers supports your efforts to build resilient applications. The system clock jumps both backwards and forwards in time. Knowing why this happens allows you to anticipate and prepare for that eventuality.

Your computer also contains multiple physical and virtual clocks. It takes some knowledge to understand the limitations of each and when these are appropriate. Understanding the limitations of each should foster a healthy skepticism about micro benchmarks and other time-sensitive code.

Some of the hardest software engineering involves distributed systems that need to agree on what the time is. If you have the resources of Google, then

you're able to maintain a network atomic clock that provides a worldwide time synchronization of 7 ms. The closest open source alternative is CockroachDB (<https://www.cockroachlabs.com/>). It relies on the NTP, which can have a (worldwide) latency of approximately dozens of milliseconds. But that doesn't make it useless. When deployed within a local network, NTP allows computers to agree on the time to within a few milliseconds or less.

On the Rust side of the equation, this chapter invests lots of time interacting with the OS internals. You'll become more confident with unsafe blocks and with using raw pointers. Readers will become familiar with chrono, the de facto standard crate for high-level time and clock operations.

## 9.1

### Background

It's easy to think that a day has 86,400 seconds ( $60\text{ s} \times 60\text{ min} \times 24\text{ h} = 86,400\text{ s}$ ). But the earth's rotation isn't quite that perfect. The length of each day fluctuates due to tidal friction with the moon and other effects such as torque at the boundary of the earth's core and its mantle.

Software does not tolerate these imperfections. Most systems assume that most seconds have an equal duration. The mismatch presents several problems.

In 2012, a large number of services—including high profile sites such as Reddit and Mozilla's Hadoop infrastructure—stopped functioning after a leap second was added to their clocks. And, at times, clocks can go back in time (this chapter does not, however, cover time travel). Few software systems are prepared for the same timestamp to appear twice. That makes it difficult to debug the logs. There are two options for resolving this impasse:

- *Keep the length of each second fixed.* This is good for computers but irritating for humans. Over time, “midday” drifts towards sunset or sunrise.
- *Adjust the length of each year to keep the sun's position relative to noon in the same place from year to year.* This is good for humans but sometimes highly irritating for computers.

In practice, we can chose both options as we do in this chapter. The world's atomic clocks use their own time zone with fixed-length seconds, called TAI. Everything else uses time zones that are periodically adjusted; these are called UTC.

TAI is used by the world's atomic clocks and maintains a fixed-length year. UTC adds leap seconds to TAI about once every 18 months. In 1972, TAI and UTC were 10 seconds apart. By 2016, they had drifted to 36 seconds apart.


In addition to the issues with earth's fickle rotational speed, the physics of your own computer make it challenging to keep accurate time. There are also (at least) two clocks running on your system. One is a battery-powered device, called the *real-time clock*. The other one is known as *system time*. System time increments itself based on hardware interrupts provided by the computer's motherboard. Somewhere in your system, a quartz crystal is oscillating rapidly.

### Dealing with hardware platforms without a real-time clock

The Raspberry Pi device does not include a battery-supported, real-time clock. When the computer turns on, the system clock is set to epoch time. That is, it is set to the number of elapsed seconds since 1 Jan 1970. During boot, it uses the NTP to identify the current time.

What about situations where there is no network connection? This is the situation faced by the Cacophony Project (<https://cacophony.org.nz/>), which develops devices to support New Zealand's native bird species by applying computer vision to accurately identify pest species.

The main sensor of the device is a thermal imaging camera. Footage needs to be annotated with accurate timestamps. To enable this, the Cacophony Project team decided to add an additional real-time clock, Raspberry Pi Hat, to their custom board. The following figure shows the internals of the prototype for the Cacophony Project's automated pest detection system.



## 9.2 Sources of time

Computers can't look at the clock on the wall to determine what time it is. They need to figure it out by themselves. To explain how this happens, let's consider how digital clocks operate generally, then how computer systems operate given some difficult constraints, such as operating without power.

Digital clocks consist of two main parts. The first part is some component that ticks at regular intervals. The second part is a pair of counters. One counter increments as ticks occur. The other increments as seconds occur. Determining "now" within digital clocks means comparing the number of seconds against some predetermined starting point. The starting point is known as the *epoch*.

Embedded hardware aside, when your computer is turned off, a small battery-powered clock continues to run. Its electric charge causes a quartz crystal to oscillate rapidly. The clock measures those oscillations and updates its internal counters. In a running computer, the CPU clock frequency becomes the source of regular ticks. A CPU core operates at a fixed frequency.<sup>1</sup> Inside the hardware, a counter can be accessed via CPU instructions and/or by accessing predefined CPU registers.<sup>2</sup>

Relying on a CPU's clock can actually cause problems in niche scientific and other high-accuracy domains, such as profiling an application's behavior. When computers use multiple CPUs, which is especially common in high performance computing, each CPU has a slightly different clock rate. Moreover, CPUs perform out-of-order execution. This means that it's impossible for someone creating a benchmarking/profiling software suite to know how long a function takes between two timestamps. The CPU instructions requesting the current timestamp may have shifted.

## 9.3 Definitions

Unfortunately, this chapter needs to introduce some jargon:

- *Absolute time*—Describes the time that you would tell someone if they were to ask for the time. Also referred to as *wall clock time* and *calendar time*.
- *Real-time clock*—A physical clock that's embedded in the computer's motherboard, which keeps time when the power is off. It's also known as the *CMOS clock*.
- *System clock*—The operating system's view of the time. Upon boot, the OS takes over timekeeping duties from the real-time clock.

All applications derive their idea of time from the system time. The system clock experiences jumps, as it can be manually set to a different position. This jumpiness can confuse some applications.

- *Monotonically increasing*—A clock that never provides the same time twice. This is a useful property for a computer application because, among other advantages,

<sup>1</sup> Dynamic adjustments to a CPU's clock speed do occur in many processors to conserve power, but these happen infrequently enough from the point of view of the clock as to be insignificant.

<sup>2</sup> For example, Intel-based processors support the RDTSC instruction, which stands for *Read Time Stamp Counter*.

log messages will never have a repeated timestamp. Unfortunately, preventing time adjustments means being permanently bound to the local clock's skew. Note that the *system clock* is not monotonically increasing.

- *Steady clock*—This clock provides two guarantees: its seconds are all equal length and it is monotonically increasing. Values from steady clocks are unlikely to align with the system clock's time or absolute time. These typically start at 0 when computers boot up, then count upwards as an internal counter progresses. Although potentially useless for knowing the absolute time, these are handy for calculating the duration between two points in time.
- *High accuracy*—A clock is highly accurate if the length of its seconds are regular. The difference between two clocks is known as *skew*. Highly accurate clocks have little skew against the atomic clocks that are humanity's best engineering effort at keeping accurate time.
- *High resolution*—Provides accuracy down to 10 nanoseconds or below. High resolution clocks are typically implemented within CPU chips because there are few devices that can maintain time at such high frequency. CPUs are able to do this. Their units of work are measured in cycles, and cycles have the same duration. A 1 GHz CPU core takes 1 nanosecond to compute one cycle.
- *Fast clock*—A clock that takes little time to read the time. Fast clocks sacrifice accuracy and precision for speed, however.

## 9.4 Encoding time

There are many ways to represent time within a computer. The typical approach is to use a pair of 32-bit integers. The first counts the number of seconds that have elapsed. The second represents a fraction of a second. The precision of the fractional part depends on the device in question.

The starting point is arbitrary. The most common epoch in UNIX-based systems is 1 Jan 1970 UTC. Alternatives include 1 Jan 1900 (which happens to be used by NTP), 1 Jan 2000 for more recent applications, and 1 Jan 1601 (which is the beginning of the Gregorian calendar). Using fixed-width integers presents two key advantages and two main challenges:

- Advantages include
  - *Simplicity*—It's easy to understand the format.
  - *Efficiency*—Integer arithmetic is the CPU's favorite activity.
- Disadvantages include
  - *Fixed-range*—All fixed-integer types are finite, implying that time eventually wraps around to 0 again.
  - *Inprecise*—Integers are discrete, while time is continuous. Different systems make different trade-offs relating to subsecond accuracy, leading to rounding errors.

It's also important to note that the general approach is inconsistently implemented. Here are some things seen in the wild to represent the seconds component:

- UNIX timestamps, a 32-bit integer, represents milliseconds since epoch (e.g., 1 Jan 1970).
- MS Windows FILETIME structures (since Windows 2000), a 64-bit unsigned integer, represents 100 nanosecond increments since 1 Jan 1601 (UTC).
- Rust community's chronos crate, a 32-bit signed integer, implements NaiveTime alongside an enum to represent time zones where appropriate.<sup>3</sup>
- `time_t` (meaning *time type* but also called *simple time* or *calendar time*) within the C standard library (libc) varies:
  - Dinkumware's libc provides an `unsigned long int` (e.g., a 32-bit unsigned integer).
  - GNU's libc includes a `long int` (e.g., a 32-bit signed integer).
  - AVR's libc uses a 32-bit unsigned integer, and its epoch begins at midnight, 1 January 2000 (UTC).

Fractional parts tend to use the same type as their whole-second counterparts, but this isn't guaranteed. Now, let's take a peek at time zones.

#### 9.4.1 Representing time zones

Time zones are political divisions, rather than technical ones. A soft consensus appears to have been formed around storing another integer that represents the number of seconds offset from UTC.

### 9.5 ***clock v0.1.0: Teaching an application how to tell the time***

To begin coding our NTP client, let's start by learning how to read time. Figure 9.1 provides a quick overview of how an application does that.




Figure 9.1 An application gets time information from the OS, usually functionally provided by the system's libc implementation.

<sup>3</sup> chronos has relatively few quirks, but one of which is sneaking leap seconds into the nanoseconds field.

Listing 9.2, which reads the system time in the local time zone, might almost feel too small to be a full-fledged example. But running the code results in the current timestamp formatted according to the ISO 8601 standard. The following listing provides its configuration. You'll find the source for this listing in ch9/ch9-clock0/Cargo.toml.

### Listing 9.1 Crate configuration for listing 9.2

```
[package]
name = "clock"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
chrono = "0.4"
```

The following listing reads and prints the system time. You'll find the source code for the listing in ch9/ch9-clock0/src/main.rs.

### Listing 9.2 Reading the system time and printing it on the screen

```
1 use chrono::Local;
2
3 fn main() {
4     let now = Local::now();
5     println!("{} ", now);
6 }
```



Asks for the time in  
the system's local  
time zone

In listing 9.2, there is a lot of complexity hidden by these eight lines of code. Much of it will be peeled away during the course of the chapter. For now, it's enough to know that chrono::Local provides the magic. It returns a typed value, containing a time zone.

**NOTE** Interacting with timestamps that don't include time zones or performing other forms of illegal time arithmetic results in the program refusing to compile.

## 9.6 clock v0.1.1: Formatting timestamps to comply with ISO 8601 and email standards

The application that we'll create is called `clock`, which reports the current time. You'll find the full application in listing 9.7. Throughout the chapter, the application will be incrementally enhanced to support setting the time manually and via NTP. For the moment, however, the following code shows the result of compiling and running the code from listing 9.8 and sending it the `--use-standard` timestamp flag.

```
$ cd ch9/ch9-clock1
$ cargo run -- --use-standard rfc2822
warning: associated function is never used: `set`  
--> src/main.rs:12:8
```

```

12 |     fn set() -> ! {
|     |
|     = note: `#[warn(dead_code)]` on by default
warning: 1 warning emitted
    Finished dev [unoptimized + debuginfo] target(s) in 0.01s
        Running `target/debug/clock --use-standard rfc2822`
Sat, 20 Feb 2021 15:36:12 +1300

```

### 9.6.1 Refactoring the clock v0.1.0 code to support a wider architecture

It makes sense to spend a short period of time creating a scaffold for the larger application that clock will become. Within the application, we'll first make a small cosmetic change. Rather than using functions to read the time and adjust it, we'll use static methods of a `Clock` struct. The following listing, an excerpt from listing 9.7, shows the change from listing 9.2.

**Listing 9.3** Reading the time from the local system clock

```

2 use chrono::{DateTime};
3 use chrono::{Local};
4
5 struct Clock;
6
7 impl Clock {
8     fn get() -> DateTime<Local> {           ←
9         Local::now()
10    }
11
12    fn set() -> ! {
13        unimplemented!()
14    }
15 }

```

**DateTime<Local>** is a  
DateTime with the Local  
time zone information.

What on earth is the return type of `set()`? The exclamation mark (!) indicates to the compiler that the function never returns (a return value is impossible). It's referred to as the Never type. If the `unimplemented!()` macro (or its shorter cousin `todo!()`) is reached at runtime, then the program panics.

`Clock` is purely acting as a namespace at this stage. Adding a struct now provides some extensibility later on. As the application grows, it might become useful for `Clock` to contain some state between calls or implement some trait to support new functionality.

**NOTE** A struct with no fields is known as a *zero-sized type* or ZST. It does not occupy any memory in the resulting application and is purely a compile-time construct.

## 9.6.2 Formatting the time

This section looks at formatting the time as a UNIX timestamp or a formatted string according to ISO 8601, RFC 2822, and RFC 3339 conventions. The following listing, an excerpt from listing 9.7, demonstrates how to produce timestamps using the functionality provided by chrono. The timestamps are then sent to stdout.

### Listing 9.4 Showing the methods used to format timestamps

```
48     let now = Clock::get();
49     match std {
50         "timestamp" => println!("{}", now.timestamp()),
51         "rfc2822"   => println!("{}", now.to_rfc2822()),
52         "rfc3339"   => println!("{}", now.to_rfc3339()),
53         _           => unreachable!(),
54     }
```

Our clock application (thanks to chrono) supports three time formats—timestamp, rfc2822, and rfc3339:

- *timestamp*—Formats the number of seconds since the epoch, also known as a *UNIX timestamp*.
- *rfc2822*—Corresponds to RPC 2822 (<https://tools.ietf.org/html/rfc2822>), which is how time is formatted within email message headers.
- *rfc3339*—Corresponds to RFC 3339 (<https://tools.ietf.org/html/rfc3339>). RFC 3339 formats time in a way that is more commonly associated with the ISO 8601 standard. However, ISO 8601 is a slightly stricter standard. Every RFC 3339-compliant timestamp is an ISO 8601-compliant timestamp, but the inverse is not true.

## 9.6.3 Providing a full command-line interface

Command-line arguments are part of the environment provided to an application from its OS when it's established. These are raw strings. Rust provides some support for accessing the raw `Vec<String>` via `std::env::args`, but it can be tedious to develop lots of parsing logic for moderately-sized applications.

Our code wants to be able to validate certain input, such that the desired output format is one that the clock app actually supports. But validating input tends to be irritatingly complex. To avoid this frustration, clock makes use of the clap crate.

There are two main types that are useful for getting started: `clap::App` and `clap::Arg`. Each `clap::Arg` represents a command-line argument and the options that it can represent. `clap::App` collects these into a single application. To support the public API in table 9.1, the code in listing 9.5 uses three `Arg` structs that are wrapped together within a single `App`.

Listing 9.5 is an excerpt from listing 9.7. It demonstrates how to implement the API presented in table 9.1 using `clap`.

**Table 9.1 Usage examples for executing the clock application from the command line. Each command needs to be supported by our parser.**

Use	Description	Example output
clock	Default usage. Prints the current time.	2018-06-17T11:25:19...
clock get	Provides a get action explicitly with default formatting.	2018-06-17T11:25:19...
clock get --use-standard timestamp	Provides a get action and a formatting standard.	1529191458
clock get -s timestamp	Provides a get action and a formatting standard using shorter notation.	1529191458
clock set <datetime>	Provides a set action explicitly with default parsing rules.	
clock set --use-standard timestamp <datetime>	Provides a set action explicitly and indicates that the input will be a UNIX timestamp.	

### Listing 9.5 Using clap to parse command-line arguments

```

18  let app = App::new("clock")
19      .version("0.1")
20      .about("Gets and (aspirationally) sets the time.")
21      .arg(
22          Arg::with_name("action")
23              .takes_value(true)
24              .possible_values(&["get", "set"])
25              .default_value("get"),
26      )
27      .arg(
28          Arg::with_name("std")
29              .short("s")
30              .long("standard")
31              .takes_value(true)
32              .possible_values(&[
33                  "rfc2822",
34                  "rfc3339",
35                  "timestamp",
36              ])
37              .default_value("rfc3339"),
38      )
39      .arg(Arg::with_name("datetime").help(
40          "When <action> is 'set', apply <datetime>. \
41          Otherwise, ignore.",
42      ));
43
44  let args = app.get_matches();

```

The backslash asks Rust to escape the newline and the following indentation.

clap automatically generates some usage documentation for our clock application on your behalf. Using the `--help` option triggers its output.

#### 9.6.4 **clock v0.1.1: Full project**

The following terminal session demonstrates the process of downloading and compiling the clock v0.1.1 project from the public Git repository. It also includes a fragment for accessing the `--help` option that is mentioned in the previous section:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch9/ch9-clock1
$ cargo build
...
Compiling clock v0.1.1 (rust-in-action/ch9/ch9-clock1)
warning: associated function is never used: `set` ←
--> src/main.rs:12:6
|   fn set() -> ! {
|   |
|   = note: `#[warn(dead_code)]` on by default
warning: 1 warning emitted
$ cargo run -- --help ← | Arguments to the right
... | of -- are sent to the
clock 0.1 | resulting executable.
Gets and sets (aspirationally) the time.

USAGE:
    clock.exe [OPTIONS] [ARGS]

FLAGS:
    -h, --help      Prints help information
    -V, --version   Prints version information

OPTIONS:
    -s, --use-standard <std>      [default: rfc3339]
                                    [possible values: rfc2822,
                                    rfc3339, timestamp]

ARGS:
    <action>      [default: get]  [possible values: get, set]
    <datetime>    When <action> is 'set', apply <datetime>.
                    Otherwise, ignore.
$ target/debug/clock ← | Executes the
2021-04-03T15:48:23.984946724+13:00 | target/debug/clock
                                         executable directly
```

This warning is  
eliminated in  
clock v0.1.2.

Arguments to the right  
of -- are sent to the  
resulting executable.

Creating the project step by step takes slightly more work. As clock v0.1.1 is a project managed by cargo, it follows the standard structure:

```

clock
└── Cargo.toml      ↪ See listing 9.6.
└── src
    └── main.rs      ↪ See listing 9.7.

```

To create it manually, follow these steps:

- From the command-line, execute these commands:

```

$ cargo new clock
$ cd clock
$ cargo install cargo-edit
$ cargo add clap@2
$ cargo add chrono@0.4

```

- Compare the contents of your project's Cargo.toml file with listing 9.6. With the exception of the authors field, these should match.
- Replace the contents of src/main.rs with listing 9.7.

The next listing is the project's Cargo.toml file. You'll find it at ch9/ch9-clock1/Cargo.toml. Following that is the project's src/main.rs file, listing 9.7. Its source is in ch9/ch9-clock1/src/main.rs.

#### **Listing 9.6 Crate configuration for clock v0.1.1**

```

[package]
name = "clock"
version = "0.1.1"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
chrono = "0.4"
clap = "2"

```

#### **Listing 9.7 Producing formatted dates from the command line, clock v0.1.1**

```

1 use chrono::DateTime;
2 use chrono::Local;
3 use clap::{App, Arg};
4
5 struct Clock;
6
7 impl Clock {
8     fn get() -> DateTime<Local> {
9         Local::now()
10    }
11
12    fn set() -> ! {
13        unimplemented!()
14    }
15 }

```

```

16
17 fn main() {
18     let app = App::new("clock")
19         .version("0.1")
20         .about("Gets and (aspirationally) sets the time.")
21         .arg(
22             Arg::with_name("action")
23                 .takes_value(true)
24                 .possible_values(&["get", "set"])
25                 .default_value("get"),
26         )
27         .arg(
28             Arg::with_name("std")
29                 .short("s")
30                 .long("use-standard")
31                 .takes_value(true)
32                 .possible_values(&[
33                     "rfc2822",
34                     "rfc3339",
35                     "timestamp",
36                 ])
37                 .default_value("rfc3339"),
38         )
39         .arg(Arg::with_name("datetime").help(
40             "When <action> is 'set', apply <datetime>. \
41             Otherwise, ignore.",
42         ));
43
44     let args = app.get_matches();
45
46     let action = args.value_of("action").unwrap();
47     let std = args.value_of("std").unwrap();
48
49     if action == "set" {
50         unimplemented!() ←
51     }
52
53     let now = Clock::get();
54     match std {
55         "timestamp" => println!("{} {}", now.timestamp()),
56         "rfc2822" => println!("{} {}", now.to_rfc2822()),
57         "rfc3339" => println!("{} {}", now.to_rfc3339()),
58         _ => unreachable!(),
59     }
60 }
```

Supplies a default value to each argument via `default_value("get")` and `default_value("rfc3339")`. It's safe to call `unwrap()` on these two lines.

Aborts early as  
we're not ready to  
set the time yet

## 9.7 clock v0.1.2: Setting the time

Setting the time is complicated because each OS has its own mechanism for doing so. This requires that we use OS-specific conditional compilation to create a cross-portable tool.

### 9.7.1 Common behavior

Listing 9.11 provides two implementations of setting the time. These both follow a common pattern:

- 1 Parsing a command-line argument to create a `DateTime<FixedOffset>` value.  
The `FixedOffset` time zone is provided by chrono as a proxy for “whichever time zone is provided by the user.” chrono doesn’t know at compile time which time zone will be selected.
- 2 Converting the `DateTime<FixedOffset>` to a `DateTime<Local>` to enable time zone comparisons.
- 3 Instantiating an OS-specific struct that’s used as an argument for the necessary system call (*system calls* are function calls provided by the OS).
- 4 Setting the system’s time within an unsafe block. This block is required because responsibility is delegated to the OS.
- 5 Printing the updated time.

**WARNING** This code uses functions to teleport the system’s clock to a different time. This jumpiness can cause system instability.

Some applications expect monotonically increasing time. A smarter (but more complex) approach is to adjust the length of a second for  $n$  seconds until the desired time is reached. Functionality is implemented within the `Clock` struct that was introduced in section 9.6.1.

### 9.7.2 Setting the time for operating systems that use libc

POSIX-compliant operating systems can have their time set via a call to `settimeofday()`, which is provided by `libc`. `libc` is the C Standard Library and has lots of historic connections with UNIX operating systems. The C language, in fact, was developed to write UNIX. Even today, interacting with a UNIX derivative involves using the tools provided by the C language. There are two mental hurdles required for Rust programmers to understanding the code in listing 9.11, which we’ll address in the following sections:

- The arcane types provided by `libc`
- The unfamiliarity of providing arguments as pointers

#### LIBC TYPE NAMING CONVENTIONS

`libc` uses conventions for naming types that differ from Rust’s. `libc` does not use Pascal-Case to denote a type, preferring to use lowercase. That is, where Rust would use `TimeVal`, `libc` uses `timeval`. The convention changes slightly when dealing with type aliases. Within `libc`, type aliases append an underscore followed by the letter `t` (`_t`) to the type’s name. The next two snippets show some `libc` imports and the equivalent Rust code for building those types.

On line 64 of listing 9.8, you will encounter this line:

```
libc::{timeval, time_t, suseconds_t};
```

It represents two type aliases and a struct definition. In Rust syntax, these are defined like this:

```
#! [allow(non_camel_case_types)]  
  
type time_t = i64;  
type suseconds_t = i64;  
  
pub struct timeval {  
    pub tv_sec: time_t,  
    pub tv_usec: suseconds_t,  
}
```

`time_t` represents the seconds that have elapsed since the epoch. `suseconds_t` represents the fractional component of the current second.

The types and functions relating to timekeeping involve a lot of indirection. The code is intended to be easy to implement, which means providing local implementors (hardware designers) the opportunity to change aspects as their platforms require. The way this is done is to use type aliases everywhere, rather than sticking to a defined integer type.

### NON-WINDOWS CLOCK CODE

The libc library provides a handy function, `settimeofday`, which we'll use in listing 9.8. The project's `Cargo.toml` file requires two extra lines to bring libc bindings into the crate for non-Windows platforms:

```
[target.'cfg(not(windows))'.dependencies] ← You can add these two lines  
libc = "0.2"
```

The following listing, an extract from listing 9.11, shows how to set the time with C's standard library, `libc`. In the listing, we use Linux and BSD operating systems or other similar ones.

#### Listing 9.8 Setting the time in a `libc` environment

t is sourced from the command line and has already been parsed.

```
62 #[cfg(not(windows))]  
63 fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {  
64     use libc::{timeval, time_t, suseconds_t};  
65     use libc::{settimeofday, timezone }  
66  
67     let t = t.with_timezone(&Local);  
68     let mut u: timeval = unsafe { zeroed() };  
69  
70     u.tv_sec = t.timestamp() as time_t;  
71     u.tv_usec =  
72         t.timestamp_subsec_micros() as suseconds_t;  
73  
74     unsafe {  
75         let mock_tz: *const timezone = std::ptr::null();  
76         gettimeofday(&u as *const timeval, mock_tz);  
77     }  
78 }
```

The `timezone` parameter of `settimeofday()` appears to be some sort of historic accident. Non-null values generate an error.

Makes OS-specific imports within the function to avoid polluting the global scope. `libc::settimeofday` is a function that modifies the system clock, and `suseconds_t`, `time_t`, `timeval`, and `timezone` are all types used to interact with it.

This code cheekily, and probably perilously, avoids checking whether the `settimeofday` function is successful. It's quite possible that it isn't. That will be remedied in the next iteration of the clock application.

### 9.7.3 **Setting the time on MS Windows**

The code for MS Windows is similar to its libc peers. It is somewhat wordier, as the struct that sets the time has more fields than the second and subsecond part. The rough equivalent of the libc library is called `kernel32.dll`, which is accessible after including the `winapi` crate.

#### **WINDOWS API INTEGER TYPES**

Windows provides its own take on what to call integral types. This code only makes use of the `WORD` type, but it can be useful to remember the two other common types that have emerged since computers have used 16-bit CPUs. The following table shows how integer types from `kernel32.dll` correspond to Rust types.

Windows type	Rust type	Remarks
<code>WORD</code>	<code>u16</code>	Refers to the width of a CPU “word” as it was when Windows was initially created
<code>DWORD</code>	<code>u32</code>	Double word
<code>QWORD</code>	<code>u64</code>	Quadruple word
<code>LARGE_INTEGER</code>	<code>i64</code>	A type defined as a crutch to enable 32-bit and 64-bit platforms to share code
<code>ULARGE_INTEGER</code>	<code>u64</code>	An unsigned version of <code>LARGE_INTEGER</code>

#### **REPRESENTING TIME IN WINDOWS**

Windows provides multiple time types. Within our clock application, however, we're mostly interested in `SYSTEMTIME`. Another type that is provided is `FILETIME`. The following table describes these types to avoid confusion.

Windows type	Rust type	Remarks
<code>SYSTEMTIME</code>	<code>winapi::SYSTEMTIME</code>	Contains fields for the year, month, day of the week, day of the month, hour, minute, second, and millisecond.
<code>FILETIME</code>	<code>winapi::FILETIME</code>	Analogous to <code>libc::timeval</code> . Contains second and millisecond fields. Microsoft's documentation warns that on 64-bit platforms, its use can cause irritating overflow bugs without finicky type casting, which is why it's not employed here.

## WINDOWS CLOCK CODE

As the `SYSTEMTIME` struct contains many fields, generating one takes a little bit longer. The following listing shows this construct.

### Listing 9.9 Setting the time using the Windows kernel32.dll API

```

19  #[cfg(windows)]
20  fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {
21      use chrono::Weekday;
22      use kernel32::SetSystemTime;
23      use winapi::{SYSTEMTIME, WORD};
24
25      let t = t.with_timezone(&Local);
26
27      let mut systime: SYSTEMTIME = unsafe { zeroed() };
28
29      let dow = match t.weekday() {
30          Weekday::Mon => 1,
31          Weekday::Tue => 2,
32          Weekday::Wed => 3,
33          Weekday::Thu => 4,
34          Weekday::Fri => 5,
35          Weekday::Sat => 6,
36          Weekday::Sun => 0,
37      };
38
39      let mut ns = t.nanosecond();
40      let mut leap = 0;
41      let is_leap_second = ns > 1_000_000_000;
42
43      if is_leap_second {
44          ns -= 1_000_000_000;
45          leap += 1;
46      }
47
48      systime.wYear = t.year() as WORD;
49      systime.wMonth = t.month() as WORD;
50      systime.wDayOfWeek = dow as WORD;
51      systime.wDay = t.day() as WORD;
52      systime.wHour = t.hour() as WORD;
53      systime.wMinute = t.minute() as WORD;
54      systime.wSecond = (leap + t.second()) as WORD;
55      systime.wMilliseconds = (ns / 1_000_000) as WORD;
56
57      let systime_ptr = &systime as *const SYSTEMTIME;
58
59      unsafe {
60          SetSystemTime(systime_ptr);
61      }
62  }

```

The `chrono::Datelike` trait provides the `weekday()` method. Microsoft's developer documentation provides the conversion table.

As an implementation detail, `chrono` represents leap seconds by adding an extra second within the nanoseconds field. To convert the nanoseconds to milliseconds as required by Windows, we need to account for this.

From the perspective of the Rust compiler, giving something else direct access to memory is unsafe. Rust cannot guarantee that the Windows kernel will be well-behaved.

### 9.7.4 ***clock v0.1.2: The full code listing***

clock v0.1.2 follows the same project structure as v0.1.1, which is repeated here. To create platform-specific behavior, some adjustments are required to Cargo.toml.

```
clock
└── Cargo.toml      ↪ See listing 9.10.
    └── src
        └── main.rs    ↪ See listing 9.11.
```

Listings 9.10 and 9.11 provide the full source code for the project. These are available for download from ch9/ch9-clock0/Cargo.toml and ch9/ch9-clock0/src/main.rs, respectively.

#### Listing 9.10 Crate configuration for listing 9.11

```
[package]
name = "clock"
version = "0.1.2"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
chrono = "0.4"
clap = "2"

[target.'cfg(windows)'.dependencies]
winapi = "0.2"
kernel32-sys = "0.2"

[target.'cfg(not(windows))'.dependencies]
libc = "0.2"
```

#### Listing 9.11 Cross-portable code for setting the system time

```
1 #[cfg(windows)]
2 use kernel32;
3 #[cfg(not(windows))]
4 use libc;
5 #[cfg(windows)]
6 use winapi;
7
8 use chrono::{DateTime, Local, TimeZone};
9 use clap::{App, Arg};
10 use std::mem::zeroed;
11
12 struct Clock;
13
14 impl Clock {
15     fn get() -> DateTime<Local> {
16         Local::now()
17     }
18 }
```

```

19 #[cfg(windows)]
20 fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {
21     use chrono::Weekday;
22     use kernel32::SetSystemTime;
23     use winapi::{SYSTEMTIME, WORD};
24
25     let t = t.with_timezone(&Local);
26
27     let mut systime: SYSTEMTIME = unsafe { zeroed() };
28
29     let dow = match t.weekday() {
30         Weekday::Mon => 1,
31         Weekday::Tue => 2,
32         Weekday::Wed => 3,
33         Weekday::Thu => 4,
34         Weekday::Fri => 5,
35         Weekday::Sat => 6,
36         Weekday::Sun => 0,
37     };
38
39     let mut ns = t.nanosecond();
40     let is_leap_second = ns > 1_000_000_000;
41
42     if is_leap_second {
43         ns -= 1_000_000_000;
44     }
45
46     systime.wYear = t.year() as WORD;
47     systime.wMonth = t.month() as WORD;
48     systime.wDayOfWeek = dow as WORD;
49     systime.wDay = t.day() as WORD;
50     systime.wHour = t.hour() as WORD;
51     systime.wMinute = t.minute() as WORD;
52     systime.wSecond = t.second() as WORD;
53     systime.wMilliseconds = (ns / 1_000_000) as WORD;
54
55     let systime_ptr = &systime as *const SYSTEMTIME;
56
57     unsafe {
58         SetSystemTime(systime_ptr);
59     }
60 }
61
62 #[cfg(not(windows))]
63 fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {
64     use libc::{timeval, time_t, suseconds_t};
65     use libc::{settimeofday, timezone};
66
67     let t = t.with_timezone(&Local);
68     let mut u: timeval = unsafe { zeroed() };
69
70     u.tv_sec = t.timestamp() as time_t;
71     u.tv_usec =
72         t.timestamp_subsec_micros() as suseconds_t;
73 }
```

```

74     unsafe {
75         let mock_tz: *const timezone = std::ptr::null();
76         settimeofday(&u as *const timeval, mock_tz);
77     }
78 }
79 }
80
81 fn main() {
82     let app = App::new("clock")
83         .version("0.1.2")
84         .about("Gets and (aspirationally) sets the time.")
85         .after_help(
86             "Note: UNIX timestamps are parsed as whole \
87             seconds since 1st January 1970 0:00:00 UTC. \
88             For more accuracy, use another format.",
89         )
90         .arg(
91             Arg::with_name("action")
92                 .takes_value(true)
93                 .possible_values(&["get", "set"])
94                 .default_value("get"),
95         )
96         .arg(
97             Arg::with_name("std")
98                 .short("s")
99                 .long("use-standard")
100                .takes_value(true)
101                .possible_values(&[
102                    "rfc2822",
103                    "rfc3339",
104                    "timestamp",
105                ])
106                .default_value("rfc3339"),
107        )
108        .arg(Arg::with_name("datetime").help(
109            "When <action> is 'set', apply <datetime>. \
110            Otherwise, ignore.",
111        ));
112
113     let args = app.get_matches();
114
115     let action = args.value_of("action").unwrap();
116     let std = args.value_of("std").unwrap();
117
118     if action == "set" {
119         let t_ = args.value_of("datetime").unwrap();
120
121         let parser = match std {
122             "rfc2822" => DateTime::parse_from_rfc2822,
123             "rfc3339" => DateTime::parse_from_rfc3339,
124             _ => unimplemented!(),
125         };
126
127         let err_msg = format!(
128             "Unable to parse {} according to {}",

```

```

129     t_, std
130   );
131   let t = parser(t_).expect(&err_msg);
132
133   Clock::set(t)
134 }
135
136 let now = Clock::get();
137
138 match std {
139   "timestamp" => println!("{}", now.timestamp()),
140   "rfc2822" => println!("{}", now.to_rfc2822()),
141   "rfc3339" => println!("{}", now.to_rfc3339()),
142   _ => unreachable!(),
143 }
144 }
```

## 9.8 Improving error handling

Those readers who have dealt with operating systems before will probably be dismayed at some of the code in section 9.7. Among other things, it doesn't check to see whether the calls to `settimeofday()` and `SetSystemTime()` were actually successful.

There are multiple reasons why setting the time might fail. The most obvious one is that the user who is attempting to set the time lacks permission to do so. The robust approach is to have `Clock::set(t)` return `Result`. As that requires modifying two functions that we have already spent some time explaining in depth, let's introduce a workaround that instead makes use of the operating system's error reporting:

```

fn main() {
    // ...
    if action == "set" {
        // ...

        Clock::set(t);

        let maybe_error =
            std::io::Error::last_os_error(); ←
        let os_error_code =
            &maybe_error.raw_os_error(); ←

        match os_error_code {
            Some(0) => (),
            Some(_) => eprintln!("Unable to set the time: {:?}", maybe_error),
            None => (),
        }
    }
}
```

**Deconstructs `maybe_error`, a Rust type, to convert it into a raw `i32` value that's easy to match**

**Matching on a raw integer saves importing an enum, but sacrifices type safety. Production-ready code shouldn't cheat in this way.**

After calls to `Clock::set(t)`, Rust happily talks to the OS via `std::io::Error::last_os_error()`. Rust checks to see if an error code has been generated.

## 9.9 **clock v0.1.3: Resolving differences between clocks with the Network Time Protocol (NTP)**

Coming to a consensus about the correct time is known formally as *clock synchronization*. There are multiple international standards for synchronizing clocks. This section focuses on the most prominent one—the Network Time Protocol (NTP).

NTP has existed since the mid-1980s, and it has proven to be very stable. Its on-wire format has not changed in the first four revisions of the protocol, with backwards compatibility retained the entire time. NTP operates in two modes that can loosely be described as *always on* and *request/response*.

The always on mode allows multiple computers to work in a peer-to-peer fashion to converge on an agreed definition of *now*. It requires a software daemon or service to run constantly on each device, but it can achieve tight synchronization within local networks.

The request/response mode is much simpler. Local clients request the time via a single message and then parse the response, keeping track of the elapsed time. The client can then compare the original timestamp with the timestamp sent from the server, alter any delays caused by network latency, and make any necessary adjustments to move the local clock towards the server’s time.

Which server should your computer connect to? NTP works by establishing a hierarchy. At the center is a small network of atomic clocks. There are also national pools of servers.

NTP allows clients to request the time from computers that are closer to atomic clocks. But that only gets us part of the way. Let’s say that your computer asks 10 computers what they think the time is. Now we have 10 assertions about the time, and the network lag will differ for each source!

### 9.9.1 **Sending NTP requests and interpreting responses**

Let’s consider a client-server situation where your computer wants to correct its own time. For every computer that you check with—let’s call these *time servers*—there are two messages:

- The message from your computer to each time server is the *request*.
- The reply is known as the *response*.

These two messages generate four time points. Note that these occur in serial:

- $T_1$ —The client’s timestamp for when the request was sent. Referred to as  $t_1$  in code.
- $T_2$ —The time server’s timestamp for when the request was received. Referred to as  $t_2$  in code.
- $T_3$ —The time server’s timestamp for when it sends its response. Referred to as  $t_3$  in code.
- $T_4$ —The client’s timestamp for when the response was received. Referred to as  $t_4$  in code.

The names  $T_1-T_4$  are designated by the RFC 2030 specification. Figure 9.2 shows the timestamps.




Figure 9.2 Timestamps that are defined within the NTP standard

To see what this means in code, spend a few moments looking through the following listing. Lines 2–12 deal with establishing a connection. Lines 14–21 produce  $T_1-T_4$ .

#### Listing 9.12 Defining a function that sends NTP messages

```

1 fn ntp_roundtrip(
2     host: &str,
3     port: u16,
4 ) -> Result<NTPResult, std::io::Error> {
5     let destination = format!("{}:{}", host, port);
6     let timeout = Duration::from_secs(1);
7
8     let request = NTPMessage::client();
9     let mut response = NTPMessage::new();
10
11    let message = request.data;
12
13    let udp = UdpSocket::bind(LOCAL_ADDR)?;
14    udp.connect(&destination).expect("unable to connect");
15
16    let t1 = Utc::now();           ← This code cheats slightly by not encoding t1 in the
17

```

This code cheats slightly by not encoding  $t_1$  in the outbound message. In practice, however, this works perfectly well and requires fractionally less work.

```

18  udp.send(&message)?;
19  udp.set_read_timeout(Some(timeout))?;
20  udp.recv_from(&mut response.data)?; ← Sends a request payload (defined
21                                     elsewhere) to the server
22  let t4 = Utc::now(); ← Blocks the application until
23                                     data is ready to be received
24
25  let t2: DateTime<Utc> = | rx_time() stands for received
26      response             | timestamp and is the time
27      .rx_time()           | that the server received the
28      .unwrap()            | client's message.
29
30  let t3: DateTime<Utc> = | tx_time() stands for
31      response             | transmitted timestamp
32      .tx_time()           | and is the time that the
33      .unwrap()            | server sent the reply.
34      .into();
35
36  Ok(NTPResult {
37      t1: t1,
38      t2: t2,
39      t3: t3,
40      t4: t4,
41  })
42 }

```

$T_1-T_4$ , encapsulated in listing 9.12 as `NTPResult`, are all that's required to judge whether the local time matches the server's time. The protocol contains more related to error handling, but that's avoided here for simplicity. Otherwise, it's a perfectly capable NTP client.

### 9.9.2 Adjusting the local time as a result of the server's response

Given that our client has received at least one (and hopefully a few more) NTP responses, all that's left to do is to calculate the “right” time. But wait, which time is right? All we have are relative timestamps. There is still no universal “truth” that we've been given access to.

**NOTE** For those readers who don't enjoy Greek letters, feel free to skim or even skip the next few paragraphs.

The NTP documentation provides two equations to help resolve the situation. Our aim is to calculate two values. Table 9.2 shows the calculations.

- *The time offset is what we're ultimately interested in.* It is denoted as  $\theta$  (theta) by the official documentation. When  $\theta$  is a positive number, our clock is fast. When it is negative, our clock is slow.
- *The delay caused by network congestion, latency, and other noise.* This is denoted as  $\delta$  (delta). A large  $\delta$  implies that the reading is less reliable. Our code uses this value to follow servers that respond quickly.

**Table 9.2 How to calculate  $\delta$  and  $\theta$  in NTP**

$\delta = (T_4 - T_1) - (T_3 - T_2)$	$(T_4 - T_1)$ calculates the total time spent on the client's side. $(T_3 - T_2)$ calculates the total time spent on the server's side.
	The distinction between the two differences (e.g., $\delta$ ), is an estimate of the difference between the clocks, plus a delay caused by network traffic and processing.
$\theta = ((T_2 - T_1) + (T_4 - T_3)) / 2$	We take the average of the two pairs of timestamps.

The mathematics can be confusing because there is always an innate desire to know what the time *actually is*. That's impossible to know. All we have are assertions.

NTP is designed to operate multiple times per day, with participants nudging their clocks incrementally over time. Given sufficient adjustments,  $\theta$  tends to 0 while  $\delta$  remains relatively stable.

The standard is quite prescriptive about the formula to carry out the adjustments. For example, the reference implementation of NTP includes some useful filtering to limit the effect of bad actors and other spurious results. But we're going to cheat. We'll just take a mean of the differences, weighted by  $1 / \theta^2$ . This aggressively penalizes slow servers. To minimize the likelihood of any negative outcomes:

- *We'll check the time with known “good” actors.* In particular, we'll use time servers hosted by major OS vendors and other reliable sources to minimize the chances of someone sending us a questionable result.
- *No single result will affect the result too much.* We'll provide a cap of 200 ms on any adjustments we make to the local time.

The following listing, an extract from listing 9.15, shows this process for multiple time servers.

#### Listing 9.13 Adjusting the time according to the responses

```

175 fn check_time() -> Result<f64, std::io::Error> {
176     const NTP_PORT: u16 = 123;
177
178     let servers = [
179         "time.nist.gov",
180         "time.apple.com",
181         "time.euro.apple.com",
182         "time.google.com",
183         "time2.google.com",
184         // "time.windows.com",
185     ];
186
187     let mut times = Vec::with_capacity(servers.len());
188
189     for &server in servers.iter() {
190         print!("{} =>", server);
191
192         let calc = ntp_roundtrip(&server, NTP_PORT);

```

Google's time servers implement leap seconds by expanding the length of a second rather than adding an extra second. Thus, for one day approximately every 18 months, this server reports a different time than the others.

At the time of writing, Microsoft's time server provides a time that's 15 s ahead of its peers.

```

193
194     match calc {
195         Ok(time) => {
196             println!(" {}ms away from local system time", time.offset());
197             times.push(time);
198         }
199         Err(_) => {
200             println!(" ? [response took too long]")
201         }
202     };
203 }
204
205 let mut offsets = Vec::with_capacity(servers.len());
206 let mut offset_weights = Vec::with_capacity(servers.len());
207
208 for time in &times {
209     let offset = time.offset() as f64;
210     let delay = time.delay() as f64;
211
212     let weight = 1_000_000.0 / (delay * delay); ←
213     if weight.is_finite() {                                Penalizes slow servers
214         offsets.push(offset);                            by substantially
215         offset_weights.push(weight);                  decreasing their
216     }
217 }
218
219 let avg_offset = weighted_mean(&offsets, &offset_weights);
220
221 Ok(avg_offset)
222 }
```

Penalizes slow servers  
by substantially  
decreasing their  
relative weights

### 9.9.3 Converting between time representations that use different precisions and epochs

chrono represents the fractional part of a second, down to a nanosecond precision, whereas NTP can represent times that differ by approximately 250 picoseconds. That's roughly four times more precise! The different internal representations used imply that some accuracy is likely to be lost during conversions.

The From trait is the mechanism for telling Rust that two types can be converted. From provides the from() method, which is encountered early on in one's Rust career (in examples such as String::from("Hello, world!")).

The next listing, a combination of three extracts from listing 9.15, provides implementations of the std::convert::From trait. This code enables the .into() calls on lines 28 and 34 of listing 9.13.

#### Listing 9.14 Converting between chrono::DateTime and NTP timestamps

```

19 const NTP_TO_UNIX_SECONDS: i64 = 2_208_988_800; ←
                                         Number of seconds between 1 Jan 1900
                                         (the NTP epoch) and 1 Jan 1970 (the UNIX epoch)
```

```

22 #[derive(Default, Debug, Copy, Clone)]
23 struct NTPTimestamp {
24     seconds: u32,
25     fraction: u32,
26 }
27
28 // Our internal type
29 // represents an NTP
30 // timestamp.
31
32 impl From<NTPTimestamp> for DateTime<Utc> {
33     fn from(ntp: NTPTimestamp) -> Self {
34         let secs = ntp.seconds as i64 - NTP_TO_UNIX_SECONDS;
35         let mut nanos = ntp.fraction as f64;
36         nanos *= 1e9;
37         nanos /= 2_f64.powi(32);
38
39         Utc.timestamp(secs, nanos as u32)
40     }
41 }
42
43 impl From<DateTime<Utc>> for NTPTimestamp {
44     fn from(utc: DateTime<Utc>) -> Self {
45         let secs = utc.timestamp() + NTP_TO_UNIX_SECONDS;
46         let mut fraction = utc.nanosecond() as f64;
47         fraction *= 2_f64.powi(32);
48         fraction /= 1e9;
49
50         NTPTimestamp {
51             seconds: secs as u32,
52             fraction: fraction as u32,
53         }
54     }
55 }
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75 }
```

You can implement these conversions using bit-shift operations, but at the expense of even less readability.

From has a reciprocal peer, Into. Implementing From allows Rust to automatically generate an Into implementation on its own, except in advanced cases. In those cases, it's likely that developers already possess the knowledge required to implement Into manually and so probably don't need assistance here.

#### 9.9.4 clock v0.1.3: The full code listing

The complete code listing for our clock application is presented in listing 9.15. Taken in its full glory, the whole of the clock application can look quite large and imposing. Hopefully, there is no new Rust syntax to digest within the listing. The source for this listing is in ch9/ch9-clock3/src/main.rs.

##### Listing 9.15 Full listing for the command-line NTP client, clock

```

1 #[cfg(windows)]
2 use kernel32;
3 #[cfg(not(windows))]
4 use libc;
5 #[cfg(windows)]
6 use winapi;
7
```

```

8 use byteorder::{BigEndian, ReadBytesExt};
9 use chrono::{
10   DateTime, Duration as ChronoDuration, TimeZone, Timelike,
11 };
12 use chrono::{Local, Utc};
13 use clap::{App, Arg};
14 use std::mem::zeroed;
15 use std::net::UdpSocket;
16 use std::time::Duration;
17
18 const NTP_MESSAGE_LENGTH: usize = 48;           ← 12 * 4 bytes (the width
19 const NTP_TO_UNIX_SECONDS: i64 = 2_208_988_800; ← of 12, 32-bit integers)
20 const LOCAL_ADDR: &'static str = "0.0.0.0:12300"; ← 12300 is the
21
22 #[derive(Default, Debug, Copy, Clone)]
23 struct NTPTimestamp {
24   seconds: u32,
25   fraction: u32,
26 }
27
28 struct NTPMessage {
29   data: [u8; NTP_MESSAGE_LENGTH],
30 }
31
32 #[derive(Debug)]
33 struct NTPResult {
34   t1: DateTime<Utc>,
35   t2: DateTime<Utc>,
36   t3: DateTime<Utc>,
37   t4: DateTime<Utc>,
38 }
39
40 impl NTPResult {
41   fn offset(&self) -> i64 {
42     let duration = (self.t2 - self.t1) + (self.t4 - self.t3);
43     duration.num_milliseconds() / 2
44   }
45
46   fn delay(&self) -> i64 {
47     let duration = (self.t4 - self.t1) - (self.t3 - self.t2);
48     duration.num_milliseconds()
49   }
50 }
51
52 impl From<NTPTimestamp> for DateTime<Utc> {
53   fn from(ntp: NTPTimestamp) -> Self {
54     let secs = ntp.seconds as i64 - NTP_TO_UNIX_SECONDS;
55     let mut nanos = ntp.fraction as f64;
56     nanos *= 1e9;
57     nanos /= 2_f64.powi(32);
58
59     Utc.timestamp(secs, nanos as u32)
60   }
61 }
62

```

```

63 impl From<DateTime<Utc>> for NTPTimestamp {
64     fn from(utc: DateTime<Utc>) -> Self {
65         let secs = utc.timestamp() + NTP_TO_UNIX_SECONDS;
66         let mut fraction = utc.nanosecond() as f64;
67         fraction *= 2_f64.powi(32);
68         fraction /= 1e9;
69
70         NTPTimestamp {
71             seconds: secs as u32,
72             fraction: fraction as u32,
73         }
74     }
75 }
76
77 impl NTPMessage {
78     fn new() -> Self {
79         NTPMessage {
80             data: [0; NTP_MESSAGE_LENGTH],
81         }
82     }
83
84     fn client() -> Self {
85         const VERSION: u8 = 0b00_011_000;
86         const MODE: u8      = 0b00_000_011;
87
88         let mut msg = NTPMessage::new();
89
90         msg.data[0] |= VERSION;
91         msg.data[0] |= MODE;
92         msg
93     }
94
95     fn parse_timestamp(
96         &self,
97         i: usize,
98     ) -> Result<NTPTimestamp, std::io::Error> {
99         let mut reader = &self.data[i..i + 8];
100        let seconds    = reader.read_u32::<BigEndian>()?;
101        let fraction   = reader.read_u32::<BigEndian>()?;
102
103        Ok(NTPTimestamp {
104            seconds: seconds,
105            fraction: fraction,
106        })
107    }
108
109    fn rx_time(
110        &self
111    ) -> Result<NTPTimestamp, std::io::Error> {
112        self.parse_timestamp(32)
113    }
114
115    fn tx_time(
116        &self
117    ) -> Result<NTPTimestamp, std::io::Error> {

```

Underscores delimit the NTP fields: leap indicator (2 bits), version (3 bits), and mode (3 bits).

The first byte of every NTP message contains three fields, but we only need to set two of these.

msg.data[0] is now equal to 0001\_1011 (27 in decimal).

Takes a slice to the first byte

RX stands for receive.

TX stands for transmit.

```
118     self.parse_timestamp(40)
119 }
120 }
121
122 fn weighted_mean(values: &[f64], weights: &[f64]) -> f64 {
123     let mut result = 0.0;
124     let mut sum_of_weights = 0.0;
125
126     for (v, w) in values.iter().zip(weights) {
127         result += v * w;
128         sum_of_weights += w;
129     }
130
131     result / sum_of_weights
132 }
133
134 fn ntp_roundtrip(
135     host: &str,
136     port: u16,
137 ) -> Result<NTPResult, std::io::Error> {
138     let destination = format!("{}:{}", host, port);
139     let timeout = Duration::from_secs(1);
140
141     let request = NTPMessage::client();
142     let mut response = NTPMessage::new();
143
144     let message = request.data;
145
146     let udp = UdpSocket::bind(LOCAL_ADDR)?;
147     udp.connect(&destination).expect("unable to connect");
148
149     let t1 = Utc::now();
150
151     udp.send(&message)?;
152     udp.set_read_timeout(Some(timeout))?;
153     udp.recv_from(&mut response.data)?;
154     let t4 = Utc::now();
155
156     let t2: DateTime<Utc> =
157         response
158             .rx_time()
159             .unwrap()
160             .into();
161     let t3: DateTime<Utc> =
162         response
163             .tx_time()
164             .unwrap()
165             .into();
166
167     Ok(NTPResult {
168         t1: t1,
169         t2: t2,
170         t3: t3,
171         t4: t4,
172     })
}
```

```

173 }
174
175 fn check_time() -> Result<f64, std::io::Error> {
176     const NTP_PORT: u16 = 123;
177
178     let servers = [
179         "time.nist.gov",
180         "time.apple.com",
181         "time.euro.apple.com",
182         "time.google.com",
183         "time2.google.com",
184         //"time.windows.com",
185     ];
186
187     let mut times = Vec::with_capacity(servers.len());
188
189     for &server in servers.iter() {
190         print!("{} =>", server);
191
192         let calc = ntp_roundtrip(&server, NTP_PORT);
193
194         match calc {
195             Ok(time) => {
196                 println!(" {}ms away from local system time", time.offset());
197                 times.push(time);
198             }
199             Err(_) => {
200                 println!(" ? [response took too long]")
201             }
202         };
203     }
204
205     let mut offsets = Vec::with_capacity(servers.len());
206     let mut offset_weights = Vec::with_capacity(servers.len());
207
208     for time in &times {
209         let offset = time.offset() as f64;
210         let delay = time.delay() as f64;
211
212         let weight = 1_000_000.0 / (delay * delay);
213         if weight.is_finite() {
214             offsets.push(offset);
215             offset_weights.push(weight);
216         }
217     }
218
219     let avg_offset = weighted_mean(&offsets, &offset_weights);
220
221     Ok(avg_offset)
222 }
223
224 struct Clock;
225
226 impl Clock {
227     fn get() -> DateTime<Local> {

```

```

228     Local::now()
229 }
230
231 #[cfg(windows)]
232 fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {
233     use chrono::Weekday;
234     use kernel32::SetSystemTime;
235     use winapi::{SYSTEMTIME, WORD};
236
237     let t = t.with_timezone(&Local);
238
239     let mut systime: SYSTEMTIME = unsafe { zeroed() };
240
241     let dow = match t.weekday() {
242         Weekday::Mon => 1,
243         Weekday::Tue => 2,
244         Weekday::Wed => 3,
245         Weekday::Thu => 4,
246         Weekday::Fri => 5,
247         Weekday::Sat => 6,
248         Weekday::Sun => 0,
249     };
250
251     let mut ns = t.nanosecond();
252     let is_leap_second = ns > 1_000_000_000;
253
254     if is_leap_second {
255         ns -= 1_000_000_000;
256     }
257
258     systime.wYear = t.year() as WORD;
259     systime.wMonth = t.month() as WORD;
260     systime.wDayOfWeek = dow as WORD;
261     systime.wDay = t.day() as WORD;
262     systime.wHour = t.hour() as WORD;
263     systime.wMinute = t.minute() as WORD;
264     systime.wSecond = t.second() as WORD;
265     systime.wMilliseconds = (ns / 1_000_000) as WORD;
266
267     let systime_ptr = &systime as *const SYSTEMTIME;
268     unsafe {
269         SetSystemTime(systime_ptr);
270     }
271 }
272
273 #[cfg(not(windows))]
274 fn set<Tz: TimeZone>(t: DateTime<Tz>) -> () {
275     use libc::settimeofday;
276     use libc::{suseconds_t, time_t, timeval, timezone};
277
278     let t = t.with_timezone(&Local);
279     let mut u: timeval = unsafe { zeroed() };
280
281     u.tv_sec = t.timestamp() as time_t;
282     u.tv_usec = t.timestamp_subsec_micros() as suseconds_t;

```

```

283
284     unsafe {
285         let mock_tz: *const timezone = std::ptr::null();
286         settimeofday(&u as *const timeval, mock_tz);
287     }
288 }
289 }
290
291 fn main() {
292     let app = App::new("clock")
293         .version("0.1.3")
294         .about("Gets and sets the time.")
295         .after_help(
296             "Note: UNIX timestamps are parsed as whole seconds since 1st \
297             January 1970 0:00:00 UTC. For more accuracy, use another \
298             format.",
299         )
300         .arg(
301             Arg::with_name("action")
302                 .takes_value(true)
303                 .possible_values(&["get", "set", "check-ntp"])
304                 .default_value("get"),
305         )
306         .arg(
307             Arg::with_name("std")
308                 .short("s")
309                 .long("use-standard")
310                 .takes_value(true)
311                 .possible_values(&["rfc2822", "rfc3339", "timestamp"])
312                 .default_value("rfc3339"),
313         )
314         .arg(Arg::with_name("datetime").help(
315             "When <action> is 'set', apply <datetime>. Otherwise, ignore.",
316         )));
317
318     let args = app.get_matches();
319
320     let action = args.value_of("action").unwrap();
321     let std = args.value_of("std").unwrap();
322
323     if action == "set" {
324         let t_ = args.value_of("datetime").unwrap();
325
326         let parser = match std {
327             "rfc2822" => DateTime::parse_from_rfc2822,
328             "rfc3339" => DateTime::parse_from_rfc3339,
329             _ => unimplemented!(),
330         };
331
332         let err_msg =
333             format!("Unable to parse {} according to {}", t_, std);
334         let t = parser(t_).expect(&err_msg);
335
336         Clock::set(t);
337

```

```

338 } else if action == "check-ntp" {
339     let offset = check_time().unwrap() as isize;
340
341     let adjust_ms_ = offset.signum() * offset.abs().min(200) / 5;
342     let adjust_ms = ChronoDuration::milliseconds(adjust_ms_ as i64);
343
344     let now: DateTime<Utc> = Utc::now() + adjust_ms;
345
346     Clock::set(now);
347 }
348
349 let maybe_error =
350     std::io::Error::last_os_error();
351 let os_error_code =
352     &maybe_error.raw_os_error();
353
354 match os_error_code {
355     Some(0) => (),
356     Some(_) => eprintln!("Unable to set the time: {:?}", maybe_error),
357     None => (),
358 }
359
360 let now = Clock::get();
361
362 match std {
363     "timestamp" => println!("{}", now.timestamp()),
364     "rfc2822" => println!("{}", now.to_rfc2822()),
365     "rfc3339" => println!("{}", now.to_rfc3339()),
366     _ => unreachable!(),
367 }
368 }
```

## Summary

- Keeping track of elapsed time is difficult. Digital clocks ultimately rely on fuzzy signals from analog systems.
- Representing time is difficult. Libraries and standards disagree about how much precision is required and when to start.
- Establishing truth in a distributed system is difficult. Although we continually deceive ourselves otherwise, there is no single arbiter of what time it is. The best we can hope for is that all of the computers in our network are reasonably close to each other.
- A struct with no fields is known as a zero-sized type or ZST. It does not occupy any memory in the resulting application and is purely a compile-time construct.
- Creating cross-portable applications is possible with Rust. Adding platform-specific implementations of functions requires the precise use of the `cfg` annotation, but it can be done.
- When interfacing with external libraries, such as the API provided by the operating system (OS), a type conversion step is almost always required. Rust's type system does not extend to libraries that it did not create!

- System calls are used to make function calls to the OS. This invokes a complex interaction between the OS, the CPU, and the application.
- The Windows API typically uses verbose PascalCase identifiers, whereas operating systems from the POSIX tradition typically use terse lowercase identifiers.
- Be precise when making assumptions about the meaning of terms such as epoch and time zone. There is often hidden context lurking beneath the surface.
- Time can go backwards. Never write an application that relies on monotonically increasing time without ensuring that it requests a monotonically increasing clock from the OS.

# 10

## Processes, threads, and containers

### This chapter covers

- Concurrent programming in Rust
- How to distinguish processes, threads, and containers
- Channels and message passing
- Task queues

So far this book has almost completely avoided two fundamental terms of systems programming: threads and processes. Instead, the book has used the single term: program. This chapter expands our vocabulary.

Processes, threads, and containers are abstractions created to enable multiple tasks to be carried out at the same time. This enables *concurrency*. Its peer term, *parallelism*, means to make use of multiple physical CPU cores at the same time.

Counterintuitively, it is possible to have a concurrent system on a single CPU core. Because accessing data from memory and I/O take a long time, threads requesting data can be set to a *blocked* state. Blocked threads are rescheduled when their data is available.

Concurrency, or doing multiple things at the same time, is difficult to introduce into a computer program. Employing concurrency effectively involves both new concepts and new syntax.

The aim of this chapter is to give you the confidence to explore more advanced material. You will have a solid understanding of the different tools that are available to you as an applications programmer. This chapter exposes you to the standard library and the well engineered crates crossbeam and rayon. It will enable you to use them, though it won't give you sufficient background to be able to implement your own concurrency crates. The chapter follows the following structure:

- *It introduces you to Rust's closure syntax in section 10.1.* Closures are also known as anonymous functions and lambda functions. The syntax is important because the standard library and many (perhaps all) external crates rely on that syntax to provide support for Rust's concurrency model.
- *It provides a quick lesson on spawning threads in section 10.2.* You'll learn what a thread is and how to create (spawn) those. You'll also encounter a discussion of why programmers are warned against spawning tens of thousands of threads.
- *It distinguishes between functions and closures in section 10.3.* Conflating these two concepts can be a source of confusion for programmers new to Rust as these are often indistinguishable in other languages.
- *It follows with a large project in section 10.4.* You'll implement a multithreaded parser and a code generator using multiple strategies. As a nice aside, you get to create procedural art along the way.
- *The chapter concludes with an overview of other forms of concurrency.* This includes processes and containers.

## 10.1 Anonymous functions

This chapter is fairly dense, so let's get some points on the board quickly with some basic syntax and practical examples. We'll circle back to fill in a lot of the conceptual and theoretical material.

Threads and other forms of code that can run concurrently use a form of function definition that we've avoided for the bulk of the book. Taking a look at it now, defining a function looks like this:

```
fn add(a: i32, b: i32) -> i32 {
    a + b
}
```

The (loosely) equivalent lambda function is

```
let add = |a,b| { a + b };
```

Lambda functions are denoted by the pair of vertical bars (`|...|`) followed by curly brackets (`{...}`). The pair of vertical bars lets you define arguments. Lambda functions in Rust can read variables from within their scope. These are *closures*.

Unlike regular functions, lambda functions cannot be defined in global scope. The following listing gets around this by defining one within its `main()`. It defines two

functions, a regular function and a lambda function, and then checks that these produce the same result.

### Listing 10.1 Defining two functions and checking the result

```
fn add(a: i32, b: i32) -> i32 {
    a + b
}

fn main() {
    let lambda_add = |a,b| { a + b };

    assert_eq!(add(4,5), lambda_add(4,5));
}
```

When you run listing 10.1, it executes happily (and silently). Let's now see how to put this functionality to work.

## 10.2 Spawning threads

Threads are the primary mechanism that operating systems provide for enabling concurrent execution. Modern operating systems ensure that each thread has fair access to the CPU. Understanding how to create threads (often referred to as spawning threads) and understanding their impact are fundamental skills for programmers wanting to make use of multi-core CPUs.

### 10.2.1 Introduction to closures

To spawn a thread in Rust, we pass an anonymous function to `std::thread::spawn()`. As described in section 10.1, anonymous functions are defined with two vertical bars to provide arguments and then curly brackets for the function's body. Because `spawn()` doesn't take any arguments, you will typically encounter this syntax:

```
thread::spawn(|| {
    // ...
});
```

When the spawned thread wants to access variables that are defined in the parent's scope, called a *capture*, Rust often complains that captures must be moved into the closure. To indicate that you want to move ownership, anonymous functions take a `move` keyword:

```
thread::spawn(move || {
    // ...
});
```

The move keyword allows the anonymous function to access variables from their wider scope.

Why is `move` required? Closures spawned in subthreads can potentially outlive their calling scope. As Rust will always ensure that accessing the data is valid, it requires

ownership to move to the closure itself. Here are some guidelines for using captures while you gain an understanding of how these work:

- To reduce friction at compile time, implement `Copy`.
- Values originating in outer scopes may need to have a `static` lifetime.
- Spawnsed subthreads can outlive their parents. That implies that ownership should pass to the subthread with `move`.

### 10.2.2 Spawning a thread

A simple task waits, sleeping the CPU for 300 ms (milliseconds). If you have a 3 GHz CPU, you're getting it to rest for nearly 1 billion cycles. Those electrons will be very relieved. When executed, listing 10.2 prints the total duration (in "wall clock" time) of both executing threads. Here's the output:

```
300.218594ms
```

#### Listing 10.2 Sleeping a subthread for 300 ms

```

1 use std::thread, time;
2
3 fn main() {
4     let start = time::Instant::now();
5
6     let handler = thread::spawn(|| {
7         let pause = time::Duration::from_millis(300);
8         thread::sleep(pause.clone());
9     });
10
11    handler.join().unwrap();
12
13    let finish = time::Instant::now();
14
15    println!("{:02?}", finish.duration_since(start));
16 }
```

If you had encountered multi-threaded programming before, you would have been introduced to `join` on line 11. Using `join` is fairly common, but what does it mean?

`join` is an extension of the thread metaphor. When threads are spawned, these are said to have *forked* from their parent thread. To `join` threads means to weave these back together again.

In practice, `join` means wait for the other thread to finish. The `join()` function instructs the OS to defer scheduling the calling thread until the other thread finishes.

### 10.2.3 Effect of spawning a few threads

In ideal settings, adding a second thread doubles the work we can do in the same amount of time. Each thread can get its work done independently. Reality is not ideal, unfortunately. This has created a myth that threads are slow to create and bulky

to maintain. This section aims to dispel that myth. When used as intended, threads perform very well.

Listing 10.3 shows a program that measures the overall time taken for two threads to perform the job that was carried out by a single thread in listing 10.2. If adding threads take a long time, we would expect the duration of listing 10.3’s code to be longer.

As you’ll notice, there is a negligible impact from creating one or two threads. As with listing 10.2, listing 10.3 prints almost the same output:

300.242328ms	←	Versus 300.218594 ms from listing 10.2
--------------	---	---

The difference in these two runs on my computer was 0.24 ms. While by no means a robust benchmark suite, it does indicate that spawning a thread isn’t a tremendous performance hit.

### **Listing 10.3 Creating two subthreads to perform work on our behalf**

```

1 use std::{thread, time};
2
3 fn main() {
4     let start = time::Instant::now();
5
6     let handler_1 = thread::spawn(move || {
7         let pause = time::Duration::from_millis(300);
8         thread::sleep(pause.clone());
9     });
10
11    let handler_2 = thread::spawn(move || {
12        let pause = time::Duration::from_millis(300);
13        thread::sleep(pause.clone());
14    });
15
16    handler_1.join().unwrap();
17    handler_2.join().unwrap();
18
19    let finish = time::Instant::now();
20
21    println!("{}?", finish.duration_since(start));
22 }
```


If you’ve had any exposure to the field before, you may have heard that threads “don’t scale.” What does that mean?

Every thread requires its own memory, and by implication, we’ll eventually exhaust our system’s memory. Before that terminal point, though, thread creation begins to trigger slowdowns in other areas. As the number of threads to schedule increases, the OS scheduler’s work increases. When there are many threads to schedule, deciding which thread to schedule next takes more time.

### 10.2.4 Effect of spawning many threads

Spawning threads is not free. It demands memory and CPU time. Switching between threads also invalidates caches.

Figure 10.1 shows the data generated by successive runs of listing 10.4. The variance stays quite tight until about 400 threads per batch. After that, there's almost no knowing how long a 20 ms sleep will take.



**Figure 10.1 Duration needed to wait for threads to sleep 20 ms**


And, if you're thinking that sleeping is not a representative workload, figure 10.2 shows the next plot, which is even more telling. It asks each thread to enter a spin loop.

Figure 10.2 provides features that are worth focusing in on briefly. First, for the first seven or so batches, the spin loop version returned closer to 20 ms. The operating system's sleep functionality isn't perfectly accurate, however. If you want to sleep pause a thread for short amounts of time, or if your application is sensitive to timing, use a spin loop.<sup>1</sup>


Second, CPU-intensive multithreading doesn't scale well past the number of physical cores. The benchmarking was performed on a 6-core CPU (the Intel i7-8750H) with hyper-threading disabled. Figure 10.3 shows that as soon as the thread count exceeds the core count, performance degrades quickly.

---

<sup>1</sup> It's also possible to use both: sleep for the bulk of the time and a spin loop towards the end.



**Figure 10.2** Comparing the time taken to wait for 20m using the sleep strategy (circles) versus the spin lock strategy (plus symbols). This chart shows the differences that occur as hundreds of threads compete.



**Figure 10.3** Comparing the time taken to wait for 20m using the sleep strategy (circles) versus the spin lock strategy (plus symbols). This chart shows the differences that occur as the number of threads exceeds the number of CPU cores (6).

### 10.2.5 Reproducing the results

Now that we've seen the effects of threading, let's look at the code that generated the input data to the plots in figures 10.1–10.2. You are welcome to reproduce the results. To do so, write the output of listings 10.4 and 10.5 to two files, and then analyze the resulting data.

Listing 10.4, whose source code is available at `c10/ch10-multijoin/src/main.rs`, suspends threads for 20 ms with a `sleep`. A `sleep` is a request to the OS that the thread should be suspended until the time has passed. Listing 10.5, whose source code is available at `c10/ch10-busythreads/src/main.rs`, uses the *busy wait* strategy (also known as *busy loop* and *spin loop*) to pause for 20 ms.

#### Listing 10.4 Using `thread::sleep` to suspend threads for 20 ms

```

1 use std::{thread, time};
2
3 fn main() {
4     for n in 1..1001 {
5         let mut handlers: Vec<thread::JoinHandle<()>> = Vec::with_capacity(n);
6
7         let start = time::Instant::now();
8         for _m in 0..n {
9             let handle = thread::spawn(|| {
10                 let pause = time::Duration::from_millis(20);
11                 thread::sleep(pause);
12             });
13             handlers.push(handle);
14         }
15
16         while let Some(handle) = handlers.pop() {
17             handle.join();
18         }
19
20         let finish = time::Instant::now();
21         println!("{}\t{:02?}", n, finish.duration_since(start));
22     }
23 }
```

#### Listing 10.5 Using a spin loop waiting strategy

```

1 use std::{thread, time};
2
3 fn main() {
4     for n in 1..1001 {
5         let mut handlers: Vec<thread::JoinHandle<()>> = Vec::with_capacity(n);
6
7         let start = time::Instant::now();
8         for _m in 0..n {
9             let handle = thread::spawn(|| {
10                 let start = time::Instant::now();
11                 let pause = time::Duration::from_millis(20);
12
13                 while time::Instant::now() - start < pause {
14                     // Busy-wait loop
15                 }
16
17                 handle.join();
18             });
19             handlers.push(handle);
20         }
21
22         let finish = time::Instant::now();
23         println!("{}\t{:02?}", n, finish.duration_since(start));
24     }
25 }
```

```

12         while start.elapsed() < pause {
13             thread::yield_now();
14         }
15     });
16     handlers.push(handle);
17 }
18
19 while let Some(handle) = handlers.pop() {
20     handle.join();
21 }
22
23 let finish = time::Instant::now();
24 println!("{}\t{:02?}", n, finish.duration_since(start));
25 }
26 }
```

The control flow we've chosen for lines 19–21 is slightly odd. Rather than iterating through the `handlers` vector, we call `pop()` and then drain it. The following two snippets compare the more familiar `for` loop (listing 10.6) with the control flow mechanism that is actually employed (listing 10.7).

#### **Listing 10.6 What we would expect to see in listing 10.5**

```

19 for handle in &handlers {
20     handle.join();
21 }
```

#### **Listing 10.7 Code that's actually used in listing 10.5**

```

19 while let Some(handle) = handlers.pop() {
20     handle.join();
21 }
```

Why use the more complex control flow mechanism? It might help to remember that once we join a thread back to the main thread, it ceases to exist. Rust won't allow us to retain a reference to something that doesn't exist. Therefore, to call `join()` on a thread handler within `handlers`, the thread handler must be removed from `handlers`. That poses a problem. A `for` loop does not permit modifications to the data being iterated over. Instead, the `while` loop allows us to repeatedly gain mutable access when calling `handlers.pop()`.

Listing 10.8 provides a broken implementation of the spin loop strategy. It is broken because it uses the more familiar `for` loop control flow that was avoided in listing 10.5. You'll find the source for this listing in `c10/ch10-busythreads-broken/src/main.rs`. Its output follows the listing.

#### **Listing 10.8 Using a spin loop waiting strategy**

```

1 use std::{thread, time};
2
```

```

3 fn main() {
4     for n in 1..1001 {
5         let mut handlers: Vec<thread::JoinHandle<()>> = Vec::with_capacity(n);
6
7         let start = time::Instant::now();
8         for _m in 0..n {
9             let handle = thread::spawn(|| {
10                 let start = time::Instant::now();
11                 let pause = time::Duration::from_millis(20);
12                 while start.elapsed() < pause {
13                     thread::yield_now();
14                 }
15             });
16             handlers.push(handle);
17         }
18
19         for handle in &handlers {
20             handle.join();
21         }
22
23         let finish = time::Instant::now();
24         println!("{} \t{:02?}", n, finish.duration_since(start));
25     }
26 }
```

Here is the output generated when attempting to compile listing 10.8:

```

$ cargo run -q
error[E0507]: cannot move out of `*handle` which is behind a
shared reference
--> src/main.rs:20:13
|
20 |         handle.join();
|         ^^^^^^ move occurs because `*handle` has type
`std::thread::JoinHandle<()>`, which does not implement the
`Copy` trait

error: aborting due to previous error

For more information about this error, try `rustc --explain E0507`.
error: Could not compile `ch10-busythreads-broken`.

To learn more, run the command again with --verbose.
```

This error is saying that taking a reference isn't valid here. That's because multiple threads might also be taking their own references to the underlying threads. And those references need to be valid.

Astute readers know that there is actually a simpler way to get around this problem than what was used in listing 10.5. As the following listing shows, simply remove the ampersand.

**Listing 10.9 What we could have used in listing 10.5**

```
19 for handle in handlers {
20     handle.join();
21 }
```

What we've encountered is one of those rare cases where taking a reference to an object causes more issues than using the object directly. Iterating over handlers directly retains ownership. That pushes any concerns about shared access to the side, and we can proceed as intended.

**YIELDING CONTROL WITH THREAD::YIELD\_NOW()**

As a reminder, the busy loop within listing 10.5 includes some unfamiliar code, repeated in the following listing. This section explains its significance.

**Listing 10.10 Showing the current thread-yielding execution**

```
14 while start.elapsed() < pause {
15     thread::yield_now();
16 }
```

`std::thread::yield_now()` is a signal to the OS that the current thread should be unscheduled. This allows other threads to proceed while the current thread is still waiting for the 20 ms to arrive. A downside to yielding is that we don't know if we'll be able to resume at exactly 20 ms.

An alternative to yielding is to use the function `std::sync::atomic::spin_loop_hint()`. `spin_loop_hint()` avoids the OS; instead, it directly signals the CPU. A CPU might use that hint to turn off functionality, thus saving power usage.


**NOTE** The `spin_loop_hint()` instruction is not present for every CPU. On platforms that don't support it, `spin_loop_hint()` does nothing.

**10.2.6 Shared variables**

In our threading benchmarks, we created pause variables in each thread. If you're not sure what I'm referring to, the following listing provides an excerpt from listing 10.5.

**Listing 10.11 Emphasizing the needless creation of time::Duration instances**

```
9 let handle = thread::spawn(|| {
10     let start = time::Instant::now();
11     let pause = time::Duration::from_millis(20);
12     while start.elapsed() < pause {
13         thread::yield_now();
14     }
15 });


```

This variable doesn't  
need to be created  
in each thread.

We want to be able to write something like the following listing. The source for this listing is ch10/ch10-sharedpause-broken/src/main.rs.

**Listing 10.12 Attempting to share a variable in multiple subthreads**

```
1 use std::thread;
2
3 fn main() {
4     let pause = time::Duration::from_millis(20);
5     let handle1 = thread::spawn(|| {
6         thread::sleep(pause);
7     });
8     let handle2 = thread::spawn(|| {
9         thread::sleep(pause);
10    });
11
12    handle1.join();
13    handle2.join();
14 }
```

If we run listing 10.12, we'll receive a verbose—and surprisingly helpful—error message:

```
$ cargo run -q
error[E0373]: closure may outlive the current function, but it borrows
`pause`, which is owned by the current function
--> src/main.rs:5:33
|
5 |     let handle1 = thread::spawn(|| {
|           ^^^ may outlive borrowed value `pause`
6 |         thread::sleep(pause);
|               ----- `pause` is borrowed here
|
note: function requires argument type to outlive `'static`  

--> src/main.rs:5:19
|
5 |     let handle1 = thread::spawn(|| {
|           ^
6 |     |----- thread::sleep(pause);
7 |     |   );
|     |
help: to force the closure to take ownership of `pause` (and any other
references variables), use the `move` keyword
|
5 |     let handle1 = thread::spawn(move || {
|           ^^^^^^
|
error[E0373]: closure may outlive the current function, but it borrows
`pause`, which is owned by the current function
--> src/main.rs:8:33
|
8 |     let handle2 = thread::spawn(|| {
|           ^^^ may outlive borrowed value `pause`
9 |         thread::sleep(pause);
|               ----- `pause` is borrowed here
|
note: function requires argument type to outlive `'static`  

--> src/main.rs:8:19
```

```

8     let handle2 = thread::spawn(|| {
9         ^_____
10        | thread::sleep(pause);
11        |_____
12
13 help: to force the closure to take ownership of `pause` (and any other
14 referenced variables), use the `move` keyword
15
16     let handle2 = thread::spawn(move || {
17         ^^^^^^
18
19 error: aborting due to 2 previous errors
20
21
22 For more information about this error, try `rustc --explain E0373`.
23 error: Could not compile `ch10-sharedpause-broken`.
24
25 To learn more, run the command again with --verbose.

```

The fix is to add the `move` keyword to where the closures are created, as hinted at in section 10.2.1. The following listing adds the `move` keyword, which switches the closures to use move semantics. That, in turn, relies on Copy.

#### Listing 10.13 Using a variable defined in a parent scope in multiple closures

```

1 use std::{thread,time};
2
3 fn main() {
4     let pause = time::Duration::from_millis(20);
5     let handle1 = thread::spawn(move || {
6         thread::sleep(pause);
7     });
8     let handle2 = thread::spawn(move || {
9         thread::sleep(pause);
10    });
11
12    handle1.join();
13    handle2.join();
14 }

```

The details of why this works are interesting. Be sure to read the following section to learn those.

### 10.3 Differences between closures and functions

There are some differences between closures (`|| {}`) and functions (`fn`). The differences prevent closures and functions from being used interchangeably, which can cause problems for learners.

Closures and functions have different internal representations. Closures are anonymous structs that implement the `std::ops::FnOnce` trait and potentially `std::ops::Fn`

and `std::ops::FnMut`. Those structs are invisible in source code but contain any variables from the closure's environment that are used inside it.

Functions are implemented as function pointers. A *function pointer* is a pointer that points to code, not data. Code, when used in this sense, is computer memory that has been marked as executable. To complicate matters, closures that do not enclose any variables from their environment are also function pointers.

### Forcing the compiler to reveal the type of closure

The concrete type of a Rust closure is inaccessible as source code. The compiler creates it. To retrieve it, force a compiler error like this:

```
1 fn main() {           Closures are values and can
2   let a = 20;         be assigned to a variable.
3
4   let add_to_a = |b| { a + b };    ←
5   add_to_a == ();      ←
6 }
```

A quick method to inspect a value's type, this attempts to perform an illegal operation on it. The compiler quickly reports it as an error message.

Among other errors, the compiler produces this one when attempting to compile the snippet as `/tmp/a-plus-b.rs`:

```
$ rustc /tmp/a-plus-b.rs
error[E0369]: binary operation `==` cannot be applied to type
`[closure@/tmp/a-plus-b.rs:4:20: 4:33]`  

 -> /tmp/a-plus-b.rs:6:14
 |
6 |     add_to_a == ();
 |     ----- ^ ^ -- ()  

 |     |
 |     [closure@/tmp/a-plus-b.rs:4:20: 4:33]

error: aborting due to previous error

For more information about this error, try `rustc --explain E0369`.
```

## 10.4 Procedurally generated avatars from a multithreaded parser and code generator

This section applies the syntax that we learned in section 10.2 to an application. Let's say that we want the users of our app to have unique pictorial avatars by default. One approach for doing this is to take their usernames and the digest of a hash function, and then use those digits as parameter inputs to some procedural generation logic. Using this approach, everyone will have visually similar yet completely distinctive default avatars.

Our application creates parallax lines. It does this by using the characters within the Base 16 alphabet as opcodes for a LOGO-like language.

### 10.4.1 How to run render-hex and its intended output

In this section, we'll produce three variations. These will all be invoked in the same way. The following listing demonstrates this. It also shows the output from invoking our render-hex project (listing 10.18):

```
$ git clone https://github.com/rust-in-action/code rust-in-action
...
$ cd rust-in-action/ch10/ch10-render-hex

$ cargo run -- $(
>   echo 'Rust in Action' |
>   shasum |
>   cut -f1 -d' '
> )
$ ls
5deaed72594aaa10edda990c5a5eed868ba8915e.svg  Cargo.toml  target
Cargo.lock                                         src

$ cat 5deaed72594aaa10edda990c5a5eed868ba8915e.svg
<svg height="400" style="outline: 5px solid #800000;">
  viewBox="0 0 400 400" width="400" xmlns="http://www.w3.org/2000/svg">
    <rect fill="#ffffff" height="400" width="400" x="0" y="0"/>
    <path d="M200,200 L200,400 L200,400 L200,400 L200,400 L200,400 L200,
        400 L480,400 L120,400 L-80,400 L560,400 L40,400 L40,400 L40,400 L40,
        400 L40,360 L200,200 L200,200 L200,200 L200,200 L200,200 L200,560 L200,
        -160 L200,200 L200,200 L400,200 L400,200 L400,0 L400,0 L400,0 L400,0 L80,
        0 L-160,0 L520,0 L200,0 L200,0 L520,0 L-160,0 L240,0 L440,0 L200,0"
      fill="none" stroke="#2f2f2f" stroke-opacity="0.9" stroke-width="5"/>
    <rect fill="#ffffff" fill-opacity="0.0" height="400" stroke="#cccccc"
      stroke-width="15" width="400" x="0" y="0"/>
  </svg>
```

The diagram illustrates the data flow from the command line to the final output. It starts with the command '\$ cargo run -- \$(...)'. The input to this command is 'echo 'Rust in Action'' followed by '| shasum | cut -f1 -d'' and ')'. A callout points to this part of the command with the text 'Generates some input from the Base 16 alphabet (e.g., 0-9 and A-F)'. The output of this command is a SHA-256 hash: '5deaed72594aaa10edda990c5a5eed868ba8915e'. This hash is used as the filename for the generated SVG file. A callout points to the filename with the text 'The project creates a filename that matches the input data.' The generated file is '5deaed72594aaa10edda990c5a5eed868ba8915e.svg'. Finally, the command '\$ cat 5deaed72594aaa10edda990c5a5eed868ba8915e.svg' is shown, which outputs the SVG code. A callout points to this command with the text 'Inspects the output'.

Any stream of valid Base 16 bytes generates a unique image. The file generated from `echo 'Rust in Action' | sha256sum` renders as shown in figure 10.4. To render SVG files, open the file in a web browser or a vector image program such as Inkscape (<https://inkscape.org/>).

### 10.4.2 Single-threaded render-hex overview

The render-hex project converts its input to an SVG file. The SVG file format succinctly describes drawings using mathematical operations. You can view the SVG file in any web browser and many graphics packages. Very little of the program relates to multithreading at this stage, so I'll skip much of the details. The program has a simple pipeline comprised of four steps:

- 1 Receives input from STDIN
- 2 Parses the input into operations that describe the movement of a pen across a sheet of paper
- 3 Converts the movement operations into its SVG equivalent
- 4 Generates an SVG file




Figure 10.4 The SHA256 digest of *Rust in Action* displayed as a diagram

Why can't we directly create path data from input? Splitting this process into two steps allows for more transformations. This pipeline is managed directly within `main()`.

The following listing shows the `main()` function for `render-hex` (listing 10.18). It parses the command-line arguments and manages the SVG generation pipeline. You'll find the source for this listing in `ch10/ch10-render-hex/src/main.rs`.

#### Listing 10.14 The `main()` function of `render-hex`

```
166 fn main() {  
167     let args = env::args().collect::<Vec<String>>();  
168     let input = args.get(1).unwrap();  
169     let default = format!("{}.svg", input);  
170     let save_to = args.get(2).unwrap_or(&default);  
171  
172     let operations = parse(input);  
173     let path_data = convert(&operations);  
174     let document = generate_svg(path_data);  
175     svg::save(save_to, &document).unwrap();  
176 }
```

Command-line argument parsing

SVG generation pipeline

### INPUT PARSING

Our job in this section is to convert hexadecimal digits to instructions for a virtual pen that travels across a canvas. The `Operation` enum, shown in the following code snippet, represents these instructions.

**NOTE** The term *operation* is used rather than *instruction* to avoid colliding with the terminology used within the SVG specification for path drawing.

```
21 #[derive(Debug, Clone, Copy)]
22 enum Operation {
23     Forward(isize),
24     TurnLeft,
25     TurnRight,
26     Home,
27     Noop(usize),
28 }
```

To parse this code, we need to treat every byte as an independent instruction. Numerals are converted to distances, and letters change the orientation of the drawing:

```
123 fn parse(input: &str) -> Vec<Operation> {
124     let mut steps = Vec::new();
125     for byte in input.bytes() {
126         let step = match byte {
127             b'0' => Home,
128             b'1'..=b'9' => {
129                 let distance = (byte - 0x30) as isize;
130                 Forward(distance * (HEIGHT/10))
131             },
132             b'a' | b'b' | b'c' => TurnLeft,
133             b'd' | b'e' | b'f' => TurnRight,
134             _ => Noop(byte),
135         };
136         steps.push(step);
137     }
138 }
139 steps
140 }
```

In ASCII, numerals start at 0x30 (48 in Base 10), so this converts the u8 value of b'2' to 2. Performing this operation on the whole range of u8 could cause a panic, but we're safe here, thanks to the guarantee provided by our pattern matching.

There's plenty of opportunity to add more instructions to produce more elaborate diagrams without increasing the parsing complexity.

Although we don't expect any illegal characters, there may be some in the input stream. Using a `Noop` operation allows us to decouple parsing from producing output.

### INTERPRET INSTRUCTIONS

The `Artist` struct maintains the state of the diagram. Conceptually, the `Artist` is holding a pen at the coordinates `x` and `y` and is moving it in the direction of heading:

```
49 #[derive(Debug)]
50 struct Artist {
51     x: isize,
52     y: isize,
53     heading: Orientation,
54 }
```

To move, Artist implements several methods of the render-hex project, two of which are highlighted in the following listing. Rust's match expressions are used to succinctly refer to and modify internal state. You'll find the source for this listing in ch10-render-hex/src/main.rs.

#### Listing 10.15 Moving Artist

```

70     fn forward(&mut self, distance: isize) {
71         match self.heading {
72             North => self.y += distance,
73             South => self.y -= distance,
74             West  => self.x += distance,
75             East  => self.x -= distance,
76         }
77     }
78
79     fn turn_right(&mut self) {
80         self.heading = match self.heading {
81             North => East,
82             South => West,
83             West  => North,
84             East  => South,
85         }
86     }

```

The convert() function in listing 10.16, an extract from the render-hex project (listing 10.18), makes use of the Artist struct. Its role is to convert the `Vec<Operation>` from `parse()` to a `Vec<Command>`. That output is used later to generate an SVG. As a nod to the LOGO language, Artist is given the local variable name `turtle`. The source for this listing is in ch10-render-hex/src/main.rs.

#### Listing 10.16 Focusing on the convert() function

```

131 fn convert(operations: &Vec<Operation>) -> Vec<Command> {
132     let mut turtle = Artist::new();
133     let mut path_data: Vec<Command> = vec![];
134     let start_at_home = Command::Move(
135         Position::Absolute, (HOME_X, HOME_Y).into()
136     );
137     path_data.push(start_at_home);
138
139     for op in operations {
140         match *op {
141             Forward(distance) => turtle.forward(distance),
142             TurnLeft => turtle.turn_left(),
143             TurnRight => turtle.turn_right(),
144             Home => turtle.home(),
145             Noop(byte) => {
146                 eprintln!("warning: illegal byte encountered: {:?}", byte)
147             },
148         };

```

To start, positions the turtle in the center of the drawing area

We don't generate a Command immediately. Instead, we modify the internal state of turtle.

```

149     let line = Command::Line(
150         Position::Absolute,
151         (turtle.x, turtle.y).into()
152     );
153     path_data.push(line);
154
155     turtle.wrap();    ←
156 }
157 path_data
158 }

```

**Creates a Command::Line  
(a straight line toward the  
turtle's current position)**

**If the turtle is out of  
bounds, returns it to  
the center**

### GENERATING AN SVG

The process of generating the SVG file is rather mechanical. `generate_svg()` (lines 161–192 of listing 10.18) does the work.

SVG documents look a lot like HTML documents, although the tags and attributes are different. The `<path>` tag is the most important one for our purposes. It has a `d` attribute (`d` is short for data) that describes how the path should be drawn. `convert()` produces a `Vec<Command>` that maps directly to the path data.

### SOURCE CODE FOR THE SINGLE-THREADED VERSION OF RENDER-HEX

The render-hex project has an orthodox structure. The whole project sits within a (fairly large) `main.rs` file managed by cargo. To download the project's source code from its public code repository, use the following commands:

```

$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
$ cd rust-in-action/ch10/ch10-render-hex

```

Otherwise, to create the project by hand, follow the commands in the following snippet, and then copy the code from listing 10.18 into `src/main.rs`:

```

$ cargo new ch10-render-hex
    Created binary (application) `ch10-render-hex` package

$ cd ch10-render-hex

$ cargo install cargo-edit
    Updating crates.io index
Downloaded cargo-edit v0.7.0
Downloaded 1 crate (57.6 KB) in 1.35s
Installing cargo-edit v0.7.0
...
$ cargo add svg@0.6
    Updating 'https://github.com/rust-lang/crates.io-index' index
    Adding svg v0.6 to dependencies

```

The standard project structure, which you can compare against the following snippet, has been created for you:

```
ch10-render-hex/
└── Cargo.toml      ← See listing 10.17.
    └── src
        └── main.rs   ← See listing 10.18.
```

The following listing shows the metadata for our project. You should check that your project's `Cargo.toml` matches the relevant details. You'll find the source for this listing in `ch10/ch10-render-hex/Cargo.toml`.

#### Listing 10.17 Project metadata for render-hex

```
[package]
name = "render-hex"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
svg = "0.6"
```

The single-threaded version of `render-hex` appears in the following listing. You'll find the source for this listing in `ch10-render-hex/src/main.rs`.

#### Listing 10.18 Source code for render-hex

```
1 use std::env;
2
3 use svg::node::element::path::{Command, Data, Position};
4 use svg::node::element::{Path, Rectangle};
5 use svg::Document;
6
7 use crate::Operation::{
8     Forward,
9     Home,
10    Noop,
11    TurnLeft,
12    TurnRight
13 };
14 use crate::Orientation::{
15     East,
16     North,
17     South,
18     West
19 };
20
21 const WIDTH: isize = 400;
22 const HEIGHT: isize = WIDTH;
23
24 const HOME_Y: isize = HEIGHT / 2;
25 const HOME_X: isize = WIDTH / 2;
```

**Operation and Orientation enum types are defined later. Including these with the `use` keyword removes a lot of noise from the source code.**

**HEIGHT and WIDTH provide the bounds of the drawing.**

**HOME\_Y and HOME\_X constants allow us to easily reset where we are drawing from. Here y is the vertical coordinate and x is the horizontal.**

**STROKE\_WIDTH, a parameter for the SVG output, defines the look of each drawn line.**

```

29 #[derive(Debug, Clone, Copy)]
30 enum Orientation {
31     North,
32     East,
33     West,
34     South,
35 }
36
37 #[derive(Debug, Clone, Copy)]
38 enum Operation {
39     Forward(isize),
40     TurnLeft,
41     TurnRight,
42     Home,
43     Noop(u8),
44 }
45
46 #[derive(Debug)]
47 struct Artist {
48     x: isize,
49     y: isize,
50     heading: Orientation,
51 }
52
53 impl Artist {
54     fn new() -> Artist {
55         Artist {
56             heading: North,
57             x: HOME_X,
58             y: HOME_Y,
59         }
60     }
61
62     fn home(&mut self) {
63         self.x = HOME_X;
64         self.y = HOME_Y;
65     }
66
67     fn forward(&mut self, distance: isize) {
68         match self.heading {
69             North => self.y += distance,
70             South => self.y -= distance,
71             West => self.x += distance,
72             East => self.x -= distance,
73         }
74     }
75
76     fn turn_right(&mut self) {
77         self.heading = match self.heading {
78             North => East,
79             South => West,
80             West => North,
81             East => South,
82         }
83     }

```

**Using descriptions rather than numerical values avoids mathematics.**

**To produce richer output, extends the operations available to your programs**

**Using isize lets us extend this example to implement a Reverse operation without adding a new variant.**

**Uses Noop when we encounter illegal input. To write error messages, we retain the illegal byte.**

**The Artist struct maintains the current state.**

**forward() mutates self within the match expression. This contrasts with turn\_left() and turn\_right(), which mutate self outside of the match expression.**

```

84
85     fn turn_left(&mut self) {
86         self.heading = match self.heading {
87             North => West,
88             South => East,
89             West => South,
90             East => North,
91         }
92     }
93
94     fn wrap(&mut self) {           ←
95         if self.x < 0 {           ←
96             self.x = HOME_X;
97             self.heading = West;
98         } else if self.x > WIDTH {
99             self.x = HOME_X;
100            self.heading = East;
101        }
102
103        if self.y < 0 {
104            self.y = HOME_Y;
105            self.heading = North;
106        } else if self.y > HEIGHT {
107            self.y = HOME_Y;
108            self.heading = South;
109        }
110    }
111 }
112
113 fn parse(input: &str) -> Vec<Operation> {
114     let mut steps = Vec::<Operation>::new();
115     for byte in input.bytes() {
116         let step = match byte {
117             b'0' => Home,
118             b'1'..=b'9' => {
119                 let distance = (byte - 0x30) as isize;   ←
120                 Forward(distance * (HEIGHT / 10))
121             }
122             b'a' | b'b' | b'c' => TurnLeft,
123             b'd' | b'e' | b'f' => TurnRight,
124             _ => Noop(byte),      ←
125         };
126         steps.push(step);
127     }
128     steps
129 }
130
131 fn convert(operations: &Vec<Operation>) -> Vec<Command> {
132     let mut turtle = Artist::new();
133
134     let mut path_data = Vec::<Command>::with_capacity(operations.len());
135     let start_at_home = Command::Move(
136         Position::Absolute, (HOME_X, HOME_Y).into()
137     );
138     path_data.push(start_at_home);

```

**forward()** mutates self within the match expression. This contrasts with **turn\_left()** and **turn\_right()**, which mutate self outside of the match expression.

**wrap()** ensures that the drawing stays within bounds.

In ASCII, numerals start at 0x30 (48). byte - 0x30 converts a u8 value of b'2' to 2. Performing this operation on the whole range of u8 could cause a panic, but we're safe here, thanks to the guarantee provided by our pattern matching.

Although we don't expect any illegal characters, there may be some in the input stream. A Noop operation allows us to decouple parsing from producing output.

```
139
140     for op in operations {
141         match *op {
142             Forward(distance) => turtle.forward(distance),
143             TurnLeft => turtle.turn_left(),
144             TurnRight => turtle.turn_right(),
145             Home => turtle.home(),
146             Noop(byte) => {
147                 eprintln!("warning: illegal byte encountered: {:?}", byte);
148             },
149         };
150
151         let path_segment = Command::Line(
152             Position::Absolute, (turtle.x, turtle.y).into()
153         );
154         path_data.push(path_segment);
155
156         turtle.wrap();
157     }
158     path_data
159 }
160
161 fn generate_svg(path_data: Vec<Command>) -> Document {
162     let background = Rectangle::new()
163         .set("x", 0)
164         .set("y", 0)
165         .set("width", WIDTH)
166         .set("height", HEIGHT)
167         .set("fill", "#ffffff");
168
169     let border = background
170         .clone()
171         .set("fill-opacity", "0.0")
172         .set("stroke", "#cccccc")
173         .set("stroke-width", 3 * STROKE_WIDTH);
174
175     let sketch = Path::new()
176         .set("fill", "none")
177         .set("stroke", "#2f2f2f")
178         .set("stroke-width", STROKE_WIDTH)
179         .set("stroke-opacity", "0.9")
180         .set("d", Data::from(path_data));
181
182     let document = Document::new()
183         .set("viewBox", (0, 0, HEIGHT, WIDTH))
184         .set("height", HEIGHT)
185         .set("width", WIDTH)
186         .set("style", "style=\"outline: 5px solid #800000;\"")
187         .add(background)
188         .add(sketch)
189         .add(border);
190
191     document
192 }
193
```

```

194 fn main() {
195     let args = env::args().collect::<Vec<String>>();
196     let input = args.get(1).unwrap();
197     let default_filename = format!("{}.svg", input);
198     let save_to = args.get(2).unwrap_or(&default_filename);
199
200     let operations = parse(input);
201     let path_data = convert(&operations);
202     let document = generate_svg(path_data);
203     svg::save(save_to, &document).unwrap();
204 }

```

### 10.4.3 Spawning a thread per logical task

Our render-hex project (listing 10.18) also presents several opportunities for parallelism. We'll focus on one of these, the `parse()` function. To begin, adding parallelism is a two-step process:

- 1 Refactor code to use a functional style.
- 2 Use the rayon crate and its `par_iter()` method.

#### USING A FUNCTIONAL PROGRAMMING STYLE

The first step in adding parallelism is to replace our `for`. Rather than `for`, the toolkit for creating a `Vec<T>` with functional programming constructs includes the `map()` and `collect()` methods and higher-order functions, typically created with closures.

To compare the two styles, consider the differences to the `parse()` function from listing 10.18 (in `ch10-render-hex/src/main.rs`), repeated in the following listing, and a more functional style in listing 10.20 (in `ch10-render-hex-functional/src/main.rs`).

**Listing 10.19 Implementing `parse()` with imperative programming constructs**

```

113 fn parse(input: &str) -> Vec<Operation> {
114     let mut steps = Vec::<Operation>::new();
115     for byte in input.bytes() {
116         let step = match byte {
117             b'0' => Home,
118             b'1'..=b'9' => {
119                 let distance = (byte - 0x30) as isize;
120                 Forward(distance * (HEIGHT / 10))
121             }
122             b'a' | b'b' | b'c' => TurnLeft,
123             b'd' | b'e' | b'f' => TurnRight,
124             _ => Noop(byte),
125         };
126         steps.push(step);
127     }
128     steps
129 }

```

**Listing 10.20 Implementing `parse()` with functional programming constructs**

```

99 fn parse(input: &str) -> Vec<Operation> {
100    input.bytes().map(|byte|{
101        match byte {
102            b'0' => Home,
103            b'1'..=b'9' => {
104                let distance = (byte - 0x30) as isize;
105                Forward(distance * (HEIGHT/10))
106            },
107            b'a' | b'b' | b'c' => TurnLeft,
108            b'd' | b'e' | b'f' => TurnRight,
109            _ => Noop(byte),
110        }).collect()
111    }

```

Listing 10.20 is shorter, more declarative, and closer to idiomatic Rust. At a surface level, the primary change is that there is no longer a need to create the temporary variable `steps`. The partnership of `map()` and `collect()` removes the need for that: `map()` applies a function to every element of an iterator, and `collect()` stores the output of an iterator into a `Vec<T>`.

There is also a more fundamental change than eliminating temporary variables in this refactor, though. It has provided more opportunities for the Rust compiler to optimize your code's execution.

In Rust, iterators are an efficient abstraction. Working with their methods directly allows the Rust compiler to create optimal code that takes up minimal memory. As an example, the `map()` method takes a closure and applies it to every element of the iterator. Rust's trick is that `map()` also returns an iterator. This allows many transformations to be chained together. Significantly, although `map()` may appear in multiple places in your source code, Rust often optimizes those function calls away in the compiled binary.

When every step that the program should take is specified, such as when your code uses `for` loops, you restrict the number of places where the compiler can make decisions. Iterators provide an opportunity for you to delegate more work to the compiler. This ability to delegate is what will shortly unlock parallelism.

### USING A PARALLEL ITERATOR

We're going to cheat here and make use of a crate from the Rust community: `rayon`. `rayon` is explicitly designed to add *data parallelism* to your code. Data parallelism applies the same function (or closure!) on different data (such as a `Vec<T>`).

Assuming that you've already worked with the base render-hex project, add `rayon` to your crate's dependencies with cargo by executing `cargo add rayon@1`:

```
$ cargo add rayon@1
```



```
Updating 'https://github.com/rust-lang/crates.io-index' index
Adding rayon v1 to dependencies
```

Ensure that the [dependencies] section of your project’s Cargo.toml matches the following listing. You’ll find the source for this listing in ch10-render-hex-parallel-iterator/Cargo.toml.

#### Listing 10.21 Adding rayon as a dependency to Cargo.toml

```
7 [dependencies]
8 svg = "0.6.0"
9 rayon = "1"
```

At the head of the main.rs file, add rayon and its prelude as listing 10.23 shows. prelude brings several traits into the crate’s scope. This has the effect of providing a `par_bytes()` method on string slices and a `par_iter()` method on byte slices. Those methods enable multiple threads to cooperatively process data. The source for this listing is in ch10-render-hex-parallel-iterator/Cargo.toml.

#### Listing 10.22 Adding rayon to our render-hex project

```
3 use rayon::prelude::*;

100 fn parse(input: &str) -> Vec<Operation> {
101     input
102         .as_bytes()           ← Converts the input string
103         .par_iter()          ← slice into a byte slice
104         .map(|byte| match byte {           Converts the byte slice
105             b'0' => Home,           into a parallel iterator
106             b'1'..=b'9' => {           ...
107                 let distance = (byte - 0x30) as isize;
108                 Forward(distance * (HEIGHT / 10))
109             }
110             b'a' | b'b' | b'c' => TurnLeft,
111             b'd' | b'e' | b'f' => TurnRight,
112             _ => Noop(*byte),      ← The byte variable has the type &u8,
113         })                     whereas the Operation::Noop(u8)
114         .collect()            variant requires a dereferenced value.
115 }
```

Using rayon’s `par_iter()` here is a “cheat mode” available to all Rust programmers, thanks to Rust’s powerful `std::iter::Iterator` trait. rayon’s `par_iter()` is guaranteed to never introduce race conditions. But what should you do if you do not have an iterator?

#### 10.4.4 Using a thread pool and task queue

Sometimes, we don’t have a tidy iterator that we want to apply a function to. Another pattern to consider is the *task queue*. This allows tasks to originate anywhere and for the task processing code to be separated from task creation code. A fleet of worker threads can then pick tasks once these have finished their current one.

There are many approaches to modeling a task queue. We could create a `Vec<Task>` and `Vec<Result>` and share references to these across threads. To prevent each thread from overwriting each other, we would need a data protection strategy.

The most common tool to protect data shared between threads is `Arc<Mutex<T>>`. Fully expanded, that's your value `T` (e.g., `Vec<Task>` or `Vec<Result>` here) protected by a `std::sync::Mutex`, which itself is wrapped within `std::sync::Arc`. A `Mutex` is a mutually-exclusive lock. Mutually exclusive in this context means that no one has special rights. A lock held by any thread prevents all others. Awkwardly, a `Mutex` must itself be protected between threads. So we call in extra support. The `Arc` provides safe multithreaded access to the `Mutex`.

`Mutex` and `Arc` are not unified into a single type to provide programmers with added flexibility. Consider a struct with several fields. You may only need a `Mutex` on a single field, but you could put the `Arc` around the whole struct. This approach provides faster read access to the fields that are not protected by the `Mutex`. A single `Mutex` retains maximum protection for the field that has read-write access. The lock approach, while workable, is cumbersome. Channels offer a simpler alternative.

Channels have two ends: sending and receiving. Programmers don't get access to what is happening inside the channel. But placing data at the sending end means it'll appear at the receiving end at some future stage. Channels can be used as a task queue because multiple items can be sent, even if a receiver is not ready to receive any messages.

Channels are fairly abstract. These hide their internal structure, preferring to delegate access to two helper objects. One can `send()`; the other can `recv()` (`receive`). Importantly, we don't get access to *how* channels transmit any information sent through the channel.

**NOTE** By convention, from radio and telegraph operators, the `Sender` is called `tx` (shorthand for *transmission*) and the `Receiver` is called `rx`.

#### ONE-WAY COMMUNICATION

This section uses the channels implementation from the crossbeam crate rather than from the `std::sync::mpsc` module within the Rust standard library. Both APIs provide the same API, but crossbeam provides greater functionality and flexibility. We'll spend a little time explaining how to use channels. If you would prefer to see them used as a task queue, feel free to skip ahead.

The standard library provides a channels implementation, but we'll make use of the third-party crate, crossbeam. It provides slightly more features. For example, it includes both *bounded queues* and *unbounded queues*. A bounded queue applies *back pressure* under contention, preventing the consumer from becoming overloaded. Bounded queues (of fixed-width types) have deterministic maximum memory usage. These do have one negative characteristic, though. They force queue producers to wait until a space is available. This can make unbounded queues unsuitable for asynchronous messages, which cannot tolerate waiting.

The channels-intro project (listings 10.23 and 10.24) provides a quick example. Here is a console session that demonstrates running the channels-intro project from its public source code repository and providing its expected output:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
$ cd ch10/ch10-channels-intro
$ cargo run
...
Compiling ch10-channels-intro v0.1.0 (/ch10/ch10-channels-intro)
Finished dev [unoptimized + debuginfo] target(s) in 0.34s
Running `target/debug/ch10-channels-intro`
Ok (42)
```

To create the project by hand, follow these instructions:

- 1** Enter these commands from the command-line:

```
$ cargo new channels-intro
$ cargo install cargo-edit
$ cd channels-intro
$ cargo add crossbeam@0.7
```

- 2** Check that the project's Cargo.toml file matches listing 10.23.
- 3** Replace the contents of src/main.rs with listing 10.24.

The following two listings make up the project. Listing 10.23 shows its Cargo.toml file. Listing 10.24 demonstrates creating a channel for i32 messages from a worker thread.

#### Listing 10.23 Cargo.toml metadata for channels-intro

```
[package]
name = "channels-intro"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
crossbeam = "0.7"
```

#### Listing 10.24 Creating a channel that receives i32 messages

```
1 #![macro_use]           ← Provides the select!
2 extern crate crossbeam;
3
4 use std::thread;
5 use crossbeam::channel::unbounded;
6
7
8 fn main() {
```

```

9   let (tx, rx) = unbounded();
10
11  thread::spawn(move || {
12      tx.send(42)
13      .unwrap();
14  });
15
16  select!{ ← Provides the select!
17      recv(rx) -> msg => println!("{}:{}", msg), ← recv(rx) is syntax
18  } defined by the macro.
19 }

```

Some notes about the channels-intro project:

- *Creating a channel with crossbeam involves calling a function that returns Sender<T> and Receiver<T>.* Within listing 10.24, the compiler infers the type parameter. tx is given the type Sender<i32> and rx is given the type Receiver<i32>.
- *The select! macro takes its name from other messaging systems like the POSIX sockets API.* It allows the main thread to block and wait for a message.
- *Macros can define their own syntax rules.* That is why the select! macro uses syntax (recv(rx) ->) that is not legal Rust.

#### WHAT CAN BE SENT THROUGH A CHANNEL?

Mentally, you might be thinking of a channel like you would envision a network protocol. Over the wire, however, you only have the type [u8] available to you. That byte stream needs to be parsed and validated before its contents can be interpreted.

Channels are richer than simply streaming bytes ([u8]). A byte stream is opaque and requires parsing to have structure extracted out of it. Channels offer you the full power of Rust's type system. I recommend using an enum for messages as it offers exhaustiveness testing for robustness and has a compact internal representation.

#### TWO-WAY COMMUNICATION

Bi-directional (duplex) communication is awkward to model with a single channel. An approach that's simpler to work with is to create two sets of senders and receivers, one for each direction.

The channels-complex project provides an example of this two channel strategy. channels-complex is implemented in listings 10.25 and 10.26. These are available in ch10/ch10-channels-complex/Cargo.toml and ch10/ch10-channels-complex/src/main.rs, respectively.

When executed, channels-complex produces three lines of output. Here is a session that demonstrates running the project from its public source code repository:

```

$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...

$ cd ch10/ch10-channels-complex

$ cargo run
...

```

```
Compiling ch10-channels-intro v0.1.0 (/ch10/ch10-channels-complex)
  Finished dev [unoptimized + debuginfo] target(s) in 0.34s
    Running `target/debug/ch10-channels-complex`~
Ok (Pong)
Ok (Pong)
Ok (Pong)
```

Some learners prefer to type everything out by hand. Here are the instructions to follow if you are one of those people:

- 1 Enter these commands from the command-line:

```
$ cargo new channels-intro
$ cargo install cargo-edit
$ cd channels-intro
$ cargo add crossbeam@0.7
```

- 2 Check that the project's Cargo.toml matches listing 10.25.
- 3 Replace src/main.rs with the contents of listing 10.26.

#### Listing 10.25 Project metadata for channels-complex

```
[package]
name = "channels-complex"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
crossbeam = "0.7"
```

#### Listing 10.26 Sending messages to and from a spawned thread

```
1 #[macro_use]
2 extern crate crossbeam;
3
4 use crossbeam::channel::unbounded;
5 use std::thread;
6
7 use crate::ConnectivityCheck::*;
8
9 #[derive(Debug)]
10 enum ConnectivityCheck {
11     Ping,
12     Pong,
13     Pang,
14 }
```

Defining a bespoke message type simplifies interpreting messages later.

```
15
16 fn main() {
17     let n_messages = 3;
18     let (requests_tx, requests_rx) = unbounded();
19     let (responses_tx, responses_rx) = unbounded();
```

```

21  thread::spawn(move || loop {
22      match requests_rx.recv().unwrap() {
23          Pong => eprintln!("unexpected pong response"),
24          Ping => responses_tx.send(Pong).unwrap(),
25          Pang => return,
26      }
27  });
28
29  for _ in 0..n_messages {
30      requests_tx.send(Ping).unwrap();
31  }
32  requests_tx.send(Pang).unwrap();
33
34  for _ in 0..n_messages {
35      select! {
36          recv(responses_rx) -> msg => println!("{}: {:?}", msg),
37      }
38  }
39 }
```

The Pang message indicates the thread should shut down.

Because all control flow is an expression, Rust allows the loop keyword here.

### IMPLEMENTING A TASK QUEUE

After spending some time discussing channels, it's time to apply these to the problem first introduced in listing 10.18. You'll notice that the code that follows shortly in listing 10.28 is quite a bit more complex than the parallel iterator approach seen in listing 10.24.

The following listing displays the metadata for the channel-based task queue implementation of render-hex. The source for this listing is in ch10/ch10-render-hex-threadpool/Cargo.toml.

#### **Listing 10.27 The channel-based task queue metadata for render-hex**

```

[package]
name = "render-hex"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
svg = "0.6"
crossbeam = "0.7" #
```

The crossbeam crate is a new dependency for the project.

The following listing focuses on the parse() function. The rest of the code is the same as listing 10.18. You'll find the code for the following listing in ch10/ch10-render-hex-threadpool/src/main.rs.

#### **Listing 10.28 Partial code for the channel-based task queue for render-hex**

```

1 use std::thread;
2 use std::env;
3
4 use crossbeam::channel::{unbounded};
```

```

99 enum Work {
100     Task((usize, u8)),
101     Finished,
102 }
103
104 fn parse_byte(byte: u8) -> Operation {
105     match byte {
106         b'0' => Home,
107         b'1'..=b'9' => {
108             let distance = (byte - 0x30) as isize;
109             Forward(distance * (HEIGHT/10))
110         },
111         b'a' | b'b' | b'c' => TurnLeft,
112         b'd' | b'e' | b'f' => TurnRight,
113         _ => Noop(byte),
114     }
115 }
116
117 fn parse(input: &str) -> Vec<Operation> {
118     let n_threads = 2;
119     let (todo_tx, todo_rx) = unbounded();
120     let (results_tx, results_rx) = unbounded();
121     let mut n_bytes = 0;
122     for (i, byte) in input.bytes().enumerate() {
123         todo_tx.send(Work::Task((i, byte))).unwrap(),
124         n_bytes += 1;
125     }
126
127     for _ in 0..n_threads {
128         todo_tx.send(Work::Finished).unwrap();
129     }
130
131     for _ in 0..n_threads {
132         let todo = todo_rx.clone();
133         let results = results_tx.clone(); | When cloned, channels can
134         thread::spawn(move || { | be shared between threads.
135             loop {
136                 let task = todo.recv();
137                 let result = match task {
138                     Err(_) => break,
139                     Ok(Work::Finished) => break,
140                     Ok(Work::Task((i, byte))) => (i, parse_byte(byte)),
141                 };
142                 results.send(result).unwrap();
143             }
144         });
145     }
146
147     let mut ops = vec![Noop(0); n_bytes];
148     for _ in 0..n_bytes {
149         let (i, op) = results_rx.recv().unwrap();
150         ops[i] = op;
151     }
152     ops
153 }

```

**Creates one channel for tasks to be completed**

**Creates a type for the messages we send through the channels**

**The usize field of this tuple indicates the position of the processed byte. This is necessary because these can be returned out of order.**

**Gives worker threads a marker message to indicate that it's time to shut down**

**Extracts the functionality that workers will need to carry out to simplify the logic**

**Creates one channel for the decoded instructions to be returned to**

**Fills the task queue with work**

**Keeps track of how many tasks there are to do**

**Sends each thread a signal that it's time to shut down**


**Because results can be returned in arbitrary order, initializes a complete `Vec<Command>` that will be overwritten by our incoming results. We use a vector rather than an array because that's what's used by the type signature, and we don't want to refactor the whole program to suit this new implementation.**

When independent threads are introduced, the order in which tasks are completed becomes non-deterministic. Listing 10.28 includes some additional complexity to handle this.

Previously, we created an empty `Vec<Command>` for the commands that we interpreted from our input. Once parsed, `main()` repeatedly added elements via the vector's `push()` method. Now, at line 147, we fully initialize the vector. Its contents don't matter. It will all be overwritten. Even so, I've chosen to use `Command::Noop` to ensure that a mistake won't result in a corrupt SVG file.

## 10.5 Concurrency and task virtualization

This section explains the difference between models of concurrency. Figure 10.5 displays some of the trade-offs.



**Figure 10.5** Trade-offs relating to different forms of task isolation in computing. In general terms, increasing the isolation level increases the overhead.

The primary benefit of more costly forms of task virtualization is isolation. What is meant by the term *isolation*?

Isolated tasks cannot interfere with each other. Interference comes in many forms. Examples include corrupting memory, saturating the network, and congestion when saving to disk. If a thread is blocked while waiting for the console to print output to the screen, none of the coroutines acting in that thread are able to progress.

Isolated tasks cannot access each other's data without permission. Independent threads in the same process share a memory address space, and all threads have equal access to data within that space. Processes, however, are prohibited from inspecting each other's memory.

Isolated tasks cannot cause another task to crash. A failure in one task should not cascade into other systems. If a process induces a kernel panic, all processes are shut down. By conducting work in virtual machines, tasks can proceed even when other tasks are unstable.

Isolation is a continuum. Complete isolation is impractical. It implies that input and output is impossible. Moreover, isolation is often implemented in software. Running extra software implies taking on extra runtime overhead.

### A small glossary of terms relating to concurrency

This subfield is filled with jargon. Here is a brief introduction to some important terms and how we use them:

- **Program**—A program, or application, is a brand name. It's a name that we use to refer to a software package. When we execute a program, the OS creates a process.
- **Executable**—A file that can be loaded into memory and then run. Running an executable means creating a process and a thread for it, then changing the CPU's instruction pointer to the first instruction of the executable.
- **Task**—This chapter uses the term task in an abstract sense. Its meaning shifts as the level of abstraction changes:
  - a When discussing processes, a task is one of the process's threads.
  - b When referring to a thread, a task might be a function call.
  - c When referring to an OS, a task might be a running program, which might be comprised of multiple processes.
- **Process**—Running programs execute as processes. A process has its own virtual address space, at least one thread, and lots of bookkeeping managed by the OS. File descriptors, environment variables, and scheduling priorities are managed per process. A process has a virtual address space, executable code, open handles to system objects, a security context, a unique process identifier, environment variables, a priority class, minimum and maximum working set sizes, and at least one thread of execution.

Each process is started with a single thread, often called the *primary thread*, but can create additional threads from any of its threads. Running programs begin their life as a single process, but it isn't uncommon to spawn subprocesses to do the work.

- **Thread**—The thread metaphor is used to hint that multiple threads can work together as a whole.
- **Thread of execution**—A sequence of CPU instructions that appear in serial. Multiple threads can run concurrently, but instructions within the sequence are intended to be executed one after another.
- **Coroutine**—Also known as *fibre*, *green thread*, and *lightweight thread*, a coroutine indicates tasks that switch within a thread. Switching between tasks becomes the responsibility of the program itself, rather than the OS. Two theoretical concepts are important to distinguish:
  - a Concurrency, which is multiple tasks of any level of abstraction running at the same time
  - b Parallelism, which is multiple threads executing on multiple CPUs at the same time

**(continued)**

Outside of the fundamental terminology, there are also interrelated terms that appear frequently: *asynchronous programming* and *non-blocking I/O*. Many operating systems provide non-blocking I/O facilities, where data from multiple sockets is batched into queues and periodically polled as a group. Here are the definitions for these:

- **Non-blocking I/O**—Normally a thread is unscheduled when it asks for data from I/O devices like the network. The thread is marked as *blocked*, while it waits for data to arrive.

When programming with non-blocking I/O, the thread can continue executing even while it waits for data. But there is a contradiction. How can a thread continue to execute if it doesn't have any input data to process? The answer lies in asynchronous programming.

- **Asynchronous programming**—Asynchronous programming describes programming for cases where the control flow is not predetermined. Instead, events outside the control of the program itself impact the sequence of what is executed. Those events are typically related to I/O, such as a device driver signalling that it is ready, or are related to functions returning in another thread.

The asynchronous programming model is typically more complicated for the developer, but results in a faster runtime for I/O-heavy workloads. Speed increases because there are fewer system calls. This implies fewer context switches between the user space and the kernel space.

### 10.5.1 Threads

A *thread* is the lowest level of isolation that an OS understands. The OS can schedule threads. Smaller forms of concurrency are invisible to the OS. You may have encountered terms such as coroutines, fibers, and green threads.

Switching between tasks here is managed by the process itself. The OS is ignorant of the fact that a program is processing multiple tasks. For threads and other forms of concurrency, context switching is required.

### 10.5.2 What is a context switch?

Switching between tasks at the same level of virtualization is known as a *context switch*. For threads to switch, CPU registers need to be cleared, CPU caches might need to be flushed, and variables within the OS need to be reset. As isolation increases, so does the cost of the context switch.

CPUs can only execute instructions in serial. To do more than one task, a computer, for example, needs to be able to press the Save Game button, switch to a new task, and resume at that task's saved spot. The CPU is *save scum*.

Why is the CPU constantly switching tasks? Because it has so much time available. Programs often need to access data from memory, disk, or the network. Because waiting for data is incredibly slow, there's often sufficient time to do something else in the meantime.

### 10.5.3 Processes

Threads exist within a process. The distinguishing characteristic of a process is that its memory is independent from other processes. The OS, in conjunction with the CPU, protects a process's memory from all others.

To share data between processes, Rust channels and data protected by `Arc<Mutex<_>>` won't suffice. You need some support from the OS. For this, reusing network sockets is common. Most operating systems provide specialized forms of interprocess communication (IPC), which are faster, while being less portable.

### 10.5.4 WebAssembly

WebAssembly (Wasm) is interesting because it is an attempt at isolating tasks within the process boundary itself. It's impossible for tasks running inside a Wasm module to access memory available to other tasks. Originating in web browsers, Wasm treats all code as potentially hostile. If you use third-party dependencies, it's likely that you haven't verified the behavior of all of the code that your process executes.

In a sense, Wasm modules are given access to address spaces within your process's address space. Wasm address spaces are called *linear memory*. Runtime interprets any request for data within linear memory and makes its own request to the actual virtual memory. Code within the Wasm module is unaware of any memory addresses that the process has access to.

### 10.5.5 Containers

Containers are extensions to processes with further isolation provided by the OS. Processes share the same filesystem, whereas containers have a filesystem created for them. The same is true for other resources, such as the network. Rather than address space, the term used for protections covering these other resources is *namespaces*.

### 10.5.6 Why use an operating system (OS) at all?

It's possible to run an application as its own OS. Chapter 11 provides one implementation. The general term for an application that runs without an OS is to describe it as *freestanding*—freestanding in the sense that it does not require the support of an OS. Freestanding binaries are used by embedded software developers when there is no OS to rely on.

Using freestanding binaries can involve significant limitations, though. Without an OS, applications no longer have virtual memory or multithreading. All of those concerns become your application's concerns. To reach a middle ground, it is possible to compile a *unikernel*. A unikernel is a minimal OS paired with a single application. The compilation process strips out everything from the OS that isn't used by the application that's being deployed.

## Summary

- Closures and functions both feel like they should be the same type, but they aren't identical. If you want to create a function that accepts either a function or a closure as an argument, then make use of the `std::ops::Fn` family of traits.
- A functional style that makes heavy use of higher-order programming and iterators is idiomatic Rust. This approach tends to work better with third-party libraries because `std::iter::Iterator` is such a common trait to support.
- Threads have less impact than you have probably heard, but spawning threads without bounds can cause significant problems.
- To create a byte (`u8`) from a literal, use single quotes (e.g., `b'a'`). Double quotes (e.g., `b"a"`) creates a byte slice (`[u8]`) of length 1.
- To increase the convenience of enums, it can be handy to bring their variants into local scope with `use crate:::`.
- Isolation is provided as a spectrum. In general, as isolation between software components increases, performance decreases.

# 11

## Kernel

### This chapter covers

- Writing and compiling your own OS kernel
- Gaining a deeper understanding of the Rust compiler's capabilities
- Extending cargo with custom subcommands

Let's build an operating system (OS). By the end of the chapter, you'll be running your own OS (or, at least, a minimal subset of one). Not only that, but you will have compiled your own bootloader, your own kernel, and the Rust language directly for that new target (which doesn't exist yet).

This chapter covers many features of Rust that are important for programming without an OS. Accordingly, the chapter is important for programmers who intend to work with Rust on embedded devices.

### 11.1 A fledgling operating system (*FledgeOS*)

In this section, we'll implement an OS kernel. The OS kernel performs several important roles, such as interacting with hardware and memory management, and coordinating work. Typically, work is coordinated through processes and threads. We won't be able to cover much of that in this chapter, but we will get off the ground. We'll fledge, so let's call the system we're building *FledgeOS*.

### **11.1.1 Setting up a development environment for developing an OS kernel**

Creating an executable for an OS that doesn't exist yet is a complicated process. For instance, we need to compile the core Rust language for the OS from your current one. But your current environment only understands your current environment. Let's extend that. We need several tools to help us out. Here are several components that you will need to install and/or configure before creating FledgeOS:

- **QEMU**—A virtualization technology. Formally part of a class of software called “*virtual machine monitors*,” it runs operating systems for any machine on any of its supported hosted architectures. Visit <https://www.qemu.org/> for installation instructions.
- **The bootimage crate and some supporting tools**—The bootimage crate does the heavy lifting for our project. Thankfully, installing it and the tools needed to work with it effectively is a lightweight process. To do that, enter the following commands from the command line:

```
$ cargo install cargo-binutils
...
Installed package `cargo-binutils v0.3.3` (executables `cargo-cov`,
`cargo-nm`, `cargo-objcopy`, `cargo-objdump`, `cargo-profdata`,
`cargo-readobj`, `cargo-size`, `cargo-strip`, `rust-ar`, `rust-cov`,
`rust-ld`, `rust-lld`, `rust-nm`, `rust-objcopy`, `rust-objdump`,
`rust-profdata`, `rust-readobj`, `rust-size`, `rust-strip`)

$ cargo install bootimage
...
Installed package `bootimage v0.10.3` (executables `bootimage`,
`cargo-bootimage`)

$ rustup toolchain install nightly
info: syncing channel updates for 'nightly-x86_64-unknown-linux-gnu'
...

$ rustup default nightly
info: using existing install for 'nightly-x86_64-unknown-linux-gnu'
info: default toolchain set to 'nightly-x86_64-unknown-linux-gnu'
...

$ rustup component add rust-src
info: downloading component 'rust-src'
...
$ rustup component add llvm-tools-preview
info: downloading component 'llvm-tools-preview'
```

Over time, this may become the llvm-tools component.

Each of these tools performs an important role:

- **The cargo-binutils crate**—Enables cargo to directly manipulate executable files via subcommands using utilities built with Rust and installed by cargo. Using

cargo-binutils rather than installing binutils via another route prevents any potential version mismatches.

- *The bootimage crate*—Enables cargo to build a *boot image*, an executable that can be booted directly on hardware.
- *The nightly toolchain*—Installing the nightly version of the Rust compiler unlocks features that have not yet been marked as stable, and thus constrained by Rust’s backward-compatibility guarantees. Some of the compiler internals that we will be accessing in this chapter are unlikely to ever be stabilized.

We set nightly to be our default toolchain to simplify the build steps for projects in this chapter. To revert the change, use the command `rustup default stable`.

- *The rust-src component*—Downloads the source code for the Rust programming language. This enables Rust to compile a compiler for the new OS.
- *The llvm-tools-preview component*—Installs extensions for the LLVM compiler, which makes up part of the Rust compiler.

## 11.12 Verifying the development environment

To prevent significant frustration later on, it can be useful to double-check that everything is installed correctly. To do that, here’s a checklist:

- *QEMU*—The `qemu-system-x86_64` utility should be on your PATH. You can check that this is the case by providing the `--version` flag:

```
$ qemu-system-x86_64 --version
QEMU emulator version 4.2.1 (Debian 1:4.2.1-3ubuntu6.14)
Copyright (c) 2003-2019 Fabrice Bellard and the QEMU Project developers
```

- *The cargo-binutils crate*—As indicated by the output of `cargo install cargo-binutils`, several executables were installed on your system. Executing any of those with the `--help` flag should indicate that all of these are available. For example, to check that `rust-strip` is installed, use this command:

```
$ rust-strip --help
OVERVIEW: llvm-strip tool

USAGE: llvm-strip [options] inputs..
...
```

- *The bootimage crate*—Use the following command to check that all of the pieces are wired together:

```
$ cargo bootimage --help
Creates a bootable disk image from a Rust kernel
...
```

- *The llvm-tools-preview toolchain component*—The LLVM tools are a set of auxiliary utilities for working with LLVM. On Linux and macOS, you can use the following commands to check that these are accessible to rustc:

```
$ export SYSROOT=$(rustc --print sysroot)

$ find "$SYSROOT" -type f -name 'llvm-*' -printf '%f\n' | sort
llvm-ar
llvm-as
llvm-cov
llvm-dis
llvm-nm
llvm-objcopy
llvm-objdump
llvm-profdata
llvm-readobj
llvm-size
llvm-strip
```

On MS Windows, the following commands produce a similar result:

```
C:\> rustc --print sysroot
C:\> cd <sysroot>
C:\> dir llvm*.exe /s /b
```



Replace <sysroot> with the output of the previous command

Great, the environment has been set up. If you encounter any problems, try reinstalling the components from scratch.

## 11.2 Fledgeos-0: Getting something working

FledgeOS requires some patience to fully comprehend. Although the code may be short, it includes many concepts that are probably novel because they are not exposed to programmers who make use of an OS. Before getting started with the code, let's see FledgeOS fly.

### 11.2.1 First boot

FledgeOS is not the world's most powerful operating system. Truthfully, it doesn't look like much at all. At least it's a graphical environment. As you can see from figure 11.1, it creates a pale blue box in the top-left corner of the screen.

To get fledgeos-0 up and running, execute these commands from a command-line prompt:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
...

$ cd rust-in-action/ch11/ch11-fledgeos-0
$ cargo +nightly run
```



Adding +nightly ensures that the nightly compiler is used.

Running: qemu-system-x86\_64 -drive  
format=raw,file=target/fledge/debug/bootimage-fledgeos.bin




Figure 11.1 Expected output from running fledgeos-0 (listings 11.1–11.4)

Don't worry about *how* the block at the top left changed color. We'll discuss the retro-computing details for that shortly. For now, success is being able to compile your own version of Rust, an OS kernel using that Rust, a bootloader that puts your kernel in the right place, and having these all work together.

Getting this far is a big achievement. As mentioned earlier, creating a program that targets an OS kernel that doesn't exist yet is complicated. Several steps are required:

- 1 Create a machine-readable definition of the conventions that the OS uses, such as the intended CPU architecture. This is the *target platform*, also known as a *compiler target* or simply *target*. You have seen targets before. Try executing `rustup target list` for a list that you can compile Rust to.
- 2 Compile Rust for the target definition to create the new target. We'll suffice with a subset of Rust called *core* that excludes the standard library (crates under `std`).
- 3 Compile the OS kernel for the new target using the “new” Rust.
- 4 Compile a bootloader that can load the new kernel.
- 5 Execute the bootloader in a virtual environment, which, in turn, runs the kernel.

Thankfully, the `bootimage` crate does all of this for us. With all of that fully automated, we're able to focus on the interesting pieces.

## 11.2.2 Compilation instructions

To make use of the publicly available source code, follow the steps in section 11.1.3. That is, execute these commands from a command prompt:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
Cloning into 'rust-in-action'...
...
$ cd rust-in-action/ch11/ch11-fledgeos-0
```

To create the project by hand, here is the recommended process:

- 1 From a command-line prompt, execute these commands:

```
$ cargo new fledgeos-0
$ cargo install cargo-edit
$ cd fledgeos-0
$ mkdir .cargo
$ cargo add bootloader@0.9
$ cargo add x86_64@0.13
```

- 2 Add the following snippet to the end of project's Cargo.toml file. Compare the result with listing 11.1, which can be downloaded from ch11/ch11-fledgeos-0/Cargo.toml:

```
[package.metadata.bootimage]
build-command = ["build"]

run-command = [
    "qemu-system-x86_64", "-drive", "format=raw,file={}"]
]
```

- 3 Create a new fledge.json file at the root of the project with the contents from listing 11.2. You can download this from the listing in ch11/ch11-fledgeos-0/fledge.json.
- 4 Create a new .cargo/config.toml file from listing 11.3, which is available in ch11/ch11-fledgeos-0/.cargo/config.toml.
- 5 Replace the contents of src/main with listing 11.4, which is available in ch11/ch11-fledgeos-0/src/main.rs.

## 11.2.3 Source code listings

The source code for the FledgeOS projects (code/ch11/ch11-fledgeos-\*) uses a slightly different structure than most cargo projects. Here is a view of their layout, using fledgeos-0 as a representative example:

```
fledgeos-0
├── Cargo.toml      ↛ See listing 11.1.
├── fledge.json     ↛ See listing 11.2.
└── .cargo
    └── config.toml ↛ See listing 11.3.
```

```

└── src
    └── main.rs

```

↳ See listing 11.4.

The projects include two extra files:

- *The project root directory contains a fledge.json file.* This is the definition of the compiler target that bootimage and friends will be building.
- *The .cargo/config.toml file provides extra configuration parameters.* These tell cargo that it needs to compile the std::core module itself for this project, rather than relying on it being preinstalled.

The following listing provides the project's Cargo.toml file. It is available in ch11/ch11-fledgeos-0/Cargo.toml.

#### Listing 11.1 Project metadata for fledgeos-0

```

[package]
name = "fledgeos"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
bootloader = "0.9"
x86_64 = "0.13"

[package.metadata.bootimage]
build-command = ["build"]
run-command = [
    "qemu-system-x86_64", "-drive", "format=raw,file={}"]

```

↳ Updates cargo run to invoke a QEMU session. The path to the OS image created during the build replaces the curly braces ({}).

The project's Cargo.toml file is slightly unique. It includes a new table, [package.metadata.bootimage], which contains a few directives that are probably confusing. This table provides instructions to the bootimage crate, which is a dependency of bootloader:

- **bootimage**—Creates a bootable disk image from a Rust kernel
- **build-command**—Instructs bootimage to use the cargo build command rather than cargo xbuild for cross-compiling
- **run\_command**—Replaces the default behavior of cargo run to use QEMU rather than invoking the executable directly

**TIP** See the documentation at <https://github.com/rust-osdev/bootimage/> for more information about how to configure bootimage.

The following listing shows our kernel target's definition. It is available from ch11/ch11-fledgeos-0/fledge.json.

### Listing 11.2 Kernel definition for FledgeOS

```
{
  "llvm-target": "x86_64-unknown-none",
  "data-layout": "e-m:e-i64:64-f80:128-n8:16:32:64-S128",
  "arch": "x86_64",
  "target-endian": "little",
  "target-pointer-width": "64",
  "target-c-int-width": "32",
  "os": "none",
  "linker": "rust-lld",
  "linker-flavor": "ld.lld",
  "executables": true,
  "features": "-mmx,-sse,+soft-float",
  "disable-redzone": true,
  "panic-strategy": "abort"
}
```

Among other things, the target kernel's definition specifies that it is a 64-bit OS built for x86-64 CPUs. This JSON specification is understood by the Rust compiler.

**TIP** Learn more about custom targets from the “Custom Targets” section of the rustc book at <https://doc.rust-lang.org/stable/rustc/targets/custom.html>.

The following listing, available from ch11/ch11-fledgeos-0/.cargo/config.toml, provides an additional configuration for building FledgeOS. We need to instruct cargo to compile the Rust language for the compiler target that we defined in the previous listing.

### Listing 11.3 Extra build-time configuration for cargo

```
[build]
target = "fledge.json"

[unstable]
build-std = ["core", "compiler_builtins"]
build-std-features = ["compiler-builtins-mem"]

[target.'cfg(target_os = "none")']
runner = "bootimage runner"
```

We are finally ready to see the kernel's source code. The next listing, available from ch11/ch11-fledgeos-0/src/main.rs, sets up the boot process, and then writes the value 0x30 to a predefined memory address. You'll read about how this works in section 11.2.5.

### Listing 11.4 Creating an OS kernel that paints a block of color

```
1 #![no_std]           | Prepares the program for
2 #![no_main]          | running without an OS
3 #![feature(core_intrinsics)]    | ← Unlocks the LLVM compiler's
4                                     | intrinsic functions
5 use core::intrinsics;
```

```

6 use core::panic::PanicInfo;           ← Allows the panic handler
7                                         to inspect where the
8 #[panic_handler]                      ←
9 #[no_mangle]                         ←
10 pub fn panic(_info: &PanicInfo) -> ! { ←
11     intrinsics::abort();              ← Crashes the
12 }                                     ← program
13
14 #[no_mangle]
15 pub extern "C" fn _start() -> ! {
16     let framebuffer = 0xb8000 as *mut u8;
17
18     unsafe {                         ← Increments the
19         framebuffer                 ← pointer's address
20             .offset(1)               ← by 1 to 0xb8001
21             .write_volatile(0x30);   ←
22     }                                 ← Sets the background
23
24     loop {}                         ← to cyan
25 }

```

Listing 11.4 looks very different from the Rust projects that we have seen so far. Here are some of the changes to ordinary programs that are intended to be executed alongside an OS:

- *The central FledgeOS functions never return.* There is no place to return to. There are no other running programs. To indicate this, our functions' return type is the Never type (!).
- *If the program crashes, the whole computer crashes.* The only thing that our program can do when an error occurs is terminate. We indicate this by relying on LLVM's `abort()` function. This is explained in more detail in section 11.2.4.
- *We must disable the standard library with `! [no_std]`.* As our application cannot rely on an OS to provide dynamic memory allocation, it's important to avoid any code that dynamically allocates memory. The `! [no_std]` annotation excludes the Rust standard library from our crate. This has the side effect of preventing many types, such as `Vec<T>`, from being available to our program.
- *We need to unlock the unstable core\_intrinsics API with the `#![core_intrinsics]` attribute.* Part of the Rust compiler is provided by LLVM, the compiler produced by the LLVM project. LLVM exposes parts of its internals to Rust, which are known as *intrinsic functions*. As LLVM's internals are not subject to Rust's stability guarantees, there is always a risk that what is offered to Rust will change. Therefore, this implies that we must use the nightly compiler toolchain and explicitly opt into the unstable API in our program.
- *We need to disable the Rust symbol-naming conventions with the `#[no_mangle]` attribute.* Symbol names are strings within the compiled binary. For multiple libraries to coexist at runtime, it's important that these names do not collide. Ordinarily, Rust avoids this by creating symbols via a process called *name mangling*. We need

to disable this from occurring in our program; otherwise, the boot process may fail.

- *We should opt into C's calling conventions with `extern "C"`.* An operating system's calling convention relates to the way function arguments are laid out in memory, among other details. Rust does not define its calling convention. By annotating the `_start()` function with `extern "C"`, we instruct Rust to use the C language's calling conventions. Without this, the boot process may fail.
- *Writing directly to memory changes the display.* Traditionally, operating systems used a simplistic model for adjusting the screen's output. A predefined block of memory, known as the *frame buffer*, was monitored by the video hardware. When the frame buffer changed, the display changed to match. One standard, used by our bootloader, is VGA (Video Graphics Array). The bootloader sets up address 0xb8000 as the start of the frame buffer. Changes to its memory are reflected onscreen. This is explained in detail in section 11.2.5.
- *We should disable the inclusion of a `main()` function with the `#![no_main]` attribute.* The `main()` function is actually quite special because its arguments are provided by a function that is ordinarily included by the compiler (`_start()`), and its return values are interpreted before the program exits. The behavior of `main()` is part of the Rust runtime. Read section 11.2.6 for more details.

### Where to go to learn more about OS development

The cargo bootimage command takes care of lots of nuisances and irritation. It provides a simple interface—a single command—to a complicated process. But if you're a tinkerer, you might like to know what's happening beneath the surface. In that case, you should search Philipp Oppermann's blog, "Writing an OS in Rust," at <https://os.phil-opp.com/> and look into the small ecosystem of tools that has emerged from it at <https://github.com/rust-osdev/>.

Now that our first kernel is live, let's learn a little bit about how it works. First, let's look at panic handling.

#### 11.2.4 Panic handling

Rust won't allow you to compile a program that doesn't have a mechanism to deal with panics. Normally, it inserts panic handling itself. This is one of the actions of the Rust runtime, but we started our code with `#![no_std]`. Avoiding the standard library is useful in that it greatly simplifies compilation, but manual panic handling is one of its costs. The following listing is an excerpt from listing 11.4. It introduces our panic-handling functionality.

#### Listing 11.5 Focusing on panic handling for FledgeOS

```
1 #![no_std]
2 #![no_main]
```

```

3 #![feature(core_intrinsics)]
4
5 use core::intrinsics;
6 use core::panic::PanicInfo;
7
8 #[panic_handler]
9 #[no_mangle]
10 pub fn panic(_info: &PanicInfo) -> ! {
11     unsafe {
12         intrinsics::abort();
13     }
14 }
```

There is an alternative to `intrinsics::abort()`. We could use an infinite loop as the panic handler, shown in the following listing. The disadvantage of that approach is that any errors in the program trigger the CPU core to run at 100% until it is shut down manually.

#### **Listing 11.6 Using an infinite loop as a panic handler**

```

#[panic_handler]
#[no_mangle]
pub fn panic(_info: &PanicInfo) -> ! {
    loop {}
}
```

The `PanicInfo` struct provides information about where the panic originates. This information includes the filename and line number of the source code. It'll come in handy when we implement proper panic handling.

### **11.2.5 Writing to the screen with VGA-compatible text mode**

The bootloader sets some magic bytes with raw assembly code in boot mode. At startup, the bytes are interpreted by the hardware. The hardware switches its display to an 80x25 grid. It also sets up a fixed-memory buffer that is interpreted by the hardware for printing to the screen.

#### **VGA-compatible text mode in 20 seconds**

Normally, the display is split into an 80x25 grid of cells. Each cell is represented in memory by 2 bytes. In Rust-like syntax, those bytes include several fields. The following code snippet shows the fields:

```

struct VGACell {
    is_blinking: u1,
    background_color: u3,
    is_bright: u1,
    character_color: u3,
    character: u8,      ←
```

These four fields  
occupy a single  
byte in memory.

Available characters are drawn from  
the code page 437 encoding, which is  
(approximately) an extension of ASCII.

**(continued)**

VGA text mode has a 16-color palette, where 3 bits make up the main 8 colors. Foreground colors also have an additional bright variant, shown in the following:

```
#[repr(u8)]
enum Color {
    Black = 0,      White = 8,
    Blue = 1,       BrightBlue = 9,
    Green = 2,      BrightGreen = 10,
    Cyan = 3,       BrightCyan = 11,
    Red = 4,        BrightRed = 12,
    Magenta = 5,    BrightMagenta = 13,
    Brown = 6,      Yellow = 14,
    Gray = 7,       DarkGray = 15,
}
```

This initialization at boot time makes it easy to display things onscreen. Each of the points in the 80x25 grid are mapped to locations in memory. This area of memory is called the *frame buffer*.

Our bootloader designates 0xb8000 as the start of a 4,000 byte frame buffer. To actually set the value, our code uses two new methods, `offset()` and `write_volatile()`, that you haven't encountered before. The following listing, an excerpt from listing 11.4, shows how these are used.

**Listing 11.7 Focusing on modifying the VGA frame buffer**

```
18 let mut framebuffer = 0xb8000 as *mut u8;
19 unsafe {
20     framebuffer
21         .offset(1)
22         .write_volatile(0x30);
23 }
```

Here is a short explanation of the two new methods:

- *Moving through an address space with offset()*—A pointer type's `offset()` method moves through the address space in increments that align to the size of the pointer. For example, calling `.offset(1)` on a `*mut u8` (mutable pointer to a `u8`) adds 1 to its address. When that same call is made to a `*mut u32` (mutable pointer to a `u32`), the pointer's address moves by 4 bytes.
- *Forcing a value to be written to memory with write\_volatile()*—Pointers provide a `write_volatile()` method that issues a “volatile” write. Volatile prevents the compiler's optimizer from optimizing away the write instruction. A smart compiler might simply notice that we are using lots of constants everywhere and initialize the program such that the memory is simply set to the value that we want it to be.

The following listing shows another way to write `framebuffer.offset(1).write_volatile(0x30)`. Here we use the dereference operator (\*) and manually set the memory to 0x30.

#### Listing 11.8 Manually incrementing a pointer

```

18  let mut framebuffer = 0xb8000 as *mut u8;
19  unsafe {
20      *(framebuffer + 1) = 0x30;    ← Sets the memory location
21  }

```

The coding style from listing 11.8 may be more familiar to programmers who have worked heavily with pointers before. Using this style requires diligence. Without the aid of type safety provided by `offset()`, it's easy for a typo to cause memory corruption. The verbose coding style used in listing 11.7 is also friendlier to programmers with less experience performing pointer arithmetic. It declares its own intent.

### 11.2.6 `_start(): The main() function for FledgeOS`

An OS kernel does not include the concept of a `main()` function, in the sense that you're used to. For one thing, an OS kernel's main loop never returns. Where would it return to? By convention, programs return an error code when they exit to an OS. But operating systems don't have an OS to provide an exit code to. Secondly, starting a program at `main()` is also a convention. But that convention also doesn't exist for OS kernels. To start an OS kernel, we require some software to talk directly to the CPU. The software is called a *bootloader*.

The linker expects to see one symbol defined, `_start`, which is the program's *entry point*. It links `_start` to a function that's defined by your source code.

In an ordinary environment, the `_start()` function has three jobs. Its first is to reset the system. On an embedded system, for example, `_start()` might clear registers and reset memory to 0. Its second job is to call `main()`. Its third is to call `_exit()`, which cleans up after `main()`. Our `_start()` function doesn't perform the last two jobs. Job two is unnecessary as the application's functionality is simple enough to keep within `_start()`. Job three is unnecessary, as is `main()`. If it were to be called, it would never return.

## 11.3 fledgeos-1: Avoiding a busy loop

Now that the foundations are in place, we can begin to add features to FledgeOS.

### 11.3.1 Being power conscious by interacting with the CPU directly

Before proceeding, FledgeOS needs to address one major shortcoming: it is extremely power hungry. The `_start()` function from listing 11.4 actually runs a CPU core at 100%. It's possible to avoid this by issuing the halt instruction (`hlt`) to the CPU.

The halt instruction, referred to as HLT in the technical literature, notifies the CPU that there's no more work to be done. The CPU resumes operating when an

interrupt triggers new action. As listing 11.9 shows, making use of the `x86_64` crate allows us to issue instructions directly to the CPU. The listing, an excerpt of listing 11.10, makes use of the `x86_64` crate to access the `hlt` instruction. It is passed to the CPU during the main loop of `_start()` to prevent excessive power consumption.

#### Listing 11.9 Using the `hlt` instruction

```

7 use x86_64::instructions::{hlt};

17 #[no_mangle]
18 pub extern "C" fn _start() -> ! {
19     let mut framebuffer = 0xb8000 as *mut u8;
20     unsafe {
21         framebuffer
22             .offset(1)
23             .write_volatile(0x30);
24     }
25     loop {
26         hlt();    ← This saves
27     }           electricity.
28 }
```

The alternative to using `hlt` is for the CPU to run at 100% utilization, performing no work. This turns your computer into a very expensive space heater.

### **11.3.2 fledgeos-1 source code**

`fledgeos-1` is mostly the same as `fledgeos-0`, except that its `src/main.rs` file includes the additions from the previous section. The new file is presented in the following listing and is available to download from `code/ch11/ch11-fledgeos-1/src/main.rs`. To compile the project, repeat the instructions in section 11.2.1, replacing references to `fledgeos-0` with `fledgeos-1`.

#### Listing 11.10 Project source code for `fledgeos-1`

```

1 #![no_std]
2 #![no_main]
3 #![feature(core_intrinsics)]
4
5 use core::intrinsics;
6 use core::panic::PanicInfo;
7 use x86_64::instructions::{hlt};
8
9 #[panic_handler]
10 #[no_mangle]
11 pub fn panic(_info: &PanicInfo) -> ! {
12     unsafe {
13         intrinsics::abort();
14     }
15 }
16
17 #[no_mangle]
```

```

18 pub extern "C" fn _start() -> ! {
19     let mut framebuffer = 0xb8000 as *mut u8;
20     unsafe {
21         framebuffer
22             .offset(1)
23             .write_volatile(0x30);
24     }
25     loop {
26         hlt();
27     }
28 }
```

The x86\_64 crate provided us with the ability to inject assembly instructions into our code. Another approach to explore is to use *inline assembly*. The latter approach is demonstrated briefly in section 12.3.

## 11.4 fledgeos-2: Custom exception handling

The next iteration of FledgeOS improves on its error-handling capabilities. FledgeOS still crashes when an error is triggered, but we now have a framework for building something more sophisticated.

### 11.4.1 Handling exceptions properly, almost

FledgeOS cannot manage any exceptions generated from the CPU when it detects an abnormal operation. To handle exceptions, our program needs to define an exception-handling personality function.

Personality functions are called on each stack frame as the stack is unwound after an exception. This means the call stack is traversed, invoking the personality function at each stage. The personality function's role is to determine whether the current stack frame is able to handle the exception. Exception handling is also known as *catching an exception*.

**NOTE** What is *stack unwinding*? When functions are called, stack frames accumulate. Traversing the stack in reverse is called *unwinding*. Eventually, unwinding the stack will hit `_start()`.

Because handling exceptions in a rigorous way is not necessary for FledgeOS, we'll implement only the bare minimum. Listing 11.11, an excerpt from listing 11.12, provides a snippet of code with the minimal handler. Inject it into `main.rs`. An empty function implies that any exception is fatal because none will be marked as the handler. When an exception occurs, we don't need to do anything.

#### Listing 11.11 Minimalist exception-handling personality routine

```

4 #![feature(lang_items)]
18 #[lang = "eh_personality"]
19 #[no_mangle]
20 pub extern "C" fn eh_personality() { }
```

**NOTE** What is a *language item*? Language items are elements of Rust implemented as libraries outside of the compiler itself. As we strip away the standard library with `#[no_std]`, we'll need to implement some of its functionality ourselves.

Admittedly, that's a lot of work to do nothing. But at least we can be comforted knowing that we are doing nothing in the right way.

### 11.4.2 fledgeos-2 source code

fledgeos-2 builds on fledgeos-0 and fledgeos-1. Its `src/main.rs` file includes the additions from the previous listing. The new file is presented in the following listing and is available to download from `code/ch11/ch11-fledgeos-2/src/main.rs`. To compile the project, repeat the instructions in section 11.2.1, replacing references to fledgeos-0 with fledgeos-2.

#### Listing 11.12 Source code for fledgeos-2

```

1 #![no_std]
2 #![no_main]
3 #![feature(core_intrinsics)]
4 #![feature(lang_items)]
5
6 use core::intrinsics;
7 use core::panic::PanicInfo;
8 use x86_64::instructions::{hlt};
9
10 #[panic_handler]
11 #[no_mangle]
12 pub fn panic(_info: &PanicInfo) -> ! {
13     unsafe {
14         intrinsics::abort();
15     }
16 }
17
18 #[lang = "eh_personality"]
19 #[no_mangle]
20 pub extern "C" fn eh_personality() { }
21
22 #[no_mangle]
23 pub extern "C" fn _start() -> ! {
24     let framebuffer = 0xb8000 as *mut u8;
25
26     unsafe {
27         framebuffer
28             .offset(1)
29             .write_volatile(0x30);
30     }
31
32     loop {
33         hlt();
34     }

```

## 11.5 fledgeos-3: Text output

Let's write some text to the screen. That way, if we really do encounter a panic, we can report it properly. This section explains the process of sending text to the frame buffer in more detail. Figure 11.2 shows the output from running fledgeos-3.



Figure 11.2 Output produced by fledgeos-3

### 11.5.1 Writing colored text to the screen

To start, we'll create a type for the color numeric constants that are used later in listing 11.16. Using an enum rather than defining a series of const values provides enhanced type safety. In some sense, it adds a semantic relationship between the values. These are all treated as members of the same group.

The following listing defines an enum that represents the VGA-compatible text mode color palette. The mapping between bit patterns and colors is defined by the VGA standard, and our code should comply with it.

#### Listing 11.13 Representing related numeric constants as an enum

```

9 #[allow(unused)]
10 #[derive(Clone, Copy)]
11 #[repr(u8)]
12 enum Color {
13     Black = 0x0,      White = 0xF,
14     Blue = 0x1,       BrightBlue = 0x9,
15     Green = 0x2,      BrightGreen = 0xA,
16     Cyan = 0x3,       BrightCyan = 0xB,

```

We won't be using every color variant in our code, so we can silence warnings.

Opts into copy semantics

Instructs the compiler to use a single byte to represent the values

```

17     Red = 0x4,      BrightRed = 0xC,
18     Magenta = 0x5,  BrightMagenta = 0xD,
19     Brown = 0x6,    Yellow = 0xE,
20     Gray = 0x7,    DarkGray = 0x8
21 }
```

### 11.5.2 Controlling the in-memory representation of enums

We've been content to allow the compiler to determine how an enum is represented. But there are times when we need to pull in the reins. External systems often demand that our data matches their requirements.

Listing 11.13 provides an example of fitting the colors from the VGA-compatible text mode palette enum into a single u8. It removes any discretion from the compiler about which bit pattern (formally called the *discriminant*) to associate with particular variants. To prescribe a representation, add the `repr` attribute. You are then able to specify any integer type (`i32`, `u8`, `i16`, `u16`,...), as well as some special cases.

Using a prescribed representation has some disadvantages. In particular, it reduces your flexibility. It also prevents Rust from making space optimizations. Some enums, those with a single variant, require no representation. These appear in source code but occupy zero space in the running program.

### 11.5.3 Why use enums?

You could model colors differently. For instance, it's possible to create numeric constants that look identical in memory. The following shows one such possibility:

```

const BLACK: u8 = 0x0;
const BLUE: u8 = 0x1;
// ...
```

Using an enum adds an extra guard. It becomes much more difficult to use an illegal value in our code than if we were using an `u8` directly. You will see this demonstrated when the `Cursor` struct is introduced in listing 11.17.

### 11.5.4 Creating a type that can print to the VGA frame buffer

To print to the screen, we'll use a `Cursor` struct that handles the raw memory manipulation and can convert between our `Color` type and what is expected by VGA. As the following listing shows, this type manages the interface between our code and the VGA frame buffer. This listing is another excerpt from listing 11.16.

#### Listing 11.14 Definition and methods for Cursor

```

25 struct Cursor {
26     position: isize,
27     foreground: Color,
28     background: Color,
29 }
30
```

```

31 impl Cursor {
32     fn color(&self) -> u8 {
33         let fg = self.foreground as u8;
34         let bg = (self.background as u8) << 4;
35         fg | bg
36     }
37
38     fn print(&mut self, text: &[u8]) {
39         let color = self.color();
40
41         let framebuffer = 0xb8000 as *mut u8;
42
43         for &character in text {
44             unsafe {
45                 framebuffer.offset(self.position).write_volatile(character);
46                 framebuffer.offset(self.position + 1).write_volatile(color);
47             }
48             self.position += 2;
49         }
50     }
51 }
```

Uses the foreground color as a base, which occupies the lower 4 bits. Shift the background color left to occupy the higher bits, then merge these together.

For expediency, the input uses a raw byte stream rather than a type that guarantees the correct encoding.

### 11.5.5 Printing to the screen

Making use of `Cursor` involves setting its position and then sending a reference to `Cursor.print()`. The following listing, an excerpt from listing 11.16, expands the `_start()` function to also print to the screen.

#### Listing 11.15 Demonstrating printing to the screen

```

67 #[no_mangle]
68 pub extern "C" fn _start() -> ! {
69     let text = b"Rust in Action";
70
71     let mut cursor = Cursor {
72         position: 0,
73         foreground: Color::BrightCyan,
74         background: Color::Black,
75     };
76     cursor.print(text);
77
78     loop {
79         hlt();
80     }
81 }
```

### 11.5.6 fledgeos-3 source code

fledgeos-3 continues to build on fledgeos-0, fledgeos-1, and fledgeos-2. Its `src/main.rs` file includes the additions from the this section. The complete file is presented in the following listing and is available to download from `code/ch11/ch11-fledgeos-3/src/main.rs`. To compile the project, repeat the instructions in section 11.2.1, replacing references to fledgeos-0 with fledgeos-3.

**Listing 11.16 FledgeOS now prints text to the screen**

```

1 #![feature(core_intrinsics)]
2 #![feature(lang_items)]
3 #![no_std]
4 #![no_main]
5
6 use core::intrinsics;
7 use core::panic::PanicInfo;
8
9 use x86_64::instructions::{hlt};
10
11 #[allow(unused)]
12 #[derive(Clone, Copy)]
13 #[repr(u8)]
14 enum Color {
15     Black = 0x0,      White = 0xF,
16     Blue = 0x1,       BrightBlue = 0x9,
17     Green = 0x2,      BrightGreen = 0xA,
18     Cyan = 0x3,       BrightCyan = 0xB,
19     Red = 0x4,        BrightRed = 0xC,
20     Magenta = 0x5,   BrightMagenta = 0xD,
21     Brown = 0x6,      Yellow = 0xE,
22     Gray = 0x7,       DarkGray = 0x8
23 }
24
25 struct Cursor {
26     position: isize,
27     foreground: Color,
28     background: Color,
29 }
30
31 impl Cursor {
32     fn color(&self) -> u8 {
33         let fg = self.foreground as u8;
34         let bg = (self.background as u8) << 4;
35         fg | bg
36     }
37
38     fn print(&mut self, text: &[u8]) {
39         let color = self.color();
40
41         let framebuffer = 0xb8000 as *mut u8;
42
43         for &character in text {
44             unsafe {
45                 framebuffer.offset(self.position).write_volatile(character);
46                 framebuffer.offset(self.position + 1).write_volatile(color);
47             }
48             self.position += 2;
49         }
50     }
51 }
52
53 #[panic_handler]

```

```

54 #[no_mangle]
55 pub fn panic(_info: &PanicInfo) -> ! {
56     unsafe {
57         intrinsics::abort();
58     }
59 }
60
61 #[lang = "eh_personality"]
62 #[no_mangle]
63 pub extern "C" fn eh_personality() { }
64
65 #[no_mangle]
66 pub extern "C" fn _start() -> ! {
67     let text = b"Rust in Action";
68
69     let mut cursor = Cursor {
70         position: 0,
71         foreground: Color::BrightCyan,
72         background: Color::Black,
73     };
74     cursor.print(text);
75
76     loop {
77         hlt();
78     }
79 }

```

## 11.6 fledgeos-4: Custom panic handling

Our panic handler, repeated in the following snippet, calls `core::intrinsics::abort()`. This shuts down the computer immediately, without providing any further input:

```

#[panic_handler]
#[no_mangle]
pub fn panic(_info: &PanicInfo) -> ! {
    unsafe {
        intrinsics::abort();
    }
}

```

### 11.6.1 Implementing a panic handler that reports the error to the user

For the benefit of anyone doing embedded development or wanting to execute Rust on microcontrollers, it's important to learn how to report where a panic occurs. A good place to start is with `core::fmt::Write`. That trait can be associated with the panic handler to display a message, as figure 11.3 shows.

### 11.6.2 Reimplementing panic() by making use of core::fmt::Write

The output shown by figure 11.3 is produced by listing 11.17. `panic()` now goes through a two-stage process. In the first stage, `panic()` clears the screen. The second stage involves the `core::write!` macro. `core::write!` takes a destination object as its



**Figure 11.3** Displaying a message when a panic occurs

first argument (`cursor`), which implements the `core::fmt::Write` trait. The following listing, an excerpt from listing 11.19, provides a panic handler that reports that an error has occurred using this process.

#### Listing 11.17 Clearing the screen and printing the message

```

61 pub fn panic(info: &PanicInfo) -> ! {
62     let mut cursor = Cursor {
63         position: 0,
64         foreground: Color::White,
65         background: Color::Red,
66     };
67     for _ in 0..(80*25) {
68         cursor.print(b" ");
69     }
70     cursor.position = 0;
71     write!(cursor, "{}", info).unwrap();
72
73     loop {}    ← Spins in an infinite loop, allowing
74 }           ← the user to read the message and
                           ← restart the machine manually
                           ← Clears the screen by
                           ← filling it with red
                           ← Resets the position
                           ← of the cursor
                           ← Prints PanicInfo
                           ← to the screen

```

### 11.6.3 Implementing `core::fmt::Write`

Implementing `core::fmt::Write` involves calling one method: `write_str()`. The trait defines several others, but the compiler can autogenerate these once an implementation of `write_str()` is available. The implementation in the following listing

reuses the `print()` method and converts the UTF-8 encoded `&str` into `&[u8]` with the `to_bytes()` method. The code for this listing is in `ch11/ch11-fledgeos-4/src/main.rs`.

**Listing 11.18 Implementing core::fmt::Write for the Cursor type**

```

54 impl fmt::Write for Cursor {
55     fn write_str(&mut self, s: &str) -> fmt::Result {
56         self.print(s.as_bytes());
57         Ok(())
58     }
59 }
```

## 11.6.4 fledge-4 source code

The following listing shows the user-friendly panic-handling code for FledgeOS. You'll find the source for this listing in `ch11/ch11-fledgeos-4/src/main.rs`. As with earlier versions, to compile the project, repeat the instructions at section 11.2.1 but replace references to `fledgeos-0` with `fledgeos-4`.

**Listing 11.19 Full code listing of FledgeOS with complete panic handling**

```

1 #![feature(core_intrinsics)]
2 #![feature(lang_items)]
3 #![no_std]
4 #![no_main]
5
6 use core::fmt;
7 use core::panic::PanicInfo;
8 use core::fmt::Write;
9
10 use x86_64::instructions::{hlt};
11
12 #[allow(unused)]
13 #[derive(Copy, Clone)]
14 #[repr(u8)]
15 enum Color {
16     Black = 0x0,      White = 0xF,
17     Blue = 0x1,       BrightBlue = 0x9,
18     Green = 0x2,      BrightGreen = 0xA,
19     Cyan = 0x3,       BrightCyan = 0xB,
20     Red = 0x4,        BrightRed = 0xC,
21     Magenta = 0x5,    BrightMagenta = 0xD,
22     Brown = 0x6,      Yellow = 0xE,
23     Gray = 0x7,       DarkGray = 0x8
24 }
25
26 struct Cursor {
27     position: isize,
28     foreground: Color,
29     background: Color,
30 }
31
32 impl Cursor {
```

```
33 fn color(&self) -> u8 {
34     let fg = self.foreground as u8;
35     let bg = (self.background as u8) << 4;
36     fg | bg
37 }
38
39 fn print(&mut self, text: &[u8]) {
40     let color = self.color();
41
42     let framebuffer = 0xb8000 as *mut u8;
43
44     for &character in text {
45         unsafe {
46             framebuffer.offset(self.position).write_volatile(character);
47             framebuffer.offset(self.position + 1).write_volatile(color);
48         }
49         self.position += 2;
50     }
51 }
52 }
53
54 impl fmt::Write for Cursor {
55     fn write_str(&mut self, s: &str) -> fmt::Result {
56         self.print(s.as_bytes());
57         Ok(())
58     }
59 }
60
61 #[panic_handler]
62 #[no_mangle]
63 pub fn panic(info: &PanicInfo) -> ! {
64     let mut cursor = Cursor {
65         position: 0,
66         foreground: Color::White,
67         background: Color::Red,
68     };
69     for _ in 0..(80*25) {
70         cursor.print(b" ");
71     }
72     cursor.position = 0;
73     write!(cursor, "{}", info).unwrap();
74
75     loop { unsafe { hlt(); } }
76 }
77
78 #[lang = "eh_personality"]
79 #[no_mangle]
80 pub extern "C" fn eh_personality() { }
81
82 #[no_mangle]
83 pub extern "C" fn _start() -> ! {
84     panic!("help!");
85 }
```

## Summary

- Writing a program that is intended to run without an operating system can feel like programming in a barren desert. Functionality that you take for granted, such as dynamic memory or multithreading, is not available to you.
- In environments such as embedded systems that do not have dynamic memory management, you will need to avoid the Rust standard library with the `#![no_std]` annotation.
- When interfacing with external components, naming symbols becomes significant. To opt out of Rust's name-mangling facilities, use the `#![no_mangle]` attribute.
- Rust's internal representations can be controlled through annotations. For example, annotating an enum with `#![repr(u8)]` forces the values to be packed into a single byte. If this doesn't work, Rust refuses to compile the program.
- Raw pointer manipulation is available to you, but type-safe alternatives exist. When it's practical to do so, use the `offset()` method to correctly calculate the number of bytes to traverse through the address space.
- The compiler's internals are always accessible to you at the cost of requiring a nightly compiler. Access compiler intrinsics like `intrinsics::abort()` to provide functionality to the program that's ordinarily inaccessible.
- cargo should be thought of as an extensible tool. It sits at the center of the Rust programmer's workflow, but its standard behavior can be changed when necessary.
- To access raw machine instructions, such as HTL, you can use helper crates like `x86_64` or rely on inline assembly.
- Don't be afraid to experiment. With modern tools like QEMU, the worst that can happen is that your tiny OS crashes, and you'll need to run it again instantly.

# 12

## *Signals, interrupts, and exceptions*

### **This chapter covers**

- What interrupts, exceptions, traps, and faults are
- How device drivers inform applications that data is ready
- How to transmit signals between running applications

This chapter describes the process by which the outside world communicates with your operating system (OS). The network constantly interrupts program execution when bytes are ready to be delivered. This means that after connecting to a database (or at any other time), the OS can demand that your application deal with a message. This chapter describes this process and how to prepare your programs for it.

In chapter 9, you learned that a digital clock periodically notifies the OS that time has progressed. This chapter explains how those notifications occur. It also introduces the concept of multiple applications running at the same time via the concept of signals. Signals emerged as part of the UNIX OS tradition. These can be used to send messages between different running programs.

We'll address both concepts—signals and interrupts—together, as the programming models are similar. But it's simpler to start with signals. Although this chapter

focuses on the Linux OS running on x86 CPUs, that's not to say that users of other operating systems won't be able to follow along.

## 12.1 Glossary

Learning how CPUs, device drivers, applications, and operating systems interact is difficult. There is a lot of jargon to take in. To make matters worse, the terms all look similar, and it certainly does not help that these are often used interchangeably. Here are some examples of the jargon that is used in this chapter. Figure 12.1 illustrates how these interrelate:

- *Abort*—An unrecoverable exception. If an application triggers an abort, the application terminates.
- *Fault*—A recoverable exception that is expected in routine operations such as a *page fault*. Page faults occur when a memory address is not available and data must be fetched from the main memory chip(s). This process is known as *virtual memory* and is explained in section 4 of chapter 6.
- *Exception*—Exception is an umbrella term that includes aborts, faults, and traps. Formally referred to as *synchronous interrupts*, exceptions are sometimes described as a form of an interrupt.
- *Hardware interrupt*—An interrupt generated by a device such as a keyboard or hard disk controller. Typically used by devices to notify the CPU that data is available to be read from the device.
- *Interrupt*—A hardware-level term that is used in two senses. It can refer only to *synchronous interrupts*, which include hardware and software interrupts. Depending on context, it can also include exceptions. Interrupts are usually handled by the OS.
- *Signal*—An OS-level term for interruptions to an application's control flow. Signals are handled by applications.
- *Software interrupt*—An interrupt generated by a program. Within Intel's x86 CPU family, programs can trigger an interrupt with the INT instruction. Among other uses of this facility, debuggers use software interrupts to set breakpoints.
- *Trap*—A recoverable exception such as an integer overflow detected by the CPU. Integer overflow is explained in section 5.2.

**NOTE** The meaning of the term *exception* may differ from your previous programming experience. Programming languages often use the term exception to refer to any error, whereas the term has a specialized meaning when referring to CPUs.

### 12.1.1 Signals vs. interrupts

The two concepts that are most important to distinguish between are signals and interrupts. A *signal* is a software-level abstraction that is associated with an OS. An *interrupt* is a CPU-related abstraction that is closely associated with the system's hardware.




Figure 12.1 A visual taxonomy of how the terms interrupt, exception, trap, and fault interact within Intel's x86 family of CPUs. Note that signals do not appear within this figure. Signals are not interrupts.

Signals are a form of limited interprocess communication. They don't contain content, but their presence indicates something. They're analogous to a physical, audible buzzer. The buzzer doesn't provide content, but the person who presses it still knows what's intended as it makes a very jarring sound. To add confusion to the mix, signals are often described as software interrupts. This chapter, however, avoids the use of the term interrupt when referring to a signal.

There are two forms of interrupts, which differ in their origin. One form of interrupt occurs within the CPU during its processing. This is the result of attempting to process illegal instructions and trying to access invalid memory addresses. This first form is known technically as a *synchronous interrupt*, but you may have heard it referred to by its more common name, *exception*.

The second form of interrupt is generated by hardware devices like keyboards and accelerometers. This is what's commonly implied by the term interrupt. This can occur at any time and is formally known as an *asynchronous interrupt*. Like signals, this can also be generated within software.

Interrupts can be specialized. A *trap* is an error detected by the CPU, so it gives the OS a chance to recover. A *fault* is another form of a recoverable problem. If the CPU is given a memory address that it can't read from, it notifies the OS and asks for an updated address.

Interrupts force an application's control flow to change, whereas many signals can be ignored if desired. Upon receiving an interrupt, the CPU jumps to handler code, irrespective of the current state of the program. The location of the handler code is predefined by the BIOS and OS during a system's bootup process.

### Treating signals as interrupts

Handling interrupts directly means manipulating the OS kernel. Because we would prefer not to do that in a learning environment, we'll play fast and loose with the terminology. The rest of this chapter, therefore, treats signals as interrupts.

Why simplify things? Writing OS components involves tweaking the kernel. Breaking things there means that our system could become completely unresponsive without a clear way to fix anything. From a more pragmatic perspective, avoiding tweaks to the kernel means that we'll avoid learning a whole new compiler toolchain.

To our advantage, code that handles signals looks similar to code that handles interrupts. Practicing with signals allows us to keep any errors within our code constrained to our application rather than risk bringing the whole system down. The general pattern is as follows:

- 1 Model your application's standard control flow.
- 2 Model the interrupted control flow and identify resources that need to be cleanly shut down, if required.
- 3 Write the interrupt/signal handler to update some state and return quickly.
- 4 You will typically delegate time-consuming operations by only modifying a global variable that is regularly checked by the main loop of the program.
- 5 Modify your application's standard control flow to look for the GO/NO GO flag that a signal handler may have changed.

## 12.2 How interrupts affect applications

Let's work through this challenge by considering a small code example. The following listing shows a simple calculation that sums two integers.

**Listing 12.1 A program that calculates the sum of two integers**

```
1 fn add(a: i32, b:i32) -> i32 {  
2     a + b  
3 }  
4  
5 fn main() {  
6     let a = 5;  
7     let b = 6;  
8     let c = add(a,b);  
9 }
```

Irrespective of the number of hardware interrupts, c is always calculated. But the program's wall clock time becomes nondeterministic because the CPU performs different tasks every time it runs.

When an interrupt occurs, the CPU immediately halts execution of the program and jumps to the interrupt handler. The next listing (illustrated in figure 12.2) details what happens when an interrupt occurs between lines 7 and 8 in listing 12.1.

### Listing 12.2 Depicting the flow of listing 12.1 as it handles an interrupt

```


1 #[allow(unused)]
2 fn interrupt_handler() {           ←
3     // ..
4 }
5
6 fn add(a: i32, b:i32) -> i32 {
7     a + b
8 }
9
10 fn main() {
11     let a = 5;
12     let b = 6;
13
14     // Key pressed on keyboard!
15     interrupt_handler()
16
17     let c = add(a,b);
18 }
```

Although presented in this listing as an extra function, the interrupt handler is typically defined by the OS.

#### Normal program execution

Control flow in the normal case operates in a linear sequence of instructions. Function calls and return statements do jump a CPU around in memory, but the order of events can be predetermined.

Dashes mark the CPU's progression through the program.



Return instruction is implicit in Rust.

#### Interrupted program execution

When a hardware interrupt occurs, the program is not unaffected directly, although there may be a negligible performance impact as the operating system must deal with the hardware.

Program is unaware of what the CPU is doing. Once it is finished with other tasks, execution proceeds as normal.




Figure 12.2 Using addition to demonstrate control flow for handling signals

One important point to remember is that, from the program's perspective, little changes. It isn't aware that its control flow has been interrupted. Listing 12.1 is still an accurate representation of the program.

## 12.3 Software interrupts

Software interrupts are generated by programs sending specific instructions to the CPU. To do this in Rust, you can invoke the `asm!` macro. The following code, available at `ch12/asm.rs`, provides a brief view of the syntax:

```
#! [feature(asm)]      ← Enables an  
use std::asm;          unstable feature  
  
fn main() {  
    unsafe {  
        asm!("int 42");  
    }  
}
```

Running the compiled executable presents the following error from the OS:

```
$ rustc +nightly asm.rs  
$ ./asm  
Segmentation fault (core dumped)
```

As of Rust 1.50, the `asm!` macro is unstable and requires that you execute the nightly Rust compiler. To install the nightly compiler, use `rustup`:

```
$ rustup install nightly
```

## 12.4 Hardware interrupts

Hardware interrupts have a special flow. Devices interface with a specialized chip, known as the *Programmable Interrupt Controller (PIC)*, to notify the CPU. Figure 12.3 provides a view of how interrupts flow from hardware devices to an application.


## 12.5 Signal handling

Signals require immediate attention. Failing to handle a signal typically results in the application being terminated.


### 12.5.1 Default behavior

Sometimes the best approach is to let the system's defaults do the work. Code that you don't need to write is code that's free from bugs that you inadvertently cause.

The default behavior for most signals is shutting down the application. When an application does not provide a special handler function (we'll learn how to do that in this chapter), the OS considers the signal to be an *abnormal* condition. When an OS detects an abnormal condition within an application, things don't end well for the application—it terminates the application. Figure 12.4 depicts this scenario.



**Figure 12.3** How applications are notified of an interrupt generated from a hardware device. Once the OS has been notified that data is ready, it then directly communicates with the device (in this case, the keyboard) to read the data into its own memory.



**Figure 12.4** An application defending itself from marauding hoards of unwanted signals. Signal handlers are the friendly giants of the computing world. They generally stay out of the way but are there when your application needs to defend its castle. Although not part of everyday control flow, signal handlers are extremely useful when the time is right. Not all signals can be handled. `SIGKILL` is particularly vicious.

Your application can receive three common signals. The following lists them and their intended actions:

- `SIGINT`—Terminates the program (usually generated by a person)
- `SIGTERM`—Terminates the program (usually generated by another program)
- `SIGKILL`—Immediately terminates the program without the ability to recover

You'll find many other less common signals. For your convenience, a fuller list is provided in table 12.2.

You may have noticed that the three examples listed here are heavily associated with terminating a running program. But that's not necessarily the case.

## 12.5.2 Suspend and resume a program's operation

There are two special signals worth mentioning: SIGSTOP and SIGCONT. SIGSTOP halts the program's execution, and it remains suspended until it receives SIGCONT. UNIX systems use this signal for job control. It's also useful to know about if you want to manually intervene and halt a running application but would like the ability to recover at some time in the future.

The following snippet shows the structure for the sixty project that we'll develop in this chapter. To download the project, enter these commands in the console:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch12/ch12-sixty
```

To create the project manually, set up a directory structure that resembles the following and populate its contents from listings 12.3 and 12.4:



The following listing shows the initial crate metadata for the sixty project. The source code for this listing is in the ch12/ch12-sixty/ directory.

### Listing 12.3 Crate metadata for the sixty project

```
[package]
name = "sixty"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]

[dependencies]
```

The next listing provides the code to build a basic application that lives for 60 seconds and prints its progress along the way. You'll find the source for this listing in ch12/ch12-sixty/src/main.rs.

### Listing 12.4 A basic application that receives SIGSTOP and SIGCONT

```
1 use std::time;
2 use std::process;
3 use std::thread::{sleep};
4
5 fn main() {
6     let delay = time::Duration::from_secs(1);
7
8     let pid = process::id();
9     println!("{} {}", pid);
10
11    for i in 1..=60 {
12        sleep(delay);
```

```

13     println!("{} {}", i);
14 }
15 }
```

Once the code from listing 12.4 is saved to disk, two consoles open. In the first, execute cargo run. A 3–5 digit number appears, followed by a counter that increments by the second. The first line number is the *PID* or *process ID*. Table 12.1 shows the operation and expected output.

**Table 12.1 How processes can be suspended and resumed with SIGSTOP and SIGCONT**

Step	Console 1	Console 2
	Executes application	Sends signals
1	\$ cd ch12/ch12-sixty	
2	\$ cargo run 23221 . 1 . 2 . 3 . 4	
3		\$ kill -SIGSTOP 23221
4	[1]+ Stopped cargo run \$	
5		\$ kill -SIGCONT 23221
6	. 5 . 6 . 7 . 8	
	:	
	. 60	

The program flow in table 12.1 follows:

- 1 In console 1, move to the project directory (created from listings 12.3 and 12.4).
- 2 Compile and run the project.

cargo provides debugging output that is omitted here. When running, the sixty program prints the PID, and then prints some numbers to the console every second. Because it was the PID for this invocation, 23221 appears as output in the table.

- 3 In console 2, execute the kill command, specifying -SIGSTOP.

If you are unfamiliar with the shell command kill, its role is to send signals. It's named after its most common role, terminating programs with either SIGKILL

or SIGTERM. The numeric argument (23221) must match the PID provided in step 2.

- 4 Console 1 returns to the command prompt as there is no longer anything running in the foreground.
- 5 Resume the program by sending SIGCONT to the PID provided in step 2.
- 6 The program resumes counting. It terminates when it hits 60, unless interrupted by Ctrl-C (SIGINT).

SIGSTOP and SIGCONT are interesting special cases. Let's continue by investigating more typical signal behavior.

### 12.5.3 Listing all signals supported by the OS

What are the other signals and what are their default handlers? To find the answer, we can ask the `kill` command to provide that information:

```
$ kill -l      ← -l stands for list.
 1) SIGHUP    2) SIGINT     3) SIGQUIT    4) SIGILL     5) SIGTRAP
 6) SIGABRT   7) SIGEMT     8) SIGFPE     9) SIGKILL   10) SIGBUS
11) SIGSEGV  12) SIGSYS    13) SIGPIPE    14) SIGALRM   15) SIGTERM
16) SIGURG   17) SIGSTOP    18) SIGTSTP    19) SIGCONT   20) SIGCHLD
21) SIGTTIN  22) SIGTTOU   23) SIGIO      24) SIGXCPU   25) SIGXFSZ
26) SIGVTALRM 27) SIGPROF   28) SIGWINCH   29) SIGPWR    30) SIGUSR1
31) SIGUSR2  32) SIGRTMAX
```

That's a lot, Linux! To make matters worse, few signals have standardized behavior. Thankfully, most applications don't need to worry about setting handlers for many of these signals (if any). Table 12.1 shows a much tighter list of signals. These are more likely to be encountered in day-to-day programming.

**Table 12.2** List of common signals, their default actions, and shortcuts for sending them from the command line

Signal	Read as	Default action	Comment	Shortcut
SIGHUP	Hung up	Terminate	Originally from telephone-based digital communications. Now often sent to background applications (daemons/services) to request that these reread their configuration files. Sent to running programs when you log out from a shell.	Ctrl-D
SIGINT	Interrupt (or perhaps interactive)	Terminate	User-generated signal to terminate a running application.	Ctrl-C
SIGTERM	Terminate	Terminate	Asks application to gracefully terminate.	

**Table 12.2 List of common signals, their default actions, and shortcuts for sending them from the command line (continued)**

Signal	Read as	Default action	Comment	Shortcut
SIGKILL	Kill	Terminate	This action is unstoppable.	
SIGQUIT	Quit		Writes memory to disk as a core dump, then terminates.	Ctrl-\
SIGTSTP	Terminal stop	Pause execution	The terminal requests the application to stop.	
SIGSTOP	Stop	Pause execution	This action is unstoppable.	
SIGCONT	Continue	Resume execution when paused		

**NOTE** SIGKILL and SIGSTOP have special status: these cannot be handled or blocked by the application. Programs can avoid the others.

## 12.6 Handling signals with custom actions

The default actions for signals are fairly limited. By default, receiving a signal tends to end badly for applications. For example, if external resources such as database connections are left open, they might not be cleaned up properly when the application ends.

The most common use case for signal handlers is to allow an application to shut down cleanly. Some common tasks that might be necessary when an application shuts down include

- Flushing the hard disk drive to ensure that pending data is written to disk
- Closing any network connections
- Deregistering from any distributed scheduler or work queue

To stop the current workload and shut down, a signal handler is required. To set up a signal handler, we need to create a function with the signature `f(i32) -> ()`. That is, the function needs to accept an `i32` integer as its sole argument and returns no value.

This poses some software engineering issues. The signal handler isn't able to access any information from the application except which signal was sent. Therefore, because it doesn't know what state anything is in, it doesn't know what needs shutting down beforehand.

There are some additional restrictions in addition to the architectural one. Signal handlers are constrained in time and scope. These must also act quickly within a subset of functionality available to general code for these reasons:

- Signal handlers can block other signals of the same type from being handled.
- Moving fast reduces the likelihood of operating alongside another signal handler of a different type.

Signal handlers have reduced scope in what they’re permitted to do. For example, they must avoid executing any code that might itself generate signals.

To wriggle out of this constrained environment, the ordinary approach is to use a Boolean flag as a global variable that is regularly checked during a program’s execution. If the flag is set, then you can call a function to shutdown the application cleanly within the context of the application. For this pattern to work, there are two requirements:

- The signal handler’s sole responsibility is to mutate the flag.
- The application must regularly check the flag to detect whether the flag has been modified.

To avoid race conditions caused by multiple signal handlers running at the same time, signal handlers typically do little. A common pattern is to set a flag via a global variable.

## 12.6.1 Global variables in Rust

Rust facilitates *global variables* (variables accessible anywhere within the program) by declaring a variable with the `static` keyword in global scope. Suppose we want to create a global value `SHUT_DOWN` that we can set to `true` when a signal handler believes it’s time to urgently shut down. We can use this declaration:

```
static mut SHUT_DOWN: bool = false;
```

**NOTE** `static mut` is read as *mutable static*, irrespective of how grammatically contorted that is.

Global variables present an issue for Rust programmers. Accessing these (even just for reading) is unsafe. This means that the code can become quite cluttered if it’s wrapped in `unsafe` blocks. This ugliness is a signal to wary programmers—avoid global state whenever possible.

Listing 12.6 presents a example of a `static mut` variable that reads from line 12 and writes to lines 7–9. The call to `rand::random()` on line 8 produces Boolean values. Output is a series of dots. About 50% of the time, you’ll receive output that looks like what’s shown in the following console session:<sup>1</sup>

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch12/ch2-toy-global
$ cargo run -q
.
```

The following listing provides the metadata for listing 12.6. You can access its source code in `ch12/ch2-toy-global/Cargo.toml`.

---

<sup>1</sup> Output assumes a fair random number generator, which Rust uses by default. This assumption holds as long as you trust your operating system’s random number generator.

### Listing 12.5 Crate metadata for listing 12.6

```
[package]
name = "ch12-toy-global"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
rand = "0.6"
```

The following listing presents our toy example. Its source code is in ch12/ch12-toy-global/src/main.rs.

### Listing 12.6 Accessing global variables (mutable statics) in Rust

```
1 use rand;
2
3 static mut SHUT_DOWN: bool = false;
4
5 fn main() {
6     loop {
7         unsafe {           ←
8             SHUT_DOWN = rand::random();      ←
9         }
10        print!(".");
11
12        if unsafe { SHUT_DOWN } {
13            break
14        }
15    }
16    println!
17 }
```

Reading from and writing  
to a static mut variable  
requires an unsafe block.

rand::random() is a shortcut that  
calls rand::thread\_rng().gen() to  
produce a random value. The  
required type is inferred from  
the type of SHUT\_DOWN.

## 12.6.2 Using a global variable to indicate that shutdown has been initiated

Given that signal handlers must be quick and simple, we'll do the minimal amount of possible work. In the next example, we'll set a variable to indicate that the program needs to shut down. This technique is demonstrated by listing 12.8, which is structured into these three functions:

- `register_signal_handlers()`—Communicates to the OS via libc, the signal handler for each signal. This function makes use of a function pointer, which treats a function as data. Function pointers are explained in section 11.7.1.
- `handle_signals()`—Handles incoming signals. This function is agnostic as to which signal is sent, although we'll only deal with SIGTERM.
- `main()`—Initializes the program and iterates through a main loop.

When run, the resulting executable produces a trace of where it is. The following console session shows the trace:

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch12/ch12-basic-handler
$ cargo run -q
1
SIGUSR1
2
SIGUSR1
3
SIGTERM
4
*
I hope that you will
forgive the cheap
ASCII art explosion.
```

**NOTE** If the signal handler is not correctly registered, Terminated may appear in the output. Make sure that you add a call to `register_signal_handler()` early within `main()`. Listing 12.8 does this on line 38.

The following listing shows the package and dependency for listing 12.8. You can view the source for this listing in ch12/ch12-basic-handler/Cargo.toml.

#### Listing 12.7 Crate setup for listing 12.10

```
[package]
name = "ch12-handler"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
libc = "0.2"
```

When executed, the following listing uses a signal handler to modify a global variable. The source for this listing is in ch12/ch12-basic-handler/src/main.rs.

#### Listing 12.8 Creating a signal handler that modifies a global variable

```
1 #![cfg(not(windows))]           ← Indicates that
2
3 use std::time::{Duration};           this code won't
4 use std::thread::sleep;             run on Windows
5 use libc::({SIGTERM, SIGUSR1});
6
7 static mut SHUT_DOWN: bool = false;
8
9 fn main() {
10     register_signal_handlers();      ← Must occur as soon as
11
12     let delay = Duration::from_secs(1);
13
14     for i in 1.. {
15         println!("{}", i);
16         unsafe {                   ← Accessing a
17             if SHUT_DOWN {          mutable static
18                 println!("*");    is unsafe.
19             }
20         }
21     }
22 }
```

```

19         return;
20     }
21 }
22
23 sleep(delay);
24
25 let signal = if i > 2 {
26     SIGTERM
27 } else {
28     SIGUSR1
29 };
30
31 unsafe {           ←
32     libc::raise(signal);
33 }
34 }
35 unreachable!();
36 }
37
38 fn register_signal_handlers() {
39     unsafe {           ←
40         libc::signal(SIGTERM, handle_sigterm as usize);
41         libc::signal(SIGUSR1, handle_sigusr1 as usize);
42     }
43 }
44
45 #[allow(dead_code)]
46 fn handle_sigterm(_signal: i32) {
47     register_signal_handlers();   ←
48
49     println!("SIGTERM");
50
51     unsafe {           ←
52         SHUT_DOWN = true;
53     }
54 }
55
56 #[allow(dead_code)]
57 fn handle_sigusr1(_signal: i32) {
58     register_signal_handlers();   ←
59
60     println!("SIGUSR1");
61 }

```

**Without this attribute, rustc warns that these functions are never called.**

**Calling libc functions is unsafe; their effects are outside of Rust's control.**

**Reregisters signals as soon as possible to minimize signal changes affecting the signal handler itself**

**Modifying a mutable static is unsafe.**

In the preceding listing, there is something special about the calls to `libc::signal()` on lines 40 and 41. `libc::signal` takes a signal name (which is actually an integer) and an untyped function pointer (known in C parlance as a *void function pointer*) as arguments and associates the signal with the function. Rust's `fn` keyword creates function pointers. `handle_sigterm()` and `handle_sigusr1()` both have the type `fn(i32) -> ()`. We need to cast these as `usize` values to erase any type information. Function pointers are explained in more detail in section 12.7.1.

### Understanding the difference between `const` and `static`

Static and constant seem similar. Here is the main difference between them:

- `static` values appear in a single location in memory.
- `const` values can be duplicated in locations where they are accessed.

Duplicating `const` values can be a CPU-friendly optimization. It allows for data locality and improved cache performance.

Why use confusingly similar names for two different things? It could be considered a historical accident. The word `static` refers to the segment of the address space that the variables live in. `static` values live outside the stack space, within the region where string literals are held, near the bottom of the address space. That means accessing a `static` variable almost certainly implies dereferencing a pointer.

The constant in `const` values refers to the value itself. When accessed from code, the data might get duplicated to every location that it's needed if the compiler believes that this will result in faster access.

## 12.7 Sending application-defined signals

Signals can be used as a limited form of messaging. Within your business rules, you can create definitions for `SIGUSR1` and `SIGUSR2`. These are unallocated by design. In listing 12.8, we used `SIGUSR1` to do a small task. It simply prints the string `SIGUSR1`. A more realistic use of custom signals is to notify a peer application that some data is ready for further processing.

### 12.7.1 Understanding function pointers and their syntax

Listing 12.8 includes some syntax that might be confusing. For example, on line 40 `handle_sigterm as usize` appears to cast a function as an integer.

What is happening here? The address where the function is stored is being converted to an integer. In Rust, the `fn` keyword creates a function pointer.

Readers who have worked through chapter 5 will understand that functions are just data. That is to say, functions are sequences of bytes that make sense to the CPU. A *function pointer* is a pointer to the start of that sequence. Refer back to chapter 5, especially section 5.7, for a refresher.

A *pointer* is a data type that acts as a stand-in for its referent. Within an application's source code, pointers contain both the address of the value referred to as well as its type. The type information is something that's stripped away in the compiled binary. The internal representation for pointers is an integer of `usize`. That makes pointers very economical to pass around. In C, making use of function pointers can feel like arcane magic. In Rust, they hide in plain sight.

Every fn declaration is actually declaring a function pointer. That means that listing 12.9 is legal code and should print something similar to the following line:

```
$ rustc ch12/fn-ptr-demo-1.rs && ./fn-ptr-demo-1
noop as usize: 0x5620bb4af530
```

**NOTE** In the output, 0x5620bb4af530 is the memory address (in hexadecimal notation) of the start of the noop() function. This number will be different on your machine.

The following listing, available at ch12/noop.rs, shows how to cast a function to usize. This demonstrates how usize can be used as a function pointer.

#### Listing 12.9 Casting a function to usize

```
fn noop() {}

fn main() {
    let fn_ptr = noop as usize;

    println!("noop as usize: 0x{:x}", fn_ptr);
}
```

But what is the type of the function pointer created from fn noop()? To describe function pointers, Rust reuses its function signature syntax. In the case of fn noop(), the type is `*const fn() -> ()`. This type is read as “a const pointer to a function that takes no arguments and returns unit.” A const pointer is immutable. A unit is Rust’s stand-in value for “nothingness.”

Listing 12.10 casts a function pointer to usize and then back again. Its output, shown in the following snippet, should show two lines that are nearly identical:

```
$ rustc ch12/fn-ptr-demo-2.rs && ./fn-ptr-demo-2
noop as usize:      0x55ab3fdb05c0
noop as *const T: 0x55ab3fdb05c0
```

**NOTE** These two numbers will be different on your machine, but the two numbers will match each other.

#### Listing 12.10 Casting a function to usize

```
fn noop() {}

fn main() {
    let fn_ptr = noop as usize;
    let typed_fn_ptr = noop as *const fn() -> ();

    println!("noop as usize: 0x{:x}", fn_ptr);
    println!("noop as *const T: {:p}", typed_fn_ptr);
}
```

Note the use of the  
pointer format  
modifier, {:p}.

## 12.8 Ignoring signals

As noted in table 12.2, most signals terminate the running program by default. This can be somewhat disheartening for the running program attempting to get its work done. (Sometimes the application knows best!) For those cases, many signals can be ignored.

SIGSTOP and SIGKILL aside, the constant `SIG_IGN` can be provided to `libc::signal()` instead of a function pointer. An example of its usage is provided by the ignore project. Listing 12.11 shows its `Cargo.toml` file, and listing 12.12 shows `src/main.rs`. These are both available from the `ch12/ch12-ignore` project directory. When executed, the project prints the following line to the console:

```
$ cd ch12/ch12-ignore
$ cargo run -q
ok
```

The ignore project demonstrates how to ignore selected signals. On line 6 of listing 12.12, `libc::SIG_IGN` (short for *signal ignore*) is provided as the signal handler to `libc::signal()`. The default behavior is reset on line 13. `libc::signal()` is called again, this time with `SIG_DFL` (short for *signal default*) as the signal handler.

**Listing 12.11 Project metadata for ignore project**

```
[package]
name = "ignore"
version = "0.1.0"
authors = ["Tim McNamara <author@rustinaction.com>"]
edition = "2018"

[dependencies]
libc = "0.2"
```

**Listing 12.12 Ignoring signals with `libc::SIG_IGN`**

```
1 use libc::{signal,raise};
2 use libc::{SIG_DFL, SIG_IGN, SIGTERM};
3
4 fn main() {
5     unsafe {
6         signal(SIGTERM, SIG_IGN);
7         raise(SIGTERM);
8     }
9
10    println!("ok");
11
12    unsafe {
13        signal(SIGTERM, SIG_DFL);
14        raise(SIGTERM);
15    }
}
```

Requires an unsafe block because Rust does not control what happens beyond the function boundaries

Ignores the SIGTERM signal

`libc::raise()` allows code to make a signal; in this case, to itself.

Resets SIGTERM to its default

Terminates the program

```

17    println!("not ok");
18 }

```

← This code is never reached,  
and therefore, this string is  
never printed.

## 12.9 Shutting down from deeply nested call stacks

What if our program is deep in the middle of a call stack and can't afford to unwind? When receiving a signal, the program might want to execute some cleanup code before terminating (or being forcefully terminated). This is sometimes referred to as *nonlocal control transfer*. UNIX-based operating systems provide some tools to enable you to make use of that machinery via two system calls—`setjmp` and `longjmp`:

- `setjmp` sets a marker location.
- `longjmp` jumps back to the previously marked location.

Why bother with such programming gymnastics? Sometimes using low-level techniques like these is the only way out of a tight spot. These approach the “Dark Arts” of systems programming. To quote the manpage:

*“setjmp() and longjmp() are useful for dealing with errors and interrupts encountered in a low-level subroutine of a program.”*

—Linux Documentation Project: `setjmp(3)`

These two tools circumvent normal control flow and allow programs to teleport themselves through the code. Occasionally an error occurs deep within a call stack. If our program takes too long to respond to the error, the OS may simply abort the program, and the program's data may be left in an inconsistent state. To avoid this, you can use `longjmp` to shift control directly to the error-handling code.

To understand the significance of this, consider what happens in an ordinary program's call stack during several calls to a recursive function as produced by the code in listing 12.13. Each call to `dive()` adds another place that control eventually returns to. See the left-hand side of table 12.3. The `longjmp` system call, used by listing 12.17, bypasses several layers of the call stack. Its effect on the call stack is visible on the right-hand side of table 12.3.

**Table 12.3 Comparing the intended output from listing 12.13 and listing 12.17**

<p>Listing 12.13 produces a symmetrical pattern. Each level is caused by a nested call to <code>dive()</code>, which is removed when the calls return.</p> <pre> # ## ### ##### ##### ### ## # </pre>	<p>Listing 12.17 produces a much different pattern. After a few calls to <code>dive()</code>, control teleports back to <code>main()</code> without returning the calls to <code>dive()</code>.</p> <pre> # ## ### early return! finishing! </pre>
---	--

On the left side of table 12.3, the call stack grows one step as functions are called, then shrinks by one as each function returns. On the right side, the code jumps directly from the third call to the top to the call stack.

The following listing depicts how the call stack operates by printing its progress as the program executes. The code for this listing is in ch10/ch10-callstack/src/main.rs.

#### Listing 12.13 Illustrating how the call stack operates

```

1 fn print_depth(depth:usize) {
2     for _ in 0..depth {
3         print!("#");
4     }
5     println!("");
6 }
7
8 fn dive(depth: usize, max_depth: usize) {
9     print_depth(depth);
10    if depth >= max_depth {
11        return;
12    }
13    } else {
14        dive(depth+1, max_depth);
15    }
16    print_depth(depth);
17 }
18
19 fn main() {
20     dive(0, 5);
21 }
```

There's a lot of work to do to make this happen. The Rust language itself doesn't have the tools to enable this control-flow trickery. It needs to access some provided by its compiler's toolchain. Compilers provide special functions known as *intrinsics* to application programs. Using an intrinsic function with Rust takes some ceremony to set up, but that operates as a standard function once the set-up is in place.

### **12.9.1 Introducing the sjlj project**

The sjlj project demonstrates contorting the normal control flow of a function. With the help of some assistance from the OS and the compiler, it's actually possible to create a situation where a function can move to anywhere in the program. Listing 12.17 uses that functionality to bypass several layers of the call stack, creating the output from the right side of table 12.3. Figure 12.5 shows the control flow for the sjlj project.

### **12.9.2 Setting up intrinsics in a program**

Listing 12.17 uses two intrinsics, `setjmp()` and `longjmp()`. To enable these in our programs, the crate must be annotated with the attribute provided. The following listing provides this documentation.




Figure 12.5 Control flow of the sjlj project. The program's control flow can be intercepted via a signal and then resumed from the point of `setjmp()`.

#### Listing 12.14 Crate-level attribute required in `main.rs`

```
#![feature(link_llvm_intrinsics)]
```

This raises two immediate questions. We'll answer the following shortly:

- What is an intrinsic function?
- What is LLVM?

Additionally, we need to tell Rust about the functions that are being provided by LLVM. Rust won't know anything about them, apart from their type signatures, which means that any use of these must occur within an unsafe block. The following listing shows how to inform Rust about the LLVM functions. The source for this listing is in `ch12/ch12-sjnj/src/main.rs`.

**Listing 12.15 Declaring the LLVM intrinsic functions within listing 12.17**

```
extern "C" {
    #[link_name = "llvm.eh.sjlj.setjmp"]
    pub fn setjmp(_: *mut i8) -> i32;

    #[link_name = "llvm.eh.sjlj.longjmp"]
    pub fn longjmp(_: *mut i8);
}
```

Provides specific instructions to the linker about where it should look to find the function definitions

As we're not using the argument's name, uses an underscore (\_) to make that explicit

This small section of code contains a fair amount of complexity. For example

- `extern "C"` means “This block of code should obey C’s conventions rather than Rust’s.”
- The `link_name` attribute tells the linker where to find the two functions that we’re declaring.
- The `eh` in `llvm.eh.sjlj.setjmp` stands for exception handling, and the `sjlj` stands for `setjmp/longjmp`.
- `*mut i8` is a pointer to a signed byte. For those with C programming experience, you might recognize this as the pointer to the beginning of a string (e.g., a `*char` type).

**WHAT IS AN INTRINSIC FUNCTION?**

*Intrinsic functions*, generally referred to as *intrinsics*, are functions made available via the compiler rather than as part of the language. Whereas Rust is largely target-agnostic, the compiler has access to the target environment. This access can facilitate extra functionality. For example, a compiler understands the characteristics of the CPU that the to-be-compiled program will run on. The compiler can make that CPU’s instructions available to the program via intrinsics. Some examples of intrinsic functions include

- *Atomic operations*—Many CPUs provide specialist instructions to optimize certain workloads. For example, the CPU might guarantee that updating an integer is an atomic operation. Atomic here is meant in the sense of being indivisible. This can be extremely important when dealing with concurrent code.
- *Exception handling*—The facilities provided by CPUs for managing exceptions differ. These facilities can be used by programming language designers to create custom control flow. The `setjmp` and `longjmp` intrinsics, introduced later in this chapter, fall into this camp.

**WHAT IS LLVM?**

From the point of view of Rust programmers, LLVM can be considered as a subcomponent of `rustc`, the Rust compiler. LLVM is an external tool that’s bundled with `rustc`. Rust programmers can draw from the tools it provides. One set of tools that LLVM provides is intrinsic functions.

LLVM is itself a compiler. Its role is illustrated in figure 12.6.




Figure 12.6 Some of the major steps required to generate an executable from Rust source code. LLVM is an essential part of the process but not one that is user-facing.

LLVM translates code produced by `rustc`, which produces LLVM IR (intermediate language) into machine-readable assembly language. To make matters more complicated, another tool, called a linker, is required to stitch multiple crates together. On Windows, Rust uses `link.exe`, a program provided by Microsoft as its linker. On other operating systems, the GNU linker `ld` is used.

Understanding more detail about LLVM implies learning more about `rustc` and compilation in general. Like many things, getting closer to the truth requires exploring through a fractal-like domain. Learning every subsystem seems to require learning about another set of subsystems. Explaining more here would be a fascinating, but ultimately distracting diversion.

### 12.9.3 Casting a pointer to another type

One of the more arcane parts of Rust's syntax is how to cast between pointer types. You'll encounter this as you make your way through listing 12.17. But problems can arise because of the type signatures of `setjmp()` and `longjmp()`. In this code snippet, extracted from listing 12.17, you can see that both functions take a `*mut i8` pointer as an argument:

```

extern "C" {
    #[link_name = "llvm.eh.sjlj.setjmp"]
    pub fn setjmp(_: *mut i8) -> i32;

    #[link_name = "llvm.eh.sjlj.longjmp"]
    pub fn longjmp(_: *mut i8);
}
  
```

Requiring a `*mut i8` as an input argument is a problem because our Rust code only has a reference to a *jmp buffer* (e.g., `&jmp_buf`).<sup>2</sup> The next few paragraphs work through the process of resolving this conflict. The `jmp_buf` type is defined like this:

```
const JMP_BUF_WIDTH: usize =  
    mem::size_of::<usize>() * 8;           ← This constant is 64 bits wide (8 × 8  
type jmp_buf = [i8; JMP_BUF_WIDTH];      bytes) in 64-bit machines and 32 bits  
                                         wide (8 × 4 bytes) on 32-bit machines.
```

The `jmp_buf` type is a type alias for an array of `i8` that is as wide as 8 `usize` integers. The role of `jmp_buf` is to store the state of the program, such that the CPU's registers can be repopulated when needed. There is only one `jmp_buf` value within listing 12.17, a global mutable static called `RETURN_HERE`, defined on line 14. The following example shows how `jmp_buf` is initialized:

```
static mut RETURN_HERE: jmp_buf = [0; JMP_BUF_WIDTH];
```

How do we treat `RETURN_HERE` as a pointer? Within the Rust code, we refer to `RETURN_HERE` as a reference (`&RETURN_HERE`). LLVM expects those bytes to be presented as a `*mut i8`. To perform the conversion, we apply four steps, which are all packed into a single line:

```
unsafe { &RETURN_HERE as *const i8 as *mut i8 }
```

Let's explain what those four steps are:

- 1 Start with `&RETURN_HERE`, a read-only reference to a global static variable of type `[i8; 8]` on 64-bit machines or `[i8; 4]` on 32-bit machines.
- 2 Convert that reference to a `*const i8`. Casting between pointer types is considered safe Rust, but dereferencing that pointer requires an `unsafe` block.
- 3 Convert the `*const i8` to a `*mut i8`. This declares the memory as mutable (read/write).
- 4 Wrap the conversion in an `unsafe` block because it deals with accessing a global variable.

Why not use something like `&mut RETURN_HERE as *mut i8`? The Rust compiler becomes quite concerned about giving LLVM access to its data. The approach provided here, starting with a read-only reference, puts Rust at ease.

#### 12.9.4 Compiling the *sjlj* project

We're now in a position where possible points of confusion about listing 12.17 should be minor. The following snippet again shows the behavior we're attempting to replicate:

---

<sup>2</sup> `jmp_buf` is the conventional name for this buffer, which might be useful for any readers who want to dive deeper themselves.

```
$ git clone https://github.com/rust-in-action/code rust-in-action
$ cd rust-in-action/ch12/ch12-sjlj
$ cargo run -q
#
#
early return!
finishing!
```

One final note: to compile correctly, the sjlj project requires that rustc is on the nightly channel. If you encounter the error “`#![feature]` may not be used on the stable release channel,” use `rustup install nightly` to install it. You can then make use of the nightly compiler by adding the `+nightly` argument to `cargo`. The following console output demonstrates encountering that error and recovering from it:

```
$ cargo run -q
error[E0554]: #![feature] may not be used on the stable release channel
--> src/main.rs:1:1
  |
1 | #![feature(link_llvm_intrinsics)]
  | ^^^^^^^^^^^^^^^^^^^^^^
  |
error: aborting due to previous error

For more information about this error, try `rustc --explain E0554`.

$ rustup toolchain install nightly
...

$ cargo +nightly run -q
#
##
###
early return!
finishing!
```

### 12.9.5 sjlj project source code

The following listing employs LLVM’s compiler to access the operating system’s `longjmp` facilities. `longjmp` allows programs to escape their stack frame and jump anywhere within their address space. The code for listing 12.6 is in `ch12/ch12-sjlj/Cargo.toml` and listing 12.17 is in `ch12/ch12-sjlj/src/main.rs`.

#### **Listing 12.16 Project metadata for sjlj**

```
[package]
name = "sjlj"
version = "0.1.0"
authors = ["Tim McNamara <code@timmcnamara.co.nz>"]
edition = "2018"

[dependencies]
libc = "0.2"
```

**Listing 12.17 Using LLVM's internal compiler machinery (intrinsics)**

```

1 #![feature(link_llvm_intrinsics)]
2 #![allow(non_camel_case_types)]
3 #![cfg(not(windows))]           ← Only compile
4                                     on supported
5                                     platforms.
6   use libc::{
7     SIGNALRM, SIGHUP, SIGQUIT, SIGTERM, SIGUSR1,
8   };
9   use std::mem;
10
11 const JMP_BUF_WIDTH: usize =
12   mem::size_of::<usize>() * 8;
13 type jmp_buf = [i8; JMP_BUF_WIDTH];
14 static mut SHUT_DOWN: bool = false;           ← When true, the
15 static mut RETURN_HERE: jmp_buf = [0; JMP_BUF_WIDTH];
16 const MOCK_SIGNAL_AT: usize = 3;             ← program exits.
17
18 extern "C" {
19   #[link_name = "llvm.eh.sjlj.setjmp"]
20   pub fn setjmp(_: *mut i8) -> i32;
21
22   #[link_name = "llvm.eh.sjlj.longjmp"]
23   pub fn longjmp(_: *mut i8);
24 }
25
26 #[inline]           ← Allows a recursion
27 fn ptr_to_jmp_buf() -> *mut i8 {           depth of 3
28   unsafe { &RETURN_HERE as *const i8 as *mut i8 }
29 }
30
31 #[inline]           ← An #[inline] attribute
32 fn return_early() {                         marks the function as being
33   let franken_pointer = ptr_to_jmp_buf();      available for inlining, which
34   unsafe { longjmp(franken_pointer) };          is a compiler optimization
35 }                                         technique for eliminating the
36
37 fn register_signal_handler() {
38   unsafe {
39     libc::signal(SIGUSR1, handle_signals as usize); ←
40   }
41 }
42
43 #[allow(dead_code)]
44 fn handle_signals(sig: i32) {
45   register_signal_handler();
46
47   let should_shut_down = match sig {
48     SIGHUP => false,
49     SIGNALRM => false,
50     SIGTERM => true,
51     SIGQUIT => true,
52     SIGUSR1 => true,

```

An `#[inline]` attribute marks the function as being available for inlining, which is a compiler optimization technique for eliminating the cost of function calls.

This is unsafe because Rust cannot guarantee what LLVM does with the memory at `RETURN_HERE`.

Asks libc to associate `handle_signals` with the `SIGUSR1` signal

```
53     _ => false,
54 };
55
56 unsafe {
57     SHUT_DOWN = should_shut_down;
58 }
59
60 return_early();
61 }
62
63 fn print_depth(depth: usize) {
64     for _ in 0..depth {
65         print!("#");
66     }
67     println!();
68 }
69
70 fn dive(depth: usize, max_depth: usize) {
71     unsafe {
72         if SHUT_DOWN {
73             println!("!");
74             return;
75         }
76     }
77     print_depth(depth);
78
79     if depth >= max_depth {
80         return;
81     } else if depth == MOCK_SIGNAL_AT {
82         unsafe {
83             libc::raise(SIGUSR1);
84         }
85     } else {
86         dive(depth + 1, max_depth);
87     }
88     print_depth(depth);
89 }
90
91 fn main() {
92     const JUMP_SET: i32 = 0;
93
94     register_signal_handler();
95
96     let return_point = ptr_to_jmp_buf();
97     let rc = unsafe { setjmp(return_point) };
98     if rc == JUMP_SET {
99         dive(0, 10);
100    } else {
101        println!("early return!");
102    }
103
104    println!("finishing!")
105 }
```

## 12.10 A note on applying these techniques to platforms without signals

Signals are a “UNIX-ism.” On other platforms, messages from the OS are handled differently. On MS Windows, for example, command-line applications need to provide a handler function to the kernel via `SetConsoleCtrlHandler`. That handler function is then invoked when a signal is sent to the application.

Regardless of the specific mechanism, the high-level approach demonstrated in this chapter should be fairly portable. Here is the pattern:

- Your CPU generates interrupts that require the OS to respond.
- Operating systems often delegate responsibility for handling interrupts via some sort of callback system.
- A callback system means creating a function pointer.

## 12.11 Revising exceptions

At the start of the chapter, we discussed the distinction between signals, interrupts, and exceptions. There was little coverage of exceptions, directly. We have treated these as a special class of interrupts. Interrupts themselves have been modeled as signals.

To wrap up this chapter (and the book), we explored some of the features available in rustc and LLVM. The bulk of this chapter utilized these features to work with signals. Within Linux, signals are the main mechanism that the OS uses to communicate with applications. On the Rust side, we have spent lots of time interacting with `libc` and unsafe blocks, unpacking function pointers, and tweaking global variables.

### Summary

- Hardware devices, such as the computer’s network card, notify applications about data that is ready to be processed by sending an interrupt to the CPU.
- Function pointers are pointers that point to executable code rather than to data. These are denoted in Rust by the `fn` keyword.
- Unix operating systems manage job control with two signals: `SIGSTOP` and `SIGCONT`.
- Signal handlers do the least amount of work possible to mitigate the risk of triggering race conditions caused when multiple signal handlers operate concurrently. A typical pattern is to set a flag with a global variable. That flag is periodically checked within the program’s main loop.
- To create a global variable in Rust, create a “mutable static.” Accessing mutable statics requires an unsafe block.
- The OS, signals, and the compiler can be utilized to implement exception handling in programming languages via the `setjmp` and `longjmp` syscalls.
- Without the `unsafe` keyword, Rust programs would not be able to interface effectively with the OS and other third-party components.



# *index*

## Symbols

! type 79–90  
? operator 275  
'static lifetime 62  
() type 79–90  
\*const fn() -> () type 406  
\*const i8 413  
\*const T 183  
\*mut i32 183  
\*mut i8 411–413  
\*mut T 183  
\*mut u32 376  
\*mut u8 376  
&'static str 189  
&dyn Rng 259  
&dyn Trait 256  
&mut dyn Trait 256  
&mut T 119  
&Rng 260  
&str type 61, 189, 222, 242, 292, 387  
&T 119  
&Trait 256  
&[u8] 292, 387  
#![allow(unused\_variables)] attribute 78  
#[core\_intrinsics] attribute 373  
#[no\_main] attribute 374  
#[no\_mangle] attribute 373, 389  
#[no\_std] attribute 373–374, 389  
#[repr(u8)] 389  
#[cfg(all(...))] 227  
#[cfg(any(...))] 227

#[cfg(not(...))] 227  
#[cfg(target\_os ! 227  
#[derive(...)] block 152  
#[derive(Debug)] 98, 272–273

## A

abort() function 373  
abort exception 391  
absolute time 296  
abstract classes 40  
ActionKV 228, 231  
actionkv  
conditional compilation 226–228  
front-end code 224–228  
full code listing 237–241  
libactionkv crate 228–249  
overview 222–223  
ActionKV::load(). open() 228  
ActionKV::open() 228–229  
activation frames 188  
address space 177  
add\_with\_lifetimes() 57  
akv\_mem executable 223  
aliasing 91  
alloc::raw\_vec::RawVec type 187  
alloc() 194, 201  
allocation records 188  
allocator 194  
alloc module 187  
always on mode 314  
Amazon Web Services (AWS) 2  
anonymous functions 9, 199, 329–330  
application-level protocol 254

Arc 354  
Arc<Mutex<\_>> 363  
Arc<Mutex<T>> 133, 354  
Arc<T> 133, 185  
arena::Arena 201  
arena::TypedArena 201  
arrays, making lists with 64–65  
Artist struct 344–345  
as keyword 39  
asm! macro 395  
AsMut<T> 189  
as operator 39  
AsRef<str> 189  
AsRef<T> 189  
associative arrays 242  
asynchronous interrupts 392  
asynchronous programming 362  
atomic operations 411  
atomic reference counter 133  
avatar generator 341–360  
render-hex 342–349  
generating SVGs 346  
input parsing 344  
interpreting  
instructions 344–346  
running 342  
source code 346–349  
spawning a thread per logical task 351–353  
functional programming style 351–352  
parallel iterators 352–353  
thread pools 353–360  
channels 356  
implementing task queues 358–360

avatar generator (*continued*)  
 one-way communication 354–356  
 two-way communication 356–358  
**AWS (Amazon Web Services)** 2

**B**

back pressure 354  
 base 2 (binary) notation 37–38  
 base 8 (octal) notation 37–38  
 base 16 (hexadecimal)  
   notation 37–38  
 b as i32 type cast 39  
 basic\_hash 243  
 big endian format 143  
 BigEndian type 232  
 [[bin]] entry 247  
 bincode format 214–216  
 bin section 223  
 bit endianness 143  
 bit numbering 143  
 bit patterns and types 137–139  
 bool 87  
 boot image 367  
 bootimage crate 366–367  
 bootloader 377  
 borrow checker 107  
 borrowed type 62  
 bounded queues 354  
 bounds checking 47  
 Box::new(T) 192  
 Box<dyn Error> 271–272  
 Box<dynstd::error::Error>  
   type 255  
 Box<dyn Trait> 256  
 Box<T> 187, 191  
 Box<Trait> 256  
 break keyword 50, 80  
   breaking from nested  
     loops 49  
   overview 48–49  
**BTreeMap**  
   deciding between 245–246  
   keys and values 241–243  
   retrieving values from 244–245  
 buffered I/O 73  
 buffer overflow 13  
 buffers 21  
 BufReader. BufReader 72  
 bug 22  
 build-command 371  
 byteorder::LittleEndian 232

byteorder::ReadBytesExt  
   trait 232  
 byteorder::WriteBytesExt  
   trait 232  
 byteorder crate 232  
 ByteString type 228  
 ByteStr type 228

**C**

cache-friendly data  
   structures 19  
 capitals 244  
 capitals["Tonga"] 245  
 capitals.index("Tonga") 245  
 captures 330  
 cargo add command 45  
 cargo-binutils crate 366–367  
 cargo bootimage command 374  
 cargo build command 371  
 cargo build –release flag 192  
 cargo build utility 18, 192  
 cargo commands 11  
 cargo doc –no-deps flag 106  
 cargo doc utility 18  
 cargo-edit crate 45  
 cargo init command 34  
 cargo new command 6, 18  
 cargo run command 6, 8, 10, 18,  
   34, 44, 54, 90, 265  
 cargo test 154  
 cargo tool  
   compiling projects with 33–34  
   creating projects with 6, 18  
   rendering docs with 104–106  
   testing projects with 154  
 cargo xbuild 371  
 carry flag 165  
 c\_char type 182  
 Cell<T> 185  
 cfg annotation 326  
 cfg attribute 226, 250  
 –cfg ATTRIBUTE command-line  
   argument 227  
 ch6-particles 200  
 char type 62  
 check\_status() function 109,  
   111–112, 115–116  
 check\_status(sat\_a) 112  
 checksums, validating I/O  
   errors with 234–236  
 CHIP-8 specification 165  
 choose() method 257  
 chrono::Local 299  
 chunks() option 219  
 clap::App type 301  
 clap::Arg type 301  
 class keyword 84  
 clear intent 221  
 Clock::set(t) 313  
 clock command 302  
 Clock struct 300, 306  
 clock synchronization 314  
 .clone() method 129–130, 153  
 Clone trait 129–131, 153  
 close() method 87  
 closures 9  
   functions vs. 340–341  
   overview 330–331  
 collect() method 351–352  
 collection 47  
 Color type 382  
 Command::Noop 360  
 command-line arguments,  
   supporting 70–72  
 command-line utilities 23–24  
 Common control flow  
   mechanisms 8  
 compilers 33  
 compiler target 226, 369  
 compile time 11  
 compiling 10  
 complex numbers 43–45  
 compound data types  
   adding methods to struct with  
     impl 84–87  
 enum  
   defining 95–96  
   using to manage internal  
     state 96–98  
 inline documentation 103–106  
   rendering docs for crates  
     and dependencies 104–106  
   rendering docs for single  
     source file 104  
 modeling files with struct 80–83  
 plain functions 78–80  
 protecting private data 102  
 returning errors 87–94

- computer architecture 206  
 concurrency 328  
   anonymous functions 329–330  
   avatar generator 341–360  
     render-hex 342–349  
     spawning a thread per logical task 351–353  
   thread pools 353–360  
   closures vs. functions 340–341  
   task virtualization and 360–363  
     containers 363  
     context switches 362  
     processes 363  
     reasons for using operating systems 363  
     threads 362  
     WebAssembly 363  
   threads 330–340  
     closures 330–331  
     effect of spawning many threads 333  
     effect of spawning some threads 331–332  
     reproducing results 335–338  
     shared variables 338–340  
     spawning threads 331  
     `thread::yield_now()`  
       method 338  
   conditional branching 49–51  
   conditional compilation 9, 226  
   constellation 108  
   const keyword 88, 91  
   const USAGE 226  
   const values 381, 405  
   containers 363  
   container variable 45  
   context switches 362  
   contiguous layout 194  
   continue keyword 8, 47  
   convert() function 345–346  
   copy semantics 113, 153  
   Copy trait 111–112, 114, 129–131, 153  
   core::fmt::Write trait 385–386  
     implementing 386–387  
     reimplementing panic()  
       385–386  
   core::intrinsic::abort() 385  
   core::ptr::Shared type 187  
   core::ptr::Unique,  
     core::ptr::Shared type 185  
   core::ptr::Unique type 187  
   core::write! macro 385  
   core module 187  
   coroutines 361  
   CPU emulation 158–173  
     CPU 4 173  
     CPU RIA/1 (Adder) 159–163  
       defining CPU 159  
       emulator's main loop 160–161  
       full code listing 163–164  
       interpreting opcodes 161–163  
       loading values into registers 159–160  
       terminology 159  
     CPU RIA/2 (Multiplier) 164–167  
       expanding CPU to support memory 164–165  
       full code listing 166–167  
       handling integer overflow 165  
       reading opcodes from memory 165  
   CPU RIA/3 (Caller) 167–173  
     defining functions and loading into memory 168–169  
     expanding CPU to include stack support 167–168  
     full code listing 170–173  
     implementing CALL and RETURN opcodes 169–170  
     cpu.position\_in\_memory variable 170  
     cpu.run() 170  
   CPU struct 164  
   CRC32 (cyclic redundancy check returning 32 bits) 235  
   create() method 219  
   cryptographic hash function 235  
   CubeSat 108, 111, 115, 119–120  
   CubeSat.CubeSat.mailbox 118  
   CubeSat.messages vector 120  
   current\_instruction field 164  
   Cursor.print() 383  
   Cursor struct 382–383
- 
- D**
- dangling pointers 12  
 data  
   bit patterns and types 137–139  
   CPU emulation 158–173  
   CPU 4 173  
   CPU RIA/1 (Adder) 159–163  
   CPU RIA/2 (Multiplier) 164–167  
   CPU RIA/3 (Caller) 167–173  
   fixed-point number formats 152–157  
   floating-point numbers 144–152  
     dissecting 150–152  
     inner workings of f32 type 144–145  
     isolating exponent 146–147  
     isolating mantissa 148–150  
     isolating sign bit 146  
     representing decimals 143–144  
   generating random probabilities from random bytes 157–158  
   integers  
     endianness 142–143  
     integer overflow 139–143  
   data-oriented programming 19  
   data processing 24  
   data races 13  
   DateTime<FixedOffset> 306  
   debug\_assertions attribute 228  
   debugging 221  
   Debug trait 99, 153, 272–273  
   declaration statements 51  
   decode\_f32\_parts() 150  
   deconstruct\_f32() 150  
   DELETE case 95  
   delete <key> 224  
   [dependencies] section 44, 353  
   dereference operator 53, 192  
   dereferencing a pointer 183  
   deserialization 249  
   Deserialize trait 214  
   desktop applications 25  
   Display trait 99–102, 272–274  
   dive() 408  
   dns.rs 283  
   domain\_name 264  
   domain name resolution 261  
   Drop 115, 132  
   drop(&mut self) 115  
   Dwarf struct 257  
   dynamically-sized types 65, 190, 256  
   dynamic dispatch 256

dynamic memory allocation  
    194  
    defined 194–199  
    impact of 199–201  
dynamic typing 65  
dyn keyword 260

**E**

Elf struct 257  
else blocks 49–51  
enchant() method 257, 259  
encoding 138  
endianness 137, 142–143  
entry point 377  
enumerate() method 63  
enums 51, 77, 84, 109  
    annotating with  
        #[derive(Debug)] 273  
    controlling in-memory representation of 382  
    defining 95–98  
    defining enums that include upstream errors as variants 273  
    reasons for using 382  
    using to manage internal state 96–98  
EOF (end of file) 230  
epochs 296  
eprintln! 10  
Eq trait 152–153  
Err 219  
Err(E) 10  
Err(err) 270  
Err(String) 92  
errno 87, 91  
error handling 268–277  
    clock project 313  
    inability to return multiple error types 269–271  
    returning errors 87–94  
        modifying known global variables 87–91  
    Result return type 92–94  
unwrap() and expect() 277  
wrapping downstream errors 272–276  
    annotating with  
        #[derive(Debug)]  
        273  
    defining enums that include the upstream errors as variants 273  
map\_err() 274–276

std::convert::From trait  
    276  
std::error::Error trait 274  
std::fmt::Display trait  
    273–274  
Error trait 274  
ethernet.rs 283  
exceptions 391  
    defined 391–393  
    handling 379–380, 411  
    revising 417  
executable 361  
\_exit() function 377  
.expect() method 219, 228, 264, 277, 292  
exponents, isolating 146–147  
expression statement 51  
extending applications 24  
extern "C" 374, 411

**F**

f1\_length 81  
f1\_name 81  
f32::EPSILON 42  
f32\_from\_parts() method  
    150  
f32\_i32 139  
f32 type 38, 41, 144, 150,  
    154–155, 232  
f4 variable 92  
f64::EPSILON 42  
f64 type 38, 41, 155  
fast clocks 297  
faults 391–392  
fearless concurrency 27  
fields variable 10  
File::create method 220  
File::open method 220, 271  
<file> command 33  
file descriptor 87  
File object 84  
files and storage  
    actionkv  
        conditional  
            compilation 226–228  
        front-end code 224–228  
        libactionkv crate 228–249  
        overview 222–223  
    file formats  
        creating 214–216  
        defined 213–214  
        writing data to disk with  
            serde and bincode  
            format 214–216

file operations 219–222  
    opening files and controlling  
        file mode 219–220  
        std::fs::Path trait 220–222  
hexdump clones 217–219  
key-value stores 222–223  
    actionkv 222–223  
    key-value model 222

FileState subtype 100  
File struct 81  
FILETIME 308  
File type 81, 96, 100  
fixed-point number  
    formats 152–157  
FledgeOS 365–368  
    compilation instructions 370  
    development environment  
        setting up 366–367  
        verifying 367–368  
exception handling 379–380  
first boot 368–369  
loops 377–379  
panic handling 374–375,  
    385–387  
    core::fmt::Write trait  
        385–387  
    reporting error to user 385  
source code 370–374, 378–  
    380, 383, 387  
\_start() function 377  
text output 381–383  
    creating type that can print to VGA frame  
        buffer 382–383  
    enums 382  
    printing to screen 383  
    writing colored text to screen 381  
writing to screen with VGA-compatible text  
    mode 375–377

floating-point numbers 36–37,  
    144–152  
dissecting 150–152  
inner workings of f32  
    type 144–145  
isolating exponent 146–147  
isolating mantissa 148–150  
isolating sign bit 146  
representing decimals 143–144  
flow control 45–52  
    break keyword  
        breaking from nested loops 49  
    overview 48–49

flow control (*continued*)  
 continue keyword 47  
 else blocks 49–51  
 for loop  
   anonymous loops 46  
   index variable 46–47  
   overview 45–46  
 if else blocks 49–51  
 if keyword 49–51  
 loop keyword 48  
 match keyword 51–52  
 while loop  
   endless looping 48  
   overview 47  
   stopping iteration once a duration is reached 47–48  
`fmt::Result` 100  
`.fmt()` method 100  
`fn` keyword 35, 404–405, 417  
`fn noop()` 406  
`fn x(a: String) type`  
   signature 189  
`fn x<T: AsRef<str>> (a: T) type`  
   signature 189  
 for item in collection 47  
 for loop  
   anonymous loops 46  
   index variable 46–47  
   overview 45–46  
 format! macro 99  
 frame buffer 374, 376  
 frames 279  
`f.read(buffer)` function 84  
`f.read_exact()` method 219  
`free()` 194, 201  
 freestanding applications 363  
`from()` method 220, 276, 318  
`From<f64>` implementation 154  
`From` trait 154, 276, 318–319  
 function pointers 341, 405–406  
 functions 56–60  
   anonymous functions 329–330  
   calling 35–36  
   closures vs. 340–341  
   defining 52  
   explicit lifetime  
   annotations 56–58  
   generic functions 58–60  
   intrinsic functions  
   defined 411  
   setting up 409–412  
   using plain functions to experiment with APIs 78–80  
`fview` 217–218

**G**

GC (garbage collection) 131  
`generate_svg()` 346  
 generic functions 58–60  
 generic type 58  
`.get()` method 245  
`git clone -depth` 90  
 global variables  
   signal handling with custom actions 401–402  
   using to indicate that shutdown has been initiated 402–405  
`goto fail` 22  
`goto fail; bug` 22–23  
`goto` keyword 49  
`grep-lite` 60–63  
`grep-lite -help` 72  
 ground station, definition 108  
`GroundStation` type 119–120, 123

**H**

handlers 338  
`handlers.pop()` 336  
`handlers` vector 336  
`handle_signals()` function 402  
`handle_sigterm()` 404  
`handle_sigterm` as `usize` 405  
`handle_sigusr1()` 404  
 hardware interrupts 391, 395  
 hash collision 243  
 hashes 241  
`HashMap`  
   creating and populating with values 243–244  
   deciding between 245–246  
   keys and values 241–243  
   retrieving values from 244–245  
 hash map 242  
 hash table 241–242  
 haystack 53  
 heading 344  
 heap 18, 190–192  
`HeapAlloc()` call 194  
`HeapFree()` 194  
 Heartbleed 21–22  
 “Hello, world!” 5–8  
 hexdump clones 217–219  
 high accuracy 297  
 high byte 161  
 higher-order programming 9

high nibble 161  
 high resolution 297  
`hlt` x86 instruction 378  
 hostnames, converting to IP addresses 261–268  
**HTTP**  
   HTTP GET requests, generating with `reqwest` library 254–256  
   raw 283–292  
`http-equiv` attribute 254  
`http.rs` file 283

**I**

`i16` type 38, 232  
`i32` type 38, 183  
`i64` type 38  
`i8` type 38  
 if else blocks 49–51  
 if keyword 49–51  
 if let construct 10  
 if let `Ok(T)` 10  
`impl` blocks 78, 84, 130, 274, 276  
   adding methods to struct with 84–87  
   simplifying object creation by implementing 84–87  
`impl` keyword 98  
`INDEX_KEY` value 247  
 Index trait 245  
 infix notation 36  
 inline assembly 379  
 inline documentation 103–106  
   rendering docs for crates and dependencies 104–106  
   rendering docs for single source file 104  
`insert <key> <value>` 224  
 integers  
   base 2, base 8, and base 16  
   notation 37–38  
 endianness 142–143  
 integer overflow 139–143  
   overview 36–37  
 interior mutability 132–133, 185  
 interrupts  
   defined 391–393  
   effect on applications 393–395  
   hardware interrupts 395  
   signals vs. 391–393  
   software interrupts 395

.into() method 318  
intrinsic functions 373  
  defined 411  
  setting up 409–412  
intrinsic::abort() 375, 389  
IP addresses, converting host-  
  names to 261–268  
ip tuntap list subcommand  
  283  
.is\_finite() method 43  
isize type 38  
.is\_nan() method 43  
ISO 8601 standard 299–305  
is\_strong 189  
.iter() method 245  
iterator invalidation 13  
.iter\_mut() variant 245  
it object 257

**J**

jmp\_buf type 413  
join() function 331, 336

**K**

kernel 365–368  
  compilation instructions 370  
  development environment  
    setting up 366–367  
    verifying 367–368  
exception handling 379–380  
first boot 368–369  
loops 377–379  
panic handling 374–375,  
  385–387  
core::fmt::Write trait  
  385–387  
reporting error to user  
  385  
source code 378–380, 383,  
  387  
source code listings 370–374  
\_start() function 377  
text output 381–383  
  creating type that can print  
    to VGA frame  
    buffer 382–383  
  enums 382  
  printing to screen 383  
  writing colored text to  
    screen 381  
writing to screen with VGA-  
  compatible text  
  mode 375–377

.keys() method 245  
.keys\_mut() variant 245  
key-value stores 222–223  
  actionkv 222–223  
  key-value model 222  
kill command 398–399

**L**

lambda functions 9, 199, 329  
language items 380  
Last In, First Out (LIFO) 188  
let keyword 91  
letters variable 16  
lexical scopes 35  
libactionkv::ActionKV 228  
libactionkv crate 228–249  
  adding database index to  
    actionkv 246–249  
BTreeMap  
  deciding between 245–246  
  keys and values 241–243  
  retrieving values from  
    244–245  
HashMap  
  creating and populating  
    with values 243–244  
  deciding between 245–246  
  keys and values 241–243  
  retrieving values from  
    244–245  
initializing ActionKV  
  struct 228–230  
inserting new key-value pairs  
  into existing  
    database 236–237  
processing individual  
  records 230–232  
validating I/O errors with  
  checksums 234–236  
writing multi-byte binary data  
  to disk in a guaranteed  
    byte order 232–233  
libc::SIG\_IGN 407  
libc::signal() 404, 407  
libc::timeval 308  
libc library  
  non-Windows clock  
    code 307–308  
  setting the time 306–308  
  type naming  
    conventions 306–307  
lifetime 110–112  
lifetime elision 57  
LIFO (Last In, First Out) 188  
linear memory 363  
link\_name attribute 411  
lists 63–67  
  arrays 64–65  
  slices 65  
  vectors 66–67  
little endian format 143  
LLVM 411–412  
llvm.eh.sjlj.setjmp 411  
llvm-tools-preview  
  component 367  
llvm-tools-preview toolchain  
  component 368  
load() 236  
long int 298  
longjmp 408–409, 412, 414,  
  417  
loop keyword 48, 80, 281  
loops  
  break keyword  
    breaking from nested  
      loops 49  
    overview 48–49  
  continue keyword 47  
FledgeOS 377–379  
  interacting with CPU  
    directly 377–378  
    source code 378–379  
for loop  
  anonymous loops 46  
  index variable 46–47  
  overview 45–46  
loop keyword 48  
while loop  
  endless looping 48  
  overview 47  
  stopping iteration once a  
    duration is reached  
    47–48  
low byte 161  
low-level programming 2  
low nibble 161

**M**

MAC addresses 277–281  
macros 36  
main.rs file 283  
Mandelbrot set 54–56  
mantissa 144, 148–150  
map() method 351–352  
map\_err() method 272,  
  274–276  
match keyword 51–52, 281  
mem::transmute 157

memory  
 pointers 178–187  
 overview 176–178  
 pointer ecosystem 185–186  
 raw pointers 183–185  
 smart pointer building  
   blocks 186–187  
 providing programs  
   with 187–201  
 dynamic memory  
   allocation 194–201  
 heap 190–192  
 stack 188–190  
 virtual memory 202–211  
   having processes scan their  
     own memory 203–205  
 overview 202–203  
 reading from and writing to  
   process memory 211  
 scanning address  
   spaces 208–210  
 translating virtual addresses  
   to physical  
     addresses 205–207  
 memory fragmentation 206  
 memory management unit  
   (MMU) 203, 206  
 message ID 263  
 messages.push() 120  
 Message struct 263  
 MessageType 264  
 message type 263  
 <meta> HTML tag 254  
 mkdir <project> 34  
 MMU (memory management  
   unit) 203, 206  
 mobile applications 25  
 mock CubeSat ground station  
   lifetime issue 110–112  
   special behavior of primitive  
     types 112–114  
 mock\_rand() 158  
 mod keyword 156  
 most significant bit 143  
 most significant byte 143  
 move keyword 330, 340  
 move semantics 113, 153  
 multicast mode 279  
 Mutex 354

**N**

NaiveTime 298  
 name mangling 373  
 namespaces 363

NAN (Not a Number)  
   values 148  
 NativeEndian type 232  
 n\_bits 149  
 networking  
   error handling 268–277  
   inability to return multiple  
     error types 269–271  
   unwrap() and expect() 277  
   wrapping downstream  
     errors 272–276  
 generating HTTP GET  
   requests with  
     request 254–256  
 implementing state machines  
   with enums 281–282  
 MAC addresses 277–281  
 overview 252–254  
 raw HTTP 283–292  
 TCP 260–268  
   converting hostnames to IP  
     addresses 261–268  
   port numbers 261  
   raw 282  
 trait objects 256–260  
   defined 256  
   function of 256  
   rpg project 257–260  
 virtual networking  
   devices 282–283  
 Network Time Protocol. *See* NTP  
   (Network Time Protocol)  
 Never type 79  
 new() method 44–45, 84–87  
 newtype pattern 81  
 nibbles 161  
 nightly toolchain 367  
 nnn variable 161  
 non-blocking I/O 362  
 None variant 177  
 nonlocal control transfer 408  
 noop() function 406  
 No Rust 2.0 27  
 Not a Number (NAN)  
   values 148  
 Notify opcodes 264  
 nth() method 219  
 NTP (Network Time  
   Protocol) 293, 314–321  
 adjusting local time  
   316–318  
 converting between time rep-  
   resentations that use dif-  
   ferent precisions and  
   epochs 318–319

full code listing 319–321  
 sending requests and inter-  
   preting responses  
   314–316  
 NTPResult 316  
 null pointer 177  
 num::complex::Complex  
   type 44  
 numbers 36–45  
   comparing  
     different types 39–43  
     operators for 38–43  
   complex numbers 43–45  
   decimal (floating-point)  
     numbers 36–37  
 integers  
   base 2, base 8, and base 16  
   notation 37–38  
   overview 36–37  
   rational numbers 43–45

**O**

offset() method 376–377, 389  
 Ok state 92  
 one\_at\_bit\_i 149  
 OpCode enum 264  
 opcodes  
   implementing CALL and  
     RETURN opcodes  
     169–170  
   interpreting 161–163  
   reading from memory 165  
 open() method 87, 92, 219  
 -open cargo doc 105  
 Operation enum 344  
 operator overloading 36  
 Option<&V> 245  
 Option<T> type 177  
 Option type 52, 250, 263  
 -O rustc 141  
 ownership 115  
   mock CubeSat ground  
     station 108–114  
     lifetime issue 110–112  
     special behavior of primi-  
       tive types 112–114  
   overview 115  
   resolving issues with 118–133  
     duplicating values 128–131  
     using fewer long-lived  
       values 123–126  
   using references where full  
     ownership is not  
       required 119–122

ownership (*continued*)  
 wrapping data within specialty types 131–133  
 shifting 115–117

---

**P**

[package.metadata.bootimage] 371  
 page fault 202  
 pages, memory 202, 206  
 page table 202  
 .panic() method 385–386  
 panic handling 385–387  
   core::fmt::Write trait  
     implementing 386–387  
     reimplementing  
       panic() 385–386  
   reporting error to user 385  
 PanicInfo struct 375  
 parallelism 328  
 parallel iterators 352–353  
 .par\_bytes() method 353  
 .par\_iter() method 351, 353  
 parity\_bit() function 235  
 parity bit checking 235–236  
 parity checking 235  
 parse::<f32>() annotation 10  
 parse::<Ipv6Addr>() 271  
 parse() function 10, 351, 358  
 .parse() method 10, 345  
 PartialEq trait 99, 152–153  
 partial equivalence relation 41  
 Particle struct 195  
 password argument 189  
 password variable 190  
 <path> tag 346  
 PathBuf value 220  
 Path trait 220–222  
 Path value 220–221  
 pause variable 338  
 PIC (Programmable Interrupt Controller) 395  
 PID (process ID) 398  
 pointers 178–187  
   function pointers 405–406  
   overview 176–178  
   pointer ecosystem 185–186  
   raw pointers 183–185  
   smart pointer building  
     blocks 186–187  
 Pointers type 178  
 polymorphism 256  
 pop() 336  
 portability 221

port numbers 261  
 position\_in\_memory 164–165,  
   167, 173  
 predicates 47  
 prelude 353  
 primitive types, special behavior  
   of 112–114  
 print() method 386  
 println! 10, 36–37, 98–99, 139,  
   153, 250  
 processes 361, 363  
 process ID (PID) 398  
 process\_record() function 231  
 process\_vm\_readv() 211  
 process\_vm\_writev() 211  
 program counter 165  
 Programmable Interrupt Controller (PIC) 395  
 programs 361  
 promotion 39  
 pub(crate) 157  
 pub(in path) 157  
 pub(self) 157  
 pub(super) 157  
 pub keyword 157  
 push() method 360

---

**Q**

Q7 154  
 -q cargo 11  
 QEMU 366–367  
 Q format 152  
 quantizing the model 152  
 queries 263  
 Query opcodes 264  
 Query struct 263

---

**R**

radix 144  
 rand::random() 401  
 rand::rngs::ThreadRng  
   struct 259  
 rand::Rng trait 259  
 rand::seq::SliceRandom  
   trait 257  
 random bytes, generating random probabilities  
   from 157–158  
 rational numbers 43–45  
 raw pointers 183–185  
 Raw pointers type 178  
 Rc::new() 131  
 Rc<RefCell<T>> 132–133, 185  
 Rc<T> 131–133, 185  
 Rc<T>.Rc<T> 131  
 RDTSC instruction 296  
 read(f, buffer) method 84  
 read function 78  
 .read\_opcode() method 165  
 ReadProcessMemory() 211  
 Read trait 98–99, 219  
 real memory 202  
 real-time clock 294, 296  
 Receiver 354  
 Receiver<i32> 356  
 Receiver<T> 356  
 .recv() method 120, 354  
 recv(rx) -> 356  
 recv\_from() 268  
 refactoring 128  
 RefCell<T> 185  
 reference counting 18, 91, 131  
 reference operator 53  
 references 53–54, 119–122  
 References type 178  
 registers 164  
 register\_signal\_handler()  
   function 403  
 register\_signal\_handlers()  
   function 402  
 regular expressions, adding support for 68–69  
 release build 11  
 -release cargo 11, 192  
 .remove() method 245  
 render-hex  
   running 342  
   single-threaded 342–349  
     generating SVGs 346  
     input parsing 344  
     interpreting  
       instructions 344–346  
       source code 346–349  
 repeat expression 64  
 report() function 79  
 ReportingAllocator struct 195  
 repr attribute 382  
 request::get(url) method 292  
 request/response mode 314  
 request::get() 255  
 request library, generating  
   HTTP GET requests  
     with 254–256  
 resource-constrained  
   environments 24–25  
 resource record type 263  
 response 314  
 response.text() method 255

response variable 255  
 Result 35, 40, 94, 228, 255, 272  
`Result<File, String>` function 92  
`Result` return type 92–94  
`Result<T, E>` 269  
`Result` type 268, 313  
`ret()` method 170  
`RETURN_HERE` mutable static 413  
`return` keyword 9, 50  
`RETURN` opcode 167, 169–170  
 RFC 3339 301  
`Rng` trait 259  
 RPC 2822 301  
`rpg` (role playing game) project 257–260  
`run()` method 160  
`run_command` 371  
 Rust  
 "Hello, world!" 5–8  
 advocating for at work 3–4  
 command-line arguments 70–72  
 compiling source code into running programs 33–34  
 compiling projects with `cargo` 33–34  
 compiling single files with `rustc` 33  
 deployments 23–26  
 command-line utilities 23–24  
 data processing 24  
 desktop applications 25  
 extending applications 24  
 mobile applications 25  
 resource-constrained environments 24–25  
 server-side applications 25  
 systems programming 26  
 web browsers 26  
 downloading source code 8  
 downsides of 20–21  
 compile times 20–21  
 cyclic data structures 20  
 hype 21  
 size of language 21  
 strictness 21  
 features of 11–12, 19–20  
 community 26  
 concurrency 20  
 memory efficiency 20  
 performance 19–20  
 flow control 45–52  
 break keyword 48–49

conditional branching 49–51  
`continue` keyword 47  
`for` loop 45–47  
`loop` keyword 48  
`match` keyword 51–52  
`while` loop 47–48  
 functions 52, 56–60  
 explicit lifetime annotations 56–58  
 generic functions 58–60  
 goals of control 18–19  
 productivity 16–18  
 safety 12–16  
`grep-lite` 60–63  
 lists 63–67  
 arrays 64–65  
 slices 65  
 vectors 66–67  
`Mandelbrot` set 54–56  
 numbers 36–45  
 base 2, base 8, and base 16 notation 37–38  
 comparing 38–43  
 complex numbers 43–45  
 floating-point numbers 36–37  
 integers 36–38  
 rational 43–45  
 reading from files 72–75  
 from `stdin` 74  
 references 53–54  
 syntax defining variables and calling functions 35–36  
 overview 34–36  
 technology leaders and startups that use 2–3  
 terminology 26–27  
 text processing 8–11  
 third-party code 67–70 adding support for regular expressions 68–69  
 generating the third-party crate documentation locally 69–70  
 managing toolchains with `rustup` 70  
 TLS security case studies 21–23  
 goto fail 22–23  
 Heartbleed 21–22

`rustc` 33, 141, 412  
`rustc -codegen opt-level` 192  
`rustc` compiler, compiling single files with 33  
`rustc <file>` command 33  
`rustdoc` tool, rendering docs for single source file 104  
`rust-src` component 367  
`rust-strip` 367  
`rustup default stable` command 367  
`rustup doc` 70  
`rustup install nightly` 414  
`rustup target list` 369  
`rustup` tool, managing tool-chains with 70

## S

---

`-s` argument to resolve 262  
`sat_id` 111  
`save scum` 362  
 segmentation fault 203–204  
 segments 203  
`select!` macro 356  
`self.messages` collection 126  
 semantic versioning 27  
`send()` method 120, 354  
`Sender` 354  
`Sender<i32>` 356  
`Sender<T>` 356  
`serde` crate 214–216  
 serialization 249  
`Serialize` trait 214  
 server-side applications 25  
`set()` type 300  
`SetConsoleCtrlHandler` handler function 417  
`set_extension()` method 221  
`setjmp` 408–409, 412, 417  
`setjmp/longjmp` 411  
`SetSystemTime()` 313  
`settimeofday` function 306–308, 313  
 shared ownership 185  
 shared variables 338–340  
`SHUT_DOWN` value 401  
`SIGCONT` signal 397, 399–400, 417  
`SIG_DFL` 407  
`SIGHUP` signal 399  
`SIGINT` signal 396, 399  
`SIGKILL` signal 396, 398, 400, 407

signals 407–408  
     application-defined  
         signals 405–406  
     applying techniques to platforms without signals 417  
     defined 391–393  
     handling 395–400  
         default behavior 395–396  
         listing all signals supported by OS 399–400  
         suspending and resuming program operation 397–399  
     with custom actions 400–405  
 interrupts vs. 391–393  
 sjlj project 409  
     casting pointers to another type 412–413  
     compiling 413–414  
     setting up intrinsics 409–412  
     source code 414–415  
 sign bit, isolating 146  
 significand 144  
 signs 144  
 SIGQUIT signal 400  
 SIGSTOP signal 397–398, 400, 407, 417  
 SIGTERM signal 396, 399  
 SIGTSTP signal 400  
 SIGUSR1 405  
 SIGUSR2 405  
 Sized 188  
 sjlj project 409  
     casting pointers to another type 412–413  
     compiling 413–414  
     setting up intrinsics 409–412  
     source code 414–415  
 slices, making lists with 65  
 smart pointers 185–187  
 software interrupts 391, 395  
 Some(T) variant 177  
 specialty types, wrapping data within 131–133  
 spin\_loop\_hint()  
     instruction 338  
 src/main.rs 54  
 SSLVerifySignedServerKey-Exchange function 22  
 stack 18  
     defined 188–190  
     expanding CPU emulation to include stack support 167–168  
 stack frames 188  
     \_start() function 374, 377, 383  
 static binaries 24  
 static dispatch 256  
 static keyword 401  
 static memory 62  
 static methods 44, 84  
 static mut 88, 401  
 static values 405  
 static variable 405  
 StatusMessage 112  
 Status opcodes 264  
 std::arc::Weak type 187  
 std::cell::RefCell type 187  
 std::cell::UnsafeCell type 187  
 std::clone::Clone 128–129  
 std::cmp::Eq 41  
 std::cmp::PartialEq 38  
 std::cmp::PartialOrd 38  
 std::collections::BTreeMap 246  
 std::collections::HashMap 224, 246  
 std::convert::From 153, 174, 270, 272, 276, 318  
 std::convert::TryFrom 154, 174  
 std::convert::TryInto 40  
 std::env::args 219, 301  
 std::error::Error 274  
 std::error::Error 255, 292  
 std::ffi::OsStr 221  
 std::ffi::OsString 62  
 std::ffi::OsString 221  
 std::fmt::Binary 139  
 std::fmt::Debug 139  
 std::fmt::Display 99–102, 139, 273–274  
 std::fs::File type 219  
 std::fs::OpenOptions 220  
 std::fs::Path 220–222  
 std::fs::PathBuf 221  
 std::io::Error 271–272  
 std::io::Error::last\_os\_error() 313  
 std::io::ErrorKind::UnexpectedEof type 230  
 std::io::File 232  
 std::io::prelude 217  
 std::io::Read 217, 232  
 std::io::Write 232  
 std::io trait 217  
 std::iter::Iterator 353, 364  
 std::marker::Copy 129  
 std::marker::Copy, Copy 128  
 std::mem::drop 192  
 std::mem::transmute()  
     function 139  
 std::net::AddrParseError 271  
 std::net::TcpStream 260  
 std::ops::Add 59  
 std::ops::Fn 341, 364  
 std::ops::FnMut 341  
 std::ops::FnOnce 340  
 std::os::raw module 182  
 std::path::Path 62, 220  
 std::path::PathBuf 220  
 std::path::PathBuf type 250  
 std::path::Path string 221  
 std::path::Path type 250  
 std::prelude module 40  
 std::rc::Rc<T> 129  
 std::rc::Weak type 185, 187  
 std::String string 221  
 std::sync::Arc 354  
 std::sync::atomic::spin\_loop\_hint() 338  
 std::sync::mpsc module 354  
 std::sync::Mutex 354  
 std::thread::spawn() 330  
 std::thread::yield\_now() 338  
 std::rc::Rc, std::rc::Rc wrapper type 131  
 std::rc::Rc type 91  
 std::sync::Arc type 91  
 stdin, reading from 74  
 steady clock 297  
 steps variable 352  
 String 61, 81–82, 118, 183, 189–190, 215, 255  
 String::from() 81  
 struct blocks 84  
 structs  
     adding methods to with impl 84–87  
     modeling files with 80–83  
     simplifying object creation by implementing new() 84–87  
 str value 61, 229  
 seconds\_t 307  
 SVGs, generating 346  
 swapping 202  
 switch keyword 51  
 synchronous interrupts 391–392  
 system clock 296  
 systems programming 2, 26  
 SYSTEMTIME 308–309  
 system time 294

**T**


---

target\_arch attribute 227  
 target\_endian attribute 227

target\_env attribute 227  
 target\_family attribute 227  
 target\_has\_atomic attribute 227  
 target\_os attribute 227  
 target platform 369  
 target\_pointer\_width  
     attribute 227  
 target\_vendor attribute 228  
 task queues,  
     implementing 358–360  
 tasks 361  
 task virtualization 360–363  
     containers 363  
     context switches 362  
     processes 363  
     reasons for using operating  
         systems 363  
     threads 362  
     WebAssembly 363  
 TCP (Transmission Control  
     Protocol) 260–268  
     converting hostnames to IP  
         addresses 261–268  
     port numbers 261  
     raw 282  
 TcpStream::connect() 261  
 TcpStream type 232  
 Terminated 403  
 test attribute 228  
 text output 381–383  
     creating type that can print  
         to VGA frame buffer  
         382–383  
 enums  
     controlling in-memory rep-  
         resentation of 382  
     reasons for using 382  
     printing to screen 383  
     writing colored text to  
         screen 381  
 text processing 8–11  
 thetime\_t 307  
 Thing type 257  
 third-party code 67–70  
     adding support for regular  
         expressions 68–69  
     generating the third-party  
         crate documentation  
         locally 69–70  
     managing toolchains with  
         rustup 70  
 thread::spawn() 14  
 thread::yield\_now()  
     method 338  
 thread of execution 361  
 thread pools 353–360  
     channels 356  
     implementing task  
         queues 358–360  
     one-way communication  
         354–356  
     two-way communication  
         356–358  
 ThreadRng 259  
 threads 330–340, 361  
     closures 330–331  
     effect of spawning many  
         threads 333  
     effect of spawning some  
         threads 331–332  
     reproducing results 335–338  
     shared variables 338–340  
     spawning a thread per logical  
         task 351–353  
         functional programming  
             style 351–352  
         parallel iterators 352–353  
     spawning threads 331  
     task virtualization 362  
     thread::yield\_now()  
         method 338  
 time and keeping  
     definitions 296–297  
     encoding time 297–298  
     error handling 313  
     formatting timestamps  
         299–305  
     formatting time 301  
     full command-line  
         interface 301–303  
     full project 303–305  
     refactoring clock code to  
         support a wider  
         architecture 300  
 overview 294–295  
 representing time zones 298  
 resolving differences with  
     NTP 314–321  
     adjusting local time 316–  
         318  
     converting between time  
         representations that use  
         different precisions and  
         epochs 318–319  
     full code listing 319–321  
     sending requests and inter-  
         preting responses  
         314–316  
 setting time 305–310  
     common behavior 306  
     for operating systems that  
         use libc 306–308  
     full code listing 310  
     on Windows 308–309  
 sources of time 296  
 teaching apps to tell  
     time 298–299  
 timestamp 301  
 time\_t 298  
 TimeVal 306  
 timeval 306  
 time zones 298  
 TLB (translated addresses) 203  
 TLS (Transport Layer  
     Security) 21–23, 254  
     goto fail 22–23  
     Heartbleed 21–22  
     to\_bytes() method 387  
     todo!() 300  
 toolchains 70  
 trait keyword 98  
 trait objects 190, 256–260  
     defined 256  
     function of 256  
     rpg project 257–260  
 traits 98–102  
     Clone trait 130–131  
     Copy trait 129–131  
     Display trait 99–102, 273–274  
     Error trait 274  
     From trait 276  
     Path trait 220–222  
     Read trait 98–99  
     Write trait  
         implementing 386–387  
         reimplementing  
         panic() 385–386  
 translated addresses (TLB) 203  
 translation lookaside buffer 206  
 Transmission Control Protocol.  
     *See* TCP  
 Transport Layer Security. *See* TLS  
 traps 391  
 tree command 6  
 tree map 242  
 trust-dns crate 268  
 try! macro 270  
 try\_into() method 40  
 T type 59, 65, 153, 183, 189  
 turtle variable 345  
 Type annotations 9  
 type classes 40  
 type erasure 272  
 type keyword 81  
 type safety 110

**U**

[u8] type 62, 222, 232, 356  
 u8 type 38, 80, 382  
 u16 type 38–39  
 u32 type 38, 139, 146  
 UDP (User Datagram Protocol) 262  
 unbounded queues 354  
 unicast 279  
 unikernel 363  
 unimplemented!() macro 300  
 unit type 79  
 UNIX timestamp 301  
 unsafe() method 40  
 unsafe blocks 115, 139, 184, 204, 294, 306, 401, 410, 413, 417  
 unsafe keyword 88, 139, 417  
 unsigned long int 298  
 unwinding 379  
 .unwrap() method 94, 292  
 unwrap() method 40, 92, 219, 264, 277  
 UPDATE case 95  
 update <key> <value> 224  
 Update opcodes 264  
 UpstreamError enum 275  
 use crate:: 364  
 use keyword 40, 44, 157  
 –use-standard timestamp flag 299  
 usize integers 413  
 usize type 38, 65, 165, 177, 185, 406  
 usize value 404–405  
 U type 153

**V**

values  
 duplicating 128–131  
 using Clone and Copy 130–131  
 using Copy 129–130

using fewer long-lived 123–126  
 .values() method 245  
 .values\_mut() variant 245  
 variable bindings 35  
 variables  
 defining 35–36  
 global variables  
 signal handling with custom actions 401–402  
 using to indicate that shutdown has been initiated 402–405  
 modifying known global variables 87–91  
 shared variables 338–340  
 Vec::new() 81  
 Vec<Cereal> 13  
 Vec<Command> 345–346, 360  
 Vec<Message> 119  
 Vec<Message> message store 125  
 Vec<Operation> 345  
 Vec<Result> 354  
 Vec<String> 301  
 Vec<T> 190, 243, 256, 351–352, 373  
 Vec<T> fields 263  
 Vec<T> vector 66  
 Vec<Task> 354  
 vectors 63–64, 66–67  
 Vec<u8> type 62, 80, 267  
 Vec<Vec<(usize, String)>> 66–67  
 version flag 367  
 virtual addresses 204  
 virtual memory 202–211  
 having processes scan their own memory 203–205  
 overview 202–203  
 reading from and writing to process memory 211

scanning address spaces 208–210  
 translating virtual addresses to physical addresses 205–207  
 void function pointer 404  
 V type 245

**W**

wall clock time 393  
 Wasm (WebAssembly) 363  
 web browsers 26  
 while loop 173, 336  
 endless looping 48  
 overview 47  
 stopping iteration once a duration is reached 47–48  
 window.draw\_2d() 199  
 Windows 308–309  
 API integer types 308  
 clock code 309  
 representing time in 308  
 words 202  
 WORD type 308  
 World struct 195  
 wrapping data within specialty types 131–133  
 WriteProcessMemory() 211  
 write\_str() 386  
 Write trait  
 implementing 386–387  
 reimplementing panic() 385–386  
 write\_volatile() method 376

**Z**

zero-cost abstractions 27, 98  
 ZST (zero-sized type) 300, 326

# Rust in Action

Tim McNamara

**R**ust is the perfect language for systems programming. It delivers the low-level power of C along with rock-solid safety features that let you code fearlessly. Ideal for applications requiring concurrency, Rust programs are compact, readable, and blazingly fast. Best of all, Rust's famously smart compiler helps you avoid even subtle coding errors.

**Rust in Action** is a hands-on guide to systems programming with Rust. Written for inquisitive programmers, it presents real-world use cases that go far beyond syntax and structure. You'll explore Rust implementations for file manipulation, networking, and kernel-level programming and discover awesome techniques for parallelism and concurrency. Along the way, you'll master Rust's unique borrow checker model for memory management without a garbage collector.

## What's Inside

- Elementary to advanced Rust programming
- Practical examples from systems programming
- Command-line, graphical and networked applications

For intermediate programmers. No previous experience with Rust required.

**Tim McNamara** uses Rust to build data processing pipelines and generative art. He is an expert in natural language processing and data engineering.

Register this print book to get free access to all ebook formats.

Visit <https://www.manning.com/freebook>

“This well-written book will help you make the most of what Rust has to offer.”

—Ramnivas Laddad  
author of *AspectJ in Action*

“Engaging writing style and crisp, easy-to-grasp examples help the reader get off the ground in no time.”

—Suman Tambe, LinkedIn

“*Rust in Action* is remarkably polished!”

—Christopher Haupt, Swoogo

“Makes it easy to explore the language and get going with it.”

—Federico Hernandez  
Meltwater

“I highly recommend this book to those who want to learn Rust.”

—Afshin Mehrabani, Etsy



ISBN: 978-1-61729-455-6



55999

9 781617 294556



MANNING

\$59.99 / Can \$79.99 [INCLUDING eBOOK]